

# Real Time Clock Handbook

400090

INCLIDES 3 VOLTAS



# REAL TIME CLOCK HANDBOOK

9913

**1993 Edition** 

**3-Volt Low Voltage Real Time Clocks** 

Real Time Clocks and Timer Clock Peripherals Application Notes

i

Appendices/Physical Dimensions

#### TRADEMARKS

Following is the most current list of National Semiconductor Corporation's trademarks and registered trademarks.

АВіС™ Abuseable<sup>™</sup> Anadig™ APPSTM ARi1TM **ASPECT™** AT/LANTIC™ Auto-Chem Deflasher™ ВСРТМ BI-FET™ BI-FET II™ BI-LINE™ BIPLAN™ **BLCTM** BLXTM ВМАС™ Brite-Lite™ BSITM BSI-2™ **CDDTM CGSTM** CIM™ **CIMBUS™** CLASIC™ COMBO® COMBO I™ COMBO IITM COPS™ microcontrollers **CRD™** DA4™ **DENSPAKTM** DIBTM **DISCERNTM DISTILLTM DNR® DPVMTM** E<sup>2</sup>CMOSTM **ELSTAR™** Embedded System Processor<sup>™</sup> ЕРТМ

E-Z-LINK™ **FACT™** FACT Quiet Series™ **FAIRCAD™** Fairtech™ **FAST®** FASTr™ Flash™ GENIX™ **GNXTM GTO™** HEX 3000™ НРС™ HyBal™ 13Ľ® ICM<sup>TM</sup> Integral ISE™ Intelisplav<sup>TM</sup> Inter-LERIC™ Inter-RIC™ **ISETM** ISE/06™ ISE/08™ ISE/16™ ISE32™ **ISOPLANAR™ ISOPLANAR-Z™** I FRICTM LMCMOS™ M<sup>2</sup>CMOS™ Macrobus™ Macrocomponent<sup>™</sup> **MACSI™** MAPLTM MAXI-ROM® Microbus™ data bus MICRO-DAC™ µtalker™ Microtalker™ **MICROWIRE™** MICROWIRE/PLUS™

**MOLE™ МРА**ТМ MST™ Naked-8™ National® National Semiconductor® National Semiconductor Corp.® NAX 800™ Nitride Plus™ Nitride Plus Oxide™ **NMLTM** NOBUS™ NSC800™ NSCISE™ NSX-16™ NS-XC-16™ **NTERCOM™ NURAM™ OPALTM OXISS™** P<sup>2</sup>CMOS™ Perfect Watch™ **PLAN™ PLANAR™ PLAYERTM** PLAYER+™ Plus-2™ Polycraft™ **POPTM** Power + Control™ POWERplanar™ QS™ QUAD3000™ **QUIKLOOK™ RATTM RIC™ RICKIT™** RTX16™ **SCAN™** 

SCXTM SERIES/800™ Series 32000® SIMPLE SWITCHER™ SofChek™ **SONIC™** SPiKe™ SPIRETM Staggered Refresh™ STAR<sup>TM</sup> Starlink™ **STARPLEX™** ST-NIC™ SuperAT™ Super-Block™ SuperChip™ SuperScript™ SYS32TM TapePak® **TDS™** TeleGate™ The National Anthem® TLC™ Trapezoidal™ TRI-CODE™ TRI-POLY™ TRI-SAFE™ TRI-STATE® **TROPIC™** Tropic Pele'™ Tropic Reef™ **TURBOTRANSCEIVER™** VIРтм VR32TM WATCHDOG™ XMOS™ **XPU™** Z STARTM 883B/RETS™ 883S/RETS™

IBM<sup>®</sup>, PC-AT<sup>®</sup> and PC-XT<sup>®</sup> are registered trademarks of International Business Machines Corporation. Microsoft<sup>™</sup> is a trademark of Microsoft Corporation. Z80<sup>®</sup> is a registered trademark of Zilog Corporation.

#### LIFE SUPPORT POLICY

NATIONAL'S PRODUCTS ARE NOT AUTHORIZED FOR USE AS CRITICAL COMPONENTS IN LIFE SUPPORT DEVICES OR SYSTEMS WITHOUT THE EXPRESS WRITTEN APPROVAL OF THE PRESIDENT OF NATIONAL SEMICONDUCTOR CORPORATION. As used herein:

- Life support devices or systems are devices or systems which, (a) are intended for surgical implant into the body, or (b) support or sustain life, and whose failure to perform, when properly used in accordance with instructions for use provided in the labeling, can be reasonably expected to result in a significant injury to the user.
- A critical component is any component of a life support device or system whose failure to perform can be reasonably expected to cause the failure of the life support device or system, or to affect its safety or effectiveness.

National Semiconductor Corporation 2900 Semiconductor Drive, P.O. Box 58090, Santa Clara, California 95052-8090 1-800-272-9959 TWX (910) 339-9240

National does not assume any responsibility for use of any circuitry described, no circuit patent licenses are implied, and National reserves the right, at any time without notice, to change said circuitry or specifications.

ü

# **Table of Contents**

Alphanumeric Index	iv
Section 1 3-Volt Low Voltage Real Time Clocks	
LV8571A Low Voltage Timer Clock Peripheral (TCP)	1-3
LV8572A Low Voltage Real Time Clock (RTC)	1-26
LV8573A Low Voltage Real Time Clock (RTC)	1-44
Section 2 Real Time Clocks	
TCP/RTC Family Comparisons	2-3
DP8570A Timer Clock Peripheral (TCP)	2-5
DP8571A Timer Clock Peripheral (TCP)	2-28
DP8572A/DP8572AM Real Time Clock (RTC)	2-51
DP8573A Real Time Clock (RTC)	2-71
MM58274C-12 Microprocessor Compatible Real Time Clock	2-86
MM58274C Microprocessor Compatible Real Time Clock	2-99
MM58174A Microprocessor Compatible Real Time Clock	2-112
MM58167B Microprocessor Real Time Clock	2-119
NS32FX211 Microprocessor Compatible Real Time Clock	2-128
Section 3 Application Notes	
AN-353 MM58167B Real Time Clock Design Guide	3-3
AN-359 The MM58174A Real Time Clock in a Battery Backed-Up Design Provides	
Reliable Clock and Calendar Functions	3-20
AN-365 The MM58274C Adds Reliable Real-Time Keeping to Any Microprocessor	
System	3-29
AN-588 Calibration of the DP8570A Family	3-45
AN-589 DP8570A Timer Clock Peripheral Test Mode and Test Considerations	3-50
AN-595 Flexible Timers on the DP8570A and DP8571A	3-54
AB-43 Typical DP8570A Interface to the IBM PC/XT for the Purpose of Engineering	
Evaluation	3-60
AN-443 Add a Hardware Clock/Calendar to Your IBM PC	3-62
AN-893 Using External Oscillators for the DP857X Real Time Clocks with the Battery	0.00
Backed Mode Selected AN-894 DP8570A Experiments to Test the Low Battery Bit or Generate a Periodic	3-83
	3-86
AN-895 Change the Battery on any DP857X Family Member Using Software without	3-00
	3-95
<b>.</b>	3-90
Section 4 Physical Dimensions/Appendices Physical Dimensions	4.0
Physical Dimensions	4-3
Distributors	
Distributors	

# Alpha-Numeric Index

AB-43 Typical DP8570A Interface to the IBM PC/XT for the Purpose of Engineering	
Evaluation	
AN-353 MM58167B Real Time Clock Design Guide	3-3
AN-359 The MM58174A Real Time Clock in a Battery Backed-Up Design Provides Reliable	
Clock and Calendar Functions	
AN-365 The MM58274C Adds Reliable Real-Time Keeping to Any Microprocessor System	3-29
AN-443 Add a Hardware Clock/Calendar to Your IBM PC	3-62
AN-588 Calibration of the DP8570A Family	
AN-589 DP8570A Timer Clock Peripheral Test Mode and Test Considerations	
AN-595 Flexible Timers on the DP8570A and DP8571A	3-54
AN-893 Using External Oscillators for the DP857X Real Time Clocks with the Battery Backed	
Mode Selected	
AN-894 DP8570A Experiments to Test the Low Battery Bit or Generate a Periodic Interrupt	3-86
AN-895 Change the Battery on any DP857X Family Member Using Software without Losing	
Time	
DP8570A Timer Clock Peripheral (TCP)	
DP8571A Timer Clock Peripheral (TCP)	
DP8572A Real Time Clock (RTC)	
DP8572AM Real Time Clock (RTC)	
DP8573A Real Time Clock (RTC)	
LV8571A Low Voltage Timer Clock Peripheral (TCP)	1-3
LV8572A Low Voltage Real Time Clock (RTC)	
LV8573A Low Voltage Real Time Clock (RTC)	
MM58167B Microprocessor Real Time Clock	
MM58174A Microprocessor Compatible Real Time Clock	
MM58274C Microprocessor Compatible Real Time Clock	
MM58274C-12 Microprocessor Compatible Real Time Clock	
NS32FX211 Microprocessor Compatible Real Time Clock	2-128



# **Product Status Definitions**

# **Definition of Terms**

Data Sheet Identification	Product Status	Definition
Advance Information	Formative or In Design	This data sheet contains the design specifications for product development. Specifications may change in any manner without notice.
Preliminary	First Production	This data sheet contains preliminary data, and supplementary data will be published at a later date. National Semiconductor Corporation reserves the right to make changes at any time without notice in order to improve design and supply the best possible product.
No Identification Noted	Full Production	This data sheet contains final specifications. National Semiconductor Corporation reserves the right to make changes at any time without notice in order to improve design and supply the best possible product.
Obsolete	Not In Production	This data sheet contains specifications on a product that has been discontinued by National Semiconductor Corporation. The data sheet is printed for reference information only.

National Semiconductor Corporation reserves the right to make changes without further notice to any products herein to improve reliability, function or design. National does not assume any liability arising out of the application or use of any product or circuit described herein; neither does it convey any license under its patent rights, nor the rights of others.



# Section 1 3-Volt Low Voltage Real Time Clocks



# Section 1 Contents

LV8571A Low Voltage Timer Clock Peripheral (TCP)	1-3
LV8572A Low Voltage Real Time Clock (RTC)	1-26
LV8573A Low Voltage Real Time Clock (RTC)	1-44



# LV8571A Low Voltage Timer Clock Peripheral (TCP)

# **General Description**

The LV8571A is intended for use in microprocessor based systems where information is required for multi-tasking, data logging or general time of day/date information. This device is implemented in low voltage silicon gate microCMOS technology to provide low standby power in battery back-up environments. The circuit's architecture is such that it looks like a contiguous block of memory or I/O ports. The address space is organized as 2 software selectable pages of 32 bytes. This includes the Control Registers, the Clock Counters, the Alarm Compare RAM, the Timers and their data RAM, and the Time Save RAM. Any of the RAM locations that are not being used for their intended purpose may be used as general purpose CMOS RAM.

Time and date are maintained from 1/100 of a second to year and leap year in a BCD format, 12 or 24 hour modes. Day of week, day of month and day of year counters are provided. Time is controlled by an on-chip crystal oscillator requiring only the addition of the crystal and two capacitors. The choice of crystal frequency is program selectable.


Two independent multifunction 10 MHz 16-bit timers are provided. These timers operate in four modes. Each has its own prescaler and can select any of 7 possible clock inputs. Thus, by programming the input clocks and the timer counter values a very wide range of timing durations can be achieved. The range is from about 400 ns (4.915 MHz oscillator) to 65,535 seconds (18 hrs., 12 min.).

Power failure logic and control functions have been integrated on chip. This logic is used by the TCP to issue a power fail

interrupt, and lock out the  $\mu p$  interface. The time power fails may be logged into RAM automatically when V\_{BB} > V\_{CC}. Additionally, two supply pins are provided. When V\_{BB} > V\_{CC}, internal circuitry will automatically switch from the main supply to the battery supply. Status bits are provided to indicate initial application of battery power, system power, and low battery detect. (Continued)

### Features

- 3.3V ±10% supply
- Full function real time clock/calendar
  - 12/24 hour mode timekeeping
  - Day of week and day of years counters
  - Four selectable oscillator frequencies
  - Parallel resonant oscillator
- Two 16-bit timers
  - 10 MHz external clock frequency
  - Programmable multi-function output
  - Flexible re-trigger facilities
- Power fail features
  - Internal power supply switch to external battery
  - Power Supply Bus glitch protection
  - Automatic log of time into RAM at power failure
- On-chip interrupt structure
- Periodic, alarm, timer and power fail interrupts
   Up to 44 bytes of CMOS RAM
- INTR/MFO pins programmable High/Low and push-pull or open drain



1

# Absolute Maximum Ratings (Notes 1 & 2)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Supply Voltage (V <sub>CC</sub> )	-0.5V to +7.0V
DC Input Voltage (VIN)	$-0.5V$ to $V_{\mbox{CC}}+0.5V$
DC Output Voltage (V <sub>OUT</sub> )	-0.5V to V <sub>CC</sub> + 0.5V
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.	) 260°C

# **Operation Conditions**

	Min	Max	Unit
Supply Voltage (V <sub>CC</sub> ) (Note 3)	3.0	3.6	V
Supply Voltage (V <sub>BB</sub> ) (Note 3)	2.2	V <sub>CC</sub> -0.4	V
DC Input or Output Voltage (VIN, VOUT)	0.0	Vcc	v
Operation Temperature (T <sub>A</sub> )	-40	+85	°C
Electr-Static Discharge Rating		1	kV
Typical Values			
θ <sub>JA</sub> DIP	Board		59°C/W
	Socket		65°C/W
θ <sub>JA</sub> PLCC	Board		77°C/W
	Socket		85°C/W

### **DC Electrical Characteristics**

 $V_{CC}$  = 3.3V ±10%,  $V_{BB}$  = 2.5V,  $V_{\overline{PFAIL}}$  > V<sub>IH</sub>,  $C_L$  = 100 pF (unless otherwise specified)

Symbol	Parameter	Conditions	Min	Max	Units
V <sub>IH</sub>	High Level Input Voltage (Note 4)	Any Inputs Except OSC IN, OSC IN with External Clock	2.0 V <sub>BB</sub> 0.2	V <sub>CC</sub> + 0.3	v v
V <sub>IL</sub>	Low Level Input Voltage	All Inputs Except OSC IN OSC IN with External Clock	-0.3 -0.3	0.8 0.2	VV
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = -20 \ \mu A$ $I_{OUT} = -2.0 \ m A$	V <sub>CC</sub> -0.2 2.4		v v
V <sub>OL</sub>	Low Level Output Voltage (Excluding OSC OUT)	l <sub>OUT</sub> = 20 μA l <sub>OUT</sub> = 2.0 mA		0.2 0.3	v v
lin	Input Current (Except OSC IN)	$V_{IN} = V_{CC} \text{ or } GND$		±0.7	μA
loz	Output TRI-STATE® Current	$V_{OUT} = V_{CC} \text{ or } GND$		±1	μΑ
llkg	Output High Leakage Current MFO, INTR Pins	V <sub>OUT</sub> = V <sub>CC</sub> or GND Outputs Open Drain		±1	μΑ
lcc	Quiescent Supply Current (Note 7)	$\begin{array}{l} F_{OSC} = 32.768 \; kHz \\ V_{IN} = V_{CC} \; or \; GND \; (Note \; 5) \\ V_{IN} = V_{CC} \; or \; GND \; (Note \; 6) \\ V_{IN} = \; V_{IH} \; or \; V_{IL} \; (Note \; 6) \end{array}$		220 700 8	μΑ μΑ mA
		F <sub>OSC</sub> = 4.194304 MHz or 4.9152 MHz V <sub>IN</sub> = V <sub>CC</sub> or GND (Note 6) V <sub>IN</sub> = V <sub>IH</sub> or V <sub>IL</sub> (Note 6)		6 8	mA mA
lcc	Quiescent Supply Current (Single Supply Mode) (Note 7)	$\begin{array}{l} V_{BB} = GND \\ V_{IN} = V_{CC} \mbox{ or } GND \\ F_{OSC} = 32.768 \mbox{ kHz} \\ F_{OSC} = 4.9152 \mbox{ MHz} \mbox{ or} \\ 4.194304 \mbox{ MHz} \end{array}$		60 6	μA mA
IBB	Standby Mode Battery Supply Current (Note 8)	$\label{eq:VCC} \begin{array}{l} V_{CC} = GND \\ OSC OUT = open circuit, \\ other pins = GND \\ F_{OSC} = 32.768  \text{kHz} \\ F_{OSC} = 4.9152  \text{MHz}  \text{or} \\ 4.194304  \text{MHz} \end{array}$		8 400	μΑ μΑ
BLK	Battery, Supply Leakage	$\begin{array}{l} 2.2V \leq V_{BB} \leq 2.6V\\ \text{other pins at GND}\\ V_{CC} = \text{GND}, V_{BB} = 2.6V\\ V_{CC} = 3.6V, V_{BB} = 2.2V \end{array}$	-0.8	0.8	μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: For  $F_{OSC} = 4.194304$  or 4.9152 MHz,  $V_{BB}$  minimum = 2.8V. In battery backed mode,  $V_{BB} \le V_{CC} - 0.4V$ . Single Supply Mode: Data retention voltage is 2.2V min. In single Supply Mode (Power connected to  $V_{CC}$  pin)  $3.0V \le V_{CC} \le 3.6V$ .

Note 4: This parameter (VIH) is not tested on all pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: This specification is tested with both the timers and OSC IN driven by a signal generator. Contents of the Test Register = 00(H), the MFO pin is not configured as buffered oscillator out and MFO, INTR, are configured as open drain.

Note 8: This specification is tested with both the timers off, and only OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

Symbol	Parameter	Min	Max	Units
AD TIMING				
t <sub>AR</sub>	Address Valid Prior to Read Strobe	10		ns
t <sub>RW</sub>	Read Strobe Width (Note 9)	100		ns
tCD	Chip Select to Data Valid Time		100	ns
t <sub>RAH</sub>	Address Hold after Read (Note 10)	2		ns
t <sub>RD</sub>	Read Strobe to Valid Data		90	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		80	ns
t <sub>RCH</sub>	Chip Select Hold after Read Strobe (Note 10)	0		ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses	70		ns
RITE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	10		ns
t <sub>WAH</sub>	Address Hold after Write Strobe (Note 10)	2		ns
<sup>t</sup> CW	Chip Select to End of Write Strobe	110		ns
tww	Write Strobe Width (Note 11)	100		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	70		ns
twoh	Data Hold after Write Strobe (Note 10)	2		ns
twch	Chip Select Hold after Write Strobe (Note 10)	0		ns

Note 9: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when both signals are low and terminates when either signal returns high.

Note 10: Hold time is guaranteed by design but not production tested. This limit is not used to calculate outgoing quality levels.

Note 11: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

# **AC Test Conditions**

Input Pulse Levels Input Rise and Fall Times	GND to 3.0V 6 ns (10%–90%)
Input and Output Reference Levels	1.3V
TRI-STATE Reference	Active High +0.5V
Levels (Note 13)	Active Low -0.5V

Note 12:  $C_L = 100 \text{ pF}$ , includes jig and scope capacitance.

Note 13: S1 =  $V_{CC}$  for active low to high impedance measurements. S1 = GND for active high to high impedance measurements.


S1 = open for all other timing measurements.

# Capacitance (T<sub>A</sub> = 25°C, f = 1 MHz)

Symbol	Parameter (Note 14)	Тур	Units
C <sub>IN</sub> .	Input Capacitance	5	pF
С <sub>ОUT</sub>	Output Capacitance	7	рF

Note 14: This parameter is not 100% tested.

Note 15: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.




TL/F/11416-2


LV8571A

# **Timing Waveforms**

LV8571A



----



# General Description (Continued)

The LV8571A's interrupt structure provides four basic types of interrupts: Periodic, Alarm/Compare, Timer, and Power Fail. Interrupt mask and status registers enable the masking and easy determination of each interrupt.

One dedicated general purpose interrupt output is provided. A second interrupt output is available on the Multiple Function Output (MFO) pin. Each of these may be selected to generate an interrupt from any source. Additionally, the MFO pin may be programmed to be either as oscillator output or Timer 0's output.

# **Pin Description**

 $\overline{CS}$ ,  $\overline{RD}$ ,  $\overline{WR}$  (Inputs): These pins interface to  $\mu P$  control lines. The  $\overline{CS}$  pin is an active low enable for the read and write operations. Read and Write pins are also active low and enable reading or writing to the TCP. All three pins are disabled when power failure is detected. However, if a read or write is in progress at this time, it will be allowed to complete its cycle.

A0-A4 (Inputs): These 5 pins are for register selection. They individually control which location is to be accessed. These inputs are disabled when power failure is detected.

**OSC IN (Input): OSC OUT (Output):** These two pins are used to connect the crystal to the internal parallel resonant oscillator. The oscillator is always running when power is applied to  $V_{BB}$  and  $V_{CC}$ , and the correct crystal select bits in the Real Time Mode Register have been set.

**MFO (Output):** The multi-function output can be used as a second interrupt output for interrupting the  $\mu$ P. This pin can also provide an output for the oscillator or the internal Timer 0. The MFO output can be programmed active high or low, open drain or push-pull. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>. This pin is configured open drain during battery operation (V<sub>BB</sub> > V<sub>CC</sub>).

**INTR (Output):** The interrupt output is used to interrupt the processor when a timing event or power fail has occurred and the respective interrupt has been enabled. The INTR output can be programmed active high or low, push-pull or open drain. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>. This pin is configured open drain during battery operation (V<sub>BB</sub> > V<sub>CC</sub>).

**D0–D7 (Input/Output):** These 8 bidirectional pins connect to the host  $\mu$ P's data bus and are used to read from and write to the TCP. When the PFAIL pin goes low and a write is not in progress, these pins are at TRI-STATE.


**FFAIL** (Input): In battery backed mode, this pin can have a digital signal applied to it via some external power detection logic. When PFAIL = logic 0 the TCP goes into a lockout mode, in a minimum of 30  $\mu$ s or a maximum of 63  $\mu$ s unless lockout delay is programmed. In the single power supply mode, this pin is not useable as an input and should be tied to V<sub>CC</sub>. Refer to section on Power Fail Functional Description.

 $\begin{array}{l} \textbf{V_{BB}} \mbox{ (Battery Power Pin): This pin is connected to a backup power supply. This power supply is switched to the internal circuitry when the V_{CC} becomes lower than V_{BB}. Utilizing this pin eliminates the need for external logic to switch in and out the back-up power supply. If this feature is not to be used then this pin must be tied to ground, the TCP programmed for single power supply only, and power applied to the V_{CC} pin. \end{array}$ 

Vcc: This is the main system power pin.

GND: This is the common ground power pin for both  $\mathsf{V}_{BB}$  and  $\mathsf{V}_{CC}.$ 

# **Connection Diagram**



**Top View** 

Order Number LV8571AN See NS Package Number N24C

# **Functional Description**

The LV8571A contains a fast access real time clock, two 10 MHz 16-bit timers, interrupt control logic, power fail detect logic, and CMOS RAM. All functions of the TCP are controlled by a set of nine registers. A simplified block diagram that shows the major functional blocks is given in *Figure 1*.

The blocks are described in the following sections:

- 1. Real Time Clock
- 2. Oscillator Prescaler
- 3. Interrupt Logic
- 4. Power Failure Logic
- 5. Additional Supply Management
- 6. Timers

The memory map of the TCP is shown in the memory addressing table. The memory map consists of two 31 byte pages with a main status register that is common to both pages. A control bit in the Main Status Register is used to select either page. *Figure 2* shows the basic concept. Page 0 contains all the clock timer functions, while page 1 has scratch pad RAM. The control registers are split into two separate blocks to allow page 1 to be used entirely as scratch pad RAM. Again a control bit in the Main Status Register is used to select either control register block.

	Page Select	= 0					
1F	RAM/TEST Re	gister			Page Select = 1		
1E	RAM	<u> </u>		1F	RAM		
1D	Months Time Se	ve RAM		1E	RAM		
1C	Day of Month Time	Save RAM		1D	RAM		
1B	Hours Time Sa	ve RAM		10	RAM		
14	Minutes Time S	ave RAM		1B	RAM		
19	Seconds Time S	ave RAM		14	RAM		
18	Day of Week Com	pare RAM		19	RAM		
17	Months Compa	re RAM		18	RAM		
16	Day of Month Com	pare RAM		17	RAM		
15	Hours Compar	e RAM		16	RAM		
14	Minutes Compa	re RAM		15	RAM		
13	Seconds Compa	re RAM		14	RAM		
12	Timer 1 M	SB		13	RAM		
- 11	Timer 1 L	.SB		12	RAM		
10	Timer O M	SB		11	RAM		
OF	Timer O L	SB		10	RAM		
OE	Day of Week Clock	c Counter		OF	RAM		
OD	100's Julian Cloc	k Counter		OE	RAM		
oc	Units Julian Cloc	k Counter		OD.	RAM		
OB	Years Clock C	ounter		OC 1	RAM		
<b>A</b> 0	Months Clock (	Counter		ОВ	RAM	•	
09	Day of Month Cloc	k Counter		0A	RAM		
08	Hours Clock C	ounter		09	RAM		
07	Minutes Clock	Counter		08	RAM		
06	Seconds Clock	Counter		07	RAM		
05	1/100 Second Co	unter		06	RAM		
	1			05	RAM		
				04	RAM		
Register Selec	ct = 0 🧹	Ne Re	gister Select = 1	03	RAM		
Interrupt Rou	ting Register 04	Interrup	t Control Register 1	02	RAM		
Periodic Fla	g Register 03	Interrup	Control Register 0	01	RAM		
Timer 1 Cont	rol Register 02	Outpu	t Mode Register				
Timer 0 Cont	trol Register 01	Real Ti	me Mode Register				
-							
				_			
		00	Main Status Register			TL/F/11416	-6
	FIGL	RE 2. LV8	571A Internal Me	mory Map		.2	-

### Functional Description (Continued) INITIAL POWER-ON of BOTH VBB and VCC

 $V_{BB}$  and  $V_{CC}$  may be applied in any sequence. In order for the power fail circuitry to function correctly, whenever power is off, the  $V_{CC}$  pin must see a path to ground through a maximum of 1 M $\Omega$ . The user should be aware that the control registers will contain random data. The first task to be carried out in an initialization routine is to start the oscillator by writing to the crystal select bits in the Real Time Mode Register. If the LV8571A is configured for single supply mode, an extra 50  $\mu A$  may be consumed until the crystal select bits are programmed. The user should also ensure that the TCP is not in test mode (see register descriptions).

#### REAL TIME CLOCK FUNCTIONAL DESCRIPTION

As shown in *Figure 2*, the clock has 10 bytes of counters, which count from 1/100 of a second to years. Each counter counts in BCD and is synchronously clocked. The count sequence of the individual byte counters within the clock is shown later in Table VII. Note that the day of week, day of month, day of year, and month counters all roll over to 1. The hours counter in 12 hour mode rolls over to 1 and the AM/PM bit toggles when the hours rolls over to 12 (AM = 0, PM = 1). The AM/PM bit is bit D7 in the hours counter.

All other counters roll over to 0. Also note that the day of year counter is 12 bits long and occupies two addresses. Upon initial application of power the counters will contain random information.

#### **READING THE CLOCK: VALIDATED READ**

Since clocking of the counter occurs asynchronously to reading of the counter, it is possible to read the counter while it is being incremented (rollover). This may result in an incorrect time reading. Thus to ensure a correct reading of the entire contents of the clock (or that part of interest), it must be read without a clock rollover occurring. In general this can be done by checking a rollover bit. On this chip the following program steps can be used to accomplish this.

- 1. Initialize program for reading clock.
- 2. Dummy read of periodic status bit to clear it.
- 3. Read counter bytes and store.
- 4. Read rollover bit, and test it.
- 5. If rollover occured go to 3.
- 6. If no rollover, done.

To detect the rollover, individual periodic status bits can be polled. The periodic bit chosen should be equal to the highest frequency counter register to be read. That is if only SECONDS through HOURS counters are read, then the SECONDS periodic bit should be used.

#### **READING THE CLOCK: INTERRUPT DRIVEN**

Enabling the periodic interrupt mask bits cause interrupts just as the clock rolls over. Enabling the desired update rate and providing an interrupt service routine that executes in less than 10 ms enables clock reading without checking for a rollover.

#### READING THE CLOCK: LATCHED READ

Another method to read the clock that does not require checking the rollover bit is to write a one into the Time Save Enable bit (D7) of the Interrupt Routing Register, and then to write a zero. Writing a one into this bit will enable the clock contents to be duplicated in the Time Save RAM. Changing the bit from a one to a zero will freeze and store the contents of the clock in Time Save RAM. The time then can be read without concern for clock rollover, since internal logic takes care of synchronization of the clock. Because only the bits used by the clock counters will be latched, the Time Save RAM should be cleared prior to use to ensure that random data stored in the unused bits do not confuse the host microprocessor. This bit can also provide time save at power failure, see the Additional Supply Management Functions section. With the Time Save Enable bit at a logical 0, the Time Save RAM may be used as RAM if the latched read function is not necessary.

#### INITIALIZING AND WRITING TO THE CALENDAR-CLOCK


Upon initial application of power to the TCP or when making time corrections, the time must be written into the clock. To correctly write the time to the counters, the clock would normally be stopped by writing the Start/Stop bit in the Real Time Mode Register to a zero. This stops the clock from counting and disables the carry circuitry. When initializing the clock's Real Time Mode Register, it is recommended that first the various mode bits be written while maintaining the Start/Stop bit reset, and then writing to the register a second time with the Start/Stop bit set.

The above method is useful when the entire clock is being corrected. If one location is being updated the clock need not be stopped since this will reset the prescaler, and time will be lost. An ideal example of this is correcting the hours for daylight savings time. To write to the clock "on the fly" the best method is to wait for the 1/100 of a second periodic interrupt. Then wait an additional 16  $\mu$ s, and then write the data to the clock.

#### PRESCALER/OSCILLATOR FUNCTIONAL DESCRIPTION

Feeding the counter chain is a programmable prescaler which divides the crystal oscillator frequency to 32 kHz and further to 100 Hz for the counter chain (see *Figure 3*). The crystal frequency that can be selected are: 32 kHz, 32.768 kHz, 4.9152 MHz, and 4.194304 MHz.

Once 32 kHz is generated it feeds both timers and the clock. The clock and timer prescalers can be independently enabled by controlling the timer or clock Start/Stop bits.





### Functional Description (Continued)

The oscillator is programmed via the Real Time Mode Register to operate at various frequencies. The crystal oscillator is designed to offer optimum performance at each frequency. Thus, at 32.768 kHz the oscillator is configured as a low frequency and low power oscillator. At the higher frequencies the oscillator inverter is reconfigured. In addition to the inverter, the oscillator feedback bias resistor is included on chip, as shown in *Figure 4*. The oscillator input may be driven from an external source if desired. Refer to test mode application note for details. The oscillator stability is enhanced through the use of an on chip regulated power supply.

The typical range of trimmer capacitor (as shown in Oscillator Circuit Diagram *Figure 4*, and in the typical application) at the oscillator input pin is suggested only to allow accurate tuning of the oscillator. This range is based on a typical printed circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases, the **load capacitance** specified by the crystal manufacturer (nominal value 11 pF for the 32.768 crystal) is what determines proper oscillation. This load capcitance is the series combination of capacitance on each side of the crystal (with respect to ground).




FIGURE 4. Oscillator Circuit Diagram

XTAL	c,	Ct	R <sub>OUT</sub> (Switched Internally)
32/32.768 kHz	47 pF	2 pF-22 pF	150 k $\Omega$ to 350 k $\Omega$
4.194304 MHz	68 pF	0 pF-80 pF	500Ω to 900Ω
4.9152 MHz	68 pF	29 pF-49 pF	500 $\Omega$ to 900 $\Omega$

#### INTERRUPT LOGIC FUNCTIONAL DESCRIPTION

The TCP has the ability to coordinate processor timing activities. To enhance this, an interrupt structure has been implemented which enables several types of events to cause interrupts. Interrupts are controlled via two Control Registers in block 1 and two Status Registers in block 0. (See Register Description for notes on paging and also *Figure 5* and Table I.) The interrupts are enabled by writing a one to the appropriate bits in Interrupt Control Register 0 and/or 1. Any of the interrupts can be routed to either the INTR pin or the MFO pin, depending on how the Interrupt Routing register is programmed. This, for example, enables the user to dedicate the MFO as a non-maskable interrupt pin to the CPU for power failure detection and enable all other interrupts to appear on the INTR pin. The polarity for the active interrupt can be programmed in the Output Mode Register for either active high or low, and open drain or push pull outputs.

# TABLE I. Registers that are Applicable to Interrupt Control

Register Name	Register Select	Page Select	Address
Main Status Register	X	х	00H
Periodic Flag Register	0	0	03H
Interrupt Routing Register	0	0	04H 、
Interrupt Control Register 0	1	0	03H
Interrupt Control Register 1	1	0	04H
Output Mode Register	1	0	02H

The Interrupt Status Flag D0, in the Main Status Register, indicates the state of INTR and MFO outputs. It is set when either output becomes active and is cleared when all TCP interrupts have been cleared and no further interrupts are pending (i.e., both INTR and MFO are returned to their inactive state). This flag enables the TCP to be rapidly polled by the  $\mu$ P to determine the source of an interrupt in a wired—OR interrupt system.

Note that the Interrupt Status Flag will only monitor the state of the MFO output if it has been configured as an interrupt output (see Output Mode Register description). This is true, regardless of the state of the Interrupt Routing Register. Thus the Interrupt Status Flag provides a true reflection of all conditions routed to the external pins.

Status for the interrupts are provided by the Main Status Register and the Periodic Flag Register. Bits D1–D5 of the Main Status Register are the main interrupt bits.

These register bits will be set when their associated timing events occur. Enabled Alarm or Timer interrupts that occur will set its Main Status Register bit to a one. However, an external interrupt will only be generated if the appropriate Alarm or Timer interrupt enable bits are set (see *Figure 5*).

Disabling the periodic bits will mask the Main Status Register periodic bit, but not the Periodic Flag Register bits. The Power Fail Interrupt bit is set when the interrupt is enabled and a power fail event has occurred, and is not reset until the power is restored. If all interrupt enable bits are 0 no interrupt will be asserted. However, status still can be read from the Main Status Register in a polled fashion (see Figure 5).

To clear a flag in bits D2–D5 of the Main Status Register a 1 must be written back into the bit location that is to be cleared. For the Periodic Flag Register reading the status will reset all the periodic flags.

# Functional Description (Continued)

Interrupts Fall Into Four Categories:

- 1. The Timer Interrupts: For description see Timer Section.
- 2. The Alarm Compare Interrupt: Issued when the value in the time compared RAM equals the counter.
- 3. The Periodic Interrupts: These are issued at every increment of the specific clock counter signal. Thus, an interrupt is issued every minute, second, etc. Each of these interrupts occurs at the roll-over of the specific counter.
- 4. The Power Fail Interrupt: Issued upon recognition of a power fail condition by the internal sensing logic. The power failed condition is determined by the signal on the PFAIL pin. The internal power fail signal is gated with the chip select signal to ensure that the power fail interrupt does not lock the chip out during a read or write.

#### ALARM COMPARE INTERRUPT DESCRIPTON

The alarm/time comparison interrupt is a special interrupt similar to an alarm clock wake up buzzer. This interrupt is generated when the clock time is equal to a value programmed into the alarm compare registers. Up to six bytes can be enabled to perform alarm time comparisons on the counter chain. These six bytes, or some subset thereof, would be loaded with the future time at which the interrupt will occur. Next, the appropriate bits in the Interrupt Control Register 1 are enabled or disabled (refer to detailed description of Interrupt Control Register 1). The TCP then compares these bytes with the clock time. When all the enabled compare registers equal the clock time an alarm interrupt is issued, but only if the alarm compare interrupt is enabled can the interrupt be generated externally. Each alarm compare bit in the Control Register will enable a specific byte for comparison to the clock. Disabling a compare byte is the same as setting its associated counter comparator to an "always equal" state. For example, to generate an interrupt at 3:15 AM of every day, load the hours compare with 0 3 (BCD), the minutes compare with 1 5 (BCD) and the faster counters with 0 0 (BCD), and then disable all other compare registers. So every day when the time rolls over from 3:14:59.99, an interrupt is issued. This bit may be reset by writing a one to bit D3 in the Main Status Register at any time after the alarm has been generated.

If time comparison for an individual byte counter is disabled, that corresponding RAM location can then be used as general purpose storage.

#### PERIODIC INTERRUPTS DESCRIPTION

The Periodic Flag Register contains six flags which are set by real-time generated "ticks" at various time intervals, see *Figure 5*. These flags constantly sense the periodic signals and may be used whether or not interrupts are enabled. These flags are cleared by any read or write operation performed on this register. To generate periodic interrupts at the desired rate, the associated Periodic Interrupt Enable bit in Interrupt Control Register 0 must be set. Any combination of periodic interrupts may be enabled to operate simultaneously. Enabled periodic interrupts will now affect the Periodic Interrupt Flag in the Main Status Register. The Periodic Route bit in the Interrupt Routing Register is used to route the periodic interrupt events to either the INTR output or the MFO output.

When a periodic event occurs, the Periodic Interrupt Flag in the Main Status Register is set, causing an interrupt to be generated. The  $\mu$ P clears both flag and interrupt by writing a "1" to the Periodic Interrupt Flag. The individual flags in the periodic Interrupt Flag Register do not require clearing to cancel the interrupt.

If all periodic interrupts are disabled and a periodic interrupt is left pending (i.e., the Periodic Interrupt Flag is still set), the Periodic Interrupt Flag will still be required to be cleared to cancel the pending interrupt.

#### POWER FAIL INTERRUPTS DESCRIPTION

The Power Fail Status Flag in the Main Status Register monitors the state of the internal power fail signal. This flag may be interrogated by the  $\mu$ P, but it cannot be cleared; it is cleared automatically by the TCP when system power is restored. To generate an interrupt when the power fails, the Power Fail Interrupt Enable bit in Interrupt Control Register 1 is set.


The Power Fail Route bit determines which output the interrupt will appear on. Although this interrupt may not be cleared, it may be masked by clearing the Power Fail Interrupt Enable bit.

# POWER FAILURE CIRCUITRY FUNCTIONAL DESCRIPTION


Since the clock must be operated from a battery when the main system supply has been turned off, the LV8571A provides circuitry to simplify design in battery backed systems. This circuitry switches over to the back up supply, and isolates the LV8571A from the host system. *Figure 6* shows a simplified block diagram of this circuitry, which consists of three major sections; 1) power loss logic: 2) battery switch over logic.

Detection of power loss occurs when  $\overrightarrow{PFAIL}$  is low. Debounce logic provides a 30  $\mu$ s-63  $\mu$ s debounce time, which will prevent noise on the  $\overrightarrow{PFAIL}$  pin from being interpreted as a system failure. After 30  $\mu$ s-63  $\mu$ s the debounce logic times out and a signal is generated indicating that system power is marginal and is failing. The Power Fail Interrupt will then be generated.





1-12



#### FIGURE 6. System-Battery Switchover (Upper Left), Power Fail and Lock-Out Circuits (Lower Right)

The user may choose to have this power failed signal lockout the TCP's data bus within 30 µs min/63 µs max or to delay the lock-out to enable µP access after power failure is detected. This delay is enabled by setting the delay enable bit in the Routing Register. Also, if the lock-out delay was not enabled the TCP will disconnect itself from the bus within 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max. If chip select is low when a power failure is detected, a safety circuit will ensure that if a read or write is held active continuously for greater than 30 µs after the power fail signal is asserted, the lock-out will be forced. If a lock-out delay is enabled, the LV8571A will remain active for 480 µs after power fail is detected. This will enable the µP to perform last minute bookkeeping before total system collapse. When the host CPU is finished accessing the TCP it may force the bus lock-out before 480 µs has elapsed by resetting the delay enable bit.

The battery switch over circuitry is completely independent of the  $\overline{\text{PFAIL}}$  pin. A separate circuit compares  $V_{CC}$  to the  $V_{BB}$  voltage. As the main supply fails, the TCP will continue to operate from the  $V_{CC}$  pin until  $V_{CC}$  falls below the  $V_{BB}$  voltage. At this time, the battery supply is switched in,  $V_{CC}$  is disconnected, and the device is now in the standby mode. If indeterminate operation of the battery switch over circuit is to be avoided, then the voltage at the  $V_{CC}$  pin must not be allowed to equal the voltage at the  $V_{BB}$  pin.

After the generation of a lock-out signal, and eventual switch in of the battery supply, the pins of the TCP will be configured as shown in Table II. Outputs that have a pull-up resistor should be connected to a voltage no greater than  $V_{\text{BB}}.$ 

#### TABLE II. Pin Isolation during a Power Failure

Pin	PFAIL = Logic 0	Standby Mode V <sub>BB</sub> > V <sub>CC</sub>
CS, RD, WR	Locked Out	Locked Out
A0-A4	Locked Out	Locked Out
D0-D7	Locked Out	Locked Out
Oscillator	Not Isolated	Not Isolated
PFAIL	Not Isolated	Not Isolated
INTR, MFO	Not Isolated	Open Drain

The Timer and Interrupt Power Fail Operation bits in the Real-Time Mode Register determine whether or not the timers and interrupts will continue to function after a power fail event.

As power returns to the system, the battery switch over circuit will switch back to  $V_{CC}$  power as soon as it becomes greater than the battery voltage. The chip will remain in the locked out state as long as  $\overrightarrow{PFAIL} = 0$ . When  $\overrightarrow{PFAIL} = 1$ 

ł.

### Functional Description (Continued)

the chip is unlocked, but only after another 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max debounce time. The system designer must ensure that his system is stable when power has returned.

The power fail circuitry contains active linear circuitry that draws supply current from V<sub>CC</sub>. In some cases this may be undesirable, so this circuit can be disabled by masking the power fail interrupt. The power fail input can perform all lock-out functions previously mentioned, except that no external interrupt will be issued. Note that the linear power fail circuitry is switched off automatically when using V<sub>BB</sub> in standby mode.

# LOW BATTERY, INITIAL POWER ON DETECT, AND POWER FAIL TIME SAVE

There are three other functions provided on the LV8571A to ease power supply control. These are an initial Power On detect circuit, which also can be used as a time keeping failure detect, a low battery detect circuit, and a time save on power failure.

On initial power up the Oscillator Fail Flag will be set to a one and the real time clock start bit reset to a zero. This indicates that an oscillator fail event has occurred, and time keeping has failed.

The Oscillator Fail flag will not be reset until the real-time clock is started. This allows the system to discriminate between an initial power-up and recovery from a power failure. If the battery backed mode is selected, then bit D6 of the Periodic Flag Register must be written low. This will not affect the contents of the Oscillator Fail Flag.

Another status bit is the low battery detect. This bit is set only when the clock is operating under the  $V_{CC}$  pin, and when the battery voltage is determined to be less than 2.1V (typical). When the power fail interrupt enable bit is low, it disables the power fail circuit and will also shut off the low battery voltage detection circuit as well.

To relieve CPU overhead for saving time upon power failure, the Time Save Enable bit is provided to do this automatically. (See also Reading the Clock: Latched Read.) The Time Save Enable bit, when set, causes the Time Save RAM to follow the contents of the clock. This bit can be reset by software, but if set before a power failure occurs, it will automatically be reset when the clock switches to the battery supply (not when a power failure is detected by the PFAIL pin). Thus, writing a one to the Time Save bit enables both a software write or power fail write.

#### SINGLE POWER SUPPLY APPLICATIONS

The LV8571A can be used in a single power supply application. To achieve this, the V<sub>BB</sub> pin must be connected to ground, and the power connected to V<sub>CC</sub> and PFAIL pins. The Oscillator Failed/Single Supply bit in the Periodic Flag Register should be set to a logic 1, which will disable the oscillator battery reference circuit. The power fail interrupt should also be disabled. This will turn off the linear power fail detection circuits, and will eliminate any quiescent power drawn through these circuits. Until the crystal select bits are initialized, the LV8571A may consume about 50  $\mu$ A due to arbitrary oscillator selection at power on.

(This extra 50  $\mu\text{A}$  is not consumed if the battery backed mode is selected).

#### TIMER FUNCTIONAL DESCRIPTION

The LV8571A contains 2 independent multi-mode timers. Each timer is composed of a 16-bit negative edge triggered

binary down counter and associated control. The operation is similar to existing  $\mu$ P peripheral timers except that several features have been enhanced. The timers can operate in four modes, and in addition, the input clock frequency can be selected from a prescaler over a wide range of frequencies. Furthermore, these timers are capable of generating interrupts and the Timer 0 output signal is available as a hardware output via the MFO pin. Timer 1 output, however, is not available as a hardware output signal. Both the interrupt and MFO outputs are fully programmable active high, or low, open drain, or push-pull.

Figure 7 shows the functional block diagram of one of the timers. The timer consists of a 16-bit counter, two 8-bit input registers, two 8-bit output registers, clock prescaler, mode control logic, and output control logic. The timer and the data registers are organized as two bytes for each timer. Under normal operations a read/write to the timer locations will read or write to the data input register. The timer contents can be read by setting the counter Read bit (RD) in the timer control register.

#### TIMER INITIALIZATION

The timer's operation is controlled by a set of registers, as listed in Table III. These consist of 2 data input registers and one control register per timer. The data input registers contain the timers count down value. The Timer Control Register is used to set up the mode of operation and the input clock rate. The timer related interrupts can be controlled by programming the Interrupt Routing Register and Interrupt Control Register 0. The timer outputs are configured by the Output Mode Register.

Register Name	Register Select	Page Select	Address
Timer 0 Data MSB	Х	0	10H
Timer 0 Data LSB	Х	0	0FH
Timer 0 Control Register	0	0	01H
Timer 1 Data MSB	Х	0	12H
Timer 1 Data LSB	Х	0	11H
Timer 1 Control Register	0	0	02H
Interrupt Routing Register	0	0	04H
Interrupt Control Reg. 0	1	0	03H
Output Mode Register	1	0	02H

All these registers must be initialized prior to starting the timer(s). The Timer Control Register should first be set to select the timer mode with the timer start/stop bit reset. Then when the timer is to be started the control register should be rewritten identically but with the start/stop bit set.

#### TIMER OPERATION

Each timer is capable of operation in one of four modes. As mentioned, these modes are programmed in each timer's Control Register which is described later. All four modes operate in a similar manner. They operate on the two 8-bit data words stored into the Data Input Register. At the beginning of a counting cycle the 2 bytes are loaded into the timer and the timer commences counting down towards zero. The exact action taken when zero is reached depends on the mode selected, but in general, the timer output will change state, and an interrupt will be generated if the timer interrupts are unmasked.

### Functional Description (Continued) INPUT CLOCK SELECTION

The input frequency to the timers may be selected. Each timer has a prescaler that gives a wide selection of clocking rates. Table IV shows the range of programmable clocks available and the corresponding setting in the Timer Control Register. Note that the output of Timer 1 may be used as the input to Timer 0. This is a cascade option for the timers and allows them to be clocked as a 32-bit down counter.

#### **TABLE IV. Programmable Timer Input Clocks**

C2	C1	CO	Selected Clock
0	0	0	Timer 1 Output
0	0	1	Crystal Oscillator
0	1	0	(Crystal Oscillator)/4
0	1	1	93.5 μs (10.7 kHz)
1	0	0	1 ms (1 kHz)
1	0	1	10 ms (100 Hz)
1	1	0	1/10 Second (10 Hz)
1	1	1	1 Second (1 Hz)

Note that the second and third selections are not fixed frequencies, but depend on the crystal oscillator frequency chosen.

Since the input clock frequencies are usually running asynchronously to the timer Start/Stop control bit, a 1 clock cycle error may result. This error results when the Start/Stop occurs just after the clock edge (max error). To minimize this error on all clocks an independent prescaler is used for each timer and is designed so that its Start/Stop error is less than 1 clock cycle.

The count hold/gate bit in the Timer Control Register can be used to suspend the timer operation in modes 0, 1, and 2 (in mode 3 it is the trigger input). Suspending the timer causes the same synchronization error that starting the timer does. The range of errors is specified in Table V.

TABLE V. Max	imum Synchron	ization Errors
--------------	---------------	----------------

<b>Clock Selected</b>	Error
External	+ Ext. Clock Period
Crystal	+ 1 Crystal Clock Period
Crystal/4	+ 1 Crystal Clock Period
10.7 kHz	+32 μs
1 kHz	+32 μs
100 Hz	+32 μs
10 Hz	+ 32 μs
1 Hz	+32 μs

#### MODES OF OPERATION


Bits M0 and M1 in the Timer Control Registers are used to specify the modes of operation. The mode selection is described in Table VI.

#### **TABLE VI. Programmable Timer Modes of Operation**

M1	мо	Function	Modes
0	0	Single Pulse Generator	Mode 0
0	1	Rate Generator, Pulse Output	Mode 1
1	0	Square Wave Output	Mode 2
1	1	Retriggerable One Shot	Mode 3

#### MODE 0: SINGLE PULSE GENERATOR

When the timer is in this mode the output will be initially low if the Timer Start/Stop bit is low (stopped). When this mode is initiated the timer output will go high on the next falling edge of the prescaler's input clock, the contents of the



#### Functional Description (Continued)

input data registers are loaded into the timer. The output will stay high until the counter reaches zero. At zero the output is reset. The result is an output pulse whose duration is equal to the input clock period times the count value (N) loaded into the input data register. This is shown in *Figure 8*.

Pulse Width = Clock Period  $\times$  N

An interrupt is generated when the zero count is reached. This can be used for one-time interrupts that are set to occur a certain amount of time in the future. In this mode the Timer Start/Stop bit (TSS) is automatically reset upon zero detection. This removes the need to reset TSS before starting another operation.

The count down operation may be temporarily suspended either under software control by setting the Count Hold/ Gate bit in the timer register high, or in hardware by setting the G0 or G1 pin high.

The above discussion assumes that the MFO output is programmed to be non-inverting outputs (active high). If the polarity of the output waveform is wrong for the application the polarity can be reversed by configuring the Output Mode Register. The drive configuration can also be programmed to be push pull or open drain.

#### MODE 1: RATE GENERATOR

When operating in this mode the timer will operate continuously. Before the timer is started its output is low. When the timer is started the input data register contents are loaded into the counter on the negative clock edge and the output is set high (again assuming the Output Mode Register is programmed active high). The timer will then count down to zero. Once the zero count is reached the output goes low for one clock period of the timer clock. Then on the next clock the counter is reloaded automatically and the countdown repeats itself. The output, shown in *Figure 9*, is a waveform whose pulse width and period is determined by N, the input register value, and the input clock period:

#### Period = (N + 1) (Clock Period) Pulse Width = Clock Period

Again, the output polarity is controllable as in mode 0. If enabled, an interrupt is generated whenever the zero count is reached. This can be used to generate a periodic interrupt.


#### MODE 2: SQUARE WAVE GENERATOR


This mode is also cyclic but in this case a square wave rather than a pulse is generated. The output square wave period is determined by the value loaded into the timer input register. This period and the duty cycle are:

Period = 2(N + 1) (Clock Period) Duty Cycle = 0.5

When the timer is stopped the output will be low, and when the Start/Stop bit is set high the timer's counter will be loaded on the next clock falling transition and the output will be set high.

The output will be toggled after the zero count is detected and the counter will then be reloaded, and the cycle will continue. Thus, every N + 1 counts the output gets toggled, as shown in *Figure 10*. Like the other modes the timer operation can be suspended by setting the count hold/gate bit (CHG) in the Timer Control Register. An interrupt will be generated every falling edge of the timer output, if enabled.





#### FIGURE 10. Timing Waveforms for Timer Mode 2 (MFO Output Programmed Active High)

#### MODE 3: RETRIGGERABLE ONE SHOT

Once the timer Start/Stop bit is set the output stays inactive, and nothing happens until the Count Hold/Gate (CHG) bit is set in the timer control register. When a transition ocurs the one shot output is set active immediately; the counter is loaded with the value in the input register on the next transition of the input clock and the countdown begins. If a retrigger occurs, regardless of the current counter value, the counters will be reloaded with the value in the input register and the counter will be restarted without changing the output state. See *Figure 11*. A trigger count can occur at any time during the count cycle. In this mode the timer will output a single pulse whose width is determined by the value in the input data register (N) and the input clock period.

#### $\textbf{Pulse Width} = \textbf{Clock Period} \times \textbf{N}$

The timer will generate an interrupt only when it reaches a count of zero. This timer mode is useful for continuous "watch dog" timing, line frequency power failure detection, etc.

#### **READING THE TIMERS**

National has discovered that some users may encounter unacceptable error rates for their applications when reading the timers on the fly asynchronously. When doing asynchronous reads of the timers, an error may occur. The error is that a successive read may be larger than the previous read. Experimental results indicate that the typical error rate is approximately one per 29000 under the following conditions:

Timer clock frequency of 5 MHz. Computer: 386/33 MHz PC/AT

Program: Microsoft 'C' 6.0, reading and saving timer contents in a continuous loop. Those users who find the error rate unacceptable may reduce the problem effectively to zero by employing a hardware work-around that synchronizes the writing of the read bit to the timer control register with respect to the decrementing clock. Refer to *Figure 1* in Appendix A, for a suggested hardware work-around.

A software work-around can reduce the errors but not as substantial as a hardware work-around. Software workarounds are based on observations that the read following a bad read appeared to be valid.

This problem concerns statistical probability and is similar to metastability issues. For more information on metastability, refer to 1991 IEEE transactions on Custom Integrated Circuits Conference, paper by T.J. Gabara of AT&T Bell Laboratories, page 29.4.1.

Normally reading the timer data register addresses, 0FH and 10H for Timer 0 and 11H and 12H for Timer 1 will result in reading the input data register which contains the preset value for the timers.


To read the contents of a timer, the  $\mu$ P first sets the timer read bit in the appropriate Timer Control Register high. This will cause the counter's contents to be latched to 2–8 bit output registers, and will enable these registers to be read if the  $\mu$ P reads the timer's input data register addresses. On reading the LSB byte the timer read bit is internally reset and subsequent reads of the timer locations will return the input register values.

#### DETAILED REGISTER DESCRIPTION

There are 5 external address bits: Thus, the host microprocessor has access to 32 locations at one time. An internal switching scheme provides a total of 67 locations.

This complete address space is organized into two pages. Page 0 contains two blocks of control registers, timers, real time clock counters, and special purpose RAM, while page 1 contains general purpose RAM. Using two blocks enables the 9 control registers to be mapped into 5 locations. The only register that does not get switched is the Main Status Register. It contains the page select bit and the register select bit as well as status information.

A memory map is shown in *Figure 2* and register addressing in Table VII. They show the name, address and page locations for the LV8571A.



### Functional Description (Continued) TABLE VII. Register/Counter/RAM


Addressing for LV8571A

A0-4	PS (Note 1)	RS (Note 2)	Descr	iption	
CONT	ROL REC	SISTERS			
00	х	х	Main Status Register		
01	0.	. 0	Timer 0 Control Regis	ter	
02	0	0	Timer 1 Control Regis	ter	
03	0	0	Periodic Flag Registe	r l	
04	0	0	Interrupt Routing Reg	ister	
01	0	1	Real Time Mode Reg	ster	
02	0	1	Output Mode Registe		
03	0	1 1	Interrupt Control Regi		
04	0	1	Interrupt Control Regi	ster 1	
COUN	ITERS (C	LOCK CA	LENDAR)		
05	0	. X .	1/100, 1/10 Seconds	(0-99)	
06	0	x	Seconds	(0-59)	
07	0	х	Minutes	(0-59)	
08	0	х	Hours	(1-12, 0-23)	
09	0	x	Days of		
			Month	(1-28/29/30/31)	
0A	0	X	Months	(1-12)	
OB	0	X	Years	(0-99)	
0C	. 0	X	Julian Date (LSB)	(1-99)	
0D	0	X	Julian Date	(0-3)	
0E	0	X	Day of Week	(1-7)	
TIME	R DATA F	EGISTER	RS		
0F	0	X	Timer 0 LSB		
10	0.	х	Timer 0 MSB		
11	0	х	Timer 1 LSB		
12	0	X	Timer 1 MSB		
TIME	COMPAR	ERAM			
13	0	х	Sec Compare RAM	(0-59)	
14	0	X	Min Compare RAM	(0-59)	
15	0	Х	Hours Compare		
				(1-12, 0-23)	
16	0	х	DOM Compare		
·			RAM	(1-28/29/30/31)	
17	0	X	Months Compare	(1.10)	
10			RAM	(1-12)	
18	0	X	DOW Compare RAM	(1-7)	
	TIME SAVE RAM				
19	0	х	Seconds Time Save F		
1A	0	х	Minutes Time Save R		
1B	0	х	Hours Time Save RA		
1C	0	X	Day of Month Time Sa		
1D	0	X	Months Time Save R/	AM	
1E	0	1	RAM		
1F	0	х	RAM/Test Mode Reg	ister	
01-1F	1	х	2nd Page General Pu	rpose RAM	
				•	

1 PS-Page Select (Bit D7 of Main Status Register)

2 RS-Register Select (Bit D6 of Main Status Register)

#### MAIN STATUS REGISTER




The Main Status Register is always located at address 0 regardless of the register block or the page selected.

**D0:** This read only bit is a general interrupt status bit that is taken directly from the interrupt pins. The bit is a one when an interrupt is pending on either the INTR pin or the MFO pin (when configured as an interrupt). This is unlike D3–D5 which can be set by an internal event but may not cause an interrupt. This bit is reset when the interrupt status bits in the Main Status Register are cleared.

**D1-D5:** These five bits of the Main Status Register are the main interrupt status bits. Any bit may be a one when any of the interrupts are pending. Once an interrupt is asserted the  $\mu$ P will read this register to determine the cause. These interrupt status bits are not reset when read. Except for D1, to reset an interrupt a one is written back to the corresponding bit that is being tested. D1 is reset whenever the PFAIL pin = logic 1. This prevents loss of interrupt status when reading the register in a polled mode. D1, D3-D5 are set regardless of whether these interrupts are masked or not by bits D6 and D7 of Interrupt Control Registers 0 and 1.

**D6 and D7:** These bits are Read/Write bits that control which register block or RAM page is to be selected. Bit D6 controls the register block to be accessed (see memory map). The memory map of the clock is further divided into two memory pages. One page is the registers, clock and timers, and the second page contains 31 bytes of general purpose RAM. The page selection is determined by bit D7.

### Functional Description (Continued) TIMER 0 AND 1 CONTROL REGISTER



These registers control the operation of the timers. Each timer has its own register.

D0: This bit will Start (1) or Stop (0) the timer. When the timer is stopped the timer's prescaler and counter are reset, and the timer will restart from the beginning when started again. In mode 0 on time out the TSS bit is internally reset.


**D1 and D2:** These control the count mode of the timers. See Table VI.

**D3-D5:** These bits control which clock signal is applied to the timer's counter input. Refer to Table IV for details.

**D6:** This is the read bit. If a one is written into this location it will cause the contents of the timer to be latched into a holding register, which can be read by the  $\mu P$  at any time. Reading the least significant byte of the timer will reset the RD bit. The timer read cycle can be aborted by writing RD to zero.

**D7:** The CHG bit has two mode dependent functions. In modes 0 through 2 writing a one to this bit will suspend the timer operation (without resetting the timer prescaler). However, in mode 3 this bit is used to trigger or re-trigger the count sequence as with the gate pins. If retriggering is desired using the CHG bit, it is not necessary to write a zero to this location prior to the re-trigger. The action of further writing a one to this bit will re-trigger the count.

#### PERIODIC FLAG REGISTER



TL/F/11416-18

The Periodic Flag Register has the same bit for bit correspondence as Interrupt Control Register 0 except for D6 and D7. For normal operation (i.e., not a single supply application) this register must be written to on initial power up or after an oscillator fail event. D0–D5 are read only bits, D6 and D7 are read/write. **D0-D5:** These bits are set by the real time rollover events: (Time Change = 1). The bits are reset when the register is read and can be used as selective data change flags.

**D6:** This bit performs a dual function. When this bit is read, a one indicates that an oscillator failure has occurred and the time information may have been lost. Some of the ways an oscillator failure might be caused are: failure of the crystal, shorting OSC IN or OSC OUT to GND or V<sub>CC</sub>, removal of crystal, removal of battery when in the battery backed mode (when a "0" is written to D6), lowering the voltage at the V<sub>BB</sub> pin to a value less than 2.2V when in the battery backed mode. Bit D6 is automatically set to 1 on initial power-up or an oscillator fail event. The oscillator fail flag is reset by writing a one to the clock start/stop bit in the Real Time Mode Register, with the crystal oscillating.


When D6 is written to, it defines whether the TCP is being used in battery backed (normal) or in a single supply mode application. When set to a one this bit configures the TCP for single power supply applications. This bit is automatically set on initial power-up or an oscillator fail event. When set, D6 disables the oscillator reference circuit. The result is that the oscillator is referenced to  $V_{CC}$ . When a zero is written to D6 the oscillator reference is enabled, thus the oscillator is referenced to  $V_{BB}$ . This allows operation in standard battery standby applications.

At initial power on, if the LV8571A is going to be programmed for battery backed mode, the V<sub>BB</sub> pin should be connected to a potential in the range of 2.2V to V<sub>CC</sub>-0.4V.

For single supply mode operation, the V<sub>BB</sub> pin should be connected to GND and the  $\overline{\text{PFAIL}}$  pin connected to V<sub>CC</sub>.

**D7:** Writing a one to this bit enables the test mode register at location 1F (see Table VII). This bit should be forced to zero during initialization for normal operation. If the test mode has been entered, clear the test mode register before leaving test mode. (See separate test mode application note for further details.)

#### INTERRUPT ROUTING REGISTER



**D0-D4:** The lower 5 bits of this register are associated with the main interrupt sources created by this chip. The purpose of this register is to route the interrupts to either the MFO (multi-function pin), or to the main interrupt pin. When any bit is set the associated interrupt signal will be sent to the MFO pin, and when zero it will be sent to the INTR pin.

### Functional Description (Continued)


**D5:** The Delay Enable bit is used when a power fail occurs. If this bit is set, a 480  $\mu$ s delay is generated internally before the  $\mu$ P interface is locked out. This will enable the  $\mu$ P to access the registers for up to 480  $\mu$ s after it receives a power fail interrupt. After a power failure is detected but prior to the 480  $\mu$ s delay timing out, the host  $\mu$ P may force immediate lock out by resetting the Delay Enable bit. Note if this bit is a 0 when power fails then after a delay of 30  $\mu$ s max the  $\mu$ P cannot read the chip.

**D6:** This read only bit is set and reset by the voltage at the  $V_{BB}$  pin. It can be used by the  $\mu$ P to determine whether the battery voltage at the  $V_{BB}$  pin is getting too low. A comparator monitors the battery and when the voltage is lower than 2.1V (typical) this bit is set. The power fail interrupt must be enabled to check for a low battery voltage.

**D7:** Time Save Enable bit controls the loading of real-timeclock data into the Time Save RAM. When a one is written to this bit the Time Save RAM will follow the corresponding clock registers, and when a zero is written to this bit the time in the Time Save RAM is frozen. This eliminates any synchronization problems when reading the clock, thus negating the need to check for a counter rollover during a read cycle.

This bit must be set to a one prior to power failing to enable the Time Save feature. When the power fails this bit is automatically reset and the time is saved in the Time Save RAM.

#### REAL TIME MODE REGISTER



D0-D1: These are the leap year counter bits. These bits are written to set the number of years from the previous leap year. The leap year counter increments on December 31st and it internally enables the February 29th counter state. This method of setting the leap year allows leap year to occur whenever the user wishes to, thus providing flexibility in implementing Japanese leap year function.

LY1	LY0	Leap Year Counter
0	0	Leap Year Current Year
0	1	Leap Year Last Year
1	0	Leap Year 2 Years Ago
1	1	Leap Year 3 Years Ago

**D2:** The count mode for the hours counter can be set to either 24 hour mode or 12 hour mode with AM/PM indicator. A one will place the clock in 12 hour mode.

D3: This bit is the master Start/Stop bit for the clock. When a one is written to this bit the real time counter's prescaler and counter chain are enabled. When this bit is reset to zero the contents of the real time counter is stopped and the prescaler is cleared. When the TCP is initially powered up this bit will be held at a logic 0 until the oscillator starts functioning correctly after which this bit may be modified. If an oscillator fail event occurs, this bit will be reset to logic 0.

D4: This bit controls the operation of the interrupt output in standby mode. If set to a one it allows Alarm, Periodic, and Power Fail interrupts to be functional in standby mode. Timer interrupts will also be functional provided that bit D5 is also set. Note that the MFO and INTR pins are configured as open drain in standby mode.

If bit D4 is set to a zero then interrupt control register 0 and bits D6 and D7 of interrupt control register 1 will be reset when the TCP enters the standby mode (V<sub>BB</sub> > V<sub>CC</sub>). They will have to be re-configured when system (V<sub>CC</sub>) power is restored.

**D5:** This bit controls the operation of the timers in standby mode. If set to a one the timers will continue to function when the TCP is in standby mode. The input pins TCK, G0, G1 are locked out in standby mode, and cannot be used.


Therefore external control of the timers is not possible in standby mode. Note also that MFO and T1 pins are automatically reconfigured open drain during standby.

**D6 and D7:** These two bits select the crystal clock frequency as per the following table:

XT1	хто	Crystal Frequency
0	0	32.768 kHz
0	1	4.194304 MHz
1	0	4.9152 MHz
1	1	32.000 kHz

All bits are Read/Write, and any mode written into this register can be determined by reading the register. On initial power up these bits are random.

#### OUTPUT MODE REGISTER



### Functional Description (Continued)

**D0 and D1:** These bits are available as general purpose RAM.

**D2:** This bit, when set to a one makes the INTR output pin active high, and when set to a zero, it makes this pin active low.

**D3:** This bit controls whether the INTR pin is an open drain or push-pull output. A one indicates push-pull.


D4: This bit, when set to a one makes the MFO output pin active high, and when set to a zero, it makes this pin active low.

**D5:** This bit controls whether the MFO pin is an open drain or push-pull output. A one indicates push-pull.

**D6 and D7:** These bits are used to program the signal appearing at the MFO output, as follows:

D7	D6	MFO Output Signal
0	0	2nd Interrupt
0	1	Timer 0 Waveform
1	X	Buffered Crystal Oscillator

#### INTERRUPT CONTROL REGISTER 0




**D0-D5:** These bits are used to enable one of the selected periodic interrupts by writing a one into the appropriate bit. These interrupts are issued at the rollover of the clock. For example, the minutes interrupt will be issued whenever the minutes counter increments. In all likelihood the interrupt will be enabled asynchronously with the real time change. Therefore, the very first interrupt will occur in less than the periodic time chosen, but after the first interrupt all subsequent interrupts will be spaced correctly. These interrupts are useful when minute, second, real time reading, or task

switching is required. When all six bits are written to a 0 this disables periodic interrupts from the Main Status Register and the interrupt pin.

**D6** and **D7**: These are individual timer enable bits. A one written to these bits enable the timers to generate interrupts to the  $\mu$ P.

#### INTERRUPT CONTROL REGISTER 1



**D0-D5:** Each of these bits are enable bits which will enable a comparison between an individual clock counter and its associated compare RAM. If any bit is a zero then that clock-RAM comparator is set to the "always equal" state and the associated TIME COMPARE RAM byte can be used as general purpose RAM. However, to ensure that an alarm interrupt is not generated at bit D3 of the Main Status Register, all bits must be written to a logic zero.

**D6:** In order to generate an external alarm compare interrupt to the  $\mu$ P from bit D3 of the Main Status Register, this bit must be written to a logic 1. If battery backed mode is selected then this bit is controlled by D4 of the Real Time Mode Register.

**D7:** The MSB of this register is the enable bit for the Power Fail Interrupt. When this bit is set to a one an interrupt will be generated to the  $\mu$ P when PFAIL = 0. If battery backed mode is selected then this bit is controlled by D4 of the Real Time Mode Register.

This bit also enables the low battery detection analog circuitry.

If the user wishes to mask the power fail interrupt, but utilize the analog circuitry, this bit should be enabled, and the Routing Register can be used to route the interrupt to the MFO pin. The MFO pin can then be left open or configured as the Timer 0 or buffered oscillator output.

Control	i anu stat	us negis	ster Auur	COC DIVI	nap			
D7	D6	D5	D4	D3	D2	D1	DO	
Main Status R	legister PS = (	0 RS = 0 A	ADDRESS = 0	он				1. Reset I
R/W	R/W	R/W <sup>1</sup>	R/W <sup>1</sup>	R/W <sup>1</sup>	R/W <sup>1</sup>	R <sup>2</sup>	R <sup>3</sup>	writing
Page	Register	Timer 1	Timer 0	Alarm	Periodic	Power Fail	Interrupt	1 to bit. 2. Set/res
Select	Select	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Status	voltage
								PFAIL
								3. Reset v
								all pene interrup
								are rem
Timer 0 Contr	r <b>ol Register</b> PS	5 = 0 RS = 0	0 Address =	01H				
Count Hold	Timer	Input Clock	Input Clock	Input Clock	Mode	Mode	Timer	
Gate	Read	Select C2	Select C1	Select C0	Select M1	Select M0	Start/Stop	All Bits R
Timor 1 Contr	al Register DC			Idroop - 0011				
	rol Register PS		<u> </u>	ddress = 02H				1
Count Hold	Timer	Input Clock	Input Clock	Input Clock	Mode	Mode	Timer	All Bits R
Gate	Read	Select C2	Select C1	Select C0	Select M1	Select M0	Start/Stop	J
Periodic Flag	Register PS =	0 RS =	= 0 Addr	ess = 03H				
R/W	R/W <sup>4</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	4. Read C
Test	Osc. Fail/	1 ms	10 ms	100 ms	Seconds	10 Second	Minute	Write 0 Backed
Mode	Single Supply	Flag	Flag	Flag	Flag	Flag	Flag	
1			Flag	Flag	Flag	Flag	Flag	Write 1
1			Flag	Flag	Flag	Flag	Flag	Write 1 Supply 5. Reset t
1			Flag	Flag	Flag	Flag	Flag	Write 1 Supply 5. Reset t positive
Mode	Single Supply	Flag	· · · · ·	• .	· .	Flag	Flag	Write 1 Supply 5. Reset t positive
Mode		Flag	· · · · ·	Flag Address = 04 <b>R/W</b>	· .	Flag R/W	Flag R/W	Write 1 Supply 5. Reset t positive
Mode Interrupt Rou R/W	Single Supply ting Register F R <sup>6</sup>	Flag PS = 0 <b>R/W</b>	RS = 0 /	Address = 04 R/W	H R/W	R/W	R/W	Write 1 Supply 5. Reset b positive of read
Mode Interrupt Rou R/W Time Save	Single Supply ting Register F R <sup>6</sup> Low Battery	Flag PS = 0 R/W Power Fail	RS = 0	Address = 04	н			Write 1 Supply 5. Reset b positive of read
Mode Interrupt Rou R/W	Single Supply ting Register F R <sup>6</sup>	Flag PS = 0 <b>R/W</b>	RS = 0 // R/W Timer 1	Address = 04 R/W Timer 0	H R/W Alarm	R/W Periodic	R/W Power Fail	Write 1 Supply 5. Reset b positive of read 6. Set and by V <sub>BB</sub>
Mode Interrupt Rou R/W Time Save Enable	Single Supply ting Register F R <sup>6</sup> Low Battery Flag	Flag PS = 0 <b>R/W</b> Power Fail Delay Enable	RS = 0 R/W Timer 1 Int. Route MFO/INT	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT	H R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route	R/W Power Fail Int. Route	Write 1 Supply 5. Reset b positive of read 6. Set and by V <sub>BB</sub>
Mode Interrupt Rou R/W Time Save Enable Real Time Mo	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A	Address = 04 R/W Timer 0 Int. Route MFO/INT ddress = 01H	H <b>R/W</b> Alarm Int. Route MFO/INT	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT	Write 1 Supply 5. Reset b positive of read 6. Set and by V <sub>BB</sub>
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock	H <b>R/W</b> Alarm Int. Route MFO/INT 12/24 Hr.	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT Leap Year	Write 1         Supply         5. Reset b         positive         of read         6. Set and         by VBB         voltage
Mode Interrupt Rou R/W Time Save Enable Real Time Mo	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A	Address = 04 R/W Timer 0 Int. Route MFO/INT ddress = 01H	H <b>R/W</b> Alarm Int. Route MFO/INT	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT	Write 1         Supply         5. Reset b         positive         of read.         6. Set and         by VBB         voltage
Mode	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal	Flag PS = 0 R/W Power Fail Delay Enable S = 0 Timers EN on Back-Up	RS = 0 $R/W$ Timer 1 Int. Route $MFO/INT$ $S = 1$ Area on Back-Up	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock	H <b>R/W</b> Alarm Int. Route MFO/INT 12/24 Hr.	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT Leap Year	Write 1         Supply         5. Reset b         positive         of read         6. Set and         by VBB         voltage
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XTO Register PS =	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS =	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H	H Alarm Int. Route MFO/INT 12/24 Hr. Mode	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Write 1         Supply         5. Reset b         positive         of read         6. Set and         by VBB         voltage
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0	Flag PS = 0 R/W Power Fail Delay Enable S = 0 Timers EN on Back-Up	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop	H <b>R/W</b> Alarm Int. Route MFO/INT 12/24 Hr.	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT Leap Year	Write 1         Supply         5. Reset b         positive         of read.         6. Set and         by VBB         voltage
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XTO Register PS = MFO as Timer 0	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Write 1         Supply         5. Reset b         positive         of read.         6. Set and         by VBB         voltage
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XTO Register PS = MFO as	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Write 1         Supply         5. Reset b         positive         of read         6. Set and         by VBB         voltage
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal Interrupt Con Timer 1	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD PS = 0 1 ms	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addro MFO Active HI/LO RS = 1 10 ms	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Write 1         Supply         5. Reset t         positive         of read         6. Set and         by V <sub>BB</sub> voltage         All Bits R/         All Bits R/
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal Interrupt Con Timer 1 Interrupt	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XTO Register PS = MFO as Timer 0 Interrupt	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/ $\overline{OD}$ PS = 0 1 ms Interrupt	RS = 0         R/W           Timer 1         Int. Route           Int. Route         MFO/INT           S = 1         Addr           Interrupt EN         on Back-Up           = 1         Addr           MFO         Active HI/LO           RS = 1         10 ms           Interrupt         Interrupt	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 3H Seconds Interrupt	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt	Write 1         Supply         5. Reset I         positive         of read         6. Set and         by V <sub>BB</sub> voltage         All Bits R.         All Bits R.
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal Interrupt Con Timer 1	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD PS = 0 1 ms	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addro MFO Active HI/LO RS = 1 10 ms	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM	Write 1         Supply         5. Reset I         positive         of read         6. Set and         by V <sub>BB</sub> voltage         All Bits R.         All Bits R.
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal Interrupt Con Timer 1 Interrupt Enable	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XTO Register PS = MFO as Timer 0 Interrupt	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO $PP/\overline{OD}$ PS = 0 1 ms Interrupt Enable	RS = 0         R/W           Timer 1         Int. Route           Int. Route         MFO/INT           S = 1         Addr           Interrupt EN         on Back-Up           = 1         Addr           MFO         Active HI/LO           RS = 1         10 ms           Interrupt         Interrupt	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO D3H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt	Write 1         Supply         5. Reset I         positive         of read         6. Set and         by V <sub>BB</sub> voltage         All Bits R.         All Bits R.
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal Interrupt Con Timer 1 Interrupt Enable Interrupt Con	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XTO Register PS MFO as Timer 0 trol Register 0 Interrupt Enable trol Register 1	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/ $\overline{OD}$ PS = 0 1 ms Interrupt Enable PS = 0	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt Enable RS = 1	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt Enable Address = 0	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 3H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt Enable	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt Enable	Write 1         Supply         5. Reset t         positive         of read         6. Set and         by V <sub>BB</sub> voltage         All Bits R/         All Bits R/
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal Interrupt Con Timer 1 Interrupt Enable Interrupt Con Power Fail	Single Supply ting Register F R6 Low Battery Flag de Register PS Crystal Freq. XT0 Register PS MFO as Timer 0 trol Register 0 Timer 0 Interrupt Enable trol Register 1 Alarm	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/ $\overline{OD}$ PS = 0 1 ms Interrupt Enable PS = 0 DOW	RS = 0 $R/W$ Timer 1 Int. Route $MFO/INT$ $S = 1$ Arrow EN $S = 1$ Addre $MFO$ Active HI/LO $RS = 1$ 10 ms Interrupt Enable $RS = 1$ Month	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt Enable Address = 0 DOM	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 33H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt Enable Minute	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt Enable Second	Write 1         Supply         5. Reset t         positive         of read         6. Set and         by VBB         voltage         All Bits R/         All Bits R/         All Bits R/
Mode Interrupt Rou R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Output Mode MFO as Crystal Interrupt Con Timer 1 Interrupt Enable Interrupt Con	Single Supply ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XTO Register PS MFO as Timer 0 trol Register 0 Interrupt Enable trol Register 1	Flag PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/ $\overline{OD}$ PS = 0 1 ms Interrupt Enable PS = 0	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt Enable RS = 1	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt Enable Address = 0	H Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 3H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt Enable	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt Enable	Write 1 Supply 5. Reset b positive of read

# **Application Hints**

Suggested initialization procedure for LV8571A in battery backed applications that use the  ${\sf V}_{\sf BB}$  pin.

- 1. Enter the test mode by writing a 1 to bit D7 in the Periodic Flag Register.
- Write zero to the RAM/TEST mode Register located in page 0, address HEX 1F.
- 3. Leave the test mode by writing a 0 to bit D7 in the Periodic Flag Register. Steps 1, 2, 3 guarantee that if the test mode had been entered during power on (due to random pulses from the system), all test mode conditions are cleared. Most important is that the OSC Fail Disable bit is cleared. Refer to AN-589 for more information on test mode operation.
- 4. After power on (V<sub>CC</sub> and V<sub>BB</sub> powered), select the correct crystal frequency bits (D7, D6 in the Real Time Mode Register) as shown in Table 1.

Frequency	D7	D6
32.768 KHz	0	0
4.194304 MHz	0	1
4.9152 MHz	1	0
32.0 KHz	1	1

5. Enter a software loop that does the following:

Set a 3 second(approx) software counter. The crystal oscillator may take 1 second to start.

5.1 Write a 1 to bit D3 in the Real Time Mode Register (try to start the clock). Make sure the crystal select bits remain the same as in step 1. Under normal operation, this bit can be set only if the oscillator is running. During the software loop, RAM, real time counters, output configuration.

**Typical Application** 

ration, interrupt control and timer functions may be initialized.

6. Test bit D6 in the Periodic Flag Register:

IF a 1, go to 5.1 If this bit remains a 1 after 3 seconds, then abort and check hardware. The crystal may be defective or not installed. There may be a short at OSC IN or OSC OUT to  $V_{CC}$  or GND, or to some impedance that is less than 10 M $\Omega$ .


IF a 0, then the oscillator is running, go to step 7.

7. Write a 0 to bit D6 in the Periodic Flag Register. This action puts the clock chip in the battery backed mode. This mode can be entered only if the OSC fail flag (bit D6 of the Periodic Flag Register) is a 0. Reminder, bit D6 is a dual function bit. When read, D6 returns oscillator status. When written, D6 causes either the Battery Backed Mode, or the Single Supply Mode of operation.

The only method to ensure the chip is in the battery backed mode is to measure the waveform at the OSC OUT pin. If the battery backed mode was selected successfully, then the peak to peak waveform at OSC OUT is referenced to the battery voltage. If not in battery backed mode, the waveform is referenced to V<sub>CC</sub>. The measurement should be made with a high impedance low capacitance probe (10 M $\Omega$ , 10 pF oscilloscope probe or better). Typical peak to peak swings are within 0.6V of V<sub>CC</sub> and ground respectively.


- 8. Write a 1 to bit D7 of Interrupt Control Register 1. This action enables the PFAIL pin and associated circuitry.
- 9. Write a 1 to bit D4 of the Real Time Mode Register. This action ensures that bit D7 of Interrupt Control Register 1 remains a 1 when  $V_{BB} > V_{CC}$  (standby mode).

10. Initialize the rest of the chip as needed.






# **Appendix A**



1-24



1-25

L

# PRELIMINARY



# LV8572A Low Voltage Real Time Clock (RTC)

# **General Description**

The LV8572A is intended for use in microprocessor based systems where information is required for multi-tasking, data logging or general time of day/date information. This device is implemented in low voltage silicon gate microCMOS technology to provide low standby power in battery back-up environments. The circuit's architecture is such that it looks like a contiguous block of memory or I/O ports. The address space is organized as 2 software selectable pages of 32 bytes. This includes the Control Registers, the Clock Counters, the Alarm Compare RAM, and the Time Save RAM. Any of the RAM locations that are not being used for their intended purpose may be used as general purpose CMOS RAM.

Time and date are maintained from 1/100 of a second to year and leap year in a BCD format, 12 or 24 hour modes. Day of week, day of month and day of year counters are provided. Time is controlled by an on-chip crystal oscillator requiring only the addition of the crystal and two capacitors. The choice of crystal frequency is program selectable.

Power failure logic and control functions have been integrated on chip. This logic is used by the RTC to issue a power fail interrupt, and lock out the  $\mu p$  interface. The time power

#### Features

- 3.3V ±10% supply
- Full function real time clock/calendar
  - 12/24 hour mode timekeeping
  - Day of week and day of years counters
  - --- Four selectable oscillator frequencies
  - Parallel resonant oscillator
- Power fail features
  - Internal power supply switch to external battery
  - Power Supply Bus glitch protection
  - Automatic log of time into RAM at power failure
- On-chip interrupt structure
- Periodic, alarm, and power fail interrupts
- Up to 44 bytes of CMOS RAM




FIGURE 1

V8572A



# Absolute Maximum Ratings (Notes 1 & 2)

Specifications for the 883 version of this product are listed separately.

Supply Voltage (V <sub>CC</sub> )	-0.5V to +7.0V
DC Input Voltage (V <sub>IN</sub> )	$-0.5 V$ to $V_{CC}$ $+0.5 V$
DC Output Voltage (V <sub>OUT</sub> )	-0.5V to V <sub>CC</sub> + 0.5V
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.)	260°C

# **Operation Conditions**

	,	Min	Max	Unit
Supply Voltage	e (V <sub>CC</sub> ) (Note 3)	3.0	3.6	٧
Supply Voltage	e (V <sub>BB</sub> ) (Note 3)	2.2	$V_{CC}-0.4$	v
DC Input or Ou (VIN, VOUT)	tput Voltage	0.0	V <sub>CC</sub>	v
Operation Terr	perature (T <sub>A</sub> )	-40	+85	°C
Electr-Static D	ischarge Rating		- 1	kV
Typical Values				
$\theta_{JA} DIP$	Board		619	°C/W
	Socket		67	°C/W
$\theta_{JA}$ PLCC	Board		80	°C/W
	Socket		88	°C/W

# **DC Electrical Characteristics**

 $V_{CC}$  = 3.3V ±10%,  $V_{BB}$  = 2.5V,  $V_{\overline{PFAIL}}$  >  $V_{IH}$ ,  $C_L$  = 100 pF (unless otherwise specified)

Symbol	Parameter	Conditions	Min	Max	Units
VIH	High Level Input Voltage (Note 4)	Any Inputs Except OSC IN, OSC IN with External Clock	2.0 V <sub>BB</sub> -0.2	V <sub>CC</sub> + 0.3	V
VIL	Low Level Input Voltage	All Inputs Except OSC IN OSC IN with External Clock	-0.3 -0.3	0.8 0.2	v v
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT, INTR)	$I_{OUT} = -20 \mu A$ $I_{OUT} = -2.0 \text{mA}$	V <sub>CC</sub> -0,2 2.4		v v
V <sub>OL</sub>	Low Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = 20 \ \mu A$ $I_{OUT} = 2.0 \ m A$		0.2 0.3	v v
I <sub>IN</sub>	Input Current (Except OSC IN)	$V_{IN} = V_{CC} \text{ or } GND$		±0.7	μA
loz	Output TRI-STATE® Current	$V_{OUT} = V_{CC} \text{ or GND}$	· .	±1	μΑ
ILKG	Output High Leakage Current MFO, INTR Pins	V <sub>OUT</sub> = V <sub>CC</sub> or GND Outputs Open Drain		±1	μA
ICC	Quiescent Supply Current (Note 7)	$\begin{array}{l} F_{OSC}=32.768 \text{ kHz} \\ V_{IN}=V_{CC} \text{ or GND} (\text{Note 5}) \\ V_{IN}=V_{CC} \text{ or GND} (\text{Note 6}) \\ V_{IN}=V_{IH} \text{ or } V_{IL} (\text{Note 6}) \end{array}$		220 700 5	μΑ μΑ mA
		F <sub>OSC</sub> = 4.194304 MHz or 4.9152 MHz V <sub>IN</sub> = V <sub>CC</sub> or GND (Note 6) V <sub>IN</sub> = V <sub>IH</sub> or V <sub>IL</sub> (Note 6)		4	mA mA
Icc	Quiescent Supply Current (Single Supply Mode) (Note 7)	$\begin{array}{l} V_{BB} = GND \\ V_{IN} = V_{CC} \mbox{ or } GND \\ F_{OSC} = 32.768 \mbox{ kHz} \\ F_{OSC} = 4.9152 \mbox{ MHz} \mbox{ or} \\ 4.194304 \mbox{ MHz} \end{array}$		30 3	μA mA
I <sub>BB</sub>	Standby Mode Battery Supply Current (Note 7)	$\begin{array}{l} V_{CC} = GND\\ OSC OUT = open circuit,\\ other pins = GND\\ F_{OSC} = 32.768  \text{kHz}\mu\text{A}\\ F_{OSC} = 4.9152  \text{MHz}  \text{or}\\ 4.194304  \text{MHz} \end{array}$		8 400	μΑ μΑ
I <sub>BLK</sub>	Battery Leakage	$\begin{array}{l} 2.2V \leq V_{BB} \leq 2.6V\\ \text{other pins at GND}\\ V_{CC} = \text{GND}, V_{BB} = 2.6V\\ V_{CC} = 3.6V, V_{BB} = 2.2V \end{array}$	-0.8	0.8	μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: For F<sub>OSC</sub> = 4.194304 or 4.9152 MHz, V<sub>BB</sub> minimum = 2.8V. In battery backed mode, V<sub>BB</sub>  $\leq$  V<sub>CC</sub> -0.4V.

Single Supply Mode: Data retention voltage is 2.2V min. In single Supply Mode (Power connected to V<sub>CC</sub> pin) 3.0V  $\leq$  V<sub>CC</sub>  $\leq$  3.6.

Note 4: This parameter ( $V_{IH}$ ) is not tested on all pins at the same time.

Note 4. This parameter (VIH) is not tested on an pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

1-27

# **AC Electrical Characteristics**

 $V_{CC}$  = 3.3V ±10%,  $V_{BB}$  = 2.5V,  $V_{PFAIL} > V_{IH}$ ,  $C_L$  = 100 pF (unless otherwise specified)

Symbol	Parameter	Min	Max	Units
AD TIMING	· · · · · · · · · · · · · · · · · · ·			
t <sub>AR</sub>	Address Valid Prior to Read Strobe	10		ns
t <sub>RW</sub>	Read Strobe Width (Note 8)	100		ns
t <sub>CD</sub>	Chip Select to Data Valid Time		100	ns
tRAH	Address Hold after Read (Note 9)	2		ns
t <sub>RD</sub>	Read Strobe to Valid Data		90	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		80	ns
t <sub>RCH</sub>	Chip Select Hold after Read Strobe (Note 9)	0		ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses	70		ns
RITE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	10		ns
twan	Address Hold after Write Strobe (Note 9)	2		ns
t <sub>CW</sub>	Chip Select to End of Write Strobe	110		ns
tww	Write Strobe Width (Note 10)	100		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	70		ns
twDH	Data Hold after Write Strobe (Note 9)	2		ns
twch	Chip Select Hold after Write Strobe (Note 9)	0		ns
ITERRUPT TIMIN	NG			
tROLL	Clock Rollover to INTR Out is Typically 20 $\mu$ s			

Note 8: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when both signals are low and terminates when either signal returns high.

Note 9: Hold time is guaranteed by design but not production tested. This limit is not used to calculate outgoing quality levels.

Note 10: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

# **AC Test Conditions**

Input Pulse Levels	GND to 3.0V
Input Rise and Fall Times	6 ns (10%–90%)
Input and Output	1.3V
Reference Levels	1.5 V
TRI-STATE Reference	Active High + 0.5V
Levels (Note 12)	Active Low -0.5V

Note 11: CL = 100 pF, includes jig and scope capacitance.

Note 12: S1 =  $V_{CC}$  for active low to high impedance measurements.


- S1 = GND for active high to high impedance measurements.
- S1 = open for all other timing measurements.


# **Capacitance** ( $T_A = 25^{\circ}C$ , f = 1 MHz)

Symbol	Parameter (Note 13)	Тур	Units
CIN	Input Capacitance	5	pF
COUT	Output Capacitance	7	рF

Note 13: This parameter is not 100% tested.

Note 14: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.





### General Description (Continued)

The LV8572A's interrupt structure provides three basic types of interrupts: Periodic, Alarm/Compare, and Power Fail. Interrupt mask and status registers enable the masking and easy determination of each interrupt.

# **Pin Description**

 $\overline{\text{CS}}$ ,  $\overline{\text{RD}}$ ,  $\overline{\text{WR}}$  (Inputs): These pins interface to  $\mu$ P control lines. The  $\overline{\text{CS}}$  pin is an active low enable for the read and write operations. Read and Write pins are also active low and enable reading or writing to the RTC. All three pins are disabled when power failure is detected. However, if a read or write is in progress at this time, it will be allowed to complete its cycle.

A0-A4 (Inputs): These 5 pins are for register selection. They individually control which location is to be accessed. These inputs are disabled when power failure is detected.

**OSC IN (Input): OSC OUT (Output):** These two pins are used to connect the crystal to the internal parallel resonant oscillator. The oscillator is always running when power is applied to V<sub>BB</sub> and V<sub>CC</sub>, and the correct crystal select bits in the Real Time Mode Register have been set.

**MFO (Output):** The multi-function output can be used as a second interrupt output for interrupting the  $\mu$ P. This pin can also provide an output for the oscillator. The MFO output is configured as push-pull, active high for normal or single power supply operation and as an open drain during standby mode (V<sub>BB</sub> > V<sub>CC</sub>). If in battery backed mode and a pullup resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>.

**INTR (Output):** The interrupt output is used to interrupt the processor when a timing event or power fail has occurred and the respective interrupt has been enabled. The **INTR** output is permanently configured active low, open drain. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>.

**D0-D7 (Input/Output):** These 8 bidirectional pins connect to the host  $\mu$ P's data bus and are used to read from and write to the RTC. When the **PFAIL** pin goes low and a write is not in progress, these pins are at TRI-STATE.


**PFAIL** (Input): In battery backed mode, this pin can have a digital signal applied to it via some external power detection logic. When  $\overrightarrow{\text{PFAIL}} = \text{logic 0}$  the RTC goes into a lockout mode, in a minimum of 30  $\mu$ s or a maximum of 63  $\mu$ s unless. lockout delay is programmed. In the single power supply mode, this pin is not useable as an input and should be tied to V<sub>CC</sub>. Refer to section on Power Fail Functional Description.

 $V_{BB}$  (Battery Power Pin): This pin is connected to a back-up power supply. This power supply is switched to the internal circuitry when the  $V_{CC}$  becomes lower than  $V_{BB}$ . Utilizing this pin eliminates the need for external logic to switch in and out the back-up power supply. If this feature is not to be used then this pin must be tied to ground, the RTC programmed for single power supply only, and power applied to the  $V_{CC}$  pin.

Vcc: This is the main system power pin.

GND: This is the common ground power pin for both  $V_{BB}$  and  $V_{CC}$ 

# **Connection Diagrams**



## **Functional Description**

The LV8572A contains a fast access real time clock, interrupt control logic, power fail detect logic, and CMOS RAM. All functions of the RTC are controlled by a set of seven registers. A simplified block diagram that shows the major functional blocks is given in *Figure 1*.

The blocks are described in the following sections:

- 1. Real Time Clock
- 2. Oscillator Prescaler
- 3. Interrupt Logic
- 4. Power Failure Logic
- 5. Additional Supply Management

The memory map of the RTC is shown in the memory addressing table. The memory map consists of two 31 byte pages with a main status register that is common to both pages. A control bit in the Main Status Register is used to select either page. *Figure 2* shows the basic concept. Page 0 contains all the clock timer functions, while page 1 has scratch pad RAM. The control registers are split into two separate blocks to allow page 1 to be used entirely as scratch pad RAM. Again a control bit in the Main Status Register is used to select either control register block. LV8572A

1F	RAM/TEST Reg	ister		Page Select = 1
1E	RAM		1F	RAM
1D	Months Time Sav	e RAM	1E	RAM
1C	Day of Month Time	Save RAM	1D	RAM
1B	Hours Time Save	e RAM	10	RAM
1A	Minutes Time Sav	ve RAM	1B	RAM
19	Seconds Time Sav	Ve RAM	1A	RAM
18	Day of Week Compa	are RAM	19	RAM
17	Months Compare	RAM	18	RAM
16	Day of Month Comp	are RAM	17	RAM
15	Hours Compare	RAM	16	RAM
14	Minutes Compare	e RAM	15	RAM
13	Seconds Compare	e RAM	14	RAM
12	N/A		. 13	RAM
11	N/A		12	RAM
10	N/A		11	RAM
OF	N/A		10	RAM
OE	Day of Week Clock	Counter	OF	RAM
OD	100's Julian Clock	Counter	OE	RAM
oc	Units Julian Clock	Counter	OD	RAM
OB	Years Clock Cou	unter	oc	RAM
04	Months Clock Co	unter	ОВ	RAM
09	Day of Month Clock	Counter	0A	RAM
08	Hours Clock Co	unter	09	RAM
07	Minutes Clock Co	ounter	08	RAM
06	Seconds Clock Co	ounter	07	RAM
05	1/100 Second Cou	nter	06	RAM
			05	RAM
			04	RAM
gister Selec	t = 0 🧹 .	💊 Register Select =	1 03	RAM
ne Save Con	trol Register 04	Interrupt Control Registe	or 1 02	RAM
Periodic Flag	Register 03	Interrupt Control Registe	r 0 01	RAM
N/A	02	Output Mode Register		
N/A	01	Real Time Mode Regist	er 🖌	
		00 Main Status Rev	nister	



1-31

TL/F/11417-7

### Functional Description (Continued) INITIAL POWER-ON of BOTH VBB and VCC

 $V_{BB}$  and  $V_{CC}$  may be applied in any sequence. In order for the power fail circuitry to function correctly, whenever power is off, the  $V_{CC}$  pin must see a path to ground through a maximum of 1 MΩ. The user should be aware that the control registers will contain random data. The first task to be carried out in an initialization routine is to start the oscillator by writing to the crystal select bits in the Real Time Mode Register. If the LV8572A is configured for single supply mode, an extra 50  $\mu$ A may be consumed until the crystal select bits are programmed. The user should also ensure that the RTC is not in test mode (see register descriptions).

#### **REAL TIME CLOCK FUNCTIONAL DESCRIPTION**

As shown in *Figure 2*, the clock has 10 bytes of counters, which count from 1/100 of a second to years. Each counter counts in BCD and is synchronously clocked. The count sequence of the individual byte counters within the clock is shown later in Table VII. Note that the day of week, day of month, day of year, and month counters all roll over to 1. The hours counter in 12 hour mode rolls over to 1 and the AM/PM bit toggles when the hours rolls over to 12 (AM = 0, PM = 1). The AM/PM bit is bit D7 in the hours counter.

All other counters roll over to 0. Also note that the day of year counter is 12 bits long and occupies two addresses. Upon initial application of power the counters will contain random information.

#### **READING THE CLOCK: VALIDATED READ**

Since clocking of the counter occurs asynchronously to reading of the counter, it is possible to read the counter while it is being incremented (rollover). This may result in an incorrect time reading. Thus to ensure a correct reading of the entire contents of the clock (or that part of interest), it must be read without a clock rollover occurring. In general this can be done by checking a rollover bit. On this chip the periodic interrupt status bits can serve this function. The following program steps can be used to accomplish this.

- 1. Initialize program for reading clock.
- 2. Dummy read of periodic status bit to clear it.
- 3. Read counter bytes and store.
- 4. Read rollover bit, and test it.
- 5. If rollover occured go to 3.
- 6. If no rollover, done.

To detect the rollover, individual periodic status bits can be polled. The periodic bit chosen should be equal to the highest frequency counter register to be read. That is if only SECONDS through HOURS counters are read, then the SECONDS periodic bit should be used.

#### **READING THE CLOCK: INTERRUPT DRIVEN**

Enabling the periodic interrupt mask bits cause interrupts just as the clock rolls over. Enabling the desired update rate and providing an interrupt service routine that executes in less than 10 ms enables clock reading without checking for a rollover.

#### **READING THE CLOCK: LATCHED READ**

Another method to read the clock that does not require checking the rollover bit is to write a one into the Time

Save Enable bit (D7) of the Time Save Control Register, and then to write a zero. Writing a one into this bit will enable the clock contents to be duplicated in the Time Save RAM. Changing the bit from a one to a zero will freeze and store the contents of the clock in Time Save RAM. The time then can be read without concern for clock rollover, since internal logic takes care of synchronization of the clock. Because only the bits used by the clock counters will be latched, the Time Save RAM should be cleared prior to use to ensure that random data stored in the unused bits do not confuse the host microprocessor. This bit can also provide time save at power failure, see the Additional Supply Management Functions section. With the Time Save Enable bit at a logical 0, the Time Save RAM may be used as RAM if the latched read function is not necessary.


# INITIALIZING AND WRITING TO THE CALENDAR-CLOCK

Upon initial application of power to the RTC or when making time corrections, the time must be written into the clock. To correctly write the time to the counters, the clock would normally be stopped by writing the Start/Stop bit in the Real Time Mode Register to a zero. This stops the clock from counting and disables the carry circuitry. When initializing the clock's Real Time Mode Register, it is recommended that first the various mode bits be written while maintaining the Start/Stop bit reset, and then writing to the register a second time with the Start/Stop bit set.

The above method is useful when the entire clock is being corrected. If one location is being updated the clock need not be stopped since this will reset the prescaler, and time will be lost. An ideal example of this is correcting the hours for daylight savings time. To write to the clock "on the fly" the best method is to wait for the 1/100 of a second periodic interrupt. Then wait an additional 16  $\mu$ s, and then write the data to the clock.

# PRESCALER/OSCILLATOR FUNCTIONAL DESCRIPTION

Feeding the counter chain is a programmable prescaler which divides the crystal oscillator frequency to 32 kHz and further to 100 Hz for the counter chain (see *Figure 3*). The crystal frequency that can be selected are: 32 kHz, 32.768 kHz, 4.9152 MHz, and 4.194304 MHz.



The oscillator is programmed via the Real Time Mode Register to operate at various frequencies. The crystal oscillator is designed to offer optimum performance at each frequency. Thus, at 32.768 kHz the oscillator is configured as a low frequency and low power oscillator. At the higher frequencies the oscillator inverter is reconfigured. In addition to the inverter, the oscillator feedback bias resistor is included on chip, as shown in *Figure 4*. The oscillator input may be driven from an external source if desired. Refer to test mode application note for details. The oscillator stability is enhanced through the use of an on chip regulated power supply.

The typical range of trimmer capacitor (as shown in Oscillator Circuit Diagram *Figure 4*, and in the typical application) at the oscillator input pin is suggested only to allow accurate tuning of the oscillator. This range is based on a typical printed circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases, the **load capacitance** specified by the crystal manufacturer (nominal value 11 pF for the 32.768 crystal) is what determines proper oscillation. This load capcitance is the series combination of capacitance on each side of the crystal (with respect to ground).




FIGURE 4. Oscillator Circuit Diagram

XTAL	C.	Ct	R <sub>OUT</sub> (Switched Internally)
32/32.768 kHz	47 pF	2 pF-22 pF	150 kΩ to 350 kΩ
4.194304 MHz	68 pF	0 pF-80 pF	500Ω to 900Ω
4.9152 MHz	68 pF	29 pF-49 pF	500Ω to 900Ω

#### INTERRUPT LOGIC FUNCTIONAL DESCRIPTION

The RTC has the ability to coordinate processor timing activities. To enhance this, an interrupt structure has been implemented which enables several types of events to cause interrupts. Interrupts are controlled via two Control Registers in block 1 and two Status Registers in block 0. (See Register Description for notes on paging and also *Figure 5* and Table I.)

The interrupts are enabled by writing a one to the appropriate bits in Interrupt Control Register 0 and/or 1.

TABLE I. Registers that are Applicable to Interrupt Control

rippineasie te interrupt eennet						
Register Name	Register Select	Page Select	Address			
Main Status Register	X	х	оон			
Periodic Flag Register	0	0	03H			
Interrupt Control Register 0	1	o	03H			
Interrupt Control Register 1	1	o	04H			
Output Mode Register	5 <b>1</b> - 5	0	02H			

The Interrupt Status Flag D0, in the Main Status Register, indicates the state of INTR and MFO outputs. It is set when either output becomes active and is cleared when all RTC interrupts have been cleared and no further interrupts are pending (i.e., both INTR and MFO are returned to their inactive state). This flag enables the RTC to be rapidly polled by the  $\mu$ P to determine the source of an interrupt in a wired—OR interrupt system. (The Interrupt Status Flag provides a true reflection of all conditions routed to the external pins.)

Status for the interrupts are provided by the Main Status Register and the Periodic Flag Register. Bits D1–D5 of the Main Status Register are the main interrupt bits.

These register bits will be set when their associated timing events occur. Enabled Alarm comparisons that occur will set its Main Status Register bit to a one. However, an external interrupt will only be generated if the Alarm interrupt enable bit is set (see *Figure 5*).

Disabling the periodic interrupts will mask the Main Status Register periodic bit, but not the Periodic Flag Register bits. The Power Fail Interrupt bit is set when the interrupt is enabled and a power fail event has occurred, and is not reset until the power is restored. If all interrupt enable bits are 0 no interrupt will be asserted. However, status still can be read from the Main Status Register in a polled fashion (see *Figure 5*).

To clear a flag in bits D2 and D3 of the Main Status Register a 1 must be written back into the bit location that is to be cleared. For the Periodic Flag Register reading the status will reset all the periodic flags.

Interrupts Fall Into Three Categories:

- 1. The Alarm Compare Interrupt: Issued when the value in the time compared RAM equals the counter.
- The Periodic Interrupts: These are issued at every increment of the specific clock counter signal. Thus, an interrupt is issued every minute, second, etc. Each of these interrupts occurs at the roll-over of the specific counter.
- 3. The Power Fail Interrupt: Issued upon recognition of a power fail condition by the internal sensing logic. The power failed condition is determined by the signal on the PFAIL pin. The internal power fail signal is gated with the chip select signal to ensure that the power fail interrupt does not lock the chip out during a read or write.

#### ALARM COMPARE INTERRUPT DESCRIPTON

The alarm/time comparison interrupt is a special interrupt similar to an alarm clock wake up buzzer. This interrupt is generated when the clock time is equal to a value programmed into the alarm compare registers. Up to six bytes can be enabled to perform alarm time comparisons on the counter chain. These six bytes, or some subset thereof, would be loaded with the future time at which the interrupt will occur. Next, the appropriate bits in the Interrupt Control Register 1 are enabled or disabled (refer to detailed description of Interrupt Control Register 1). The RTC then compares these bytes with the clock time. When all the enabled compare registers equal the clock time an alarm interrupt is issued, but only if the alarm compare interrupt is enabled can the interrupt be generated externally. Each alarm compare bit in the Control Register will enable a specific byte for comparison to the clock. Disabling a compare byte is the same as setting its associated counter comparator to an "always equal" state. For example, to generate an interrupt at 3:15 AM of every day, load the hours compare with 0 3 (BCD), the minutes compare with 1 5 (BCD) and the faster counters with 0 0 (BCD), and then disable all other compare registers. So every day when the time rolls over from 3:14:59.99, an interrupt is issued. This bit may be reset by writing a one to bit D3 in the Main Status Register at any time after the alarm has been generated.

If time comparison for an individual byte counter is disabled, that corresponding RAM location can then be used as general purpose storage.

#### PERIODIC INTERRUPTS DESCRIPTION

The Periodic Flag Register contains six flags which are set by real-time generated "ticks" at various time intervals, see *Figure 5.* These flags constantly sense the periodic signals and may be used whether or not interrupts are enabled. These flags are cleared by any read or write operation performed on this register.

To generate periodic interrupts at the desired rate, the associated Periodic Interrupt Enable bit in Interrupt Control Register 0 must be set. Any combination of periodic interrupts may be enabled to operate simultaneously. Enabled periodic interrupts will now affect the Periodic Interrupt Flag in the Main Status Register.

When a periodic event occurs, the Periodic Interrupt Flag in the Main Status Register is set, causing an interrupt to be generated. The  $\mu$ P clears both flag and interrupt by writing a "1" to the Periodic Interrupt Flag. The individual flags in the periodic Interrupt Flag Register do not require clearing to cancel the interrupt.

If all periodic interrupts are disabled and a periodic interrupt is left pending (i.e., the Periodic Interrupt Flag is still set), the Periodic Interrupt Flag will still be required to be cleared to cancel the pending interrupt.

#### POWER FAIL INTERRUPTS DESCRIPTION

The Power Fail Status Flag in the Main Status Register monitors the state of the internal power fail signal. This flag may be interrogated by the  $\mu$ P, but it cannot be cleared; it is cleared automatically by the RTC when system power is restored. To generate an interrupt when the power fails, the Power Fail Interrupt Enable bit in Interrupt Control Register 1 is set. Although this interrupt may not be cleared, it may be masked by clearing the Power Fail Interrupt Enable bit.

# POWER FAILURE CIRCUITRY FUNCTIONAL DESCRIPTION

Since the clock must be operated from a battery when the main system supply has been turned off, the LV8572A provides circuitry to simplify design in battery backed systems. This switches over to the back up supply, and isolates itself from the host system. *Figure 6* shows a simplified block diagram of this circuitry, which consists of three major sections; 1) power loss logic: 2) battery switch over logic: and 3) isolation logic.

Detection of power loss occurs when  $\overrightarrow{PFAIL}$  is low. Debounce logic provides a 30  $\mu$ s-63  $\mu$ s debounce time, which will prevent noise on the  $\overrightarrow{PFAIL}$  pin from being interpreted as a system failure. After 30  $\mu$ s-63  $\mu$ s the debounce logic times out and a signal is generated indicating that system power is marginal and is failing. The Power Fail Interrupt will then be generated.


Functional Description (Continued) Interrupt Control Registers Main Status Interrrupt Control Register Register Output Mode Register Control **Buffered Oscillator** Real 0-Bit Time eriodic Periodic inter-Pulse rupt 🖇 Signals (also to Enables Periodic MFO Periodic Status Signal MUX MFO Output Bit 🕅 Flags) Output Buffer Alarm Alarm Interrupt Status Interrupt Mode Alarm Bit 🖇 Enable Alarm Selected Compare Compare Enables Signals Power Fail Power 🔅 Fail 🔅 Interrupt Status Bit 🖇 Enable 🖇 Power Fail Detect INTR Output Interrupt Status Output Buffer Bit 🛛 TL/F/11417-10 FIGURE 5. Interrupt Control Logic Overview

A2728VJ

-----

1

÷.



TL/F/11417-11

FIGURE 6. System-Battery Switchover (Upper Left), Power Fail and Lock-Out Circuits (Lower Right)

If chip select is low when a power failure is detected, a safety circuit will ensure that if a read or write is held active continuously for greater than 30  $\mu$ s after the power fail signal is asserted, the lock-out will be forced. If a lock-out delay is enabled, the LV8572A will remain active for 480  $\mu$ s after power fail is detected. This will enable the  $\mu$ P to perform last minute bookkeeping before total system collapse. When the host CPU is finished accessing the RTC it may force the bus lock-out before 480  $\mu$ s has elapsed by resetting the delay enable bit.

The battery switch over circuitry is completely independent of the  $\overline{\text{PFAIL}}$  pin. A separate circuit compares  $V_{CC}$  to the  $V_{BB}$  voltage. As the main supply fails, the RTC will continue to operate from the  $V_{CC}$  pin until  $V_{CC}$  falls below the  $V_{BB}$  voltage. At this time, the battery supply is switched in,  $V_{CC}$  is disconnected, and the device is now in the standby mode. If indeterminate operation of the battery switch over circuit is to be avoided, then the voltage at the  $V_{CC}$  pin must not be allowed to equal the voltage at the  $V_{BB}$  pin.

After the generation of a lock-out signal, and eventual switch in of the battery supply, the pins of the RTC will be configured as shown in Table II. Outputs that have a pull-up

resistor should be connected to a voltage no greater than  $V_{\text{BB}}$ 

TABLE II	. Pin Isola	tion during	a Power	Failure
----------	-------------	-------------	---------	---------

Pin	PFAIL = Logic 0	Standby Mode V <sub>BB</sub> > V <sub>CC</sub>
CS, RD, WR	Locked Out	Locked Out
A0-A4	Locked Out	Locked Out
D0-D7	Locked Out	Locked Out
Oscillator	Not Isolated	Not Isolated
PFAIL	Not Isolated	Not Isolated
INTR, MFO	Not Isolated	Open Drain

The Interrupt Power Fail Operation bit in the Real-Time Mode Register determine whether or not the interrupts will continue to function after a power fail event.

As power returns to the system, the battery switch over circuit will switch back to V<sub>CC</sub> power as soon as it becomes greater than the battery voltage. The chip will remain in the locked out state as long as  $\overrightarrow{PFAIL} = 0$ . When  $\overrightarrow{PFAIL} = 1$ 

the chip is unlocked, but only after another 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max debounce time. The system designer must ensure that his system is stable when power has returned.

The power fail circuitry contains active linear circuitry that draws supply current from V<sub>CC</sub>. In some cases this may be undesirable, so this circuit can be disabled by masking the power fail interrupt. The power fail input can perform all lock-out functions previously mentioned, except that no external interrupt will be issued. Note that the linear power fail circuitry is switched off automatically when using V<sub>BB</sub> in standby mode.

# LOW BATTERY, INITIAL POWER ON DETECT, AND POWER FAIL TIME SAVE

There are three other functions provided on the LV8572A to ease power supply control. These are an initial Power On detect circuit, which also can be used as a time keeping failure detect, a low battery detect circuit, and a time save on power failure.

On initial power up the Oscillator Fail Flag will be set to a one and the real time clock start bit reset to a zero. This indicates that an oscillator fail event has occurred, and time keeping has failed.

The Oscillator Fail flag will not be reset until the real-time clock is started. This allows the system to discriminate between an initial power-up and recovery from a power failure. If the battery backed mode is selected, then bit D6 of the Periodic Flag Register must be written low. This will not affect the contents of the Oscillator Fail Flag.

Another status bit is the low battery detect. This bit is set only when the clock is operating under the  $V_{CC}$  pin, and when the battery voltage is determined to be less than 2.1V (typical). When the power fail interrupt enable bit is low, it disables the power fail circuit and will also shut off the low battery voltage detection circuit as well.

To relieve CPU overhead for saving time upon power failure, the Time Save Enable bit is provided to do this automatically. (See also Reading the Clock: Latched Read.) The Time Save Enable bit, when set, causes the Time Save RAM to follow the contents of the clock. This bit can be reset by software, but if set before a power failure occurs, it will automatically be reset when the clock switches to the battery supply (not when a power failure is detected by the PFAIL pin). Thus, writing a one to the Time Save bit enables both a software write or power fail write.

#### SINGLE POWER SUPPLY APPLICATIONS

The LV8572A can be used in a single power supply application. To achieve this, the V<sub>BB</sub> pin must be connected to ground, and the power connected to V<sub>CC</sub> and PFAIL pins. The Oscillator Failed/Single Supply bit in the Periodic Flag Register should be set to a logic 1, which will disable the oscillator battery reference circuit. The power fail interrupt should also be disabled. This will turn off the linear power fail detection circuits, and will eliminate any quiescent power drawn through these circuits. Until the crystal select bits are initialized, the LV8572A may consume about 50  $\mu$ A due to arbitrary oscillator selection at power on.

(This extra 50  $\mu$ A is not consumed if the battery backed mode is selected).

#### DETAILED REGISTER DESCRIPTION

There are 5 external address bits: Thus, the host microprocessor has access to 28 locations at one time. An internal switching scheme provides a total of 61 locations. This complete address space is organized into two pages. Page 0 contains two blocks of control registers, timers, real time clock counters, and special purpose RAM, while page 1 contains general purpose RAM. Using two blocks enables the 9 control registers to be mapped into 5 locations. The only register that does not get switched is the Main Status Register. It contains the page select bit and the register select bit as well as status information.


A memory map is shown in *Figure 2* and register addressing in Table III. They show the name, address and page locations for the LV8572A.

TABLE III. Register/Counter/RAM Addressing for LV8572A

A0-4	PS (Note 1)	RS (Note 2)	Descr	iption		
CONT	ROL REG	GISTERS				
00	х	Х	Main Status Register			
03	0	0	Periodic Flag Registe	r		
04	0	0	Time Save Control Re			
01	0	1	Real Time Mode Reg	ister		
02	0	1	Output Mode Registe			
03	0	1	Interrupt Control Regi			
04	0	1	Interrupt Control Regi	ster 1		
COUN	ITERS (C	LOCK CA	LENDAR)			
05	0	X	1/100, 1/10 Seconds	(0-99)		
06	0	X	Seconds	(0–59)		
07	0	X	Minutes	(0-59)		
08	0	X	Hours	(1–12, 0–23)		
09	0	X	Days of	· · ·		
	-		Month	(1-28/29/30/31)		
OA	0	X	Months	(1–12)		
0B	0	X	Years	(0-99)		
0C	0	X	Julian Date (LSB)	(1-99)		
0D	0	х	Julian Date	(0-3)		
0E	0	Х	Day of Week	(1–7)		
TIME	COMPAR	ERAM				
13	0	х	Sec Compare RAM	(0-59)		
14	0	Х	Min Compare RAM	(0-59)		
15	0	Х	Hours Compare			
			RAM	(1–12, 0–23)		
16	0	х	DOM Compare			
			RAM	(1-28/29/30/31)		
17	0	x	Months Compare	(1.10)		
1		v	RAM	(1-12)		
18	0	X	DOW Compare RAM	(1-7)		
	SAVE RA			:		
19	0	X	Seconds Time Save F			
1A	0	X	Minutes Time Save RAM			
1B	0	X	Hours Time Save RA			
10	0	X	Day of Month Time Sa			
1D	0	X	Months Time Save R/	AM.		
1E	0	1	RAM			
1F	0	X	RAM/Test Mode Reg	ister		
01–1F	1	Х	2nd Page General Pu	rpose RAM		

1 PS—Page Select (Bit D7 of Main Status Register) 2 RS—Register Select (Bit D6 of Main Status Register)

#### MAIN STATUS REGISTER



The Main Status Register is always located at address 0 regardless of the register block or the page selected.


**D0:** This read only bit is a general interrupt status bit that is taken directly from the interrupt pins. The bit is a one when an interrupt is pending on either the INTR pin or the MFO pin (when configured as an interrupt). This is unlike D3 which can be set by an internal event but may not cause an interrupt. This bit is reset when the interrupt status bits in the Main Status Register are cleared.

**D1-D3:** These three bits of the Main Status Register are the main interrupt status bits. Any bit may be a one when any of the interrupts are pending. Once an interrupt is asserted the  $\mu$ P will read this register to determine the cause. These interrupt status bits are not reset when read. Except for D1, to reset an interrupt a one is written back to the corresponding bit that is being tested. D1 is reset whenever the PFAIL pin = logic 1. This prevents loss of interrupt status when reading the register in a polled mode. D1 and D3 are set regardless of whether these interrupts are masked or not by bits D6 and D7 of Interrupt Control Registers 0 and 1.

#### D4-D5: General purpose RAM bits.

**D6 and D7:** These bits are Read/Write bits that control which register block or RAM page is to be selected. Bit D6 controls the register block to be accessed (see memory map). The memory map of the clock is further divided into two memory pages. One page is the registers, clock and timers, and the second page contains 31 bytes of general purpose RAM. The page selection is determined by bit D7.

#### PERIODIC FLAG REGISTER



The Periodic Flag Register has the same bit for bit correspondence as Interrupt Control Register 0 except for D6 and D7. For normal operation (i.e., not a single supply application) this register must be written to on initial power up or after an oscillator fail event. D0–D5 are read only bits, D6 and D7 are read/write.

**D0-D5:** These bits are set by the real time rollover events: (Time Change = 1). The bits are reset when the register is read and can be used as selective data change flags.

**D6:** This bit performs a dual function. When this bit is read, a one indicates that an oscillator failure has occurred and the time information may have been lost. Some of the ways an oscillator failure might be caused are: failure of the crystal, shorting OSC IN or OSC OUT to GND or V<sub>CC</sub>, removal of crystal, removal of battery when in the battery backed mode (when a "0" is written to D6), lowering the voltage at the V<sub>BB</sub> pin to a value less than 2.2V when in the battery backed mode. Bit D6 is automatically set to 1 on initial power-up or an oscillator fail event. The oscillator fail flag is reset by writing a one to the clock start/stop bit in the Real Time Mode Register, with the crystal oscillating.


When D6 is written to, it defines whether the TCP is being used in battery backed (normal) or in a single supply mode application. When set to a one this bit configures the TCP for single power supply applications. This bit is automatically set on initial power-up or an oscillator fail event. When set, D6 disables the oscillator reference circuit. The result is that the oscillator is referenced to  $V_{CC}$ . When a zero is written to D6 the oscillator reference is enabled, thus the oscillator is referenced to  $V_{BB}$ . This allows operation in standard battery standby applications.

At initial power on, if the LV8572A is going to be programmed for battery backed mode, the  $V_{BB}$  pin should be connected to a potential in the range of 2.2V to  $V_{CC}$  – 0.4V.

For single supply mode operation, the  $V_{BB}$  pin should be connected to GND and the PFAIL pin connected to  $V_{CC}$ .

**D7:** Writing a one to this bit enables the test mode register at location 1F (see Table III). This bit should be forced to zero during initialization for normal operation. If the test mode has been entered, clear the test mode register before leaving test mode. (See separate test mode application note for further details.)

#### TIME SAVE CONTROL REGISTER



D0-D4: General purpose RAM bits.


**D5:** The Delay Enable bit is used when a power fail occurs. If this bit is set, a 480  $\mu$ s delay is generated internally before the  $\mu$ P interface is locked out. This will enable the  $\mu$ P to access the registers for up to 480  $\mu$ s after it receives a power fail interrupt. After a power failure is detected but prior to the 480  $\mu$ s delay timing out, the host  $\mu$ P may force immediate lock out by resetting the Delay Enable bit. Note if this bit is a 0 when power fails then after a delay of 30  $\mu$ s min/63  $\mu$ s max the  $\mu$ P cannot read the chip.

**D6:** This read only bit is set and reset by the voltage at the V<sub>BB</sub> pin. It can be used by the  $\mu$ P to determine whether the battery voltage at the V<sub>BB</sub> pin is getting too low. A comparator monitors the battery and when the voltage is lower than 2.1V (typical) this bit is set. The power fail interrupt must be enabled to check for a low battery voltage.

**D7:** Time Save Enable bit controls the loading of real-timeclock data into the Time Save RAM. When a one is written to this bit the Time Save RAM will follow the corresponding clock registers, and when a zero is written to this bit the time in the Time Save RAM is frozen. This eliminates any synchronization problems when reading the clock, thus negating the need to check for a counter rollover during a read cycle.

This bit must be set to a one prior to power failing to enable the Time Save feature. When the power fails this bit is automatically reset and the time is saved in the Time Save RAM.

#### **REAL TIME MODE REGISTER**



TL/F/11417-15

D0-D1: These are the leap year counter bits. These bits are written to set the number of years from the previous leap year. The leap year counter increments on December 31st and it internally enables the February 29th counter state. This method of setting the leap year allows leap year to occur whenever the user wishes to, thus providing flexibility in implementing Japanese leap year function.

LY1	LY0	Leap Year Counter
0	0	Leap Year Current Year
0	1	Leap Year Last Year
1	0	Leap Year 2 Years Ago
1	1	Leap Year 3 Years Ago

**D2:** The count mode for the hours counter can be set to either 24 hour mode or 12 hour mode with AM/PM indicator. A one will place the clock in 12 hour mode.

D3: This bit is the master Start/Stop bit for the clock. When a one is written to this bit the real time counter's prescaler and counter chain are enabled. When this bit is reset to zero the contents of the real time counter is stopped and the prescaler is cleared. When the RTC is initially powered up this bit will be held at a logic 0 until the oscillator starts functioning correctly after which this bit may be modified. If an oscillator fail event occurs, this bit will be reset to logic 0.

**D4:** This bit controls the operation of the interrupt output in standby mode. If set to a one it allows Alarm, Periodic, and Power Fail interrupts to be functional in standby mode. Note that the MFO pin is configured as open drain in standby mode.

If bit D4 is set to a zero then interrupt control register and the periodic interrupt flag will be reset when the RTC enters the standby mode (V<sub>BB</sub> > V<sub>CC</sub>). They will have to be reconfigured when system (V<sub>CC</sub>) power is restored.


D5: General purpose RAM.

**D6 and D7:** These two bits select the crystal clock frequency as per the following table:

XT1	ХТО	Crystal Frequency
0	0	32.768 kHz
0	. 1	4.194304 MHz
1	0	4.9152 MHz
1	1	32.000 kHz


All bits are Read/Write, and any mode written into this register can be determined by reading the register. On initial power up these bits are random.


#### **OUTPUT MODE REGISTER**



D0-D6: General Purpose RAM

**D7:** This bit is used to program the signal appearing at the MFO output, as follows:






TL/F/11417-17

D0-D5: These bits are used to enable one of the selected periodic interrupts by writing a one into the appropriate bit. These interrupts are issued at the rollover of the clock. For example, the minutes interrupt will be issued whenever the minutes counter increments. In all likelihood the interrupt will be enabled asynchronously with the real time change. Therefore, the very first interrupt will occur in less than the periodic time chosen, but after the first interrupt all subsequent interrupts will be spaced correctly. These interrupts are useful when minute, second, real time reading, or task switching is required. When all six bits are written to a 0 this disables periodic interrupts from the Main Status Register and the interrupt pin.

D6 and D7: General Purpose RAM.

#### **INTERRUPT CONTROL REGISTER 1**



D0-D5: Each of these bits are enable bits which will enable a comparison between an individual clock counter and its associated compare RAM. If any bit is a zero then that clock-RAM comparator is set to the "always equal" state and the associated TIME COMPARE RAM byte can be used as general purpose RAM. However, to ensure that an alarm interrupt is not generated at bit D3 of the Main Status Register, all bits must be written to a logic zero.

**D6:** In order to generate an external alarm compare interrupt to the  $\mu$ P from bit D3 of the Main Status Register, this bit must be written to a logic 1. If battery backed mode is selected then this bit is controlled by D4 of the Real Time Mode Register.

**D7:** The MSB of this register is the enable bit for the Power Fail Interrupt. When this bit is set to a one an interrupt will be generated to the  $\mu$ P when V<sub>BB</sub> > V<sub>CC</sub>. If battery backed mode is selected then this bit is controlled by D4 of the Real Time Mode Register.

This bit also enables the low battery detection analog circuitry.

Contro	l and Stat	us Regis	ster Addı	ess Bit I	Лар			
D7	D6	D5	D4	D3	D2	D1	D0	
Main Status R	legister PS = 3	K RS = X	ADDRESS = (	юн				1. Reset by
R/W	R/W	R/W	R/W	R/W <sup>1</sup>	R/W <sup>1</sup>	R <sup>2</sup>	R <sup>3</sup>	writing
Page	Register	5.4.4		Alarm	Periodic	Power Fail	Interrupt	1 to bit.
Select	Select	RAM	RAM	Interrupt	Interrupt	Interrupt	Status	2. Set/reset by voltage at
L							\	PFAIL pin.
								3. Reset when
								all pending
								interrupts
Periodic Flag	Register PS =	0 RS =	nbA 0 =	ess = 03H				are removed.
R/W	R/W <sup>4</sup>	R5	R5	R5	R5	R5	<b>B</b> <sup>5</sup>	4. Read Osc fail
						10 Second	Minute	Write 0 Batt-
Test Mode	Osc. Fail/ Single Supply	1 ms Flag	10 ms Flag	100 ms Flag	Seconds Flag	Flag	Flag	Backed Mode
		I lay	l lag	Tiay	iag	Tiag	i iag	Write 1 Single Supply Mode
		-						5. Reset by
								positive edge
								of read.
	ontrol Register		RS = 0	Address = 0				
R/W	R <sup>6</sup>	R/W	R/W	R/W	R/W	R/W	R/W	<b>-</b>
Time Save	Low Battery	Power Fail						6. Set and reset
Enable	Flag	Delay	RAM	RAM	RAM	RAM	RAM	by V <sub>BB</sub>
		Enable			L			voltage.
Real Time Mo	de Register PS	S = 0 R	<u>S = 1</u> A	ddress = 01H	I			_
Crystal	Crystal	RAM	Interrupt EN	Clock	12/24 Hr.	Leap Year	Leap Year	All Bits R/W
Freq. XT1	Freq. XT0		on Back-Up	Start/Stop	Mode	MSB	LSB	
Output Mode	Register PS =	0 RS =	= 1 Addr	ess = 02H				
MFO as	BAM	RAM	RAM	RAM	BAM	BAM	RAM	All Bits R/W
Crystal	HAM	нам		RAM				
Interrupt Con	trol Register 0	PS = 0	RS = 1	Address = 0	эн			_
		1 ms	10 ms	100 ms	Seconds	10 Second	Minute	
RAM	RAM	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	All Bits R/W
		Enable	Enable	Enable	Enable	Enable	Enable	
Interrupt Con	trol Register 1	PS = 0	RS = 1	Address = 0	04H			-
Power Fail	Alarm	DOW	Month	DOM	Hours	Minute	Second	
Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	All Bits R/W
Enable	Enable	Enable	Enable	Enable	Enable	Enable	Enable	

-----

LV8572A

## **Application Hints**

Suggested Initialization Procedure for LV8572A in Battery Backed Applications that use the  $V_{BB}$  Pin.

- 1. Enter the test mode by writing a 1 to bit D7 in the Periodic Flag Register.
- 2. Write zero to the RAM/TEST mode Register located in page 0, address HEX 1F.
- 3. Leave the test mode by writing a 0 to bit D7 in the Periodic Flag Register. Steps 1,2,3 guarantee that if the test mode had been entered during power on (due to random pulses from the system), all test mode conditions are cleared. Most important is that the OSC Fail Disable bit is cleared. Refer to AN-589 for more information on test mode operation.
- After power on (V<sub>CC</sub> and V<sub>BB</sub> powered), select the correct crystal frequency bits (D7, D6 in the Real Time Mode Register) as shown in Table IV.

Frequency	D7	D6		
32.768 kHz	0	0		
4.194304 MHz	0	1		
4.9152 MHz	1	0		
32.0 kHz	- 1	1		

TABLE IV

- Enter a software loop that does the following: Set a 3 second(approx) software counter. The crystal oscillator may take 1 second to start.
- 5.1 Write a 1 to bit D3 in the Real Time Mode Register (try to start the clock). Make sure the crystal select bits re-

main the same as in step 1. Under normal operation, this bit can be set only if the oscillator is running. During the software loop, RAM, real time counters, output configuration, interrupt control and timer functions may be initialized.

6. Test bit D6 in the Periodic Flag Register:


IF a 1, go to 5.1. If this bit remains a 1 after 3 seconds, then abort and check hardware. The crystal may be defective or not installed. There may be a short at OSC IN or OSC OUT to V<sub>CC</sub> or GND, or to some impedance that is less than 10 M $\Omega$ .

IF a 0, then the oscillator is running, go to step 7.


7. Write a 0 to bit D6 in the Periodic Flag Register. This action puts the clock chip in the battery backed mode. This mode can be entered only if the OSC fail flag (bit D6 of the Periodic Flag Register) is a 0. Reminder, Bit D6 is a dual function bit. When read, D6 returns oscillator status. When written, D6 causes either the Battery Backed Mode, or the Single Supply Mode of operation.

The only method to ensure the chip is in the battery backed mode is to measure the waveform at the OSC OUT pin. If the battery backed mode was selected successfully, then the peak to peak waveform at OSC OUT is referenced to the battery voltage. If not in battery backed mode, the waveform is referenced to V<sub>CC</sub>. The measurement should be made with a high impedance low capacitance probe (10 M $\Omega$ , 10 pF oscilloscope probe or better). Typical peak to peak swings are within 0.6V of V<sub>CC</sub> and ground respectively.

- 8. Write a 1 to bit D7 of Interrupt Control Register 1. This action enables the PFAIL pin and associated circuitry.
- 9. Initialize the rest of the chip as needed.



-V8572A



## PRELIMINARY



# LV8573A Low Voltage Real Time Clock (RTC)

## **General Description**

The LV8573A is intended for use in microprocessor based systems where information is required for multi-tasking, data logging or general time of day/date information. This device is implemented in low voltage silicon gate microCMOS technology to provide low standby power in battery back-up environments. The circuit's architecture is such that it looks like a contiguous block of memory or I/O ports organized as one block of 32 bytes. This includes the Control Registers, the Clock Counters, the Alarm Compare RAM, and the Time Save RAM.

Time and date are maintained from 1/100 of a second to year and leap year in a BCD format, 12 or 24 hour modes. Day of week and day of month counters are provided. Time is controlled by an on-chip crystal oscillator requiring only the addition of the 32.768 kHz crystal and two capacitors.

Power failure logic and control functions have been integrated on chip. This logic is used by the RTC to issue a power fail interrupt, and lock out the  $\mu P$  interface. The time power fails may be logged into RAM automatically when V\_{BB} > V\_{CC}. Additionally, two supply pins are provided. When V\_{BB}


**Block Diagram** 

> V<sub>CC</sub>, internal circuitry will automatically switch from the main supply to the battery supply.

The LV8573A's interrupt structure provides three basic types of interrupts: Periodic, Alarm/Compare, and Power Fail. Interrupt mask and status registers enable the masking and easy determination of each interrupt.

### **Features**

- 3.3V ±10% supply
- Full function real time clock/calendar
  - 12/24 hour mode timekeeping
  - Day of week counter
  - Parallel resonant oscillator
- Power fail features
  - Internal power supply switch to external battery
  - --- Power Supply Bus glitch protection
  - Automatic log of time into RAM at power failure
- On-chip interrupt structure
  - Periodic, alarm, and power fail interrupts



**FIGURE 1** 



### Absolute Maximum Ratings (Notes 1 & 2)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Supply Voltage (V <sub>CC</sub> )	-0.5V to +7.0V
DC Input Voltage (VIN)	$-0.5 V$ to $V_{CC}$ $+0.5 V$
DC Output Voltage (V <sub>OUT</sub> )	-0.5V to V <sub>CC</sub> + 0.5V
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.	) 260°C

# **Operation Conditions**

Supply Voltag	ie (V <sub>CC</sub> ) (Note 3)	<b>Min</b> 3.0	Max 3.6	Unit V
		3.0	3.0	v
Supply Voltag	je (V <sub>BB</sub> ) (Note 3)	2.2	V <sub>CC</sub> -0.4	V
DC Input or O (V <sub>IN</sub> , V <sub>OUT</sub> )	utput Voltage	0.0	V <sub>CC</sub>	V
Operation Te	mperature (T <sub>A</sub> )	-40	+ 85	°C
Electr-Static	Discharge Rating		1	kV
Typical Value	S			
$\theta_{\rm JA} \rm DIP$	Board		61°C/W	
	Socket		67°C/W	
$\theta_{JA} PLCC$	Board Socket		80°C/W 88°C/W	

### **DC Electrical Characteristics**

 $V_{CC}$  = 3.3V ±10%,  $V_{BB}$  = 2.5V,  $V_{\overline{PFAIL}}$  >  $V_{IH}$ ,  $C_L$  = 100 pF unless otherwise specified

Symbol	Parameter	Conditions	Min	Max	Units
VIH	High Level Input Voltage (Note 4)	Any Inputs Except OSC IN, OSC IN with External Clock	2.0 V <sub>BB</sub> - 0.2	V <sub>CC</sub> +0.3	v v
V <sub>iL</sub>	Low Level Input Voltage	All Inputs Except OSC IN OSC IN with External Clock	-0.3 -0.3	0.8 0.2	V
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT, INTR)	$I_{OUT} = -20 \ \mu A$ $I_{OUT} = -2.0 \ m A$	V <sub>CC</sub> -0.2 2.4		v v
V <sub>OL</sub>	Low Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = -20 \ \mu A$ $I_{OUT} = 2.0 \ m A$		0.2 0.3	> >
lin	Input Current (Except OSC IN)	$V_{IN} = V_{CC} \text{ or } GND$		±0.7	μΑ
loz	Output TRI-STATE® Current	$V_{OUT} = V_{CC} \text{ or } GND$		±1	μA
I <sub>LKG</sub>	Output High Leakage Current MFO, INTR Pins	V <sub>OUT</sub> = V <sub>CC</sub> or GND Outputs Open Drain		±1	μΑ
lcc	Quiescent Supply Current (Note 6)	$\begin{split} F_{OSC} &= 32.768 \text{ kHz} \\ V_{IN} &= V_{CC} \text{ or GND (Note 5)} \\ V_{IN} &= V_{CC} \text{ or GND (Note 6)} \\ V_{IN} &= V_{IH} \text{ or } V_{IL} \text{ (Note 6)} \end{split}$		220 700 5	μA μA mA
Icc	Quiescent Supply Current (Single Supply Mode) (Note 7)	$V_{BB} = GND$ $V_{IN} = V_{CC} \text{ or } GND$ $F_{OSC} = 32.768 \text{ kHz}$		30	μΑ
IBB	Standby Mode Battery Supply Current (Note 7)	$V_{CC} = GND$ OSC OUT = open circuit, other pins = GND $F_{OSC} = 32.768 \text{ kHz}$		8	μΑ
I <sub>BLK</sub>	Battery Leakage	$\begin{array}{l} 2.2 V \leq V_{BB} \leq 2.6 V \\ \text{other pins at GND} \\ V_{CC} = \text{GND}, V_{BB} = 2.6 V \\ V_{CC} = 3.6 V, V_{BB} = 2.2 V \end{array}$	-0.8	0.8	μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: In battery backed mode,  $V_{BB} \le V_{CC} - 0.4V$ .

Single Supply Mode: Data retention voltage is 2.2V min.

In single Supply Mode (Power connected to V<sub>CC</sub> pin) 3.0V  $\leq$  V<sub>CC</sub>  $\leq$  3.6V.

Note 4: This parameter (V<sub>IH</sub>) is not tested on all pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

AC Electrical	Characteristics
---------------	-----------------

 $V_{CC}$  = 3.3V ±10%,  $V_{BB}$  = 2.5V,  $V_{\overline{PFAIL}}$  >  $V_{IH}$ ,  $C_L$  = 100 pF unless otherwise specified

Symbol	Parameter Min Max		Max	Units
AD TIMING				
t <sub>AR</sub>	Address Valid Prior to Read Strobe	10		ns
t <sub>RW</sub>	Read Strobe Width (Note 8)	100		ns
tCD	Chip Select to Data Valid Time		100	ns
tRAH	Address Hold after Read (Note 9)	2		ns
t <sub>RD</sub>	Read Strobe to Valid Data		90	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		80	ns
tRCH	Chip Select Hold after Read Strobe (Note 9)	0		ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses	70		ns
RITE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	10		ns
twah	Address Hold after Write Strobe (Note 9)	2		ns
t <sub>CW</sub>	Chip Select to End of Write Strobe	110		ns
tww	Write Strobe Width (Note 10)	100		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	70		ns
twDH	Data Hold after Write Strobe (Note 9)	2		ns
twch	Chip Select Hold after Write Strobe (Note 9)	0		ns
ITERRUPT TIMI	NG			• .
t <sub>ROLL</sub>	Clock rollover to INTR out typically 20 µs			

Note 8: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when both signals are low and terminates when either signal returns high.

Note 9: Hold time is guaranteed by design but not production tested. This limit is not used to calculate outgoing quality levels.

Note 10: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

# **AC Test Conditions**

Input Pulse Levels Input Rise and Fall Times	GND to 3.0V 6 ns (10%–90%)
Input and Output Reference Levels	1.3V
TRI-STATE Reference	Active High + 0.5V
Levels (Note 12)	Active Low -0.5V

Note 11: C<sub>L</sub> = 100 pF, includes jig and scope capacitance.

Note 12: S1 =  $V_{CC}$  for active low to high impedance measurements. S1 = GND for active high to high impedance measurements.


S1 = open for all other timing measurements.


## **Capacitance** ( $T_A = 25^{\circ}C, f = 1 \text{ MHz}$ )

Symbol	Parameter (Note 13)	Тур	Units
C <sub>IN</sub>	Input Capacitance	5	рF
COUT	Output Capacitance	7	рF

Note 13: This parameter is not 100% tested.

Note 14: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.





# **Pin Description**

 $\overline{\text{CS}}$ ,  $\overline{\text{RD}}$ ,  $\overline{\text{WR}}$  (Inputs): These pins interface to  $\mu P$  control lines. The  $\overline{\text{CS}}$  pin is an active low enable for the read and write operations. Read and Write pins are also active low and enable reading or writing to the RTC. All three pins are disabled when power failure is detected. However, if a read or write is in progress at this time, it will be allowed to complete its cycle.

A0-A4 (Inputs): These 5 pins are for register selection. They individually control which location is to be accessed. These inputs are disabled when power failure is detected.

OSC IN (Input): OSC OUT (Output): These two pins are used to connect the crystal to the internal parallel resonant oscillator. The oscillator is always running when power is applied to  $V_{BB}$  and  $V_{CC}$ .

**MFO (Output):** The multi-function output can be used as a second interrupt (Power fail) output for interrupting the  $\mu$ P. This pin can also provide an output for the oscillator. The MFO output is configured as push-pull, active high for normal or single power supply operation and as an open drain during standby mode (V<sub>BB</sub> > V<sub>CC</sub>). If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>.

**INTR (Output):** The interrupt output is used to interrupt the processor when a timing event or power fail has occurred and the respective interrupt has been enabled. The INTR

output is permanently configured active low, open drain. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>.

**D0–D7 (Input/Output):** These 8 bidirectional pins connect to the host  $\mu$ P's data bus and are used to read from and write to the RTC. When the **PFAIL** pin goes low and a write is not in progress, these pins are at TRI-STATE.


**FFAIL (Input):** In battery backed mode, this pin can have a digital signal applied to it via some external power detection logic. When PFAIL = logic 0 the RTC goes into a lockout mode, in a minimum of 30  $\mu$ s or a maximum of 63  $\mu$ s unless lockout delay is programmed. In the single power supply mode, this pin is not useable as an input and should be tied to V<sub>CC</sub>. Refer to section on Power Fail Functional Description.

 $V_{BB}$  (Battery Power Pin): This pin is connected to a backup power supply. This power supply is switched to the internal circuitry when the  $V_{CC}$  becomes lower than  $V_{BB}$ . Utilizing this pin eliminates the need for external logic to switch in and out the back-up power supply. If this feature is not to be used then this pin must be tied to ground, the RTC programmed for single power supply only, and power applied to the  $V_{CC}$  pin.

Vcc: This is the main system power pin.

GND: This is the common ground power pin for both  $V_{BB}$  and  $V_{CC}.$ 

### **Connection Diagrams**



Top View

Order Number LV8573AN See NS Package Number N24C

# **Functional Description**

The LV8573A contains a fast access real time clock, interrupt control logic, and power fail detect logic. All functions of the RTC are controlled by a set of seven registers. A simplified block diagram that shows the major functional blocks is given in *Figure 1*.

The blocks are described in the following sections:

- 1. Real Time Clock
- 2. Oscillator Prescaler
- 3. Interrupt Logic
- 4. Power Failure Logic
- 5. Additional Supply Management

The memory map of the RTC is shown in the memory addressing table (*Figure 2*). A control bit in the Main Status Register is used to select either control register block.


#### INITIAL POWER-ON of BOTH VBB and VCC

 $V_{BB}$  and  $V_{CC}$  may be applied in any sequence. In order for the power fail circuitry to function correctly, whenever power is off, the  $V_{CC}$  pin must see a path to ground through a maximum of 1  $M\Omega$ . The user should be aware that the control registers will contain random data. The user should ensure that the RTC is not in test mode (see register descriptions).

#### **REAL TIME CLOCK FUNCTIONAL DESCRIPTION**


As shown in *Figure 2*, the clock has 8 bytes of counters, which count from 1/100 of a second to years. Each counter counts in BCD and is synchronously clocked. The count sequence of the individual byte counters within the clock is shown later in Table VII. Note that the day of week, day of month, and month counters all roll over to 1. The hours counter in 12 hour mode rolls over to 1 and the AM/PM bit toggles when the hours rolls over to 12 (AM = 0, PM = 1). The AM/PM bit is bit D7 in the hours counter.

All other counters roll over to 0. Upon initial application of power the counters will contain random information.



Top View

#### Order Number LV8573AV See NS Package Number V28A



#### READING THE CLOCK: VALIDATED READ

Since clocking of the counter occurs asynchronously to reading of the counter, it is possible to read the counter while it is being incremented (rollover). This may result in an incorrect time reading. Thus to ensure a correct reading of the entire contents of the clock (or that part of interest), it must be read without a clock rollover occurring. In general this can be done by checking a rollover bit. On this chip the periodic interrupt status bits can serve this function. The following program steps can be used to accomplish this.

- 1. Initialize program for reading clock.
- 2. Dummy read of periodic status bit to clear it.
- 3. Read counter bytes and store.
- 4. Read rollover bit, and test it.
- 5. If rollover occured go to 3.
- 6. If no rollover, done.

To detect the rollover, individual periodic status bits can be polled. The periodic bit chosen should be equal to the highest frequency counter register to be read. That is if only SECONDS through HOURS counters are read, then the SECONDS periodic bit should be used.

#### **READING THE CLOCK: INTERRUPT DRIVEN**

Enabling the periodic interrupt mask bits cause interrupts just as the clock rolls over. Enabling the desired update rate and providing an interrupt service routine that executes in less than 10 ms enables clock reading without checking for a rollover.

#### **READING THE CLOCK: LATCHED READ**

Another method to read the clock that does not require checking the rollover bit is to write a one into the Time Save Enable bit (D7) of the Time Save Control Register, and then to write a zero. Writing a one into this bit will enable the clock contents to be duplicated in the Time Save RAM. Changing the bit from a one to a zero will freeze and store the contents of the clock in Time Save RAM. The time then can be read without concern for clock rollover, since internal logic takes care of synchronization of the clock. Because only the bits used by the clock counters will be latched, the Time Save RAM should be cleared prior to use to ensure that random data stored in the unused bits do not confuse the host microprocessor. This bit can also provide time save at power failure, see the Additional Supply Management Functions section. With the Time Save Enable bit at a logical 0, the Time Save RAM may be used as RAM if the latched read function is not necessary.

# INITIALIZING AND WRITING TO THE CALENDAR-CLOCK

Upon initial application of power to the TCP or when making time corrections, the time must be written into the clock. To correctly write the time to the counters, the clock would normally be stopped by writing the Start/Stop bit in the Real Time Mode Register to a zero. This stops the clock from counting and disables the carry circuitry. When initializing the clock's Real Time Mode Register, it is recommended that first the various mode bits be written while maintaining the Start/Stop bit reset, and then writing to the register a second time with the Start/Stop bit set. The above method is useful when the entire clock is being corrected. If one location is being updated the clock need not be stopped since this will reset the prescaler, and time will be lost. An ideal example of this is correcting the hours for daylight savings time. To write to the clock "on the fly" the best method is to wait for the 1/100 of a second periodic ic interrupt. Then wait an additional 16  $\mu$ s, and then write the data to the clock.

# PRESCALER/OSCILLATOR FUNCTIONAL DESCRIPTION

Feeding the counter chain is a programmable prescaler which divides the crystal oscillator frequency to 32 kHz and further to 100 Hz for the counter chain (see *Figure 3*).






#### FIGURE 3. Programmable Clock Prescaler Block

In addition to the inverter, the oscillator feedback bias resistor is included on chip, as shown in *Figure 4*. The oscillator input may be driven from an external source if desired. Refer to test mode application note for details. The oscillator stability is enhanced through the use of an on chip regulated power supply.

The typical range of trimmer capacitor (as shown in Oscillator Circuit Diagram *Figure 4*, and in the typical application) at the oscillator input pin is suggested only to allow accurato tuning of the oscillator. This range is based on a typical printed circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases, the **load capacitance** specified by the crystal manufacturer (nominal value 11 pF for the 32.768 crystal) is what determines proper oscillation. This load capcitance is the series combination of capacitance on each side of the crystal (with respect to ground).





XTAL	Co	Ct	R <sub>OUT</sub>
32.768 kHz	47 pF	2 pF-22 pF	150 k $\Omega$ to 350 k $\Omega$

#### INTERRUPT LOGIC FUNCTIONAL DESCRIPTION

The RTC has the ability to coordinate processor timing activities. To enhance this, an interrupt structure has been implemented which enables several types of events to cause interrupts. Interrupts are controlled via two Control Registers in block 1 and two Status Registers in block 0. (See Register Description for notes on paging and Table I.)

The interrupts are enabled by writing a one to the appropriate bits in Interrupt Control Register 0 and/or 1.

TABLE I. Registers that are Applicable to Interrupt Control

Register Name	Register Select	Address
Main Status Register	X	00Н
Periodic Flag Register	0	03H
Interrupt Control Register 0	1	03H
Interrupt Control Register 1	1	04H
Output Mode Register	<sup>1</sup>	02H

The Interrupt Status Flag D0, in the Main Status Register, indicates the state of INTR and MFO outputs. It is set when either output becomes active and is cleared when all RTC interrupts have been cleared and no further interrupts are pending (i.e., both INTR and MFO are returned to their inactive state). This flag enables the RTC to be rapidly polled by the  $\mu$ P to determine the source of an interrupt in a wired—OR interrupt system. (The Interrupt Status Flag provides a true reflection of all conditions routed to the external pins.)

Status for the interrupts are provided by the Main Status Register and the Periodic Flag Register. Bits D1-D5 of the Main Status Register are the main interrupt bits.

These register bits will be set when their associated timing events occur. Enabled Alarm comparisons that occur will set its Main Status Register bit to a one. However, an external interrupt will only be generated if the Alarm interrupt enable bit is set (see *Figure 5*).

Disabling the periodic interrupts will mask the Main Status Register periodic bit, but not the Periodic Flag Register bits. The Power Fail Interrupt bit is set when the interrupt is enabled and a power fail event has occurred, and is not reset until the power is restored. If all interrupt enable bits are 0 no interrupt will be asserted. However, status still can be read from the Main Status Register in a polled fashion (see *Figure 5*).

To clear a flag in bits D2 and D3 of the Main Status Register a 1 must be written back into the bit location that is to be cleared. For the Periodic Flag Register reading the status will reset all the periodic flags.

Interrupts Fall Into Three Categories:

- 1. The Alarm Compare Interrupt: Issued when the value in the time compared RAM equals the counter.
- The Periodic Interrupts: These are issued at every increment of the specific clock counter signal. Thus, an interrupt is issued every minute, second, etc. Each of these interrupts occurs at the roll-over of the specific counter.

3. The Power Fail Interrupt: Issued upon recognition of a power fail condition by the internal sensing logic. The power failed condition is determined by the signal on the PFAIL pin. The internal power fail signal is gated with the chip select signal to ensure that the power fail interrupt does not lock the chip out during a read or write.

#### ALARM COMPARE INTERRUPT DESCRIPTON

The alarm/time comparison interrupt is a special interrupt similar to an alarm clock wake up buzzer. This interrupt is generated when the clock time is equal to a value programmed into the alarm compare registers. Up to six bytes can be enabled to perform alarm time comparisons on the counter chain. These six bytes, or some subset thereof, would be loaded with the future time at which the interrupt will occur. Next, the appropriate bits in the Interrupt Control Register 1 are enabled or disabled (refer to detailed description of Interrupt Control Register 1). The RTC then compares these bytes with the clock time. When all the enabled compare registers equal the clock time an alarm interrupt is issued, but only if the alarm compare interrupt is enabled can the interrupt be generated externally. Each alarm compare bit in the Control Register will enable a specific byte for comparison to the clock. Disabling a compare byte is the same as setting its associated counter comparator to an "always equal" state. For example, to generate an interrupt at 3:15 AM of every day, load the hours compare with 0 3 (BCD), the minutes compare with 1 5 (BCD) and the faster counters with 0 0 (BCD), and then disable all other compare registers. So every day when the time rolls over from 3:14:59.99, an interrupt is issued. This bit may be reset by writing a one to bit D3 in the Main Status Register at any time after the alarm has been generated.

If time comparison for an individual byte counter is disabled, that corresponding RAM location can then be used as general purpose storage.

#### PERIODIC INTERRUPTS DESCRIPTION

The Periodic Flag Register contains six flags which are set by real-time generated "ticks" at various time intervals, see *Figure 5*. These flags constantly sense the periodic signals and may be used whether or not interrupts are enabled. These flags are cleared by any read or write operation performed on this register.

To generate periodic interrupts at the desired rate, the associated Periodic Interrupt Enable bit in Interrupt Control Register 0 must be set. Any combination of periodic interrupts may be enabled to operate simultaneously. Enabled periodic interrupts will now affect the Periodic Interrupt Flag in the Main Status Register.

When a periodic event occurs, the Periodic Interrupt Flag in the Main Status Register is set, causing an interrupt to be generated. The  $\mu$ P clears both flag and interrupt by writing a "1" to the Periodic Interrupt Flag. The individual flags in the periodic Interrupt Flag Register do not require clearing to cancel the interrupt.

If all periodic interrupts are disabled and a periodic interrupt is left pending (i.e., the Periodic Interrupt Flag is still set), the Periodic Interrupt Flag will still be required to be cleared to cancel the pending interrupt.

Interrupt Control Registers Interrrupt Control Register Main Status Register Output Mode Register Control Bit **Buffered Oscillator** Real 0-Time Periodia Periodic Inter-Pulse rupt Signals Enables (also to Periodic MFO Status Periodic Signal Bit 🕈 MFO Output Flags) MUX Output Buffer Alarm Alarm Interrupt Status nterrupt Mode Alarm Bit 🕺 Enable Alarm Selected ompare Compare Signals Enables Power Power Fail 🛛 🗛 il 🔅 Interrupt Status Bit Enable Power Fail Detect INTR Output Interrupt Status Output Buffer Bit TL/F/11418-10 FIGURE 5. Interrupt Control Logic Overview

1-51

Functional Description (Continued)

1

÷

ł

i

#### POWER FAIL INTERRUPTS DESCRIPTION

The Power Fail Status Flag in the Main Status Register monitors the state of the internal power fail signal. This flag may be interrogated by the  $\mu$ P, but it cannot be cleared; it is cleared automatically by the RTC when system power is restored. To generate an interrupt when the power fails, the Power Fail Interrupt Enable bit in Interrupt Control Register 1 is set. Although this interrupt may not be cleared, it may be masked by clearing the Power Fail Interrupt Enable bit.

# POWER FAILURE CIRCUITRY FUNCTIONAL DESCRIPTION

Since the clock must be operated from a battery when the main system supply has been turned off, the LV8573A provides circuitry to simplify design in battery backed systems. This switches over to the back up supply, and isolates itself from the host system. *Figure 6* shows a simplified block diagram of this circuitry, which consists of three major sections; 1) power loss logic: 2) battery switch over logic: and 3) isolation logic.

Detection of power loss occurs when  $\overrightarrow{\text{PFAIL}}$  is low. Debounce logic provides a 30  $\mu$ s-63  $\mu$ s debounce time, which will prevent noise on the  $\overrightarrow{\text{PFAIL}}$  pin from being interpreted as a system failure. After 30  $\mu$ s-63  $\mu$ s the debounce logic times out and a signal is generated indicating that system power is marginal and is failing. The Power Fail Interrupt will then be generated.

If chip select is low when a power failure is detected, a safety circuit will ensure that if a read or write is held active continuously for greater than 30  $\mu$ s after the power fail signal is asserted, the lock-out will be forced.

The battery switch over circuitry is completely independent of the  $\overline{\text{PFAIL}}$  pin. A separate circuit compares  $V_{CC}$  to the  $V_{BB}$  voltage. As the main supply fails, the RTC will continue to operate from the  $V_{CC}$  pin until  $V_{CC}$  falls below the  $V_{BB}$  voltage. At this time, the battery supply is switched in,  $V_{CC}$  is

disconnected, and the device is now in the standby mode. If indeterminate operation of the battery switch over circuit is to be avoided, then the voltage at the V<sub>CC</sub> pin must not be allowed to equal the voltage at the V<sub>BB</sub> pin.

After the generation of a lock-out signal, and eventual switch in of the battery supply, the pins of the RTC will be configured as shown in Table II. Outputs that have a pull-up resistor should be connected to a voltage no greater than  $V_{BB}.$ 

TABLE II.	Pin Isolation	during a	<b>Power Failure</b>
		uuning a	romer ranure

	-	
Pin	PFAIL = Logic 0	Standby Mode V <sub>BB</sub> > V <sub>CC</sub>
CS, RD, WR	Locked Out	Locked Out
A0-A4	Locked Out	Locked Out
D0-D7	Locked Out	Locked Out
Oscillator	Not Isolated	Not Isolated
PFAIL	Not Isolated	Not Isolated
INTR, MFO	Not Isolated	Open Drain

The Interrupt Power Fail Operation bit in the Real-Time Mode Register determines whether or not the interrupts will continue to function after a power fail event.

As power returns to the system, the battery switch over circuit will switch back to  $V_{CC}$  power as soon as it becomes greater than the battery voltage. The chip will remain in the locked out state as long as  $\overline{PFAIL}=0$ . When  $\overline{PFAIL}=1$  the chip is unlocked, but only after another 30  $\mu s$  min  $\rightarrow$  63  $\mu s$  max debounce time. The system designer must ensure that his system is stable when power has returned.

The power fail circuitry contains active linear circuitry that draws supply current from V<sub>CC</sub>. In some cases this may be undesirable, so this circuit can be disabled by masking the power fail interrupt. The power fail input can perform all lock-out functions previously mentioned, except that no ex-




FIGURE 6. System-Battery Switchover (Upper Left), Power Fail and Lock-Out Circuits (Lower Right)

TL/F/11418-11

ternal interrupt will be issued. Note that the linear power fail circuitry is switched off automatically when using  $V_{BB}$  in standby mode.

#### INITIAL POWER ON DETECT AND POWER FAIL TIME SAVE

There are two other functions provided on the LV8573A to ease power supply control. These are an initial Power On detect circuit, which also can be used as a time keeping failure detect, and a time save on power failure.

On initial power up the Oscillator Fail Flag will be set to a one and the real time clock start bit reset to a zero. This indicates that an oscillator fail event has occurred, and time keeping has failed.

The Oscillator Fail flag will not be reset until the real-time clock is started. This allows the system to discriminate between an initial power-up and recovery from a power failure. If the battery backed mode is selected, then bit D6 of the Periodic Flag Register must be written low. This will not affect the contents of the Oscillator Fail Flag.

To relieve CPU overhead for saving time upon power failure, the Time Save Enable bit is provided to do this automatically. (See also Reading the Clock: Latched Read.) The Time Save Enable bit, when set, causes the Time Save RAM to follow the contents of the clock. This bit can be reset by software, but if set before a power failure occurs, it will automatically be reset when the clock switches to the battery supply (not when a power failure is detected by the PFAIL pin). Thus, writing a one to the Time Save bit enables both a software write or power fail write.

#### SINGLE POWER SUPPLY APPLICATIONS

The LV8573A can be used in a single power supply application. To achieve this, the V<sub>BB</sub> pin must be connected to ground, and the power connected to V<sub>CC</sub>. The Oscillator Failed/Single Supply bit in the Periodic Flag Register should be set to a logic 1, which will disable the oscillator battery reference circuit. The power fail interrupt should also be disabled. This will turn off the linear power fail detection circuits, and will eliminate any quiescent power drawn through these circuits.

#### DETAILED REGISTER DESCRIPTION

There are 5 external address bits: Thus, the host microprocessor has access to 28 locations at one time. An internal switching scheme provides a total of 30 locations.

The only register that does not get switched is the Main Status Register. It contains the register select bit as well as status information.

A memory map is shown in *Figure 2* and register addressing in Table III. They show the name, address and page locations for the LV8573A.


#### TABLE III. Register/Counter/RAM Addressing for LV8573A

Addressing for LV8573A			
A0-4	RS (Note 1)	Descrip	tion
CONT	TROL REC	SISTERS	
00	х	Main Status Register	
01	0	N/A	
02	0	N/A	
03	0	Periodic Flag Register	
04	0	Time Save Control Reg	ister
01	1	Real Time Mode Regist	er
02	1	Output Mode Register	
03	1	Interrupt Control Regist	er0
04	1.	Interrupt Control Regist	er 1
COU	NTERS (C	LOCK CALENDAR)	
05	X	1/100, 1/10 Seconds	(0-99)
06	x	Seconds	(059)
07	x	Minutes	(0-59)
08	X	Hours	(1-12, 0-23)
09	х	Days of Month	(1-28/29/30/31)
0A	Х	Months	(1-12)
0B	X	Years	(0-99)
0C	Х	RAM	
0D	Х	D0, D1 bits only	
0E	Х	Day of Week	(1-7)
0F	X	N/A	
10	X	N/A	
11	X	N/A	
12	X	N/A	
TIME	COMPAR	ERAM	
13	х	Sec Compare RAM	(0-59)
14	X	Min Compare RAM	(0-59)
15	X	Hours Compare RAM	(1-12, 0-23)
16	X	DOM Compare RAM	(1-28/29/30/31)
17	X	Months Compare RAM	(1-12).
18	X	DOW Compare RAM	(1-7)
TIME	TIME SAVE RAM		
19	X	Seconds Time Save RA	M
1A	x	Minutes Time Save RA	vt
1B	x	Hours Time Save RAM	
1C	x	Day of Month Time Sav	e RAM
1D	X	Months Time Save RAM	Λ
1E	1	RAM	
1F	X	RAM/Test Mode Regis	ter

Note 1: RS-Register Select (Bit D6 of Main Status Register)

LV8573A

### Functional Description (Continued) MAIN STATUS REGISTER



TL/F/11418-12

The Main Status Register is always located at address 0 regardless of the register block selected.


**D0:** This read only bit is a general interrupt status bit that is taken directly from the interrupt pins. The bit is a one when an interrupt is pending on either the  $\overline{\rm INTR}$  pin or the MFO pin (when configured as an interrupt). This is unlike D3 which can be set by an internal event but may not cause an interrupt. This bit is reset when the interrupt status bits in the Main Status Register are cleared.

**D1-D3:** These three bits of the Main Status Register are the main interrupt status bits. Any bit may be a one when any of the interrupts are pending. Once an interrupt is asserted the  $\mu$ P will read this register to determine the cause. These interrupt status bits are not reset when read. Except for D1, to reset an interrupt a one is written back to the corresponding bit that is being tested. D1 is reset whenever the PFAIL pin = logic 1. This prevents loss of interrupt status when reading the register in a polled mode. D1 and D3 are set regardless of whether these interrupts are masked or not by bits D6 and D7 of Interrupt Control Registers 0 and 1.

D4, D5 and D7: General purpose RAM bits.

**D6:** Bit D6 controls the register block to be accessed (see memory map).

#### PERIODIC FLAG REGISTER



TL/F/11418-13

The Periodic Flag Register has the same bit for bit correspondence as Interrupt Control Register 0 except for D6 and D7. For normal operation (i.e., not a single supply application) this register must be written to on initial power up or after an oscillator fail event. D0–D5 are read only bits, D6 and D7 are read/write.

**D0-D5:** These bits are set by the real time rollover events: (Time Change = 1). The bits are reset when the register is read and can be used as selective data change flags.

**D6:** This bit performs a dual function. When this bit is read, a one indicates that an oscillator failure has occurred and the time information may have been lost. Some of the ways an oscillator failure might be caused are: failure of the crystal, shorting OSC IN or OSC OUT to GND or V<sub>CC</sub>, removal of crystal, removal of battery when in the battery backed mode (when a "0" is written to D6), lowering the voltage at the

 $V_{BB}$  pin to a value less than 2.2V when in the battery backed mode. Bit D6 is automatically set to 1 on initial power-up or an oscillator fail event. The oscillator fail flag is reset by writing a one to the clock start/stop bit in the Real Time Mode Register, with the crystal oscillating.


When D6 is written to, it defines whether the TCP is being used in battery backed (normal) or in a single supply mode application. When set to a one this bit configures the TCP for single power supply applications. This bit is automatically set on initial power-up or an oscillator fail event. When set, D6 disables the oscillator reference circuit. The result is that the oscillator is referenced to V<sub>CC</sub>. When a zero is written to D6 the oscillator reference is enabled, thus the oscillator is referenced to V<sub>BB</sub>. This allows operation in standard battery standby applications.

At initial power on, if the LV8573A is going to be programmed for battery backed mode, the  $V_{BB}$  pin should be connected to a potential in the range of 2.2V to  $V_{CC}-0.4V.$ 

For single supply mode operation, the  $V_{BB}$  pin should be connected to GND and the PFAIL pin connected to  $V_{CC}$ .

**D7:** Writing a one to this bit enables the test mode register at location 1F (see Table III). This bit should be forced to zero during initialization for normal operation. If the test mode has been entered, clear the test mode register before leaving test mode. (See separate test mode application note for further details.)

#### TIME SAVE CONTROL REGISTER



TL/F/11418-14


D0-D5: General purpose RAM bits.

D6: Not Available, appears as logic 0 when read.

**D7:** Time Save Enable bit controls the loading of real-timeclock data into the Time Save RAM. When a one is written to this bit the Time Save RAM will follow the corresponding clock registers, and when a zero is written to this bit the time in the Time Save RAM is frozen. This eliminates any synchronization problems when reading the clock, thus negating the need to check for a counter rollover during a read cycle.

This bit must be set to a one prior to power failing to enable the Time Save feature. When the power fails this bit is automatically reset and the time is saved in the Time Save RAM.

#### REAL TIME MODE REGISTER



D0-D1: These are the leap year counter bits. These bits are written to set the number of years from the previous leap year. The leap year counter increments on December 31st and it internally enables the February 29th counter state. This method of setting the leap year allows leap year to occur whenever the user wishes to, thus providing flexibility in implementing Japanese leap year function.

1.27

LY1	LYO	Leap Year Counter
0	0	Leap Year Current Year
0	1	Leap Year Last Year
1	0	Leap Year 2 Years Ago
1	1	Leap Year 3 Years Ago

**D2:** The count mode for the hours counter can be set to either 24 hour mode or 12 hour mode with AM/PM indicator. A one will place the clock in 12 hour mode.


**D3:** This bit is the master Start/Stop bit for the clock. When a one is written to this bit the real time counter's prescaler and counter chain are enabled. When this bit is reset to zero the contents of the real time counter is stopped. When the RTC is initially powered up this bit will be held at a logic 0 until the oscillator starts functioning correctly after which this bit may be modified. If an oscillator fail event occurs, this bit will be reset to logic 0.

**D4:** This bit controls the operation of the interrupt output in standby mode. If set to a one it allows Alarm, Periodic, and Power Fail interrupts to be functional in standby mode. Note that the MFO pin is configured as open drain in standby mode.

If bit D4 is set to a zero then the interrupt control register and the periodic interrupt flag will be reset when the RTC enters the standby mode (V<sub>BB</sub> > V<sub>CC</sub>). They will have to be re-configured when system (V<sub>CC</sub>) power is restored.

D5-D7: General purpose RAM bits.

#### **OUTPUT MODE REGISTER**




TL/F/11418-16

D0-D6: General purpose RAM bits.

**D7:** This bit is used to program the signal appearing at the MFO output, as follows:

D7	MFO Output Signal
0	Power Fail Interrupt
1	Buffered Crystal Oscillator

#### INTERRUPT CONTROL REGISTER 0




TL/F/11418-17

D0-D5: These bits are used to enable one of the selected periodic interrupts by writing a one into the appropriate bit. These interrupts are issued at the rollover of the clock. For example, the minutes interrupt will be issued whenever the minutes counter increments. In all likelihood the interrupt will be enabled asynchronously with the real time change. Therefore, the very first interrupt will occur in less than the periodic time chosen, but after the first interrupt all subsequent interrupts will be spaced correctly. These interrupts are useful when minute, second, real time reading, or task switching is required. When all six bits are written to a 0 this disables periodic interrupts from the Main Status Register and the interrupt pin.

D6 and D7: General purpose RAM.

#### **INTERRUPT CONTROL REGISTER 1**



TL/F/11418-18

**D0-D5:** Each of these bits are enable bits which will enable a comparison between an individual clock counter and its associated compare RAM. If any bit is a zero then that clock-RAM comparator is set to the "always equal" state and the associated TIME COMPARE RAM byte can be used as general purpose RAM. However, to ensure that an alarm interrupt is not generated at bit D3 of the Main Status Register, all bits must be written to a logic zero.

**D6:** In order to generate an external alarm compare interrupt to the  $\mu$ P from bit D3 of the Main Status Register, this bit must be written to a logic 1. If battery backed mode is selected, then this bit is controlled by D4 of the Real Time Mode Register.

**D7:** The MSB of this register is the enable bit for the Power Fail Interrupt. When this bit is set to a one an interrupt will be generated to the  $\mu$ P when a V<sub>BB</sub> > V<sub>CC</sub>. If battery backed mode is selected, then this bit is controlled by D4 of the Real Time Mode Register.

D7	D6	D5	D4	D3	D2	D1	D0	
	legister PS = >					_		1. Reset by
R/W	R/W	R/W	R/W	R/W <sup>1</sup>	R/W <sup>1</sup>	R <sup>2</sup>	R <sup>3</sup>	writing
RAM	Register	RAM	RAM	Alarm	Periodic	Power Fail	Interrupt	2. Set/reset b
10.00	Select		10.00	Interrupt	Interrupt	Interrupt	Status	voltage at
								PFAIL pin.
								<ol> <li>Reset when all pending</li> </ol>
							1	interrupts
								are remove
-	Register PS =			ess = 03H	_	_	_	4. Read Osc f
R/W	R/W <sup>4</sup>	R <sup>5</sup>	<sup>.</sup> R <sup>5</sup>	R <sup>5</sup>	R5	R <sup>5</sup>	R5	4. Read Osc 1
Test	Osc. Fail/	1 ms	10 ms	100 ms	Seconds	10 Second	Minute	Backed Mo
Mode	Single Supply	Flag	Flag	Flag	Flag	Flag	Flag	Write 1 Sin
								Supply Mo 5. Reset by
						an a		positive ed
								of read.
ime Save Co	ontrol Register	PS = 0	RS = 0 Addr	ess = 04H				
Time Save					BAM	RAM	BAM	]
	ntrol Register	PS = 0 RAM	RS = 0 Addr RAM	ess = 04H RAM	RAM	RAM	RAM	All Bits R/W
Time Save Enable		RAM	RAM			RAM	RAM	
Time Save Enable eal Time Mo	N/A de Register PS	RAM S = 0 R	RAM S = 1 A	RAM ddress = 01H				] All Bits R/W
Time Save Enable	N/A	RAM	RAM	RAM		RAM Leap Year MSB	RAM Leap Year LSB	]
Time Save Enable eal Time Mo RAM	N/A de Register PS RAM	RAM S = 0 R RAM	RAM S = 1 A Interrupt EN on Back-Up	RAM ddress = 01H Clock Start/Stop	12/24 Hr.	Leap Year	Leap Year	] All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode	N/A de Register PS	RAM S = 0 R RAM	RAM S = 1 A Interrupt EN on Back-Up	RAM ddress = 01H Clock	12/24 Hr.	Leap Year	Leap Year	] All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as	N/A de Register PS RAM	RAM S = 0 R RAM	RAM S = 1 A Interrupt EN on Back-Up	RAM ddress = 01H Clock Start/Stop	12/24 Hr.	Leap Year	Leap Year	] All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode	N/A de Register PS RAM Register PS =	RAM S = 0 R RAM 0 RS =	RAM S = 1 A Interrupt EN on Back-Up = 1 Addr	RAM ddress = 01H Clock Start/Stop ess = 02H	12/24 Hr. Mode	Leap Year MSB	Leap Year LSB	All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as Crystal	N/A de Register PS RAM Register PS =	RAM S = 0 R RAM 0 RS = RAM	RAM S = 1 A Interrupt EN on Back-Up = 1 Addr	RAM ddress = 01H Clock Start/Stop ess = 02H	12/24 Hr. Mode RAM	Leap Year MSB	Leap Year LSB	All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as Crystal	N/A de Register PS RAM Register PS = RAM	RAM S = 0 R RAM 0 RS = RAM	RAM S = 1 A Interrupt EN on Back-Up = 1 Addr RAM	RAM ddress = 01H Clock Start/Stop ess = 02H RAM	12/24 Hr. Mode RAM	Leap Year MSB	Leap Year LSB	All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as Crystal	N/A de Register PS RAM Register PS = RAM	RAM S = 0 R RAM 0 RS = RAM PS = 0	RAM S = 1 A Interrupt EN on Back-Up = 1 Addr RAM RS = 1	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0	12/24 Hr. Mode RAM 3H	Leap Year MSB RAM 10 Second Interrupt	Leap Year LSB RAM	] All Bits R/W ] All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as Crystal sterrupt Con	N/A de Register PS RAM Register PS = RAM trol Register 0	RAM S = 0 R RAM 0 RS = RAM PS = 0 1 ms	$\begin{array}{c c} RAM\\ S = 1 & A\\ Interrupt EN\\ on Back-Up\\ = 1 & Addr\\ \hline RAM\\ \hline RS = 1\\ \hline 10 \text{ ms} \end{array}$	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms	12/24 Hr. Mode RAM 3H Seconds	Leap Year MSB RAM 10 Second	Leap Year LSB RAM Minute	All Bits R/W All Bits R/W All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as Crystal tterrupt Con RAM	N/A de Register PS RAM Register PS = RAM trol Register 0	RAM S = 0 R RAM 0 RS = RAM PS = 0 1 ms Interrupt Enable	$\begin{array}{c c} RAM\\ S = 1 & A\\ Interrupt EN\\ on Back-Up\\ \hline \\ 1 & Addr\\ \hline \\ RAM\\ \hline \\ RS = 1\\ \hline \\ 10 \text{ ms}\\ Interrupt\\ \end{array}$	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms Interrupt	12/24 Hr. Mode RAM 3H Seconds Interrupt Enable	Leap Year MSB RAM 10 Second Interrupt	Leap Year LSB RAM Minute Interrupt	All Bits R/W All Bits R/W All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as Crystal tterrupt Con RAM	N/A de Register PS RAM Register PS = RAM trol Register 0 RAM	RAM S = 0 R RAM 0 RS = RAM PS = 0 1 ms Interrupt Enable	$\begin{array}{c} \text{RAM} \\ \text{S} = 1 & \text{A} \\ \text{Interrupt EN} \\ \text{on Back-Up} \\ = 1 & \text{Addr} \\ \hline \\ \text{RAM} \\ \hline \\ \text{RS} = 1 \\ \hline \\ 10 \text{ ms} \\ \text{Interrupt} \\ \text{Enable} \\ \hline \\ \text{RS} = 1 \\ \hline \end{array}$	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms Interrupt Enable Address = 0	12/24 Hr. Mode RAM 3H Seconds Interrupt Enable 4H	Leap Year MSB RAM 10 Second Interrupt	Leap Year LSB RAM Minute Interrupt Enable	All Bits R/W All Bits R/W All Bits R/W
Time Save Enable eal Time Mo RAM utput Mode MFO as Crystal tterrupt Con RAM	N/A de Register PS RAM Register PS = RAM trol Register 0 RAM	RAM $S = 0 R$ $RAM$ $0 RS =$ $RAM$ $PS = 0$ $1 ms$ $Interrupt$ $Enable$ $PS = 0$	RAM S = 1 A Interrupt EN on Back-Up = 1 Addr RAM RS = 1 10 ms Interrupt Enable	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms Interrupt Enable	12/24 Hr. Mode RAM 3H Seconds Interrupt Enable	Leap Year MSB RAM 10 Second Interrupt Enable	Leap Year LSB RAM Minute Interrupt	All Bits R/W All Bits R/W All Bits R/W

# **Application Hints**

LV8573A

Suggested Initialization Procedure for LV8573A in Battery Backed Applications that use the  $V_{BB}\,\text{Pin}$ 

- 1. Enter the test mode by writing a 1 to bit D7 in the Periodic Flag Register.
- 2. Write zero to the RAM/TEST mode Register located in page 0, address HEX 1F.
- 3. Leave the test mode by writing a 0 to bit D7 in the Periodic Flag Register. Steps 1, 2, 3 guarantee that if the test mode had been entered during power on (due to random pulses from the system), all test mode conditions are cleared. Most important is that the OSC Fail Disable bit is cleared. Refer to AN-589 for more information on test mode operation.
- Enter a software loop that does the following: Set a 3 second(approx) software counter. The crystal oscillator may take 1 second to start.
- 4.1 Write a 1 to bit D3 in the Real Time Mode Register (try to start the clock). Under normal operation, this bit can be set only if the oscillator is running. During the software loop, RAM, real time counters, output configuration, interrupt control and timer functions may be initialized.

### Application Hints (Continued)

5. Test bit D6 in the Periodic Flag Register:

IF a 1, go to 4.1. If this bit remains a 1 after 3 seconds, then abort and check hardware. The crystal may be defective or not installed. There may be a short at OSC IN or OSC OUT to V<sub>CC</sub> or GND, or to some impedance that is less than 10 M $\Omega$ .

· · · · · · ·

IF a 0, then the oscillator is running, go to step 7.


6. Write a 0 to bit D6 in the Periodic Flag Register. This action puts the clock chip in the battery backed mode. This mode can be entered only if the OSC fail flag (bit D6 of the Periodic Flag Register) is a 0. Reminder, bit D6 is a dual function bit. When read, D6 returns oscillator status. When written, D6 causes either the Battery Backed Mode, or the Single Supply Mode of operation.


**Typical Application** 

The only method to ensure the chip is in the battery backed mode is to measure the waveform at the OSC OUT pin. If the battery backed mode was selected successfully, then the peak to peak waveform at OSC OUT is referenced to the battery voltage. If not in battery backed mode, the waveform is referenced to V<sub>CC</sub>. The measurement should be made with a high impedance low capacitance probe (10 M $\Omega$ , 10 pF oscilloscope probe or better). Typical peak to peak swings are within 0.6V of V<sub>CC</sub> and ground respectively.

LV8573A

- 7. Write a 1 to bit D7 of Interrupt Control Register 1. This action enables the PFAIL pin and associated circuitry.
- 8. Initialize the rest of the chip as needed.





LV8573A



2

Section 2 Real Time Clocks and Timer Clock Peripherals



# **Section 2 Contents**

TCP/RTC Family Comparisons	2-3
DP8570A Timer Clock Peripheral (TCP)	
DP8571A Timer Clock Peripheral (TCP)	
DP8572A/DP8572AM Real Time Clock (RTC)	2-51
DP8573A Real Time Clock (RTC)	
MM58274C-12 Microprocessor Compatible Real Time Clock	2-86
MM58274C Microprocessor Compatible Real Time Clock	2-99
MM58174A Microprocessor Compatible Real Time Clock	2-112
MM58167B Microprocessor Real Time Clock	2-119
NS32FX211 Microprocessor Compatible Real Time Clock	2-128

.



Г

Features	DP8570A	LV8571A/DP8571A	LV8572A/DP8572A	LV8573A/DP8573A
TIMEKEEPING		· · · · · · · · · · · · · · · · · · ·		· ·
Mode	12 or 24 Hour	12 or 24 Hour	12 or 24 Hour	12 or 24 Hour
Range	0.01 sec thru Years	0.01 sec thru Years	0.01 sec thru Years	0.01 sec thru Years
Leap Year	Yes	Yes	Yes	Yes
Rollover	Status Bit	Status Bit	Status Bit	Status Bit
BUS				
Mode	Parallel	Parallel	Parallel	Parallel
Address (# Bits)	5	5	5	5
Data (# Bits)	8	8	8	8
Max Access Time	100 ns	100 ns	100 ns	100 ns.:
(Address to Data Valid)				
RAM				
On-Chip	44 Bytes	44 Bytes	44 Bytes	14 Bytes
Timer	2 16-Bit	2 16-Bit	No	No
INTERRUPTS				
Programmable	0.001 sec thru 1 min	0.001 sec thru 1 min	0.001 sec thru 1 min	0.001 sec thru 1 min
Alarm Compare	Yes	Yes	Yes	Yes
Standby Mode	Yes	Yes	Yes	Yes
Status Register	Yes	Yes	Yes	Yes
Timer	Yes	Yes	No	No
TIMEBASE				
Oscillator Frequency	4 Selectable (Note 1)	4 Selectable (Note 1)	4 Selectable (Note 1)	32.768 kHz
Buffered Oscillator Output	Yes	Yes	Yes	Yes
POWER SUPPLY				
Voltage				
Operational	4.5-5.5V	3-3.6V/4.5-5.5V	3-3.6V/4.5-5.5V	3-3.6V/4.5-5.5V
Standby	2.2V min	2.2V min	2.2V min	2.2V min
Current (32.768 kHz)				
Operational	5 mA	5 mA	5 mA	5 mA
Standby (I <sub>DD</sub> Max)	10 μA	10 μA	10 μA	10 μA
PROCESS TECHNOLOGY				
	microCMOS	microCMOS	microCMOS	microCMOS
PACKAGING				
Pins/Type	28 DIP	24 DIP (Note 2)	24 DIP (Note 2)	24 DIP (Note 2)
	28 PCC (Note 2)	· , ,	28 PCC (Note 2)	28 PCC (Note

Note 1: 32 kHz, 32.768 kHz, 4.194304 MHz, 4.9152 MHz

Note 2: Socket equivalent pin outs

**RTC Family Comparison Guide** 

Features	MM58167B	MM58174A	MM58274C
IMEKEEPING			
Mode	24 Hour	24 Hour	12 or 24 Hour
Range	0.001 sec thru Months	0.1 sec thru Months	0.1 sec thru Years
Leap Year	No	Yes	Yes
Rollover	Status Bit	Yes	Status Bit
IUS			
Mode	Parallel	Parallel	Parallel
Address (# Bits)	5	4	4
Data (# Bits)	8	4	4
Max Access Time	1050 ns	2.35 μs	650 ns
(Address to Data Valid)		<i>µ</i>	
AM	· · · · ·		
On-Chip	56 Bits	No	No
	(14 × 4)		
NTERRUPTS			
Programmable	0.1 sec thru Months	0.5, 5, and 60 sec	0.1, 0.5, 1, 5, 10,
<b>C</b>			30 and 60 sec
Alarm Compare	Yes	No	No
Standby Mode	Yes	No	No
Status Register	Yes	Yes (intr)	Yes
TIMEBASE			
Oscillator Frequency	32.768 kHz	32.768 kHz	32.768 kHz
Buffered Oscillator Output	No	Yes (16.384 kHz)	Yes
POWER SUPPLY	······		
Voltage			· · · · · · · · · · · · · · · · · · ·
Operational	4.5-5.5V	4.5-5.5V	4.5-5.5V
Standby	2.2V min	2.2V min	2.2V min
Current			
Operational	5 mA	1 mA	1 mA
Standby (I <sub>DD</sub> Max)	20 µA	10 μA	10 µA
ROCESS TECHNOLOGY		······································	
··· ··· ··· ··· ·· · · · · · · ·	CMOS	CMOS	CMOS
ACKAGING	- <b>J</b>	······································	
Pins/Type	24 DIP	16 DIP	16 DIP
1 110/ 1900	28 PCC	10 81	20 PCC



# **DP8570A Timer Clock Peripheral (TCP)**

# **General Description**

The DP8570A is intended for use in microprocessor based systems where information is required for multi-tasking, data logging or general time of day/date information. This device is implemented in low voltage silicon gate microCMOS technology to provide low standby power in battery back-up environments. The circuit's architecture is such that it looks like a contiguous block of memory or I/O ports. The address space is organized as 2 software selectable pages of 32 bytes. This includes the Control Registers, the Clock Counters, the Alarm Compare RAM, the Timers and their data RAM, and the Time Save RAM. Any of the RAM locations that are not being used for their intended purpose may be used as general purpose CMOS RAM.

Time and date are maintained from 1/100 of a second to year and leap year in a BCD format, 12 or 24 hour modes. Day of week, day of month and day of year counters are provided. Time is controlled by an on-chip crystal oscillator requiring only the addition of the crystal and two capacitors. The choice of crystal frequency is program selectable.


Two independent multifunction 10 MHz 16-bit timers are provided. These timers operate in four modes. Each has its own prescaler and can select any of 8 possible clock inputs. Thus, by programming the input clocks and the timer counter values a very wide range of timing durations can be achieved. The range is from about 400 ns (4.915 MHz oscillator) to 65,535 seconds (18 hrs., 12 min.).

Power failure logic and control functions have been integrated on chip. This logic is used by the TCP to issue a power fail interrupt, and lock out the  $\mu p$  interface. The time power fails may be logged into RAM automatically when  $V_{BB} > V_{CC}.$  Additionally, two supply pins are provided. When  $V_{BB} > V_{CC}$ , internal circuitry will automatically switch from the main supply to the battery supply. Status bits are provided to indicate initial application of battery power, system power, and low battery detect. (Continued)

### **Features**

- Full function real time clock/calendar
  - 12/24 hour mode timekeeping
  - Day of week and day of years counters
  - Four selectable oscillator frequencies
  - Parallel Resonant Oscillator
- Two 16-bit timers
  - 10 MHz external clock frequency
  - Programmable multi-function output
  - Flexible re-trigger facilities
- Power fail features
  - Internal power supply switch to external battery
  - Power Supply Bus glitch protection
  - Automatic log of time into RAM at power failure
- On-chip interrupt structure
  - Periodic, alarm, timer and power fail interrupts
- Up to 44 bytes of CMOS RAM
- INTR/MFO/T1 pins programmable High/Low and pushpull or open drain

## **Block Diagram**



### Absolute Maximum Ratings (Notes 1 & 2)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Supply Voltage (V <sub>CC</sub> )	-0.5V to +7.0V
DC Input Voltage (V <sub>IN</sub> )	-0.5V to V <sub>CC</sub> +0.5V
DC Output Voltage (V <sub>OUT</sub> )	-0.5V to V <sub>CC</sub> + 0.5V
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.)	260°C

### **Operation Conditions**

<b>Min</b> 4.5	<b>Max</b> 5.5	Unit V	
2.2	$V_{CC}-0.4$	v	
0.0	V <sub>CC</sub>	V	
-40	+ 85	°C	
	1	kV	
	15,200		
· • E	30ard = 45	°C/W	
- S	ocket = 50	°C/W	
1	Board = 77	°C/W	
j S	ocket = 85	°C/W	
	4.5 2.2 0.0 40	4.5 5.5 2.2 $V_{CC} - 0.4$ 0.0 $V_{CC}$ -40 +85 1 15,200 Board = 45 Socket = 50 Board = 77	$\begin{array}{cccccc} 4.5 & 5.5 & V \\ 2.2 & V_{CC} - 0.4 & V \\ 0.0 & V_{CC} & V \\ -40 & +85 & ^{\circ}C \\ & 1 & kV \end{array}$

# **DC Electrical Characteristics**

 $V_{CC} = 5V \pm 10\%$ ,  $V_{BB} = 3V$ ,  $V_{\overline{PFAIL}} > V_{IH}$ ,  $C_L = 100 \text{ pF}$  (unless otherwise specified)

Symbol	Parameter	Conditions	Min	Max	Units
VIH .	High Level Input Voltage (Note 4)	Any Inputs Except OSC IN, OSC IN with External Clock	2.0 V <sub>BB</sub> -0.1		VV
V <sub>IL</sub>	Low Level Input Voltage	All Inputs Except OSC IN OSC IN with External Clock		0.8 0.1	V
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = -20 \mu A$ $I_{OUT} = -4.0 \mu A$	V <sub>CC</sub> -0.1 3.5		V V
V <sub>OL</sub>	Low Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = 20 \ \mu A$ $I_{OUT} = 4.0 \ m A$		0.1 0.25	V V
l <sub>IN</sub>	Input Current (Except OSC IN)	$V_{IN} = V_{CC} \text{ or } GND$		±1.0	μA
loz	Output TRI-STATE® Current	$V_{OUT} = V_{CC} \text{ or } GND$		±5.0	μΑ
I <sub>LKG</sub>	Output High Leakage Current T1, MFO, INTR Pins	V <sub>OUT</sub> = V <sub>CC</sub> or GND Outputs Open Drain		±5.0	μΑ
ICC	Quiescent Supply Current (Note 7)	$\begin{array}{l} F_{OSC} = 32.768 \text{ kHz} \\ V_{IN} = V_{CC} \text{ or GND} (\text{Note 5}) \\ V_{IN} = V_{CC} \text{ or GND} (\text{Note 6}) \\ V_{IN} = V_{IH} \text{ or } V_{IL} (\text{Note 6}) \end{array}$		260 1.0 12.0	μA mA mA
		$\begin{array}{l} F_{OSC} = \ 4.194304 \ \text{MHz or} \\ 4.9152 \ \text{MHz} \\ V_{IN} = \ V_{CC} \ \text{or} \ \text{GND} \ (\text{Note} \ 6) \\ V_{IN} = \ V_{IH} \ \text{or} \ V_{IL} \ (\text{Note} \ 6) \end{array}$		8 20	mA mA
Icc	Quiescent Supply Current (Single Supply Mode) (Note 7)	$\begin{array}{l} V_{BB} = GND \\ V_{IN} = V_{CC}  or  GND \\ F_{OSC} = 32.768  \text{kHz} \\ F_{OSC} = 4.9152  \text{MHz}  or \\ 4.194304  \text{MHz} \end{array}$		80 7.5	μA mA
I <sub>BB</sub>	Standby Mode Battery Supply Current (Note 8)	$\begin{array}{l} V_{CC} = GND\\ OSC OUT = Open Circuit,\\ Other Pins = GND\\ F_{OSC} = 32.768  \text{kHz}\\ F_{OSC} = 4.9152  \text{MHz}  \text{or}\\ 4.194304  \text{MHz} \end{array}$		10 400	μΑ μΑ
I <sub>BLK</sub>	Battery Supply Leakage	$\begin{array}{l} 2.2V \leq V_{BB} \leq 4.0V\\ \text{Other Pins at GND}\\ V_{CC} = \text{GND}, V_{BB} = 4.0V\\ V_{CC} = 5.5V, V_{BB} = 2.2V \end{array}$	-5	1.5	μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: For  $F_{OSC}$  = 4.194304 or 4.9152 MHz, V<sub>BB</sub> minimum = 2.8V. In battery backed mode, V<sub>BB</sub>  $\leq$  V<sub>CC</sub> -0.4V.

Single Supply Mode: Data retention voltage is 2.2V min.

In single Supply Mode (Power connected to V\_{CC} pin) 4.5V  $\,\leq\,$  V\_{CC}  $\,\leq\,$  5.5V.

Note 4: This parameter (VIH) is not tested on all pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: This specification is tested with both the timers and OSC IN driven by a signal generator. Contents of the Test Register = 00(H), the MFO pin is not configured as buffered oscillator out and MFO, T1, INTR, are configured as open drain.

Note 8: This specification is tested with both the timers off, and only OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

Symbol	Parameter	Min	Max	Units
READ TIMING		141111	Max	01113
t <sub>AR</sub>	Address Valid Prior to Read Strobe	20		ns
t <sub>RW</sub>	Read Strobe Width (Note 9)	80		ns
t <sub>CD</sub>	Chip Select to Data Valid Time		80	ns
t <sub>RAH</sub>	Address Hold after Read (Note 10)	3		ns
t <sub>RD</sub>	Read Strobe to Valid Data		70	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		60	ns
t <sub>RCH</sub>	Chip Select Hold after Read Strobe	0		ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses	50		ns
WRITE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	20		ns
twah	Address Hold after Write Strobe (Note 10)	3		ns
t <sub>CW</sub>	Chip Select to End of Write Strobe	90		ns
t <sub>ww</sub>	Write Strobe Width (Note 11)	80		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	50		ns
twDH	Data Hold after Write Strobe (Note 10)	3		ns
twch .	Chip Select Hold after Write Strobe	. 0		ns
IMER 0/TIMER 1	TIMING			
F <sub>TCK</sub>	Input Frequency Range	DC	10	MHz
t <sub>CK</sub>	Propagation Delay Clock to Output		120	ns
t <sub>GO</sub>	Propagation Delay G0 to G1 to Timer Output (Note 12)		100	ns
t <sub>PGW</sub>	Pulse Width G0 or G1 _T_ (Note 12)	25		ns
t <sub>GS</sub>	Setup Time, G0, G1 to TCK (Note 13)	<sub>100</sub>		ns

Note 9: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when both signals are low and terminates when either signal returns high.

Note 10: Hold time is guaranteed by design but not production tested. This limit is not used to calculate outgoing quality levels.

Note 11: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

Note 12: Timers in Mode 3.

Note 13: Guaranteed by design, not production tested. This limit is not used to calculate outgoing quality levels.

5 5

### **AC Test Conditions**

Input Pulse Levels	GND to 3.0V
Input Rise and Fall Times	6 ns (10%–90%)
Input and Output Reference Levels	1.3V
TRI-STATE Reference	Active High +0.5V
Levels (Note 15)	Active Low -0.5V


Note 14: CL = 100 pF, includes jig and scope capacitance.

- Note 15: S1 =  $V_{CC}$  for active low to high impedance measurements.
  - S1 = GND for active high to high impedance measurements. S1 = open for all other timing measurements.

Symbol	Parameter (Note 16)	Тур	Units	
CiN	Input Capacitance	5	pF	
COUT	Output Capacitance	7	рF	

Note 16: This parameter is not 100% tested.


Note 17: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.



2


DP8570A

## **Timing Waveforms**



TL/F/8638-24





DP8570A

## General Description (Continued)

The DP8570A's interrupt structure provides four basic types of interrupts: Periodic, Alarm/Compare, Timer, and Power Fail. Interrupt mask and status registers enable the masking and easy determination of each interrupt.

One dedicated general purpose interrupt output is provided. A second interrupt output is available on the Multiple Function Output (MFO) pin. Each of these may be selected to generate an interrupt from any source. Additionally, the MFO pin may be programmed to be either as oscillator output or Timer 0's output.

## **Pin Description**

 $\overline{\text{CS}}$ ,  $\overline{\text{RD}}$ ,  $\overline{\text{WR}}$  (Inputs): These pins interface to  $\mu$ P control lines. The  $\overline{\text{CS}}$  pin is an active low enable for the read and write operations. Read and Write pins are also active low and enable reading or writing to the TCP. All three pins are disabled when power failure is detected. However, if a read or write is in progress at this time, it will be allowed to complete its cycle.

A0-A4 (Inputs): These 5 pins are for register selection. They individually control which location is to be accessed. These inputs are disabled when power failure is detected.

**OSC IN (Input): OSC OUT (Output):** These two pins are used to connect the crystal to the internal parallel resonant oscillator. The oscillator is always running when power is applied to  $V_{BB}$  and  $V_{CC}$ , and the correct crystal select bits in the Real Time Mode Register have been set.

**MFO (Output):** The multi-function output can be used as a second interrupt output for interrupting the  $\mu$ P. This pin can also provide an output for the oscillator or the internal Timer 0. The MFO output can be programmed active high or low, open drain or push-pull. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>. This pin is configured open drain during battery operation (V<sub>BB</sub> > V<sub>CC</sub>).

**INTR (Output):** The interrupt output is used to interrupt the processor when a timing event or power fail has occurred and the respective interrupt has been enabled. The INTR output can be programmed active high or low, push-pull or open drain. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>. This pin is configured open drain during battery operation (V<sub>BB</sub> > V<sub>CC</sub>). The output is a DC voltage level. To clear the INTR, write a 1 to the appropriate bit(s) in the Main Status Register.

**D0–D7 (Input/Output):** These 8 bidirectional pins connect to the host  $\mu$ P's data bus and are used to read from and write to the TCP. When the **PFAIL** pin goes low and a write is not in progress, these pins are at TRI-STATE.

**PFAIL** (Input): In battery backed mode, this pin can have a digital signal applied to it via some external power detection logic. When **PFAIL** = logic 0 the TCP goes into a lockout mode, in a minimum of 30  $\mu$ s or a maximum of 63  $\mu$ s unless lockout delay is programmed. In the single power supply mode, this pin is not useable as an input and should be tied to V<sub>CC</sub>. Refer to section on Power Fail Functional Description.


 $V_{BB}$  (Battery Power Pin): This pin is connected to a backup power supply. This power supply is switched to the internal circuitry when the  $V_{CC}$  becomes lower than  $V_{BB}$ . Utilizing this pin eliminates the need for external logic to switch in and out the back-up power supply. If this feature is not to be used then this pin must be tied to ground, the TCP programmed for single power supply only, and power applied to the  $V_{CC}$  pin.

TCK, G1, G0, (Inputs), T1 (Output): TCK is the clock input to both timers when they have an external clock selected. In modes 0, 1, and 2, G0 and G1 are active low enable inputs for timers 0 and 1 respectively. In mode 3, G0 and G1 are positive edge triggers to the timers. T1 is dedicated to the timer 1 output. The T1 output can be programmed active high or low, push-pull or open drain. Timer 0 output is available through MFO pin if desired. If in battery backed mode and a pull-up resistor is attached to T1, it should be connected to a voltage no greater than  $V_{BB}$ . The T1 pin is configured open drain during battery operation ( $V_{BB} > V_{CC}$ ).

Vcc: This is the main system power pin.

GND: This is the common ground power pin for both  $\mathsf{V}_{BB}$  and  $\mathsf{V}_{CC}.$ 


## **Connection Diagrams**



TL/F/8638-5

Top View Order Number DP8570AN See NS Package Number N28B

#### Plastic Chip Carrier



TL/F/8638-6

Top View Order Number DP8570AV See NS Package Number V28A

# DP8570A

## **Functional Description**

The DP8570A contains a fast access real time clock, two 10 MHz 16-bit timers, interrupt control logic, power fail detect logic, and CMOS RAM. All functions of the TCP are controlled by a set of nine registers. A simplified block diagram that shows the major functional blocks is given in *Figure 1*.

The blocks are described in the following sections:

- 1. Real Time Clock
- 2. Oscillator Prescaler
- 3. Interrupt Logic
- 4. Power Failure Logic
- 5. Additional Supply Management
- 6. Timers

The memory map of the TCP is shown in the memory addressing table. The memory map consists of two 31 byte pages with a main status register that is common to both pages. A control bit in the Main Status Register is used to select either page. *Figure 2* shows the basic concept. Page 0 contains all the clock timer functions, while page 1 has scratch pad RAM. The control registers are split into two separate blocks to allow page 1 to be used entirely as scratch pad RAM. Again a control bit in the Main Status Register is used to select either control register block.

	Page Select = 0		
1F	RAM/TEST Register	1	Page Select = 1
	RAM	15	RAM
10	Months Time Save RAM	16	RAM
10	Day of Month Time Save RAM	1D	RAM
. 1B	Hours Time Save RAM	10	RAM
· 18	Minutes Time Save RAM	10 18	RAM
19	Seconds Time Save RAM	14	RAM
19	Day of Week Compare RAM	19	RAM
17	Months Compare RAM	19	RAM
16	Day of Month Compare RAM	18	RAM
15	Hours Compare RAM	16	RAM
14	Minutes Compare RAM	15	RAM
13	Seconds Compare RAM	13	RAM
12	Timer 1 MSB	13	RAM
11	Timer 1 LSB	13	RAM
10	Timer 0 MSB	11	RAM
0F	Timer 0 LSB	10	RAM
OE	Day of Week Clock Counter	OF	RAM
0D	100's Julian Clock Counter	OE	RAM
00	Units Julian Clock Counter	OD OD	RAM
08	Years Clock Counter	OC OC	RAM
08 0A	Months Clock Counter	0C 0B	RAM
09	Day of Month Clock Counter	40 A0	RAM
03	Hours Clock Counter	09	RAM
07	Minutes Clock Counter	08	RAM
06	Seconds Clock Counter	07	RAM
05	1/100 Second Counter	06	RAM
00		05	RAM
		04	RAM
Register Selec	ct = 0 Re	egister Select = 1 03	RAM
nterrupt Rout	ting Register 04 Interrupt	Control Register 1 02	RAM
Periodic Fla		Control Register 0 01	RAM
Timer 1 Cont		t Mode Register	NAM
Timer 0 Cont		me Mode Register	
•		Main Status Register	- -
	FIGURE 2. DP8	3570A Internal Memory N	ар

TL/F/8638-4

## Functional Description (Continued) INITIAL POWER-ON of BOTH V<sub>BB</sub> and V<sub>CC</sub>

 $V_{BB}$  and  $V_{CC}$  may be applied in any sequence. In order for the power fail circuitry to function correctly, whenever power is off, the  $V_{CC}$  pin must see a path to ground through a maximum of 1 MΩ. The user should be aware that the control registers will contain random data. The first task to be carried out in an initialization routine is to start the oscillator by writing to the crystal select bits in the Real Time Mode Register. If the DP8570A is configured for single supply mode, an extra 50  $\mu A$  may be consumed until the crystal select bits are programmed. The user should also ensure that the TCP is not in test mode (see register descriptions).

#### **REAL TIME CLOCK FUNCTIONAL DESCRIPTION**

As shown in *Figure 2*, the clock has 10 bytes of counters, which count from 1/100 of a second to years. Each counter counts in BCD and is synchronously clocked. The count sequence of the individual byte counters within the clock is shown later in Table VII. Note that the day of week, day of month, day of year, and month counters all roll over to 1. The hours counter in 12 hour mode rolls over to 1 and the AM/PM bit toggles when the hours rolls over to 12 (AM = 0, PM = 1). The AM/PM bit is bit D7 in the hours counter.

All other counters roll over to 0. Also note that the day of year counter is 12 bits long and occupies two addresses. Upon initial application of power the counters will contain random information.

## READING THE CLOCK: VALIDATED READ

Since clocking of the counter occurs asynchronously to reading of the counter, it is possible to read the counter while it is being incremented (rollover). This may result in an incorrect time reading. Thus to ensure a correct reading of the entire contents of the clock (or that part of interest), it must be read without a clock rollover occurring. In general this can be done by checking a rollover bit. On this chip the periodic interrupt status bits can serve this function. The following program steps can be used to accomplish this.

- 1. Initialize program for reading clock.
- 2. Dummy read of periodic status bit to clear it.
- 3. Read counter bytes and store.
- 4. Read rollover bit, and test it.
- 5. If rollover occured go to 3.
- 6. If no rollover, done.

To detect the rollover, individual periodic status bits can be polled. The periodic bit chosen should be equal to the highest frequency counter register to be read. That is if only SECONDS through HOURS counters are read, then the SECONDS periodic bit should be used.

#### **READING THE CLOCK: INTERRUPT DRIVEN**

Enabling the periodic interrupt mask bits cause interrupts just as the clock rolls over. Enabling the desired update rate and providing an interrupt service routine that executes in less than 10 ms enables clock reading without checking for a rollover.

## READING THE CLOCK: LATCHED READ

Another method to read the clock that does not require checking the rollover bit is to write a one into the Time

Save Enable bit (D7) of the Interrupt Routing Register, and then to write a zero. Writing a one into this bit will enable the clock contents to be duplicated in the Time Save RAM. Changing the bit from a one to a zero will freeze and store the contents of the clock in Time Save RAM. The time then can be read without concern for clock rollover, since internal logic takes care of synchronization of the clock. Because only the bits used by the clock counters will be latched, the Time Save RAM should be cleared prior to use to ensure that random data stored in the unused bits do not confuse the host microprocessor. This bit can also provide time save at power failure, see the Additional Supply Management Functions section. With the Time Save Enable bit at a logical 0, the Time Save RAM may be used as RAM if the latched read function is not necessary.

# INITIALIZING AND WRITING TO THE CALENDAR-CLOCK

Upon initial application of power to the TCP or when making time corrections, the time must be written into the clock. To correctly write the time to the counters, the clock would normally be stopped by writing the Start/Stop bit in the Real Time Mode Register to a zero. This stops the clock from counting and disables the carry circuitry. When initializing the clock's Real Time Mode Register, it is recommended that first the various mode bits be written while maintaining the Start/Stop bit reset, and then writing to the register a second time with the Start/Stop bit set.

The above method is useful when the entire clock is being corrected. If one location is being updated the clock need not be stopped since this will reset the prescaler, and time will be lost. An ideal example of this is correcting the hours for daylight savings time. To write to the clock "on the fly" the best method is to wait for the 1/100 of a second periodic interrupt. Then wait an additional 16  $\mu$ s, and then write the data to the clock.

# PRESCALER/OSCILLATOR FUNCTIONAL DESCRIPTION

Feeding the counter chain is a programmable prescaler which divides the crystal oscillator frequency to 32 kHz and further to 100 Hz for the counter chain (see *Figure 3*). The crystal frequency that can be selected are: 32 kHz, 32.768 kHz, 4.9152 MHz, and 4.194304 MHz.

Once 32 kHz is generated it feeds both timers and the clock. The clock and timer prescalers can be independently enabled by controlling the timer or clock Start/Stop bits.




FIGURE 3. Programmable Clock Prescaler Block

The oscillator is programmed via the Real Time Mode Register to operate at various frequencies. The crystal oscillator is designed to offer optimum performance at each frequency. Thus, at 32.768 kHz the oscillator is configured as a low frequency and low power oscillator. At the higher frequencies the oscillator inverter is reconfigured. In addition to the inverter, the oscillator feedback bias resistor is included on chip, as shown in *Figure 4*. The oscillator input may be driven from an external source if desired. Refer to test mode application note for details. The oscillator stability is enhanced through the use of an on chip regulated power supply.

The typical range of trimmer capacitor (as shown in Oscillator Circuit Diagram *Figure 4*, and in the typical application) at the oscillator input pin is suggested only to allow accurate tuning of the oscillator. This range is based on a typical printed circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases, the **load capacitance** specified by the crystal manufacturer (nominal value 11 pF for the 32.768 crystal) is what determines proper oscillation. This load capcitance is the series combination of capacitance on each side of the crystal (with respect to ground).




FIGURE 4. Oscillator Circuit Diagram

XTAL	C <sub>o</sub>	Ct	R <sub>OUT</sub> (Switched Internally)
32/32.768 kHz	47 pF	2 pF-22 pF	150 kΩ to 350 kΩ
4.194304 MHz	68 pF	0 pF-80 pF	500Ω to 900Ω
4.9152 MHz	68 pF	29 pF-49 pF	500 $\Omega$ to 900 $\Omega$

## INTERRUPT LOGIC FUNCTIONAL DESCRIPTION

The TCP has the ability to coordinate processor timing activities. To enhance this, an interrupt structure has been implemented which enables several types of events to cause interrupts. Interrupts are controlled via two Control Registers in block 1 and two Status Registers in block 0. (See Register Description for notes on paging and also *Figure 5* and Table I.) The interrupts are enabled by writing a one to the appropriate bits in Interrupt Control Register 0 and/or 1. Any of the interrupts can be routed to either the INTR pin or the MFO pin, depending on how the Interrupt Routing register is programmed. This, for example, enables the user to dedicate the MFO as a non-maskable interrupt pin to the CPU for power failure detection and enable all other interrupts to appear on the INTR pin. The polarity for the active interrupt can be programmed in the Output Mode Register for either active high or low, and open drain or push pull outputs.

TABLE I	. Registers	; that are	Applicable
	to Interru	pt Contr	ol

Register Name	Register Select	Page Select	Address		
Main Status Register	X	X	00H		
Periodic Flag Register	0	. 0	03H		
Interrupt Routing Register	0	0	04H		
Interrupt Control Register 0	1	0	озн		
Interrupt Control Register 1	1	0	04H		
Output Mode Register	1	0	02H		

The Interrupt Status Flag D0, in the Main Status Register, indicates the state of INTR and MFO outputs. It is set when either output becomes active and is cleared when all TCP interrupts have been cleared and no further interrupts are pending (i.e., both INTR and MFO are returned to their inactive state). This flag enables the TCP to be rapidly polled by the  $\mu$ P to determine the source of an interrupt in a wired—OR interrupt system.

Note that the Interrupt Status Flag will only monitor the state of the MFO output if it has been configured as an interrupt output (see Output Mode Register description). This is true, regardless of the state of the Interrupt Routing Register. Thus the Interrupt Status Flag provides a true reflection of all conditions routed to the external pins.

Status for the interrupts are provided by the Main Status Register and the Periodic Flag Register. Bits D1–D5 of the Main Status Register are the main interrupt bits.

These register bits will be set when their associated timing events occur. Enabled Alarm or Timer interrupts that occur will set its Main Status Register bit to a one. However, an external interrupt will only be generated if the appropriate Alarm or Timer interrupt enable bits are set (see *Figure 5*).

Disabling the periodic bits will mask the Main Status Register periodic bit, but not the Periodic Flag Register bits. The Power Fail Interrupt bit is set when the interrupt is enabled and a power fail event has occurred, and is not reset until the power is restored. If all interrupt enable bits are 0 no interrupt will be asserted. However, status still can be read from the Main Status Register in a polled fashion (see *Figure 5*).

To clear a flag in bits D2–D5 of the Main Status Register a 1 must be written back into the bit location that is to be cleared. For the Periodic Flag Register reading the status will reset all the periodic flags.

Interrupts Fall Into Four Categories:

- 1. The Timer Interrupts: For description see Timer Section.
- 2. The Alarm Compare Interrupt: Issued when the value in the time compared RAM equals the counter.
- 3. The Periodic Interrupts: These are issued at every increment of the specific clock counter signal. Thus, an interrupt is issued every minute, second, etc. Each of these interrupts occurs at the roll-over of the specific counter.
- 4. The Power Fail Interrupt: Issued upon recognition of a power fail condition by the internal sensing logic. The power failed condition is determined by the signal on the PFAIL pin. The internal power fail signal is gated with the chip select signal to ensure that the power fail interrupt does not lock the chip out during a read or write.

## ALARM COMPARE INTERRUPT DESCRIPTON

The alarm/time comparison interrupt is a special interrupt similar to an alarm clock wake up buzzer. This interrupt is generated when the clock time is equal to a value programmed into the alarm compare registers. Up to six bytes can be enabled to perform alarm time comparisons on the counter chain. These six bytes, or some subset thereof, would be loaded with the future time at which the interrupt will occur. Next, the appropriate bits in the Interrupt Control Register 1 are enabled or disabled (refer to detailed description of Interrupt Control Register 1). The TCP then compares these bytes with the clock time. When all the enabled compare registers equal the clock time an alarm interrupt is issued, but only if the alarm compare interrupt is enabled can the interrupt be generated externally. Each alarm compare bit in the Control Register will enable a specific byte for comparison to the clock. Disabling a compare byte is the same as setting its associated counter comparator to an "always equal" state. For example, to generate an interrupt at 3:15 AM of every day, load the hours compare with 0 3 (BCD), the minutes compare with 1 5 (BCD) and the faster counters with 0 0 (BCD), and then disable all other compare registers. So every day when the time rolls over from 3:14:59.99, an interrupt is issued. This bit may be reset by writing a one to bit D3 in the Main Status Register at any time after the alarm has been generated.

If time comparison for an individual byte counter is disabled, that corresponding RAM location can then be used as general purpose storage.

#### PERIODIC INTERRUPTS DESCRIPTION

The Periodic Flag Register contains six flags which are set by real-time generated "ticks" at various time intervals, see *Figure 5*. These flags constantly sense the periodic signals and may be used whether or not interrupts are enabled. These flags are cleared by any read or write operation performed on this register. To generate periodic interrupts at the desired rate, the associated Periodic Interrupt Enable bit in Interrupt Control Register 0 must be set. Any combination of periodic interrupts may be enabled to operate simultaneously. Enabled periodic interrupts will now affect the Periodic Interrupt Flag in the Main Status Register. The Periodic Route bit in the Interrupt Routing Register is used to route the periodic interrupt events to either the INTR output or the MFO output.

When a periodic event occurs, the Periodic Interrupt Flag in the Main Status Register is set, causing an interrupt to be generated. The  $\mu$ P clears both flag and interrupt by writing a "1" to the Periodic Interrupt Flag. The individual flags in the periodic Interrupt Flag Register do not require clearing to cancel the interrupt.

If all periodic interrupts are disabled and a periodic interrupt is left pending (i.e., the Periodic Interrupt Flag is still set), the Periodic Interrupt Flag will still be required to be cleared to cancel the pending interrupt.

## POWER FAIL INTERRUPTS DESCRIPTION

The Power Fail Status Flag in the Main Status Register monitors the state of the internal power fail signal. This flag may be interrogated by the  $\mu$ P, but it cannot be cleared; it is cleared automatically by the TCP when system power is restored. To generate an interrupt when the power fails, the Power Fail Interrupt Enable bit in Interrupt Control Register 1 is set.

The Power Fail Route bit determines which output the interrupt will appear on. Although this interrupt may not be cleared, it may be masked by clearing the Power Fail Interrupt Enable bit.


# POWER FAILURE CIRCUITRY FUNCTIONAL DESCRIPTION

Since the clock must be operated from a battery when the main system supply has been turned off, the DP8570A provides circuitry to simplify design in battery backed systems. This circuitry switches over to the back up supply, and isolates the DP8570A from the host system. *Figure 6* shows a simplified block diagram of this circuitry, which consists of three major sections; 1) power loss logic: 2) battery switch over logic: and 3) isolation logic.


Detection of power loss occurs when  $\overrightarrow{\mathsf{PFAIL}}$  is low. Debounce logic provides a 30  $\mu$ s-63  $\mu$ s debounce time, which will prevent noise on the  $\overrightarrow{\mathsf{PFAIL}}$  pin from being interpreted as a system failure. After 30  $\mu$ s-63  $\mu$ s the debounce logic times out and a signal is generated indicating that system power is marginal and is failing. The Power Fail Interrupt will then be generated.

## DP8570A

4



2-14



#### FIGURE 6. System-Battery Switchover (Upper Left), Power Fail and Lock-Out Circuits (Lower Right)

The user may choose to have this power failed signal lockout the TCP's data bus within 30 µs min/63 µs max or to delay the lock-out to enable µP access after power failure is detected. This delay is enabled by setting the delay enable bit in the Routing Register. Also, if the lock-out delay was not enabled the TCP will disconnect itself from the bus within 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max. If chip select is low when a power failure is detected, a safety circuit will ensure that if a read or write is held active continuously for greater than 30 µs after the power fail signal is asserted, the lock-out will be forced. If a lock-out delay is enabled, the DP8570A will remain active for 480 µs after power fail is detected. This will enable the µP to perform last minute bookkeeping before total system collapse. When the host CPU is finished accessing the TCP it may force the bus lock-out before 480 μs has elapsed by resetting the delay enable bit.

The battery switch over circuitry is completely independent of the  $\overline{\text{PFAIL}}$  pin. A separate circuit compares  $V_{CC}$  to the  $V_{BB}$  voltage. As the main supply fails, the TCP will continue to operate from the  $V_{CC}$  pin until  $V_{CC}$  falls below the  $V_{BB}$  voltage. At this time, the battery supply is switched in  $V_{CC}$  is disconnected, and the device is now in the standby mode. If indeterminate operation of the battery switch over circuit is to be avoided, then the voltage at the  $V_{CC}$  pin must not be allowed to equal the voltage at the  $V_{BB}$  pin.

After the generation of a lock-out signal, and eventual switch in of the battery supply, the pins of the TCP will be configured as shown in Table II. Outputs that have a pull-up resistor should be connected to a voltage no greater than  $V_{BB}$ .

DP8570A

TABLE II. Pin Isolation during a Power Failure

Pin	PFAIL = Logic 0	Standby Mode V <sub>BB</sub> > V <sub>CC</sub>
CS, RD, WR	Locked Out	Locked Out
A0-A4	Locked Out	Locked Out
D0-D7	Locked Out	Locked Out
Oscillator .	Not Isolated	Not Isolated
TCK, G0, G1	Not Isolated	Locked Out
PFAIL	Not Isolated	Not Isolated
INTR, MFO T1	Not Isolated	Open Drain

The Timer and Interrupt Power Fail Operation bits in the Real-Time Mode Register determine whether or not the timers and interrupts will continue to function after a power fail event.

As power returns to the system, the battery switch over circuit will switch back to V<sub>CC</sub> power as soon as it becomes greater than the battery voltage. The chip will remain in the locked out state as long as  $\overrightarrow{PFAIL} = 0$ . When  $\overrightarrow{PFAIL} = 1$ 

the chip is unlocked, but only after another 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max debounce time. The system designer must ensure that his system is stable when power has returned.

The power fail circuitry contains active linear circuitry that draws supply current from V<sub>CC</sub>. In some cases this may be undesirable, so this circuit can be disabled by masking the power fail interrupt. The power fail input can perform all lock-out functions previously mentioned, except that no external interrupt will be issued. Note that the linear power fail circuitry is switched off automatically when using V<sub>BB</sub> in standby mode.

# LOW BATTERY, INITIAL POWER ON DETECT, AND POWER FAIL TIME SAVE

There are three other functions provided on the DP8570A to ease power supply control. These are an initial Power On detect circuit, which also can be used as a time keeping failure detect, a low battery detect circuit, and a time save on power failure.

On initial power up the Oscillator Fail Flag will be set to a one and the real time clock start bit reset to a zero. This indicates that an oscillator fail event has occurred, and time keeping has failed.

The Oscillator Fail flag will not be reset until the real-time clock is started. This allows the system to discriminate between an initial power-up and recovery from a power failure. If the battery backed mode is selected, then bit D6 of the Periodic Flag Register must be written low. This will not affect the contents of the Oscillator Fail Flag.

Another status bit is the low battery detect. This bit is set only when the clock is operating under the  $V_{CC}$  pin, and when the battery voltage is determined to be less than 2.1V (typical). When the power fail interrupt enable bit is low, it disables the power fail circuit and will also shut off the low battery voltage detection circuit as well.

To relieve CPU overhead for saving time upon power failure, the Time Save Enable bit is provided to do this automatically. (See also Reading the Clock: Latched Read.) The Time Save Enable bit, when set, causes the Time Save RAM to follow the contents of the clock. This bit can be reset by software, but if set before a power failure occurs, it will automatically be reset when the clock switches to the battery supply (not when a power failure is detected by the PFAIL pin). Thus, writing a one to the Time Save bit enables both a software write or power fail write.

#### SINGLE POWER SUPPLY APPLICATIONS

The DP8570A can be used in a single power supply application. To achieve this, the V<sub>BB</sub> pin must be connected to ground, and the power connected to V<sub>CC</sub> and PFAIL pins. The Oscillator Failed/Single Supply bit in the Periodic Flag Register should be set to a logic 1, which will disable the oscillator battery reference circuit. The power fail interrupt should also be disabled. This will turn off the linear power fail detection circuits, and will eliminate any quiescent power drawn through these circuits. Until the crystal select bits are initialized, the DP8570A may consume about 50  $\mu$ A due to arbitrary oscillator selection at power on.

(This extra 50  $\mu$ A is not consumed if the battery backed mode is selected).

#### TIMER FUNCTIONAL DESCRIPTION

The DP8570A contains 2 independent multi-mode timers. Each timer is composed of a 16-bit negative edge triggered binary down counter and associated control. The operation is similar to existing  $\mu$ P peripheral timers except that several features have been enhanced. The timers can operate in four modes, and in addition, the input clock frequency can be selected from a prescaler over a wide range of frequencies. Furthermore, these timers are capable of generating interrupts as well as hardware output signals, and both the interrupt and timer outputs are fully programmable active high, or low, open drain, or push-pull.

Figure 7 shows the functional block diagram of one of the timers. The timer consists of a 16-bit counter, two 8-bit input registers, two 8-bit output registers, clock prescaler, mode control logic, and output control logic. The timer and the data registers are organized as two bytes for each timer. Under normal operations a read/write to the timer locations will read or write to the data input register. The timer contents can be read by setting the counter Read bit (RD) in the timer control register.

#### TIMER INITIALIZATION

The timer's operation is controlled by a set of registers, as listed in Table III. These consist of 2 data input registers and one control register per timer. The data input registers contain the timers count down value. The Timer Control Register is used to set up the mode of operation and the input clock rate. The timer related interrupts can be controlled by programming the Interrupt Routing Register and Interrupt Control Register 0. The timer outputs are configured by the Output Mode Register.

TABLE III	Timer	Associated	Registers
-----------	-------	------------	-----------

Register Name	Register Select	Page Select	Address
Timer 0 Data MSB	х	0	10H
Timer 0 Data LSB	X	0	0FH
Timer 0 Control Register	0	0	01H
Timer 1 Data MSB	<b>X</b> .	0	12H
Timer 1 Data LSB	X	. 0	11H
Timer 1 Control Register	0	· 0	02H
Interrupt Routing Register	0	- 0	04H
Interrupt Control Reg. 0	. d .	0.	03H 🚊
Output Mode Register	<b>1</b>	. O	02H

All these registers must be initialized prior to starting the timer(s). The Timer Control Register should first be set to select the timer mode with the timer start/stop bit reset. Then when the timer is to be started the control register should be rewritten identically but with the start/stop bit set.

#### TIMER OPERATION

Each timer is capable of operation in one of four modes. As mentioned, these modes are programmed in each timer's Control Register which is described later. All four modes operate in a similar manner. They operate on the two 8-bit data words stored into the Data Input Register. At the beginning of a counting cycle the 2 bytes are loaded into the timer and the timer commences counting down towards zero. The exact action taken when zero is reached depends on the mode selected, but in general, the timer output will change state, and an interrupt will be generated if the timer interrupts are unmasked.

INPUT CLOCK SELECTION

The input frequency to the timers may be selected. Each timer has a prescaler that gives a wide selection of clocking rates. In addition, the DP8570A has a single external clock input pin that can be selected for either of the timers. Table IV shows the range of programmable clocks available and the corresponding setting in the Timer Control Register.

## TABLE IV. Programmable Timer Input Clocks

Selected Clock	C0	C1	C2
External	0	0	0
Crystal Oscillator	1	0	°o
(Crystal Oscillator)/4	0	1	0
93.5 μs (10.7 kHz)	1	1	0
1 ms (1 kHz)	0	0	1
10 ms (100 Hz)	1	. 0	1
1/10 Second (10 Hz)	0	1	1
1 Second (1 Hz)	1	. 1	1

Note that the second and third selections are not fixed frequencies, but depend on the crystal oscillator frequency chosen.

Since the input clock frequencies are usually running asynchronously to the timer Start/Stop control bit, a 1 clock cycle error may result. This error results when the Start/Stop occurs just after the clock edge (max error). To minimize this error on all clocks an independent prescaler is used for each timer and is designed so that its Start/Stop error is less than 1 clock cycle.

The count hold/gate bit in the Timer Control Register and the external enable pins, G0/G1, can be used to suspend the timer operation in modes 0, 1, and 2 (in mode 3 it is the trigger input). The external pin and the register bit are OR'ed together, so that when either is high the timers are suspended. Suspending the timer causes the same synchronization error that starting the timer does. The range of errors is specified in Table V.

Clock Selected	Error
External	+ Ext. Clock Period
Crystal	+ 1 Crystal Clock Period
Crystal/4	+ 1 Crystal Clock Period
10.7 kHz	+ 32 μs
1 kHz	+ 32 µs
100 Hz	+32 μs
10 Hz	+ 32 µs
1 Hz	+ 32 μs

## MODES OF OPERATION


Bits M0 and M1 in the Timer Control Registers are used to specify the modes of operation. The mode selection is described in Table VI.

<b>TABLE VI. Programmab</b>	e Timer Modes of	Operation
-----------------------------	------------------	-----------

M1	MO	Function	Modes
0	0	Single Pulse Generator	Mode 0
0	1	Rate Generator, Pulse Output	Mode 1
1	0	Square Wave Output	Mode 2
1	1	Retriggerable One Shot	Mode 3

## MODE 0: SINGLE PULSE GENERATOR

When the timer is in this mode the output will be initially low if the Timer Start/Stop bit is low (stopped). When this mode is initiated the timer output will go high on the next falling edge of the prescaler's input clock, the contents



of the input data registers are loaded into the timer. The output will stay high until the counter reaches zero. At zero the output is reset. The result is an output pulse whose duration is equal to the input clock period times the count value (N) loaded into the input data register. This is shown in *Figure 8*.

Pulse Width = Clock Period  $\times$  N

An interrupt is generated when the zero count is reached. This can be used for one-time interrupts that are set to occur a certain amount of time in the future. In this mode the Timer Start/Stop bit (TSS) is automatically reset upon zero detection. This removes the need to reset TSS before starting another operation.

The count down operation may be temporarily suspended either under software control by setting the Count Hold/ Gate bit in the timer register high, or in hardware by setting the G0 or G1 pin high.

The above discussion assumes that the timer outputs were programmed to be non-inverting outputs (active high). If the polarity of the output waveform is wrong for the application the polarity can be reversed by configuring the Output Mode Register. The drive configuration can also be programmed to be push pull or open drain.

#### MODE 1: RATE GENERATOR

When operating in this mode the timer will operate continuously. Before the timer is started its output is low. When the timer is started the input data register contents are loaded into the counter on the negative clock edge and the output is set high (again assuming the Output Mode Register is programmed active high). The timer will then count down to zero. Once the zero count is reached the output goes low for one clock period of the timer clock. Then on the next clock the counter is reloaded automatically and the countdown repeats itself. The output, shown in *Figure 9*, is a waveform whose pulse width and period is determined by N, the input register value, and the input clock period:

Period = (N + 1) (Clock Period)

Pulse Width = Clock Period

The G0 or G1 pin and the count hold/gate bit can be used to suspend the appropriate timer countdown when either is high. Again, the output polarity is controllable as in mode 0. If enabled, an interrupt is generated whenever the zero count is reached. This can be used to generate a periodic interrupt.


#### **MODE 2: SQUARE WAVE GENERATOR**


This mode is also cyclic but in this case a square wave rather than a pulse is generated. The output square wave period is determined by the value loaded into the timer input register. This period and the duty cycle are:


Period = 2(N + 1) (Clock Period) Duty Cycle = 0.5

When the timer is stopped the output will be low, and when the Start/Stop bit is set high the timer's counter will be loaded on the next clock falling transition and the output will be set high.

The output will be toggled after the zero count is detected and the counter will then be reloaded, and the cycle will continue. Thus, every N + 1 counts the output gets toggled, as shown in *Figure 10*. Like the other modes the timer operation can be suspended either by software setting the count hold/gate bit (CHG) in the Timer Control Register or by using the gate pins. An interrupt will be generated every falling edge of the timer output, if enabled.







#### MODE 3: RETRIGGERABLE ONE SHOT

This mode is different from the previous three modes in that this is the only mode which uses the external gate to trigger the output. Once the timer Start/Stop bit is set the output stays inactive, and nothing happens until a positive transition is received on the G1 or G0 pins, or the Count Hold/ Gate (CHG) bit is set in the timer control register. When a transition ocurs the one shot output is set active immediately; the counter is loaded with the value in the input register on the next transition of the input clock and the countdown begins. If a retrigger occurs, regardless of the current counter value, the counters will be reloaded with the value in the input register and the counter will be restarted without changing the output state. See Figure 11. A trigger count can occur at any time during the count cycle and can be a hardware or software signal (G0, G1 or CHG). In this mode the timer will output a single pulse whose width is determined by the value in the input data register (N) and the input clock period.

## $\textbf{Pulse Width} = \textbf{Clock Period} \times \textbf{N}$

Before entering mode 3, if a spurious edge has occurred on G0/G1 or the CHG bit is set to logic 1, then a pulse will appear at MFO or T1 or INTR output pin when the timer is started. To ensure this does not happen, do the following steps before entering mode 3: Configure the timer for mode 0, load a count of zero, then start the timer.

The timer will generate an interrupt only when it reaches a count of zero. This timer mode is useful for continuous "watch dog" timing, line frequency power failure detection, etc.

#### READING THE TIMERS

National has discovered that some users may encounter unacceptable error rates for their applications when reading the timers on the fly asynchronously. When doing asynchronous reads of the timers, an error may occur. The error is that a successive read may be larger than the previous read. Experimental results indicate that the typical error rate Is approximately one per 29,000 under the following conditions:

Timer clock frequency of 5 MHz.

Computer: 386/33 MHz PC/AT

Program: Microsoft "C" 6.0, reading and saving timer contents in a continuous loop.

Those users who find the error rate unacceptable may reduce the problem effectively to zero by employing a hardware work-around that synchronizes the writing of the read bit to the timer control register with respect to the decrementing clock. Refer to *Figure 1* in Appendix A, for a suggested hardware work-around.

A software work-around can reduce the errors but not as substantial as a hardware work-around. Software workarounds are based on observations that the read following a bad read appeared to be valid.

This problem concerns statistical probability and is similar to metastability issues. For more information on metastability, refer to 1991 IEEE transactions on Custom Integrated Circuits Conference, paper by T.J. Gabara of AT&T Bell Laboratories, page 29.4.1.

Normally reading the timer data register addresses, 0FH and 10H for Timer 0 and 11H and 12H for Timer 1 will result in reading the input data register which contains the preset value for the timers.

To read the contents of a timer, the  $\mu$ P first sets the timer read bit in the appropriate Timer Control Register high. This will cause the counters contents to be latched to 2-bit-8-bit output registers, and will enable these registers to be read if the  $\mu$ P reads the timers input data register addresses. On reading the LSB byte the timer read bit is internally reset and subsequent reads of the timer locations will return the input register values.

#### DETAILED REGISTER DESCRIPTION

There are 5 external address bits: Thus, the host microprocessor has access to 32 locations at one time. An internal switching scheme provides a total of 67 locations.

This complete address space is organized into two pages. Page 0 contains two blocks of control registers, timers, real time clock counters, and special purpose RAM, while page 1 contains general purpose RAM. Using two blocks enables the 9 control registers to be mapped into 5 locations. The only register that does not get switched is the Main Status Register. It contains the page select bit and the register select bit as well as status information.

A memory map is shown in *Figure 2* and register addressing in Table VII. They show the name, address and page locations for the DP8570A.




TABLE VII. Register/Counter/RAM Addressing for DP8570A


ſ						
A0-4	PS	RS	Descr	iption		
	·	(Note 2)	l,			
CONT	ROL REC	SISTERS				
00	X	х	Main Status Register			
01	0	0	Timer 0 Control Regis	ster		
02	0	0	Timer 1 Control Regis	ster		
03	· 0	0.	Periodic Flag Registe	r		
04	0	0	Interrupt Routing Reg	ister		
01	0	1	Real Time Mode Reg	ister		
02	0	1	Output Mode Registe			
03	0	1	Interrupt Control Regi			
04	0	1	Interrupt Control Regi	ister 1		
COUN	ITERS (C	LOCK CA	LENDAR)			
05	0	х	1/100, 1/10 Seconds	s (0–99)		
06	0	х	Seconds	(0-59)		
07	0	х	Minutes	(0-59)		
08	0	х	Hours	(1–12, 0–23)		
09	0	х	Days of			
			Month	(1-28/29/30/31)		
OA	0	х	Months	(1-12)		
0B	0	х	Years	(0-99)		
0C	0	х	Julian Date (LSB)	(0-99) (Note 3)		
0D	0	х	Julian Date	(0-3)		
0E	0	X	Day of Week	(1-7)		
TIME	R DATA F	EGISTE	RS			
0F	0	х	Timer 0 LSB			
10	0	х	Timer 0 MSB			
11	0	х	Timer 1 LSB			
12	0	х	Timer 1 MSB			
TIME	COMPAR	ERAM				
13	0	х	Sec Compare RAM	(0-59)		
14	ō	x	Min Compare RAM	(0-59)		
15	o	x	Hours Compare	(* ***		
	-		RAM	(1-12, 0-23)		
16	o	x	DOM Compare	(,,		
1	-		RAM	(1-28/29/30/31)		
17	0	х	Months Compare	· · ·		
I .			RAM	(1-12)		
18	0	X	DOW Compare RAM	(1-7)		
TIME	TIME SAVE RAM					
19	0	X	Seconds Time Save F	AM		
1A	0	х	Minutes Time Save R	AM		
1B	. 0	х	Hours Time Save RAI	М		
1C	0	х	Day of Month Time Sa	ave RAM		
1D	0	х	Months Time Save R	AM		
1E	0	1	BAM			
1F	ŏ	x	RAM/Test Mode Reg	ister		
01-1F	1	x				
01-1F		<u> </u>	2nd Page General Pu	IPOSE HAM		

Note 1: PS-Page Select (Bit D7 of Main Status Register)

Note 2: RS-Register Select (Bit D6 of Main Status Register)

Note 3: The LSB counters count 0-99 until the hundreds of days counter reaches 3. Then the LSB counters count to 65 or 66 (if a leap year). The rollover is from 365/366 to 1.

## MAIN STATUS REGISTER




The Main Status Register is always located at address 0 regardless of the register block or the page selected.

D0: This read only bit is a general interrupt status bit that is taken directly from the interrupt pins. The bit is a one when an interrupt is pending on either the INTR pin or the MFO pin (when configured as an interrupt). This is unlike D3–D5 which can be set by an internal event but may not cause an interrupt. This bit is reset when the interrupt status bits in the Main Status Register are cleared.

**D1-D5:** These five bits of the Main Status Register are the main interrupt status bits. Any bit may be a one when any of the interrupts are pending. Once an interrupt is asserted the  $\mu$ P will read this register to determine the cause. These interrupt status bits are not reset when read. Except for D1, to reset an interrupt a one is written back to the corresponding bit that is being tested. D1 is reset whenever the PFAIL pin = logic 1. This prevents loss of interrupt status when reading the register in a polled mode. D1, D3-D5 are set regardless of whether these interrupts are to the bits D6 and D7 of Interrupt Control Registers 0 and 1.

D6 and D7: These bits are Read/Write bits that control which register block or RAM page is to be selected. Bit D6 controls the register block to be accessed (see memory map). The memory map of the clock is further divided into two memory pages. One page is the registers, clock and timers, and the second page contains 31 bytes of general purpose RAM. The page selection is determined by bit D7.

## Functional Description (Continued) TIMER 0 AND 1 CONTROL REGISTER



These registers control the operation of the timers. Each timer has its own register.

D0: This bit will Start (1) or Stop (0) the timer. When the timer is stopped the timer's prescaler and counter are reset, and the timer will restart from the beginning when started again. In mode 0 on time out the TSS bit is internally reset.


D1 and D2: These control the count mode of the timers. See Table VI.

**D3-D5:** These bits control which clock signal is applied to the timer's counter input. There is one external clock input pin (TCK) and either (or both) timer(s) can be selected to run off this pin: refer to Table IV for details.

**D6:** This is the read bit. If a one is written into this location it will cause the contents of the timer to be latched into a holding register, which can be read by the  $\mu$ P at any time. Reading the least significant byte of the timer will reset the RD bit. The timer read cycle can be aborted by writing RD to zero.

**D7:** The CHG bit has two mode dependent functions. In modes 0 through 2 writing a one to this bit will suspend the timer operation (without resetting the timer prescaler). However, in mode 3 this bit is used to trigger or re-trigger the count sequence as with the gate pins. If retriggering is desired using the CHG bit, it is not necessary to write a zero to this location prior to the re-trigger. The action of further writing a one to this bit will re-trigger the count.

## PERIODIC FLAG REGISTER



TL/F/8638-16

The Periodic Flag Register has the same bit for bit correspondence as Interrupt Control Register 0 except for D6 and D7. For normal operation (i.e., not a single supply application) this register must be written to on initial power up or after an oscillator fail event. D0–D5 are read only bits, D6 and D7 are read/write. **D0-D5:** These bits are set by the real time rollover events: (Time Change = 1). The bits are reset when the register is read and can be used as selective data change flags.

D6: This bit performs a dual function. When this bit is read, a one indicates that an oscillator failure has occurred and the time information may have been lost. Some of the ways an oscillator failure may be caused are: failure of the crystal; shorting OSC IN or OSC OUT to GND or V<sub>CC</sub>; removal of crystal; removal of battery when in the battery backed mode (when a '0' is written to D6); lowering the voltage at the V<sub>BB</sub> pin to a value less than 2.2V when in the battery backed mode. Bit D6 is automatically set to 1 on initial power-up or an oscillator fail event. The oscillator fail flag is reset by writing a one to the clock start/stop bit in the Real Time Mode Register, with the crystal oscillating.


When D6 is written to, it defines whether the TCP is being used in battery backed (normal) or in a single supply mode application. When set to a one this bit configures the TCP for single power supply applications. This bit is automatically set on initial power-up or an oscillator fail event. When set, D6 disables the oscillator reference circuit. The result is that the oscillator is referenced to V<sub>CC</sub>. When a zero is written to D6 the oscillator reference is enabled, thus the oscillator is referenced to V<sub>BB</sub>. This allows operation in standard battery standby applications.

At initial power on, if the DP8570A is going to be programmed for battery backed mode, the  $V_{BB}$  pin should be connected to a potential in the range of 2.2V to  $V_{CC}$  – 0.4V.

For single supply mode operation, the V\_BB pin should be connected to GND and the  $\overline{\text{PFAIL}}$  pin connected to V\_CC.

D7: Writing a one to this bit enables the test mode register at location 1F (see Table VII). This bit should be forced to zero during initialization for normal operation. If the test mode has been entered, clear the test mode register before leaving test mode. (See separate test mode application note for further details.)

## INTERRUPT ROUTING REGISTER



D0-D4: The lower 5 bits of this register are associated with the main interrupt sources created by this chip. The purpose of this register is to route the interrupts to either the MFO (multi-function pin), or to the main interrupt pin. When any bit is set the associated interrupt signal will be sent to the MFO pin, and when zero it will be sent to the INTR pin.


**D5:** The Delay Enable bit is used when a power fail occurs. If this bit is set, a 480  $\mu$ s delay is generated internally before the  $\mu$ P interface is locked out. This will enable the  $\mu$ P to access the registers for up to 480  $\mu$ s after it receives a power fail interrupt. After a power failure is detected but prior to the 480  $\mu$ s delay timing out, the host  $\mu$ P may force immediate lock out by resetting the Delay Enable bit. Note if this bit is a 0 when power fails then after a delay of 30  $\mu$ s min/63  $\mu$ s max the  $\mu$ P cannot read the chip.

**D6:** This read only bit is set and reset by the voltage at the V<sub>BB</sub> pin. It can be used by the  $\mu$ P to determine whether the battery voltage at the V<sub>BB</sub> pin is getting too low. A comparator monitors the battery and when the voltage is lower than 2.1V (typical) this bit is set. The power fail interrupt must be enabled to check for a low battery voltage.

**D7:** Time Save Enable bit controls the loading of real-timeclock data into the Time Save RAM. When a one is written to this bit the Time Save RAM will follow the corresponding clock registers, and when a zero is written to this bit the time in the Time Save RAM is frozen. This eliminates any synchronization problems when reading the clock, thus negating the need to check for a counter rollover during a read cycle.

This bit must be set to a one prior to power failing to enable the Time Save feature. When the power fails this bit is automatically reset and the time is saved in the Time Save RAM.

## REAL TIME MODE REGISTER



D0-D1: These are the leap year counter bits. These bits are written to set the number of years from the previous leap year. The leap year counter increments on December 31st and it internally enables the February 29th counter state. This method of setting the leap year allows leap year to occur whenever the user wishes to, thus providing flexibility in implementing Japanese leap year function.

LY1	LY0	Leap Year Counter
0	0	Leap Year Current Year
0	1	Leap Year Last Year
. 1 .	. 0	Leap Year 2 Years Ago
1	1	Leap Year 3 Years Ago

**D2:** The count mode for the hours counter can be set to either 24 hour mode or 12 hour mode with AM/PM indicator. A one will place the clock in 12 hour mode.

D3: This bit is the master Start/Stop bit for the clock. When a one is written to this bit the real time counter's prescaler and counter chain are enabled. When this bit is reset to zero the contents of the real time counter is stopped and the prescaler is cleared. When the TCP is initially powered up this bit will be held at a logic 0 until the oscillator starts functioning correctly after which this bit may be modified. If an oscillator fail event occurs, this bit will be reset to logic 0.

D4: This bit controls the operation of the interrupt output in standby mode. If set to a one it allows Alarm, Periodic, and Power Fail interrupts to be functional in standby mode. Timer interrupts will also be functional provided that bit D5 is also set. Note that the MFO and INTR pins are configured as open drain in standby mode.

If bit D4 is set to a zero then interrupt control register 0 and bits D6 and D7 of interrupt control register 1 will be reset when the TCP enters the standby mode (V<sub>BB</sub> > V<sub>CC</sub>). They will have to be re-configured when system (V<sub>CC</sub>) power is restored.

**D5:** This bit controls the operation of the timers in standby mode. If set to a one the timers will continue to function when the TCP is in standby mode. The input pins TCK, G0, G1 are locked out in standby mode, and cannot be used.


Therefore external control of the timers is not possible in standby mode. Note also that MFO and T1 pins are automatically reconfigured open drain during standby.

**D6 and D7:** These two bits select the crystal clock frequency as per the following table:

XT1	ХТО	Crystal Frequency
0	0	32.768 kHz
0	1	4.194304 MHz
1	0	4.9152 MHz
1	1	32.000 kHz

All bits are Read/Write, and any mode written into this register can be determined by reading the register. On initial power up these bits are random.

#### **OUTPUT MODE REGISTER**



D0: This bit, when set to a one makes the T1 (timer 1) output pin active high, and when set to a zero, it makes this pin active low.

**D1:** This bit controls whether the T1 pin is an open drain or push-pull output. A one indicates push pull.

**D2:** This bit, when set to a one makes the INTR output pin active high, and when set to a zero, it makes this pin active low.

**D3:** This bit controls whether the INTR pin is an open drain or push-pull output. A one indicates push-pull.


D4: This bit, when set to a one makes the MFO output pin active high, and when set to a zero, it makes this pin active low.

**D5:** This bit controls whether the MFO pin is an open drain or push-pull output. A one indicates push-pull.

**D6 and D7:** These bits are used to program the signal appearing at the MFO output, as follows:

D7	D6	MFO Output Signal
0	0	2nd Interrupt
0	1	Timer 0 Waveform
1	Х	Buffered Crystal Oscillator

#### **INTERRUPT CONTROL REGISTER 0**




If battery backed mode is selected and the DP8570A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then all bits are controlled by D4 of the Real Time Mode Register.

**D0-D5:** These bits are used to enable one of the selected periodic interrupts by writing a one into the appropriate bit. These interrupts are issued at the rollover of the clock. For example, the minutes interrupt will be issued whenever the minutes counter increments. In all likelihood the interrupt will be enabled asynchronously with the real time change. Therefore, the very first interrupt will occur in less than the

periodic time chosen, but after the first interrupt all subsequent interrupts will be spaced correctly. These interrupts are useful when minute, second, real time reading, or task switching is required. When all six bits are written to a 0 this disables periodic interrupts from the Main Status Register and the interrupt pin.

**D6 and D7:** These are individual timer enable bits. A one written to these bits enable the timers to generate interrupts to the  $\mu$ P.

#### **INTERRUPT CONTROL REGISTER 1**



**D0-D5:** Each of these bits are enable bits which will enable a comparison between an individual clock counter and its associated compare RAM. If any bit is a zero then that clock-RAM comparator is set to the "always equal" state and the associated TIME COMPARE RAM byte can be used as general purpose RAM. However, to ensure that an alarm interrupt is not generated at bit D3 of the Main Status Register, all bits must be written to a logic zero.

**D6:** In order to generate an external alarm compare interrupt to the  $\mu$ P from bit D3 of the Main Status Register, this bit must be written to a logic 1. If battery backed mode is selected and the DP8570A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then this bit is controlled by D4 of the Real Time Mode Register.

**D7:** The MSB of this register is the enable bit for the Power Fail Interrupt. When this bit is set to a one an interrupt will be generated to the  $\mu$ P when PFAIL = 0. If battery backed mode is selected and the DP8570A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then this bit is controlled by D4 of the Real Time Mode Register.

This bit also enables the low battery detection analog circuitry.

If the user wishes to mask the power fail interrupt, but utilize the analog circuitry, this bit should be enabled, and the Routing Register can be used to route the interrupt to the MFO pin. The MFO pin can then be left open or configured as the Timer 0 or buffered oscillator output.

D7 Jain Status Br	D6 eqister PS = (	<b>D5</b> 0 RS = 0 /	D4 ADDRESS = 0	D3	D2	D1	D0	1. Reset by
R/W	R/W	R/W <sup>1</sup>	R/W <sup>1</sup>	R/W <sup>1</sup>	R/W <sup>1</sup>	R <sup>2</sup>	R <sup>3</sup>	writing
Page	Register	Timer 1	Timer 0	Alarm	Periodic	Power Fail	Interrupt	1 to bit. 2. Set/reset by
Select	Select	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Status	voltage at
								PFAIL pin.
								<ol> <li>Reset when all pending</li> </ol>
								interrupts
imer 0 Contro	ol Register PS	S=0 RS=	0 Address =	01H				are removed
Count Hold	Timer	Input Clock	Input Clock	Input Clock	Mode	Mode	Timer	
Gate	Read	Select C2	Select C1	Select C0	Select M1	Select M0	Start/Stop	All Bits R/W
imer 1 Contro	ol Register PS	S=0 R	S = 0 A	ddress = 02H				1 a
Count Hold	Timer	Input Clock	Input Clock	Input Clock	Mode	Mode	Timer	All Bits R/W
Gate	Read	Select C2	Select C1	Select C0	Select M1	Select M0	Start/Stop	All Bits H/ W
eriodic Flag I	Register PS =	•0 RS •	= 0 Addr	ress = 03H				
R/W	R/W <sup>4</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	4. Read Osc fa
Test	Osc. Fail/	1 ms	10 ms	100 ms	Seconds	10 Second	Minute	Write 0 Batt- Backed Mod
Mode	Single Supply	Flag	Flag	Flag	Flag	Flag	Flag	Write 1 Sing
Mode	Single Supply	1 149						0
							<u> </u>	Supply Mode 5. Reset by
<b>L</b>	ting Register F			Address = 04 R/W		R/W	R/W	Supply Mode 5. Reset by positive edge
nterrupt Rout R/W	ting Register F R <sup>6</sup>	PS = 0	RS = 0	Address = 04	IH	• .	· ·	Supply Mode 5. Reset by positive edge of read.
nterrupt Rout R/W Time Save	ti <b>ng Register</b> F R <sup>6</sup> Low Battery	PS = 0 R/W Power Fail Delay	RS = 0 R/W Timer 1 Int. Route	Address = 04 R/W Timer 0 Int. Route	IH R/W Alarm Int. Route	R/W Periodic Int. Route	R/W Power Fail Int. Route	Supply Mode 5. Reset by positive edge of read. 6. Set and rese by V <sub>BB</sub>
nterrupt Rout R/W	ting Register F R <sup>6</sup>	PS = 0 R/W Power Fail	RS = 0 <b>R/W</b> Timer 1	Address = 04 R/W Timer 0	IH R/W Alarm	R/W Periodic	R/W Power Fail	Supply Mode 5. Reset by positive edg of read. 6. Set and rese
nterrupt Rout R/W Time Save Enable	ti <b>ng Register</b> F R <sup>6</sup> Low Battery	PS = 0 R/W Power Fail Delay Enable	RS = 0 R/W Timer 1 Int. Route MFO/INT	Address = 04 R/W Timer 0 Int. Route	IH R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route	R/W Power Fail Int. Route	Supply Mode 5. Reset by positive edge of read. 6. Set and rese by V <sub>BB</sub>
nterrupt Rout R/W Time Save Enable	t <b>ing Register</b> F <b>R</b> <sup>6</sup> Low Battery Flag	PS = 0 R/W Power Fail Delay Enable	RS = 0 R/W Timer 1 Int. Route MFO/INT	Address = 04 R/W Timer 0 Int. Route MFO/INT ddress = 01H Clock	IH R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route	R/W Power Fail Int. Route MFO/INT Leap Year	Supply Mode 5. Reset by positive edge of read. 6. Set and rese by V <sub>BB</sub> voltage.
nterrupt Rout R/W Time Save Enable Real Time Moo	ting Register F R <sup>6</sup> Low Battery Flag de Register PS	PS = 0 <b>R/W</b> Power Fail Delay Enable S = 0 R	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 011	IH <b>B/W</b> Alarm Int. Route MFO/INT	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT	Supply Mode 5. Reset by positive edge of read. 6. Set and rese by V <sub>BB</sub>
nterrupt Rout R/W Time Save Enable Real Time Moo Crystal Freq. XT1	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal	PS = 0 <b>R/W</b> Power Fail Delay Enable S = 0 Timers EN on Back-Up	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up	Address = 04 R/W Timer 0 Int. Route MFO/INT ddress = 01H Clock	H R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route MFO/INT Leap Year	R/W Power Fail Int. Route MFO/INT Leap Year	Supply Mode 5. Reset by positive edge of read. 6. Set and rese by V <sub>BB</sub> voltage.
nterrupt Rout R/W Time Save Enable Real Time Moo Crystal Freq. XT1	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0	PS = 0 <b>R/W</b> Power Fail Delay Enable S = 0 Timers EN on Back-Up 0 RS = MFO	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR	IH <b>R/W</b> Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Supply Mode 5. Reset by positive edge of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W
nterrupt Rout R/W Time Save Enable Real Time Moo Crystal Freq. XT1	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS =	PS = 0 <b>R/W</b> Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS =	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H	H Alarm Int. Route MFO/INT 12/24 Hr. Mode	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage.
nterrupt Rout R/W Time Save Enable deal Time Moo Crystal Freq. XT1 Dutput Mode F MFO as Crystal	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as	PS = 0 <b>R/W</b> Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W
nterrupt Rout R/W Time Save Enable deal Time Mod Crystal Freq. XT1 Dutput Mode I MFO as Crystal MFO as Crystal terrupt Cont Timer 1	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0	$PS = 0$ $R/W$ Power Fail Delay Enable $S = 0 \qquad R$ Timers EN on Back-Up $0 \qquad RS =$ $MFO$ $PP/\overline{OD}$ $0 PS = 0$ 1 ms	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR PP/OD Address = 0 100 ms	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO D3H Seconds	R/W Periodic Int. Route MFO/INT Leap Year MSB T1 PP/OD	R/W Power Fail Int. Route MFO/INT Leap Year LSB T1 Active HI/LO Minute	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W
nterrupt Rout R/W Time Save Enable teal Time Moo Crystal Freq. XT1 Dutput Mode I MFO as Crystal MFO as Crystal Interrupt Cont Timer 1 Interrupt	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0 Interrupt	$PS = 0$ $R/W$ Power Fail Delay Enable $S = 0 \qquad R$ Timers EN on Back-Up $0 \qquad RS =$ $MFO$ $PP/\overline{OD}$ $PS = 0$ 1 ms Interrupt	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR PP/OD Address = 0 100 ms Interrupt	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt	R/W Periodic Int. Route MFO/INT Leap Year MSB T1 PP/OD	R/W Power Fail Int. Route MFO/INT Leap Year LSB T1 Active HI/LO Minute Interrupt	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W
terrupt Rout R/W Time Save Enable eal Time Moo Crystal Freq. XT1 utput Mode F MFO as Crystal terrupt Cont Timer 1	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0	$PS = 0$ $R/W$ Power Fail Delay Enable $S = 0 \qquad R$ Timers EN on Back-Up $0 \qquad RS =$ $MFO$ $PP/\overline{OD}$ $0 PS = 0$ 1 ms	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR PP/OD Address = 0 100 ms	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO D3H Seconds	R/W Periodic Int. Route MFO/INT Leap Year MSB T1 PP/OD	R/W Power Fail Int. Route MFO/INT Leap Year LSB T1 Active HI/LO Minute	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W
terrupt Rout R/W Time Save Enable eal Time Moo Crystal Freq. XT1 utput Mode I MFO as Crystal MFO as Crystal terrupt Cont Timer 1 Interrupt Enable	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0 Interrupt	PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO $PP/\overline{OD}$ PS = 0 1 ms Interrupt Enable	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR PP/OD Address = 0 100 ms Interrupt	H R/W Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB T1 PP/OD	R/W Power Fail Int. Route MFO/INT Leap Year LSB T1 Active HI/LO Minute Interrupt	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W
nterrupt Rout R/W Time Save Enable teal Time Mod Crystal Freq. XT1 Dutput Mode F MFO as Crystal nterrupt Cont Timer 1 Interrupt Enable nterrupt Cont Power Fail	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0 Interrupt Enable	PS = 0 R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO $PP/\overline{OD}$ PS = 0 1 ms Interrupt Enable	RS = 0 R/W Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt Enable RS = 1 Month	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR PP/OD Address = 0 100 ms Interrupt Enable Address = 0	H R/W Alarm Int. Route MFO/INT H 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt Enable 04H Hours	R/W Periodic Int. Route MFO/INT Leap Year MSB T1 PP/OD 10 Second Interrupt Enable	R/W Power Fail Int. Route MFO/INT Leap Year LSB T1 Active HI/LO Minute Interrupt Enable	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W All Bits R/W
Interrupt Rout R/W Time Save Enable Real Time Moo Crystal Freq. XT1 Output Mode I MFO as Crystal Interrupt Cont Interrupt Enable	ting Register F R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0 Interrupt Enable	$PS = 0$ $R/W$ Power Fail Delay Enable $S = 0 \qquad R$ Timers EN on Back-Up $0 \qquad RS =$ $MFO$ $PP/OD$ $PS = 0$ 1 ms Interrupt Enable $PS = 0$	RS = 0 R/W Timer 1 Int. Route MFO/INT IS = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt Enable RS = 1	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ress = 02H INTR PP/OD Address = 0 100 ms Interrupt Enable Address = 0	IH R/W Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt Enable 04H	R/W Periodic Int. Route MFO/INT Leap Year MSB T1 PP/OD 10 Second Interrupt Enable	R/W Power Fail Int. Route MFO/INT Leap Year LSB T1 Active HI/LO Minute Interrupt Enable	Supply Mod 5. Reset by positive edg of read. 6. Set and rese by V <sub>BB</sub> voltage. All Bits R/W

# DP8570A

Suggested Initialization Procedure for DP8570A in battery backed applications that use the  $V_{BB}\ \text{pin}$ 

- 1. Enter the test mode by writing a 1 to bit D7 in the Periodic Flag Register.
- Write zero to the RAM/TEST mode Register located in page 0, address HEX 1F.
- 3. Leave the test mode by writing a 0 to bit D7 in the Periodic Flag Register. Steps 1, 2, 3 guarantee that if the test mode had been entered during power on (due to random pulses from the system), all test mode conditions are cleared. Most important is that the OSC Fail Disable bit is cleared. Refer to AN-589 for more information on test mode operation.
- 4. After power on ( $V_{CC}$  and  $V_{BB}$  powered), select the correct crystal frequency bits (D7, D6 in the Real Time Mode Register) as shown in Table I.

TABLE I
---------

Frequency	D7	D6
32.768 kHz	0	0
4.194304 MHz	0	1
4.9152 MHz	1	. 0
32.0 kHz	1	1

5. Enter a software loop that does the following:

Set a 3 second (approx.) software counter. The crystal oscillator may take 1 second to start.

5.1 Write a 1 to bit D3 in the Real Time Mode Register (try to start the clock). Make sure the crystal select bits remain the same as in step 1. Under normal operation, this bit can be set only if the oscillator is running. During the software loop, RAM, real time counters, output configuration, interrupt control and timer functions may be initialized.

6. Test bit D6 in the Periodic Flag Register:

IF a 1, go to 5.1. If this bit remains a 1 after 3 seconds, then abort and check hardware. The crystal may be defective or not installed. There may be a short at OSC IN or OSC OUT to V<sub>CC</sub> or GND, or to some impedance that is less than 10 M $\Omega$ .


IF a 0, then the oscillator is running, go to step 7.


7. Write a 0 to bit D6 in the Periodic Flag Register. This action puts the clock chip in the battery backed mode. This mode can be entered only if the osc fail flag (bit D6 of the Periodic Flag Register) is a 0. Reminder, Bit D6 is a dual function bit. When read, D6 returns oscillator status. When written, D6 causes either the Battery Backed Mode, or the Single Supply Mode of operation.

The only method to ensure the chip is in the battery backed mode is to measure the waveform at the OSC OUT pin. If the battery backed mode was selected successfully, then the peak to peak waveform at OSC OUT is referenced to the battery voltage. If not in battery backed mode, the waveform is referenced to V<sub>CC</sub>. The measurement should be made with a high impedance low capacitance probe (10 M $\Omega$ , 10 pF oscilloscope probe or better). Typical peak to peak swings are within 0.6V of V<sub>CC</sub> and ground respectively.

- 8. Write a 1 to bit D7 of Interrupt Control Register 1. This action enables the PFAIL pin and associated circuitry.
- 9. Write a 1 to bit D4 of the Real Time Mode Register. This action ensures that bit D7 of Interrupt Control Register 1 remains a 1 when  $V_{BB} > V_{CC}$  (Standby Mode).
- 10. Initialize the rest of the chip as needed.








**DP8570A** 

\*7

FIGURE A1. Typical Interface Where the "Write Strobe" is Synchronized to the Decrementing Clock of the Timer



2-27

2

# **DP8571A**

## Nationa Semiconductor

# DP8571A Timer Clock Peripheral (TCP)

## **General Description**

The DP8571A is intended for use in microprocessor based systems where information is required for multi-tasking, data logging or general time of day/date information. This device is implemented in low voltage silicon gate microCMOS technology to provide low standby power in battery back-up environments. The circuit's architecture is such that it looks like a contiguous block of memory or I/O ports. The address space is organized as 2 software selectable pages of 32 bytes. This includes the Control Registers, the Clock Counters, the Alarm Compare RAM, the Timers and their data RAM, and the Time Save RAM, Any of the RAM locations that are not being used for their intended purpose may be used as general purpose CMOS RAM.


Time and date are maintained from 1/100 of a second to year and leap year in a BCD format, 12 or 24 hour modes. Day of week, day of month and day of year counters are provided. Time is controlled by an on-chip crystal oscillator requiring only the addition of the crystal and two capacitors. The choice of crystal frequency is program selectable.

Two independent multifunction 10 MHz 16-bit timers are provided. These timers operate in four modes. Each has its own prescaler and can select any of 7 possible clock inputs. Thus, by programming the input clocks and the timer counter values a very wide range of timing durations can be achieved. The range is from about 400 ns (4.915 MHz oscillator) to 65,535 seconds (18 hrs., 12 min.).

Power failure logic and control functions have been integrated on chip. This logic is used by the TCP to issue a power fail interrupt, and lock out the µp interface. The time power fails may be logged into RAM automatically when  $V_{BB} > V_{CC}$ . Additionally, two supply pins are provided. When VBB > V<sub>CC</sub>, internal circuitry will automatically switch from the main supply to the battery supply. Status bits are provided to indicate initial application of battery power, system power, and low battery detect. (Continued)

## Features

- Full function real time clock/calendar
  - 12/24 hour mode timekeeping
  - Day of week and day of years counters
  - Four selectable oscillator frequencies
  - Parallel resonant oscillator
- Two 16-bit timers
  - 10 MHz external clock frequency
  - Programmable multi-function output
  - Flexible re-trigger facilities
- Power fail features
  - Internal power supply switch to external battery
  - Power Supply Bus glitch protection
  - Automatic log of time into RAM at power failure
  - On-chip interrupt structure
  - Periodic, alarm, timer and power fail interrupts
- Up to 44 bytes of CMOS RAM
- INTR/MFO pins programmable High/Low and push-pull or open drain



Block Diagram

## Absolute Maximum Ratings (Notes 1 & 2)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Supply Voltage (V <sub>CC</sub> )	-0.5V to +7.0V
DC Input Voltage (VIN)	$-0.5 V$ to $V_{CC}$ $+0.5 V$
DC Output Voltage (V <sub>OUT</sub> )	$-0.5V$ to $V_{\mbox{CC}}$ + $0.5V$
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.	.) 260°C

## **Operation Conditions**

85°C/W

-	Min	Max	Unit
Supply Voltage (V <sub>CC</sub> ) (Note 3)	4.5	5.5	V
Supply Voltage (V <sub>BB</sub> ) (Note 3)	2.2	V <sub>CC</sub> -0.4	V
DC Input or Output Voltage (V <sub>IN</sub> , V <sub>OUT</sub> )	0.0	V <sub>CC</sub>	v
Operation Temperature (T <sub>A</sub> )	-40	+85	°C
Electr-Static Discharge Rating TBD		1	kV
Transistor Count		15,200	
Typical Values			
$\theta_{\rm JA}$ DIP	Board		
	Socket		
$\theta_{JA} PLCC$	Board		77°C/W

Socket

## **DC Electrical Characteristics**

 $V_{CC} = 5V \pm 10\%$ ,  $V_{BB} = 3V$ ,  $V_{\overline{PFAIL}} > V_{IH}$ ,  $C_L = 100 \text{ pF}$  (unless otherwise specified)

Symbol	Parameter	Conditions	Min	Max	Units
VIH	High Level Input Voltage (Note 4)	Any Inputs Except OSC IN, OSC IN with External Clock	2.0 V <sub>BB</sub> -0.1		>>
VIL	Low Level Input Voltage	All Inputs Except OSC IN OSC IN with External Clock		0.8 0.1	>>
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = -20 \ \mu A$ $I_{OUT} = -4.0 \ m A$	V <sub>CC</sub> -0.1 3.5		v v
Vol	Low Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = 20 \ \mu A$ $I_{OUT} = 4.0 \ m A$		0.1 0.25	> >
I <sub>IN</sub>	Input Current (Except OSC IN)	$V_{IN} = V_{CC} \text{ or } GND$		±1.0	μΑ
l <sub>oz</sub>	Output TRI-STATE® Current	$V_{OUT} = V_{CC} \text{ or } GND$		±5.0	μA
I <sub>LKG</sub>	Output High Leakage Current T1, MFO, INTR Pins	V <sub>OUT</sub> = V <sub>CC</sub> or GND Outputs Open Drain		±5.0	μΑ
ICC	Quiescent Supply Current (Note 7)	$\begin{array}{l} F_{OSC}=32.768 \ \text{kHz} \\ V_{IN}=V_{CC} \ \text{or GND} \ (\text{Note 5}) \\ V_{IN}=V_{CC} \ \text{or GND} \ (\text{Note 6}) \\ V_{IN}=V_{IH} \ \text{or } V_{IL} \ (\text{Note 6}) \end{array}$		260 1.0 12.0	μA mA mA
		F <sub>OSC</sub> = 4.194304 MHz or 4.9152 MHz V <sub>IN</sub> = V <sub>CC</sub> or GND (Note 6) V <sub>IN</sub> = V <sub>IH</sub> or V <sub>IL</sub> (Note 6)		8 20	mA mA
lcc	Quiescent Supply Current (Single Supply Mode) (Note 7)	$\begin{array}{l} V_{BB} = GND \\ V_{IN} = V_{CC} \mbox{ or } GND \\ F_{OSC} = 32.768 \mbox{ kHz} \\ F_{OSC} = 4.9152 \mbox{ MHz} \mbox{ or} \\ 4.194304 \mbox{ MHz} \end{array}$		80 7.5	μA mA
I <sub>BB</sub>	Standby Mode Battery Supply Current (Note 8)	$\begin{array}{l} V_{CC} = GND\\ OSC OUT = open circuit,\\ other pins = GND\\ F_{OSC} = 32.768  \text{kHz}\\ F_{OSC} = 4.9152  \text{MHz}  \text{or}\\ 4.194304  \text{MHz} \end{array}$		10 400	μΑ μΑ
I <sub>BLK</sub>	Battery, Supply Leakage	$\begin{array}{l} 2.2V \leq V_{BB} \leq 4.0V \\ \text{other pins at GND} \\ V_{CC} = \text{GND}, V_{BB} = 4.0V \\ V_{CC} = 5.5V, V_{BB} = 2.2V \end{array}$	-5	1.5	μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: For  $F_{OSC} = 4.194304$  or 4.9152 MHz,  $V_{BB}$  minimum = 2.8V. In battery backed mode,  $V_{BB} \le V_{CC} - 0.4V$ . Single Supply Mode: Data retention voltage is 2.2V min. In single Supply Mode (Power connected to  $V_{CC}$  pin) 4.5V  $\le V_{CC} \le 5.5V$ .

Note 4: This parameter (V<sub>IH</sub>) is not tested on all pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: This specification is tested with both the timers and OSC IN driven by a signal generator. Contents of the Test Register = 00(H), the MFO pin is not configured as buffered oscillator out and MFO, INTR, are configured as open drain.

Note 8: This specification is tested with both the timers off, and only OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

2

## **AC Electrical Characteristics**

 $V_{CC} = 5V \pm 10\%$ ,  $V_{BB} = 3V$ ,  $V_{\overline{PFAIL}} > V_{IH}$ ,  $C_L = 100 \text{ pF}$  (unless otherwise specified)

Symbol	Parameter	Min	Max	Units
AD TIMING				
t <sub>AR</sub>	Address Valid Prior to Read Strobe	20		ns
t <sub>RW</sub>	Read Strobe Width (Note 9)	80		ns
t <sub>CD</sub>	Chip Select to Data Valid Time		80	ns
t <sub>RAH</sub>	Address Hold after Read (Note 10)	3		ns
t <sub>RD</sub>	Read Strobe to Valid Data		70	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		60	ns
t <sub>RCH</sub>	Chip Select Hold after Read Strobe	0		ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses	50		ns
ITE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	20		ns
t <sub>WAH</sub>	Address Hold after Write Strobe (Note 10)	3		ns
t <sub>CW</sub>	Chip Select to End of Write Strobe	90		ns
tww	Write Strobe Width (Note 11)	80		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	50		ns
twoh	Data Hold after Write Strobe (Note 10)	3		ns
	twch Chip Select Hold after Write Strobe			ns

 t<sub>ROLL</sub>
 Clock rollover to INTR out is typically 16.5 μs

 Note 9: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when

both signals are low and terminates when either signal returns high.

Note 10: Hold time is guaranteed by design but not production tested. This limit is not used to calculate outgoing quality levels.

Note 11: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

## **AC Test Conditions**

Input Pulse Levels	GND to 3.0V
Input Rise and Fall Times	6 ns (10%–90%)
Input and Output	1.3V
Reference Levels	1.50
TRI-STATE Reference	Active High + 0.5V
Levels (Note 13)	Active Low -0.5V

Note 12:  $C_L = 100 \text{ pF}$ , includes jig and scope capacitance.

Note 13: S1 =  $V_{CC}$  for active low to high impedance measurements. S1 = GND for active high to high impedance measurements.


S1 = open for all other timing measurements.

## **Capacitance** ( $T_A = 25^{\circ}C$ , f = 1 MHz)


Symbol	Parameter (Note 14)	Тур	Units	],
C <sub>IN</sub>	Input Capacitance	5	рF	
COUT	Output Capacitance	7	pF	



Note 15: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.



TL/F/9979-2



- <del>-</del> -

•1,7

2-31

## General Description (Continued)

The DP8571A's interrupt structure provides four basic types of interrupts: Periodic, Alarm/Compare, Timer, and Power Fail. Interrupt mask and status registers enable the masking and easy determination of each interrupt.

One dedicated general purpose interrupt output is provided. A second interrupt output is available on the Multiple Function Output (MFO) pin. Each of these may be selected to generate an interrupt from any source. Additionally, the MFO pin may be programmed to be either as oscillator output or Timer 0's output.

## **Pin Description**

**CS, RD, WR (Inputs):** These pins interface to  $\mu$ P control lines. The **CS** pin is an active low enable for the read and write operations. Read and Write pins are also active low and enable reading or writing to the TCP. All three pins are disabled when power failure is detected. However, if a read or write is in progress at this time, it will be allowed to complete its cycle.

A0-A4 (Inputs): These 5 pins are for register selection. They individually control which location is to be accessed. These inputs are disabled when power failure is detected.

**OSC IN (Input): OSC OUT (Output):** These two pins are used to connect the crystal to the internal parallel resonant oscillator. The oscillator is always running when power is applied to  $V_{BB}$  and  $V_{CC}$ , and the correct crystal select bits in the Real Time Mode Register have been set.

**MFO (Output):** The multi-function output can be used as a second interrupt output for interrupting the  $\mu$ P. This pin can also provide an output for the oscillator or the internal Timer 0. The MFO output can be programmed active high or low, open drain or push-pull. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>. This pin is configured open drain during battery operation (V<sub>BB</sub> > V<sub>CC</sub>).

**INTR (Output):** The interrupt output is used to interrupt the processor when a timing event or power fail has occurred and the respective interrupt has been enabled. The INTR output can be programmed active high or low, push-pull or open drain. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>. This pin is configured open drain during battery operation (V<sub>BB</sub> > V<sub>CC</sub>). The output is a DC voltage level. To clear the INTR, write a 1 to the appropriate bit(s) in the Main Status Register.

**D0–D7 (Input/Output):** These 8 bidirectional pins connect to the host  $\mu$ P's data bus and are used to read from and write to the TCP. When the **PFAIL** pin goes low and a write is not in progress, these pins are at TRI-STATE.


**PFAIL** (Input): In battery backed mode, this pin can have a digital signal applied to it via some external power detection logic. When **PFAIL** = logic 0 the TCP goes into a lockout mode, in a minimum of 30  $\mu$ s or a maximum of 63  $\mu$ s unless lockout delay is programmed. In the single power supply mode, this pin is not useable as an input and should be tied to V<sub>CC</sub>. Refer to section on Power Fail Functional Description.

 $V_{BB} \mbox{ (Battery Power Pin): This pin is connected to a backup power supply. This power supply is switched to the internal circuitry when the V_{CC} becomes lower than V_{BB}. Utilizing this pin eliminates the need for external logic to switch in and out the back-up power supply. If this feature is not to be used then this pin must be tied to ground, the TCP programmed for single power supply only, and power applied to the V_{CC} pin.$ 

Vcc: This is the main system power pin.

GND: This is the common ground power pin for both  $V_{BB}$  and  $V_{CC}.$ 

## **Connection Diagram**



Top View

TL/F/9979-5

Order Number DP8571AN See NS Package Number N24C

## **Functional Description**

The DP8571A contains a fast access real time clock, two 10 MHz 16-bit timers, interrupt control logic, power fail detect logic, and CMOS RAM. All functions of the TCP are controlled by a set of nine registers. A simplified block diagram that shows the major functional blocks is given in *Figure 1*.

The blocks are described in the following sections:

- 1. Real Time Clock
- 2. Oscillator Prescaler
- 3. Interrupt Logic
- 4. Power Failure Logic
- 5. Additional Supply Management
- 6. Timers

dressing table. The memory map consists of two 31 byte pages with a main status register that is common to both pages. A control bit in the Main Status Register is used to select either page. *Figure 2* shows the basic concept. Page 0 contains all the clock timer functions, while page 1 has scratch pad RAM. The control registers are split into two separate blocks to allow page 1 to be used entirely as scratch pad RAM. Again a control bit in the Main Status

Register is used to select either control register block.

The memory map of the TCP is shown in the memory ad-

Page Select = 0 RAM/TEST Register RAM Months Time Save RAM Day of Month Time Save RAM Hours Time Save RAM Minutes Time Save RAM Seconds Time Save RAM Day of Week Compare RAM Months Compare RAM Months Compare RAM Hours Compare RAM Hours Compare RAM Seconds Compare RAM Seconds Compare RAM Timer 1 LSB Timer 1 LSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Years Clock Counter Months Clock Counter Months Clock Counter Months Clock Counter Months Clock Counter		1F         1E         1D         1C         1B         1A         19         18         17         16         17         16         17         16         17         16         17         16         07         04         05         00         00         00         00	Page Select = 1 RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
RAM Months Time Save RAM Hours Time Save RAM Hours Time Save RAM Minutes Time Save RAM Seconds Time Save RAM Day of Week Compare RAM Months Compare RAM Hours Compare RAM Hours Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 LSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Years Clock Counter Years Clock Counter Months Clock Counter		1E       1D       1C       1B       1A       19       18       17       16       15       14       13       12       11       10       0F       0E       0D       0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Months Time Save RAM Day of Month Time Save RAM Hours Time Save RAM Minutes Time Save RAM Seconds Time Save RAM Day of Week Compare RAM Months Compare RAM Hours Compare RAM Hours Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Years Clock Counter Years Clock Counter Day of Month Clock Counter		1E       1D       1C       1B       1A       19       18       17       16       15       14       13       12       11       10       0F       0E       0D       0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Day of Month Time Save RAM Hours Time Save RAM Minutes Time Save RAM Seconds Time Save RAM Day of Week Compare RAM Months Compare RAM Hours Compare RAM Hours Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 LSB Timer 1 LSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Years Clock Counter Years Clock Counter Months Clock Counter		1E       1D       1C       1B       1A       19       18       17       16       15       14       13       12       11       10       0F       0E       0D       0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Hours Time Save RAM Minutes Time Save RAM Seconds Time Save RAM Day of Week Compare RAM Months Compare RAM Hours Compare RAM Hours Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter		1C 1B 14 19 19 18 17 16 15 114 115 114 115 114 115 115 114 115 115	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Minutes Time Save RAM Seconds Time Save RAM Day of Week Compare RAM Months Compare RAM Hours Compare RAM Hours Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		1B 1A 19 18 17 16 15 14 15 14 15 17 16 15 17 16 17 17 16 17 17 17 17 17 17 17 17 17 17 17 17 17	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Seconds Time Save RAM Day of Week Compare RAM Months Compare RAM Day of Month Compare RAM Hours Compare RAM Minutes Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter		1A 19 18 17 16 15 14 13 12 11 10 0F 0E 0D 0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Day of Week Compare RAM Months Compare RAM Day of Month Compare RAM Hours Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 MSB Timer 0 MSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		19 18 17 16 15 14 13 12 11 10 0F 0E 0D 0D	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Months Compare RAM Day of Month Compare RAM Hours Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 MSB Timer 0 MSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Years Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		18 17 16 15 14 13 12 11 0F 0F 0D 0D 0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Day of Month Compare RAM Hours Compare RAM Minutes Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Years Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		17 16 15 14 13 12 11 10 0F 0E 0D 0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Hours Compare RAM Minutes Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		16 15 14 13 12 11 10 0F 0E 0D 0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Minutes Compare RAM Seconds Compare RAM Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		15 14 13 12 11 10 0F 0E 0D 0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Seconds Compare RAM Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		14 13 12 11 10 0F 0D 0D 0C	RAM RAM RAM RAM RAM RAM RAM RAM RAM	
Timer 1 MSB Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		13 12 11 10 0F 0E 0D 0C	RAM RAM RAM RAM RAM RAM RAM RAM	
Timer 1 LSB Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		12 11 10 0F 0E 0D 0C	RAM RAM RAM RAM RAM RAM RAM	
Timer 0 MSB Timer 0 LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		11 10 0F 0E 0D 0C	RAM RAM RAM RAM RAM RAM	
Timer D LSB Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		10 0F 0E 0D 0C	RAM RAM RAM RAM RAM	
Day of Week Clock Counter 100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		OF OE OD OC	RAM RAM RAM RAM	
100's Julian Clock Counter Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		OE OD OC	RAM RAM RAM	
Units Julian Clock Counter Years Clock Counter Months Clock Counter Day of Month Clock Counter		0D 0C	RAM RAM	· · · · · · · · · · · · · · · · · · ·
Years Clock Counter Months Clock Counter Day of Month Clock Counter		0C	RAM	
Months Clock Counter Day of Month Clock Counter				
Day of Month Clock Counter				
the second s		OB	RAM	
		0A	RAM	
Hours Clock Counter		09	RAM	
Minutes Clock Counter		08	RAM	
Seconds Clock Counter		07	RAM	The second
1/100 Second Counter		06	RAM	
		05	RAM	
		04	RAM	· · · ·
= 0 🖉 💦 Reg	gister Select = 1	03	RAM	
Register 04 Interrupt	Control Register 1	02	RAM	
Register 03 Interrupt	Control Register 0	01	RAM	
Register 02 Output	t Mode Register			
Register 01 Real Tim	ne Mode Register		<ul> <li>March 19</li> </ul>	
		-		
00	Main Status Register	]		
	571A Internal Men			TL/F/9979-6
F	Register 03 Interrupt I Register 02 Outpu I Register 01 Real Tir 00 00	Register 03 Interrupt Control Register 0 Register 02 Output Mode Register Register 01 Real Time Mode Register	Register 03 Interrupt Control Register 01 I Register 02 Output Mode Register 01 I Register 01 Real Time Mode Register	Register 03 Interrupt Control Register 0 I Register 02 Output Mode Register I Register 01 Real Time Mode Register

DP8571A

## Functional Description (Continued) INITIAL POWER-ON of BOTH VBB and VCC

 $V_{BB}$  and  $V_{CC}$  may be applied in any sequence. In order for the power fail circuitry to function correctly, whenever power is off, the  $V_{CC}$  pin must see a path to ground through a maximum of 1 MΩ. The user should be aware that the control registers will contain random data. The first task to be carried out in an initialization routine is to start the oscillator by writing to the crystal select bits in the Real Time Mode Register. If the DP8571A is configured for single supply mode, an extra 50  $\mu$ A may be consumed until the crystal select bits are programmed. The user should also ensure that the TCP is not in test mode (see register descriptions).

## **REAL TIME CLOCK FUNCTIONAL DESCRIPTION**

As shown in *Figure 2*, the clock has 10 bytes of counters, which count from 1/100 of a second to years. Each counter counts in BCD and is synchronously clocked. The count sequence of the individual byte counters within the clock is shown later in Table VII. Note that the day of week, day of month, day of year, and month counters all roll over to 1. The hours counter in 12 hour mode rolls over to 1 and the AM/PM bit toggles when the hours rolls over to 12 (AM = 0, PM = 1). The AM/PM bit is bit D7 in the hours counter.

All other counters roll over to 0. Also note that the day of year counter is 12 bits long and occupies two addresses. Upon initial application of power the counters will contain random information.

## **READING THE CLOCK: VALIDATED READ**

Since clocking of the counter occurs asynchronously to reading of the counter, it is possible to read the counter while it is being incremented (rollover). This may result in an incorrect time reading. Thus to ensure a correct reading of the entire contents of the clock (or that part of interest), it must be read without a clock rollover occurring. In general this can be done by checking a rollover bit. On this chip the periodic interrupt status bits can serve this function. The following program steps can be used to accomplish this.

- 1. Initialize program for reading clock.
- 2. Dummy read of periodic status bit to clear it.
- 3. Read counter bytes and store.
- 4. Read rollover bit, and test it.
- 5. If rollover occured go to 3.
- 6. If no rollover, done.

To detect the rollover, individual periodic status bits can be polled. The periodic bit chosen should be equal to the highest frequency counter register to be read. That is if only SECONDS through HOURS counters are read, then the SECONDS periodic bit should be used.

## **READING THE CLOCK: INTERRUPT DRIVEN**

Enabling the periodic interrupt mask bits cause interrupts just as the clock rolls over. Enabling the desired update rate and providing an interrupt service routine that executes in less than 10 ms enables clock reading without checking for a rollover.

## **READING THE CLOCK: LATCHED READ**

Another method to read the clock that does not require checking the rollover bit is to write a one into the Time

Save Enable bit (D7) of the Interrupt Routing Register, and then to write a zero. Writing a one into this bit will enable the clock contents to be duplicated in the Time Save RAM. Changing the bit from a one to a zero will freeze and store the contents of the clock in Time Save RAM. The time then can be read without concern for clock rollover, since internal logic takes care of synchronization of the clock. Because only the bits used by the clock counters will be latched, the Time Save RAM should be cleared prior to use to ensure that random data stored in the unused bits do not confuse the host microprocessor. This bit can also provide time save at power failure, see the Additional Supply Management Functions section. With the Time Save Enable bit at a logical 0, the Time Save RAM may be used as RAM if the latched read function is not necessary.

# INITIALIZING AND WRITING TO THE CALENDAR-CLOCK


Upon initial application of power to the TCP or when making time corrections, the time must be written into the clock. To correctly write the time to the counters, the clock would normally be stopped by writing the Start/Stop bit in the Real Time Mode Register to a zero. This stops the clock from counting and disables the carry circuitry. When initializing the clock's Real Time Mode Register, it is recommended that first the various mode bits be written while maintaining the Start/Stop bit reset, and then writing to the register a second time with the Start/Stop bit set.


The above method is useful when the entire clock is being corrected. If one location is being updated the clock need not be stopped since this will reset the prescaler, and time will be lost. An ideal example of this is correcting the hours for daylight savings time. To write to the clock "on the fly" the best method is to wait for the 1/100 of a second periodic interrupt. Then wait an additional 16  $\mu$ s, and then write the data to the clock.

# PRESCALER/OSCILLATOR FUNCTIONAL DESCRIPTION

Feeding the counter chain is a programmable prescaler which divides the crystal oscillator frequency to 32 kHz and further to 100 Hz for the counter chain (see *Figure 3*). The crystal frequency that can be selected are: 32 kHz, 32.768 kHz, 4.9152 MHz, and 4.194304 MHz.

Once 32 kHz is generated it feeds both timers and the clock. The clock and timer prescalers can be independently enabled by controlling the timer or clock Start/Stop bits.





The oscillator is programmed via the Real Time Mode Register to operate at various frequencies. The crystal oscillator is designed to offer optimum performance at each frequency. Thus, at 32.768 kHz the oscillator is configured as a low frequency and low power oscillator. At the higher frequencies the oscillator inverter is reconfigured. In addition to the inverter, the oscillator feedback bias resistor is included on chip, as shown in *Figure 4*. The oscillator input may be driven from an external source if desired. Refer to test mode application note for details. The oscillator stability is enhanced through the use of an on chip regulated power supply.

The typical range of trimmer capacitor (as shown in Oscillator Circuit Diagram *Figure 4*, and in the typical application) at the oscillator input pin is suggested only to allow accurate tuning of the oscillator. This range is based on a typical printed circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases, the **load capacitance** specified by the crystal manufacturer (nominal value 11 pF for the 32.768 crystal) is what determines proper oscillation. This load capcitance is the series combination of capacitance on each side of the crystal (with respect to ground).




FIGURE 4. Oscillator Circuit Diagram

XTAL	Co	Ct	R <sub>OUT</sub> (Switched Internally)
32/32.768 kHz	47 pF	2 pF–22 pF	150 k $\Omega$ to 350 k $\Omega$
4.194304 MHz	68 pF	0 pF-80 pF	500 $\Omega$ to 900 $\Omega$
4.9152 MHz	68 pF	29 pF-49 pF	500 $\Omega$ to 900 $\Omega$

## INTERRUPT LOGIC FUNCTIONAL DESCRIPTION

The TCP has the ability to coordinate processor timing activities. To enhance this, an interrupt structure has been implemented which enables several types of events to cause interrupts. Interrupts are controlled via two Control Registers in block 1 and two Status Registers in block 0. (See Register Description for notes on paging and also *Figure 5* and Table I.) The interrupts are enabled by writing a one to the appropriate bits in Interrupt Control Register 0 and/or 1. Any of the interrupts can be routed to either the INTR pin or the MFO pin, depending on how the Interrupt Routing register is programmed. This, for example, enables the user to dedicate the MFO as a non-maskable interrupt pin to the CPU for power failure detection and enable all other interrupts to appear on the INTR pin. The polarity for the active interrupt can be programmed in the Output Mode Register for either active high or low, and open drain or push pull outputs.

## TABLE I. Registers that are Applicable to Interrupt Control

Register Name	Register Select	Page Select	Address
Main Status Register	х	х	00H
Periodic Flag Register	0	0	03H
Interrupt Routing Register	0	0	04H
Interrupt Control Register 0	1	0	03H
Interrupt Control Register 1	1	0	04H
Output Mode Register	1	0	02H

The Interrupt Status Flag D0, in the Main Status Register, indicates the state of INTR and MFO outputs. It is set when either output becomes active and is cleared when all TCP interrupts have been cleared and no further interrupts are pending (i.e., both INTR and MFO are returned to their inactive state). This flag enables the TCP to be rapidly polled by the  $\mu$ P to determine the source of an interrupt in a wired—OR interrupt system.

Note that the Interrupt Status Flag will only monitor the state of the MFO output if it has been configured as an interrupt output (see Output Mode Register description). This is true, regardless of the state of the Interrupt Routing Register. Thus the Interrupt Status Flag provides a true reflection of all conditions routed to the external pins.

Status for the interrupts are provided by the Main Status Register and the Periodic Flag Register. Bits D1–D5 of the Main Status Register are the main interrupt bits.

These register bits will be set when their associated timing events occur. Enabled Alarm or Timer interrupts that occur will set its Main Status Register bit to a one. However, an external interrupt will only be generated if the appropriate Alarm or Timer interrupt enable bits are set (see *Figure 5*).

Disabling the periodic bits will mask the Main Status Register periodic bit, but not the Periodic Flag Register bits. The Power Fail Interrupt bit is set when the interrupt is enabled and a power fail event has occurred, and is not reset until the power is restored. If all interrupt enable bits are 0 no interrupt will be asserted. However, status still can be read from the Main Status Register in a polled fashion (see *Figure 5*).

To clear a flag in bits D2–D5 of the Main Status Register a 1 must be written back into the bit location that is to be cleared. For the Periodic Flag Register reading the status will reset all the periodic flags.

Interrupts Fall Into Four Categories:

- 1. The Timer Interrupts: For description see Timer Section.
- 2. The Alarm Compare Interrupt: Issued when the value in the time compared RAM equals the counter.
- The Periodic Interrupts: These are issued at every increment of the specific clock counter signal. Thus, an interrupt is issued every minute, second, etc. Each of these interrupts occurs at the roll-over of the specific counter.
- 4. The Power Fail Interrupt: Issued upon recognition of a power fail condition by the internal sensing logic. The power failed condition is determined by the signal on the PFAIL pin. The internal power fail signal is gated with the chip select signal to ensure that the power fail interrupt does not lock the chip out during a read or write.

#### ALARM COMPARE INTERRUPT DESCRIPTON

The alarm/time comparison interrupt is a special interrupt similar to an alarm clock wake up buzzer. This interrupt is generated when the clock time is equal to a value programmed into the alarm compare registers. Up to six bytes can be enabled to perform alarm time comparisons on the counter chain. These six bytes, or some subset thereof, would be loaded with the future time at which the interrupt will occur. Next, the appropriate bits in the Interrupt Control Register 1 are enabled or disabled (refer to detailed description of Interrupt Control Register 1). The TCP then compares these bytes with the clock time. When all the enabled compare registers equal the clock time an alarm interrupt is issued, but only if the alarm compare interrupt is enabled can the interrupt be generated externally. Each alarm compare bit in the Control Register will enable a specific byte for comparison to the clock. Disabling a compare byte is the same as setting its associated counter comparator to an "always equal" state. For example, to generate an interrupt at 3:15 AM of every day, load the hours compare with 0 3 (BCD), the minutes compare with 1 5 (BCD) and the faster counters with 0 0 (BCD), and then disable all other compare registers. So every day when the time rolls over from 3:14:59.99, an interrupt is issued. This bit may be reset by writing a one to bit D3 in the Main Status Register at any time after the alarm has been generated.

If time comparison for an individual byte counter is disabled, that corresponding RAM location can then be used as general purpose storage.

## PERIODIC INTERRUPTS DESCRIPTION

The Periodic Flag Register contains six flags which are set by real-time generated "ticks" at various time intervals, see *Figure 5*. These flags constantly sense the periodic signals and may be used whether or not interrupts are enabled. These flags are cleared by any read or write operation performed on this register. To generate periodic interrupts at the desired rate, the associated Periodic Interrupt Enable bit in Interrupt Control Register 0 must be set. Any combination of periodic interrupts may be enabled to operate simultaneously. Enabled periodic interrupts will now affect the Periodic Interrupt Flag in the Main Status Register. The Periodic Route bit in the Interrupt Routing Register is used to route the periodic interrupt events to either the INTR output or the MFO output.

When a periodic event occurs, the Periodic Interrupt Flag in the Main Status Register is set, causing an interrupt to be generated. The  $\mu$ P clears both flag and interrupt by writing a "1" to the Periodic Interrupt Flag. The individual flags in the periodic Interrupt Flag Register do not require clearing to cancel the interrupt.

If all periodic interrupts are disabled and a periodic interrupt is left pending (i.e., the Periodic Interrupt Flag is still set), the Periodic Interrupt Flag will still be required to be cleared to cancel the pending interrupt.

## POWER FAIL INTERRUPTS DESCRIPTION


The Power Fail Status Flag in the Main Status Register monitors the state of the internal power fail signal. This flag may be interrogated by the  $\mu$ P, but it cannot be cleared; it is cleared automatically by the TCP when system power is restored. To generate an interrupt when the power fails, the Power Fail Interrupt Enable bit in Interrupt Control Register 1 is set.

The Power Fail Route bit determines which output the interrupt will appear on. Although this interrupt may not be cleared, it may be masked by clearing the Power Fail Interrupt Enable bit.

# POWER FAILURE CIRCUITRY FUNCTIONAL DESCRIPTION

Since the clock must be operated from a battery when the main system supply has been turned off, the DP8571A provides circuitry to simplify design in battery backed systems. This circuitry switches over to the back up supply, and isolates the DP8571A from the host system. *Figure 6* shows a simplified block diagram of this circuitry, which consists of three major sections; 1) power loss logic: 2) battery switch over logic: and 3) isolation logic.

Detection of power loss occurs when  $\overrightarrow{PFAIL}$  is low. Debounce logic provides a 30  $\mu$ s-63  $\mu$ s debounce time, which will prevent noise on the  $\overrightarrow{PFAIL}$  pin from being interpreted as a system failure. After 30  $\mu$ s-63  $\mu$ s the debounce logic times out and a signal is generated indicating that system power is marginal and is failing. The Power Fail Interrupt will then be generated.




2-37

N

Ar78890

4

1



#### FIGURE 6. System-Battery Switchover (Upper Left), Power Fail and Lock-Out Circuits (Lower Right)

The user may choose to have this power failed signal lockout the TCP's data bus within 30 µs min/63 µs max or to delay the lock-out to enable µP access after power failure is detected. This delay is enabled by setting the delay enable bit in the Routing Register. Also, if the lock-out delay was not enabled the TCP will disconnect itself from the bus within 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max. If chip select is low when a power failure is detected, a safety circuit will ensure that if a read or write is held active continuously for greater than 30 µs after the power fail signal is asserted, the lock-out will be forced. If a lock-out delay is enabled, the DP8571A will remain active for 480  $\mu$ s after power fail is detected. This will enable the µP to perform last minute bookkeeping before total system collapse. When the host CPU is finished accessing the TCP it may force the bus lock-out before 480 µs has elapsed by resetting the delay enable bit.

The battery switch over circuitry is completely independent of the  $\overline{\text{PFAIL}}$  pin. A separate circuit compares  $V_{CC}$  to the  $V_{BB}$  voltage. As the main supply fails, the TCP will continue to operate from the  $V_{CC}$  pin until  $V_{CC}$  falls below the  $V_{BB}$  voltage. At this time, the battery supply is switched in,  $V_{CC}$  is disconnected, and the device is now in the standby mode. If indeterminate operation of the battery switch over circuit is to be avoided, then the voltage at the  $V_{CC}$  pin must not be allowed to equal the voltage at the  $V_{BB}$  pin.

After the generation of a lock-out signal, and eventual switch in of the battery supply, the pins of the TCP will be configured as shown in Table II. Outputs that have a pull-up resistor should be connected to a voltage no greater than  $V_{BB}$ .

#### **TABLE II. Pin Isolation during a Power Failure**

Pin	PFAIL = Logic 0	Standby Mode V <sub>BB</sub> > V <sub>CC</sub>
CS, RD, WR	Locked Out	Locked Out
A0-A4	Locked Out	Locked Out
D0-D7	Locked Out	Locked Out
Oscillator	Not Isolated	Not Isolated
PFAIL	Not Isolated	Not Isolated
INTR, MFO	Not Isolated	Open Drain

The Timer and Interrupt Power Fail Operation bits in the Real-Time Mode Register determine whether or not the timers and interrupts will continue to function after a power fail event.

As power returns to the system, the battery switch over circuit will switch back to  $V_{CC}$  power as soon as it becomes greater than the battery voltage. The chip will remain in the locked out state as long as PFAIL = 0. When PFAIL = 1

the chip is unlocked, but only after another 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max debounce time. The system designer must ensure that his system is stable when power has returned.

The power fail circuitry contains active linear circuitry that draws supply current from V<sub>CC</sub>. In some cases this may be undesirable, so this circuit can be disabled by masking the power fail interrupt. The power fail input can perform all lock-out functions previously mentioned, except that no external interrupt will be issued. Note that the linear power fail circuitry is switched off automatically when using V<sub>BB</sub> in standby mode.

# LOW BATTERY, INITIAL POWER ON DETECT, AND POWER FAIL TIME SAVE

There are three other functions provided on the DP8571A to ease power supply control. These are an initial Power On detect circuit, which also can be used as a time keeping failure detect, a low battery detect circuit, and a time save on power failure.

On initial power up the Oscillator Fail Flag will be set to a one and the real time clock start bit reset to a zero. This indicates that an oscillator fail event has occurred, and time keeping has failed.

The Oscillator Fail flag will not be reset until the real-time clock is started. This allows the system to discriminate between an initial power-up and recovery from a power failure. If the battery backed mode is selected, then bit D6 of the Periodic Flag Register must be written low. This will not affect the contents of the Oscillator Fail Flag.

Another status bit is the low battery detect. This bit is set only when the clock is operating under the  $V_{CC}$  pin, and when the battery voltage is determined to be less than 2.1V (typical). When the power fail interrupt enable bit is low, it disables the power fail circuit and will also shut off the low battery voltage detection circuit as well.

To relieve CPU overhead for saving time upon power failure, the Time Save Enable bit is provided to do this automatically. (See also Reading the Clock: Latched Read.) The Time Save Enable bit, when set, causes the Time Save RAM to follow the contents of the clock. This bit can be reset by software, but if set before a power failure occurs, it will automatically be reset when the clock switches to the battery supply (not when a power failure is detected by the PFAIL pin). Thus, writing a one to the Time Save bit enables both a software write or power fail write.

## SINGLE POWER SUPPLY APPLICATIONS

The DP8571A can be used in a single power supply application. To achieve this, the V<sub>BB</sub> pin must be connected to ground, and the power connected to V<sub>CC</sub> and PFAIL pins. The Oscillator Failed/Single Supply bit in the Periodic Flag Register should be set to a logic 1, which will disable the oscillator battery reference circuit. The power fail interrupt should also be disabled. This will turn off the linear power fail detection circuits, and will eliminate any quiescent power drawn through these circuits. Until the crystal select bits are initialized, the DP8571A may consume about 50  $\mu$ A due to arbitrary oscillator selection at power on.

(This extra 50  $\mu\text{A}$  is not consumed if the battery backed mode is selected).

## TIMER FUNCTIONAL DESCRIPTION

The DP8571A contains 2 independent multi-mode timers. Each timer is composed of a 16-bit negative edge triggered

binary down counter and associated control. The operation is similar to existing  $\mu$ P peripheral timers except that several features have been enhanced. The timers can operate in four modes, and in addition, the input clock frequency can be selected from a prescaler over a wide range of frequencies. Furthermore, these timers are capable of generating interrupts and the Timer 0 output signal is available as a hardware output via the MFO pin. Timer 1 output, however, is not available as a hardware output signal. Both the interrupt and MFO outputs are fully programmable active high, or low, open drain, or push-pull.

Figure 7 shows the functional block diagram of one of the timers. The timer consists of a 16-bit counter, two 8-bit input registers, two 8-bit output registers, clock prescaler, mode control logic, and output control logic. The timer and the data registers are organized as two bytes for each timer. Under normal operations a read/write to the timer locations will read or write to the data input register. The timer contents an be read by setting the counter Read bit (RD) in the timer control register.

## TIMER INITIALIZATION

The timer's operation is controlled by a set of registers, as listed in Table III. These consist of 2 data input registers and one control register per timer. The data input registers contain the timers count down value. The Timer Control Register is used to set up the mode of operation and the input clock rate. The timer related interrupts can be controlled by programming the Interrupt Routing Register and Interrupt Control Register.

Register Name	Register Select	Page Select	Address
Timer 0 Data MSB	x	0	10H
Timer 0 Data LSB	Х	0	0FH
Timer 0 Control Register	0	0	01H
Timer 1 Data MSB	Х	0	12H
Timer 1 Data LSB	X	0	11H
Timer 1 Control Register	0	0	02H
Interrupt Routing Register	0	0	04H
Interrupt Control Reg. 0	1	0	03H
Output Mode Register	1	0	02H

All these registers must be initialized prior to starting the timer(s). The Timer Control Register should first be set to select the timer mode with the timer start/stop bit reset. Then when the timer is to be started the control register should be rewritten identically but with the start/stop bit set.

## TIMER OPERATION

Each timer is capable of operation in one of four modes. As mentioned, these modes are programmed in each timer's Control Register which is described later. All four modes operate in a similar manner. They operate on the two 8-bit data words stored into the Data Input Register. At the beginning of a counting cycle the 2 bytes are loaded into the timer and the timer commences counting down towards zero. The exact action taken when zero is reached depends on the mode selected, but in general, the timer output will change state, and an interrupt will be generated if the timer interrupts are unmasked.

## Functional Description (Continued) INPUT CLOCK SELECTION

The input frequency to the timers may be selected. Each timer has a prescaler that gives a wide selection of clocking rates. Table IV shows the range of programmable clocks available and the corresponding setting in the Timer Control Register. Note that the output of Timer 1 may be used as the input to Timer 0. This is a cascade option for the timers and allows them to be clocked as a 32-bit down counter.

#### TABLE IV. Programmable Timer Input Clocks

C2	C1	CO	Selected Clock
0	0	0	Timer 1 Output
0	0	1	Crystal Oscillator
0	1.	. 0	(Crystal Oscillator)/4
0	1	1	93.5 μs (10.7 kHz)
1	0	0	1 ms (1 kHz)
1.	0	1	10 ms (100 Hz)
1 1	1	0	1/10 Second (10 Hz)
1	1	1	1 Second (1 Hz)

Note that the second and third selections are not fixed frequencies, but depend on the crystal oscillator frequency chosen.

Since the input clock frequencies are usually running asynchronously to the timer Start/Stop control bit, a 1 clock cycle error may result. This error results when the Start/Stop occurs just after the clock edge (max error). To minimize this error on all clocks an independent prescaler is used for each timer and is designed so that its Start/Stop error is less than 1 clock cycle.

The count hold/gate bit in the Timer Control Register can be used to suspend the timer operation in modes 0, 1, and 2 (in mode 3 it is the trigger input). Suspending the timer causes the same synchronization error that starting the timer does. The range of errors is specified in Table V.

TABLE	V. Maximum	Synchronization	Errors
-------	------------	-----------------	--------

Clock Selected	Error
External	+ Ext. Clock Period
Crystal	+ 1 Crystal Clock Period
Crystal/4	+ 1 Crystal Clock Period
10.7 kHz	+32 μs
1 kHz	+ 32 µs
100 Hz	+32 μs
10 Hz .	+ 32 µs
1 Hz	+ 32 µs

## MODES OF OPERATION


Bits M0 and M1 in the Timer Control Registers are used to specify the modes of operation. The mode selection is described in Table VI.

## TABLE VI. Programmable Timer Modes of Operation

M1	MO	Function	Modes
0	0	Single Pulse Generator	Mode 0
0	1	Rate Generator, Pulse Output	Mode 1
1	0	Square Wave Output	Mode 2
1	1	Retriggerable One Shot	Mode 3

## MODE 0: SINGLE PULSE GENERATOR

When the timer is in this mode the output will be initially low if the Timer Start/Stop bit is low (stopped). When this mode is initiated the timer output will go high on the next falling edge of the prescaler's input clock, the contents of the



input data registers are loaded into the timer. The output will stay high until the counter reaches zero. At zero the output is reset. The result is an output pulse whose duration is equal to the input clock period times the count value (N) loaded into the input data register. This is shown in *Figure 8*.

Pulse Width = Clock Period  $\times$  N

An interrupt is generated when the zero count is reached. This can be used for one-time interrupts that are set to occur a certain amount of time in the future. In this mode the Timer Start/Stop bit (TSS) is automatically reset upon zero detection. This removes the need to reset TSS before starting another operation.

The count down operation may be temporarily suspended either under software control by setting the Count Hold/ Gate bit in the timer register high, or in hardware by setting the G0 or G1 pin high.

The above discussion assumes that the MFO output is programmed to be non-inverting outputs (active high). If the polarity of the output waveform is wrong for the application the polarity can be reversed by configuring the Output Mode Register. The drive configuration can also be programmed to be push pull or open drain.

#### MODE 1: RATE GENERATOR

When operating in this mode the timer will operate continuously. Before the timer is started its output is low. When the timer is started the input data register contents are loaded into the counter on the negative clock edge and the output is set high (again assuming the Output Mode Register is programmed active high). The timer will then count down to zero. Once the zero count is reached the output goes low for one clock period of the timer clock. Then on the next clock the counter is reloaded automatically and the countdown repeats itself. The output, shown in *Figure 9*, is a waveform whose pulse width and period is determined by N, the input register value, and the input clock period:

Period = (N + 1) (Clock Period)

#### Pulse Width = Clock Period

Again, the output polarity is controllable as in mode 0. If enabled, an interrupt is generated whenever the zero count is reached. This can be used to generate a periodic interrupt.


#### **MODE 2: SQUARE WAVE GENERATOR**


This mode is also cyclic but in this case a square wave rather than a pulse is generated. The output square wave period is determined by the value loaded into the timer input register. This period and the duty cycle are:

 $Period = 2(N + 1) (Clock Period) \qquad Duty Cycle = 0.5$ 

When the timer is stopped the output will be low, and when the Start/Stop bit is set high the timer's counter will be loaded on the next clock falling transition and the output will be set high.

The output will be toggled after the zero count is detected and the counter will then be reloaded, and the cycle will continue. Thus, every N + 1 counts the output gets toggled, as shown in *Figure 10*. Like the other modes the timer operation can be suspended by setting the count hold/gate bit (CHG) in the Timer Control Register. An interrupt will be generated every falling edge of the timer output, if enabled.





(MFO Output Programmed Active High)

#### MODE 3: RETRIGGERABLE ONE SHOT

Once the timer Start/Stop bit is set the output stays inactive, and nothing happens until the Count Hold/Gate (CHG) bit is set in the timer control register. When a transition ocurs the one shot output is set active immediately; the counter is loaded with the value in the input register on the next transition of the input clock and the countdown begins. If a retrigger occurs, regardless of the current counter value, the counters will be reloaded with the value in the input register and the counter will be restarted without changing the output state. See *Figure 11*. A trigger count can occur at any time during the count cycle. In this mode the timer will output a single pulse whose width is determined by the value in the input data register (N) and the input clock period.

#### Pulse Width = Clock Period $\times$ N

The timer will generate an interrupt only when it reaches a count of zero. This timer mode is useful for continuous "watch dog" timing, line frequency power failure detection, etc.

#### **READING THE TIMERS**

National has discovered that some users may encounter unacceptable error rates for their applications when reading the timers on the fly asynchronously. When doing asynchronous reads of the timers, an error may occur. The error is that a successive read may be larger than the previous read. Experimental results indicate that the typical error rate is approximately one per 29,000 under the following conditions:

Timer clock frequency of 5 MHz.

Computer: 386/33 MHz PC/AT

Program: Microsoft "C" 6.0, reading and saving timer contents in a continuous loop. Those users who find the error rate unacceptable may reduce the problem effectively to zero by employing a hardware work-around that synchronizes the writing of the read bit to the timer control register with respect to the decrementing clock. Refer to *Figure 1* in Appendix A, for a suggested hardware work-around.

A software work-around can reduce the errors but not as substantial as a hardware work-around. Software workarounds are based on observations that the read following a bad read appeared to be valid.

This problem concerns statistical probability and is similar to metastability issues. For more information on metastability, refer to 1991 IEEE transactions on Custom Integrated Circuits Conference, paper by T.J. Gabara of AT&T Bell Laboratories, page 29.4.1.


Normally reading the timer data register addresses, 0FH and 10H for Timer 0 and 11H and 12H for Timer 1 will result in reading the input data register which contains the preset value for the timers.

To read the contents of a timer, the  $\mu$ P first sets the timer read bit in the appropriate Timer Control Register high. This will cause the counter's contents to be latched to 2-bit-8-bit output registers, and will enable these registers to be read if the  $\mu$ P reads the timer's input data register addresses. On reading the LSB byte the timer read bit is internally reset and subsequent reads of the timer locations will return the input register values.

#### DETAILED REGISTER DESCRIPTION

There are 5 external address bits: Thus, the host microprocessor has access to 32 locations at one time. An internal switching scheme provides a total of 67 locations.

This complete address space is organized into two pages. Page 0 contains two blocks of control registers, timers, real time clock counters, and special purpose RAM, while page 1 contains general purpose RAM. Using two blocks enables the 9 control registers to be mapped into 5 locations. The only register that does not get switched is the Main Status Register. It contains the page select bit and the register select bit as well as status information.



A memory map is shown in *Figure 2* and register addressing in Table VII. They show the name, address and page locations for the DP8571A.

TABLE VII. Register/Counter/RAM
Addressing for DP8571A


A0-4	PS (Note 1)	RS (Note 2)	Description		
CONTROL REGISTERS					
00	х	х	Main Status Register		
01	0	0	Timer 0 Control Register		
02	0	0	Timer 1 Control Register		
03	0	0	Periodic Flag Register		
04	0	0	Interrupt Routing Register		
01	0	1	Real Time Mode Register		
02	0	1	Output Mode Register		
03	0	1	Interrupt Control Register 0		
04	0	1	Interrupt Control Register 1		
COUNTERS (CLOCK CALENDAR)					
05	0	х	1/100, 1/10 Seconds (0-99)		
06	0	х	Seconds	(0-59)	
07	0	X	Minutes	(0-59)	
08	0	х	Hours	(1-12, 0-23)	
09	0	х	Days of		
			Month	(1-28/29/30/31)	
0A	0	х	Months	(1-12)	
0B	0	х	Years	(0-99)	
0C	0	х	Julian Date (LSB)	(0-99) (Note 3)	
0D	0	х	Julian Date	(0-3)	
0E	0	х	Day of Week	(1-7)	
TIMER DATA REGISTERS					
0F	0	х	Timer 0 LSB		
10	0	х	Timer 0 MSB		
11	0	х	Timer 1 LSB		
12	0	Х	Timer 1 MSB		
TIME COMPARE RAM					
13	0	х	Sec Compare RAM	(0-59)	
14	0	х	Min Compare RAM	(0-59)	
15	0	х	Hours Compare		
			RAM	(1-12, 0-23)	
16	0	х	DOM Compare		
			RAM	(1-28/29/30/31)	
17	0	х	Months Compare		
			RAM	(1-12)	
18	0	х	DOW Compare RAM		
TIME SAVE RAM					
19	0	х	Seconds Time Save F	RAM .	
1A	0	х	Minutes Time Save RAM		
1B	0	х	Hours Time Save RAM		
1C	Ō	x	Day of Month Time Save RAM		
1D	ō	x	Months Time Save RAM		
1E	0	1	RAM		
1F	ō	x		RAM/Test Mode Register	
01–1F	1	х	2nd Page General Purpose RAM		

Note 1: PS-Page Select (Bit D7 of Main Status Register)

Note 2: RS-Register Select (Bit D6 of Main Status Register)

Note 3: The LSB counters count 0-99 until the hundreds of days counter reaches 3. Then the LSB counters count to 65 or 66 (if a leap year). The rollover is from 365/366 to 1.

## MAIN STATUS REGISTER



TL/F/9979-16

The Main Status Register is always located at address 0 regardless of the register block or the page selected.


D0: This read only bit is a general interrupt status bit that is taken directly from the interrupt pins. The bit is a one when an interrupt is pending on either the INTR pin or the MFO pin (when configured as an interrupt). This is unlike D3–D5 which can be set by an internal event but may not cause an interrupt. This bit is reset when the interrupt status bits in the Main Status Register are cleared.

**D1-D5:** These five bits of the Main Status Register are the main interrupt status bits. Any bit may be a one when any of the interrupts are pending. Once an interrupt is asserted the  $\mu$ P will read this register to determine the cause. These interrupt status bits are not reset when read. Except for D1, to reset an interrupt a one is written back to the corresponding bit that is being tested. D1 is reset whenever the PFAIL pin = logic 1. This prevents loss of interrupt status when reading the register in a polled mode. D1, D3-D5 are set regardless of whether these interrupts are to bits D6 and D7 of Interrupt Control Registers 0 and 1.

**D6 and D7:** These bits are Read/Write bits that control which register block or RAM page is to be selected. Bit D6 controls the register block to be accessed (see memory map). The memory map of the clock is further divided into two memory pages. One page is the registers, clock and timers, and the second page contains 31 bytes of general purpose RAM. The page selection is determined by bit D7.



## Functional Description (Continued) TIMER 0 AND 1 CONTROL REGISTER



These registers control the operation of the timers. Each timer has its own register.

D0: This bit will Start (1) or Stop (0) the timer. When the timer is stopped the timer's prescaler and counter are reset, and the timer will restart from the beginning when started again. In mode 0 on time out the TSS bit is internally reset.


D1 and D2: These control the count mode of the timers. See Table VI.

**D3-D5:** These bits control which clock signal is applied to the timer's counter input. Refer to Table IV for details.

**D6:** This is the read bit. If a one is written into this location it will cause the contents of the timer to be latched into a holding register, which can be read by the  $\mu$ P at any time. Reading the least significant byte of the timer will reset the RD bit. The timer read cycle can be aborted by writing RD to zero.

**D7:** The CHG bit has two mode dependent functions. In modes 0 through 2 writing a one to this bit will suspend the timer operation (without resetting the timer prescaler). However, in mode 3 this bit is used to trigger or re-trigger the count sequence as with the gate pins. If retriggering is desired using the CHG bit, it is not necessary to write a zero to this location prior to the re-trigger. The action of further writing a one to this bit will re-trigger the count.

#### PERIODIC FLAG REGISTER



The Periodic Flag Register has the same bit for bit correspondence as Interrupt Control Register 0 except for D6 and D7. For normal operation (i.e., not a single supply application) this register must be written to on initial power up or after an oscillator fail event. D0–D5 are read only bits, D6 and D7 are read/write. **D0-D5:** These bits are set by the real time rollover events: (Time Change = 1). The bits are reset when the register is read and can be used as selective data change flags.

**D6:** This bit performs a dual function. When this bit is read, a one indicates that an oscillator failure has occurred and the time information may have been lost. Some of the ways an oscillator failure may be caused are: failure of the crystal, shorting OSC IN or OSC OUT to GND or V<sub>CC</sub>, removal of battery when in the battery backed mode (when a "0" is written to D6), lowering the voltage at the V<sub>BB</sub> pin to a value less than 2.2V when in the battery backed mode. Bit D6 is automatically set to 1 on initial power-up or an oscillator fail event. The oscillator fail flag is reset by writing a one to the clock start/stop bit in the Real Time Mode Register, with the crystal oscillating.


When D6 is written to, it defines whether the TCP is being used in battery backed (normal) or in a single supply mode application. When set to a one this bit configures the TCP for single power supply applications. This bit is automatically set on initial power-up or an oscillator fail event. When set, D6 disables the oscillator reference circuit. The result is that the oscillator is referenced to  $V_{CC}$ . When a zero is written to D6 the oscillator reference is enabled, thus the oscillator is referenced to  $V_{BC}$ . This allows operation in standard battery standby applications.

At initial power on, if the DP8571A is going to be programmed for battery backed mode, the  $V_{BB}$  pin should be connected to a potential in the range of 2.2V to  $V_{CC}$ -0.4V.

For single supply mode operation, the  $V_{BB}$  pin should be connected to GND and the  $\overline{\text{PFAIL}}$  pin connected to  $V_{CC}.$ 

**D7:** Writing a one to this bit enables the test mode register at location 1F (see Table VII). This bit should be forced to zero during initialization for normal operation. If the test mode has been entered, clear the test mode register before leaving test mode. (See separate test mode application note for further details.)

#### INTERRUPT ROUTING REGISTER



**D0-D4:** The lower 5 bits of this register are associated with the main interrupt sources created by this chip. The purpose of this register is to route the interrupts to either the MFO (multi-function pin), or to the main interrupt pin. When any bit is set the associated interrupt signal will be sent to the MFO pin, and when zero it will be sent to the INTR pin.


**D5:** The Delay Enable bit is used when a power fail occurs. If this bit is set, a 480  $\mu$ s delay is generated internally before the  $\mu$ P interface is locked out. This will enable the  $\mu$ P to access the registers for up to 480  $\mu$ s after it receives a power fail interrupt. After a power failure is detected but prior to the 480  $\mu$ s delay timing out, the host  $\mu$ P may force immediate lock out by resetting the Delay Enable bit. Note if this bit is a 0 when power fails then after a delay of 30  $\mu$ s min/63  $\mu$ s max the  $\mu$ P cannot read the chip.

**D6:** This read only bit is set and reset by the voltage at the  $V_{BB}$  pin. It can be used by the  $\mu P$  to determine whether the battery voltage at the  $V_{BB}$  pin is getting too low. A comparator monitors the battery and when the voltage is lower than 2.1V (typical) this bit is set. The power fail interrupt must be enabled to check for a low battery voltage.

**D7:** Time Save Enable bit controls the loading of real-timeclock data into the Time Save RAM. When a one is written to this bit the Time Save RAM will follow the corresponding clock registers, and when a zero is written to this bit the time in the Time Save RAM is frozen. This eliminates any synchronization problems when reading the clock, thus negating the need to check for a counter rollover during a read cycle.

This bit must be set to a one prior to power failing to enable the Time Save feature. When the power fails this bit is automatically reset and the time is saved in the Time Save RAM.

#### REAL TIME MODE REGISTER



D0-D1: These are the leap year counter bits. These bits are written to set the number of years from the previous leap year. The leap year counter increments on December 31st and it internally enables the February 29th counter state. This method of setting the leap year allows leap year to occur whenever the user wishes to, thus providing flexibility in implementing Japanese leap year function.

LY1	LYO	Leap Yea <del>r</del> Counter
0	0	Leap Year Current Year
0	1	Leap Year Last Year
1	0	Leap Year 2 Years Ago
1	1	Leap Year 3 Years Ago

**D2:** The count mode for the hours counter can be set to either 24 hour mode or 12 hour mode with AM/PM indicator. A one will place the clock in 12 hour mode.

D3: This bit is the master Start/Stop bit for the clock. When a one is written to this bit the real time counter's prescaler and counter chain are enabled. When this bit is reset to zero the contents of the real time counter is stopped and the prescaler is cleared. When the TCP is initially powered up this bit will be held at a logic 0 until the oscillator starts functioning correctly after which this bit may be modified. If an oscillator fail event occurs, this bit will be reset to logic 0.

**D4:** This bit controls the operation of the interrupt output in standby mode. If set to a one it allows Alarm, Periodic, and Power Fail interrupts to be functional in standby mode. Timer interrupts will also be functional provided that bit D5 is also set. Note that the MFO and INTR pins are configured as open drain in standby mode.

If bit D4 is set to a zero then interrupt control register 0 and bits D6 and D7 of interrupt control register 1 will be reset when the TCP enters the standby mode (V<sub>BB</sub> > V<sub>CC</sub>). They will have to be re-configured when system (V<sub>CC</sub>) power is restored.

**D5:** This bit controls the operation of the timers in standby mode. If set to a one the timers will continue to function when the TCP is in standby mode. The input pins TCK, G0, G1 are locked out in standby mode, and cannot be used.


Therefore external control of the timers is not possible in standby mode. Note also that MFO and T1 pins are automatically reconfigured open drain during standby.

**D6 and D7:** These two bits select the crystal clock frequency as per the following table:

XT1	ХТО	Crystal Frequency
0	0	32.768 kHz
0	1	4.194304 MHz
1	0	4.9152 MHz
1	1	32.000 kHz

All bits are Read/Write, and any mode written into this register can be determined by reading the register. On initial power up these bits are random.

#### OUTPUT MODE REGISTER



 ${\rm D0}$  and  ${\rm D1:}$  These bits are available as general purpose RAM.

D2: This bit, when set to a one makes the INTR output pin active high, and when set to a zero, it makes this pin active low.

**D3:** This bit controls whether the INTR pin is an open drain or push-pull output. A one indicates push-pull.


D4: This bit, when set to a one makes the MFO output pin active high, and when set to a zero, it makes this pin active low.

**D5:** This bit controls whether the MFO pin is an open drain or push-pull output. A one indicates push-pull.

**D6 and D7:** These bits are used to program the signal appearing at the MFO output, as follows:

D7	D6	MFO Output Signal
0	0	2nd Interrupt
0	1	Timer 0 Waveform
1	X	Buffered Crystal Oscillator

#### **INTERRUPT CONTROL REGISTER 0**




If battery backed mode is selected and the DP8571A is in standby (V\_BB > V\_CC) then all bits are controlled by D4 of the Real Time Mode Register.

D0-D5: These bits are used to enable one of the selected periodic interrupts by writing a one into the appropriate bit. These interrupts are issued at the rollover of the clock. For example, the minutes interrupt will be issued whenever the minutes counter increments. In all likelihood the interrupt will be enabled asynchronously with the real time change. Therefore, the very first interrupt will occur in less than the periodic time chosen, but after the first interrupt all subse quent interrupts will be spaced correctly. These interrupts are useful when minute, second, real time reading, or task switching is required. When all six bits are written to a 0 this disables periodic interrupts from the Main Status Register and the interrupt pin.

**D6 and D7:** These are individual timer enable bits. A one written to these bits enable the timers to generate interrupts to the  $\mu$ P.

#### INTERRUPT CONTROL REGISTER 1



TL/F/9979-23

D0-D5: Each of these bits are enable bits which will enable a comparison between an individual clock counter and its associated compare RAM. If any bit is a zero then that clock-RAM comparator is set to the "always equal" state and the associated TIME COMPARE RAM byte can be used as general purpose RAM. However, to ensure that an alarm interrupt is not generated at bit D3 of the Main Status Register, all bits must be written to a logic zero.

**D6:** In order to generate an external alarm compare interrupt to the  $\mu P$  from bit D3 of the Main Status Register, this bit must be written to a logic 1. If battery backed mode is selected and the DP8571A is in standby (V<sub>BB</sub> > V<sub>CC</sub>) then this bit is controlled by D4 of the Real Time Mode Register.

**D7:** The MSB of this register is the enable bit for the Power Fail Interrupt. When this bit is set to a one an interrupt will be generated to the  $\mu$ P when PFAIL = 0. If battery backed mode is selected and the DP8571A is in standby (V<sub>BB</sub> > V<sub>CC</sub>) then this bit is controlled by D4 of the Real Time Mode Register.

This bit also enables the low battery detection analog circuitry.

If the user wishes to mask the power fail interrupt, but utilize the analog circuitry, this bit should be enabled, and the Routing Register can be used to route the interrupt to the MFO pin. The MFO pin can then be left open or configured as the Timer 0 or buffered oscillator output.

D7	D6	D5	D4	D3	D2	D1	D0	
lain Status F	Register PS =	0 RS = 0 /	ADDRESS = 0	0H				1. Reset by
R/W	R/W	R/W <sup>1</sup>	R/W <sup>1</sup>	R/W <sup>1</sup>	R/W <sup>1</sup>	R <sup>2</sup>	R3	writing 1 to bit.
Page Select	Register Select	Timer 1 Interrupt	Timer 0 Interrupt	Alarm Interrupt	Periodic Interrupt	Power Fail Interrupt	Interrupt Status	2. Set/reset by voltage at
fimer 0 Conti	rol Register PS	S = 0 RS =	0 Address =	01H				PFAIL pin. 3. Reset when all pending interrupts are removed.
Count Hold	Timer	Input Clock	Input Clock	Input Clock	Mode	Mode	Timer	]
Gate	Read	Select C2	Select C1	Select C0	Select M1	Select M0	Start/Stop	All Bits R/W
limer 1 Cont	rol Register PS	S = 0 R	S = 0 Ad	ddress = 02H	I			
Count Hold	Timer	Input Clock	Input Clock	Input Clock	Mode	Mode	Timer	All Bits R/W
Gate	Read	Select C2	Select C1	Select C0	Select M1	Select M0	Start/Stop	
Periodic Flag	Register PS =	= 0 RS =	= 0 Addr	ess = 03H				
R/W	R/W4	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	4. Read Osc fail Write 0 Batt-
Test	Osc. Fail/	1 ms	10 ms	100 ms	Seconds	10 Second	Minute	Backed Mode
Mode	Single Supply	Flag	Flag	Flag	Flag	Flag	Flag	Write 1 Single
		1	v		<u>_</u>	<b>`</b>		
		L			<u>1</u>			5. Reset by positive edge of read.
nterrupt Rou R/W	iting Register   R <sup>6</sup>	PS = 0 R/W		Address = 04 R/W	<u>1</u>	R/W	R/W	Supply Mode 5. Reset by positive edge
R/W	R <sup>6</sup>		RS = 0	Address = 04	IH			Supply Mode 5. Reset by positive edge
R/W Time Save	R <sup>6</sup>	R/W	RS = 0 R/W Timer 1 Int. Route	Address = 04 R/W Timer 0 Int. Route	IH R/W Alarm Int. Route	R/W Periodic Int. Route	R/W Power Fail Int. Route	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub>
R/W	R <sup>6</sup>	R/W Power Fail	RS = 0 <b>R/W</b> Timer 1	Address = 04 R/W Timer 0	IH <b>R/W</b> Alarm	R/W Periodic	R/W Power Fail	Supply Mode 5. Reset by positive edge of read. 6. Set and reset
R/W Time Save Enable	R <sup>6</sup>	R/W Power Fail Delay Enable	RS = 0 R/W Timer 1 Int. Route MFO/INT	Address = 04 R/W Timer 0 Int. Route	IH R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route	R/W Power Fail Int. Route	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub>
R/W Time Save Enable	R <sup>6</sup> Low Battery Flag	R/W Power Fail Delay Enable	RS = 0 R/W Timer 1 Int. Route MFO/INT	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT	IH R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT Leap Year	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage.
R/W Time Save Enable Real Time Mo	R <sup>6</sup> Low Battery Flag	<b>R/W</b> Power Fail Delay Enable S = 0 R	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H	IH R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub>
R/W Time Save Enable Real Time Mo Crystal Freq. XT1	R6 Low Battery Flag de Register P3 Crystal	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock	H R/W Alarm Int. Route MFO/INT	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT Leap Year	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage.
R/W Time Save Enable Real Time Mo Crystal Freq. XT1	R <sup>5</sup> Low Battery Flag de Register P Crystal Freq. XT0	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR	IH R/W Alarm Int. Route MFO/INT I 12/24 Hr. Mode INTR	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode	R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS =	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H	H Alarm Int. Route MFO/INT 12/24 Hr. Mode	R/W Periodic Int. Route MFO/INT	R/W Power Fail Int. Route MFO/INT Leap Year	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage.
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode MFO as Crystal	R <sup>6</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO	R/W Periodic Int. Route MFO/INT Leap Year MSB	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode MFO as Crystal	R <sup>5</sup> Low Battery Flag de Register P Crystal Freq. XT0 Register PS = MFO as Timer 0	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM	R/W Power Fail Int. Route MFO/INT Leap Year LSB	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode MFO as Crystal nterrupt Con Timer 1 Interrupt	R <sup>5</sup> Low Battery Flag ode Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0 Interrupt	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD PS = 0 1 ms Interrupt	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode MFO as Crystal nterrupt Con Timer 1	R <sup>5</sup> Low Battery Flag ode Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD PS = 0 1 ms	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms	IH Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode MFO as Crystal nterrupt Con Timer 1 Interrupt Enable	R <sup>5</sup> Low Battery Flag ode Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Timer 0 Interrupt	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD 0 PS = 0 1 ms Interrupt Enable	RS = 0 <b>R/W</b> Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt	H R/W Alarm Int. Route MFO/INT 1 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode MFO as Crystal mterrupt Con Timer 1 Interrupt Enable nterrupt Con Power Fail	R <sup>5</sup> Low Battery Flag de Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Interrupt Enable trol Register 1 Alarm	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD PS = 0 1 ms Interrupt Enable IPS = 0 DOW	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt Enable	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt Enable	H R/W Alarm Int. Route MFO/INT 1 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt Enable Minute	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W
R/W Time Save Enable Real Time Mo Crystal Freq. XT1 Dutput Mode MFO as Crystal mterrupt Con Timer 1 Interrupt Enable	R <sup>6</sup> Low Battery Flag ode Register PS Crystal Freq. XT0 Register PS = MFO as Timer 0 trol Register 0 Interrupt Enable	R/W Power Fail Delay Enable S = 0 R Timers EN on Back-Up 0 RS = MFO PP/OD PS = 0 1 ms Interrupt Enable PS = 0	RS = 0 R/W Timer 1 Int. Route MFO/INT S = 1 A Interrupt EN on Back-Up = 1 Addr MFO Active HI/LO RS = 1 10 ms Interrupt Enable RS = 1	Address = 04 <b>R/W</b> Timer 0 Int. Route MFO/INT ddress = 01H Clock Start/Stop ess = 02H INTR PP/OD Address = 0 100 ms Interrupt Enable Address = 0	IH R/W Alarm Int. Route MFO/INT 12/24 Hr. Mode INTR Active HI/LO 03H Seconds Interrupt Enable	R/W Periodic Int. Route MFO/INT Leap Year MSB RAM 10 Second Interrupt Enable	R/W Power Fail Int. Route MFO/INT Leap Year LSB RAM Minute Interrupt Enable	Supply Mode 5. Reset by positive edge of read. 6. Set and reset by V <sub>BB</sub> voltage. All Bits R/W

2-47

## **Application Hints**

Suggested initialization procedure for DP8571A in battery backed applications that use the  $V_{BB}$  pin.

- 1. Enter the test mode by writing a 1 to bit D7 in the Periodic Flag Register.
- 2. Write zero to the RAM/TEST mode Register located in page 0, address HEX 1F.
- 3. Leave the test mode by writing a 0 to bit D7 in the Periodic Flag Register. Steps 1, 2, 3 guarantee that if the test mode had been entered during power on (due to random pulses from the system), all test mode conditions are cleared. Most important is that the OSC Fail Disable bit is cleared. Refer to AN-589 for more information on test mode operation.
- After power on (V<sub>CC</sub> and V<sub>BB</sub> powered), select the correct crystal frequency bits (D7, D6 in the Real Time Mode Register) as shown in Table 1.

Frequency	D7	D6
32.768 KHz	0	0
4.194304 MHz	0	1
4.9152 MHz	1	0
32.0 KHz	1	1

Table 1

5. Enter a software loop that does the following:

Set a 3 second(approx) software counter. The crystal oscillator may take 1 second to start.

5.1 Write a 1 to bit D3 in the Real Time Mode Register (try to start the clock). Make sure the crystal select bits remain the same as in step 1. Under normal operation, this bit can be set only if the oscillator is running. During the software loop, RAM, real time counters, output configured to the software loop.


## **Typical Application**

ration, interrupt control and timer functions may be initialized.


- 6. Test bit D6 in the Periodic Flag Register:
  - IF a 1, go to 5.1 If this bit remains a 1 after 3 seconds, then abort and check hardware. The crystal may be defective or not installed. There may be a short at OSC IN or OSC OUT to  $V_{CC}$  or GND, or to some impedance that is less than 10 M $\Omega$ .

IF a 0, then the oscillator is running, go to step 7.

- 7. Write a 0 to bit D6 in the Periodic Flag Register. This action puts the clock chip in the battery backed mode. This mode can be entered only if the OSC fail flag (bit D6 of the Periodic Flag Register) is a 0. Reminder, bit D6 is a dual function bit. When read, D6 returns oscillator status. When written, D6 causes either the Battery Backed Mode, or the Single Supply Mode of operation.
  - The only method to ensure the chip is in the battery backed mode is to measure the waveform at the OSC OUT pin. If the battery backed mode was selected successfully, then the peak to peak waveform at OSC OUT is referenced to the battery voltage. If not in battery backed mode, the waveform is referenced to  $V_{CC}$ . The measurement should be made with a high impedance low capacitance probe (10 M $\Omega$ , 10 pF oscilloscope probe or better). Typical peak to peak swings are within 0.6V of  $V_{CC}$  and ground respectively.
- Write a 1 to bit D7 of Interrupt Control Register 1. This action enables the PFAIL pin and associated circuitry.
- Write a 1 to bit D4 of the Real Time Mode Register. This action ensures that bit D7 of Interrupt Control Register 1 remains a 1 when V<sub>BB</sub> > V<sub>CC</sub> (standby mode).
- 10. Initialize the rest of the chip as needed.




2-48



and the second second

2



DP8571A

2.0

2.5

3.0

 $V_{BB}$  (Volts)

3.5

4.0

4.5

TL/F/9979-27

## **Typical Performance Characteristics**

3.0

25

3.5

V<sub>BB</sub> (Volts)

4.0

4.5

TL/F/9979-28



# DP8572A/DP8572AM Real Time Clock (RTC)

## **General Description**

The DP8572A (8572AM-militarized version) is intended for use in microprocessor based systems where information is required for multi-tasking, data logging or general time of day/date information. This device is implemented in low voltage silicon gate microCMOS technology to provide low standby power in battery back-up environments. The circuit's architecture is such that it looks like a contiguous block of memory or I/O ports. The address space is organized as 2 software selectable pages of 32 bytes. This includes the Control Registers, the Clock Counters, the Alarm Compare RAM, and the Time Save RAM. Any of the RAM locations that are not being used for their intended purpose may be used as general purpose CMOS RAM.


Time and date are maintained from 1/100 of a second to year and leap year in a BCD format, 12 or 24 hour modes. Day of week, day of month and day of year counters are provided. Time is controlled by an on-chip crystal oscillator requiring only the addition of the crystal and two capacitors. The choice of crystal frequency is program selectable.

Power failure logic and control functions have been integrated on chip. This logic is used by the RTC to issue a power fail interrupt, and lock out the µp interface. The time power fails may be logged into RAM automatically when  $V_{BB}$  >

V<sub>CC</sub>. Additionally, two supply pins are provided. When V<sub>BB</sub> > V<sub>CC</sub>, internal circuitry will automatically switch from the main supply to the battery supply. Status bits are provided to indicate initial application of battery power, system power, and low battery detect. (Continued)

## Features

- Full function real time clock/calendar
  - 12/24 hour mode timekeeping
  - Day of week and day of years counters
  - Four selectable oscillator frequencies
  - Parallel resonant oscillator
- Power fail features
  - --- Internal power supply switch to external battery
  - Power Supply Bus glitch protection
  - Automatic log of time into RAM at power failure
- On-chip interrupt structure - Periodic, alarm, and power fail interrupts
- Up to 44 bytes of CMOS RAM
- MIL-STD-883C compliant
- SMD #5962-91641-01MJX (future)



**Block Diagram** 

# 8572A

Absolute Maximum Ratings (Notes 1 & 2) Specifications for the 883 version of this product are listed separately.

Supply Voltage (V <sub>CC</sub> )	-0.5V to $+7.0V$
DC Input Voltage (VIN)	$-0.5V$ to $V_{CC}$ $+0.5V$
DC Output Voltage (V <sub>OUT</sub> )	$-0.5V$ to $V_{CC}+0.5V$
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.	) 260°C

## **Operation Conditions**

5.2

		Min	Max	Unit
Supply Voltage	(V <sub>CC</sub> ) (Note 3)	4.5	5.5	V
Supply Voltage	2.2	V <sub>CC</sub> -0.4	V	
DC Input or Out (V <sub>IN</sub> , V <sub>OUT</sub> )	0.0	V <sub>CC</sub>	v	
Operation Tem	-40	+ 85	°C	
Electr-Static Di	scharge Rating TBD		1	kV
Transistor Cour	ht		10	0,300
Typical Values				
$\theta_{\rm JA}$ DIP	Board		59	°C/W
		65	°C/W	
$\theta_{\rm JA}$ PLCC		80	°C/W	
		88	°C/W	

## **DC Electrical Characteristics**

 $V_{CC}$  = 5V ±10%,  $V_{BB}$  = 3V,  $V_{\overline{PFAIL}} >$   $V_{IH},$   $C_L$  = 100 pF (unless otherwise specified)

Symbol	Parameter	Conditions	Min	Max	Units
VIH	High Level Input Voltage (Note 4)	Any Inputs Except OSC IN, OSC IN with External Clock	2.0 V <sub>BB</sub> -0.1		V V
VIL	Low Level Input Voltage	All Inputs Except OSC IN OSC IN with External Clock		0.8 0.1	V V
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = -20 \ \mu A$ $I_{OUT} = -4.0 \ m A$	V <sub>CC</sub> -0.1 3.5		v v
V <sub>OL</sub>	Low Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = 20 \ \mu A$ $I_{OUT} = 4.0 \ m A$		0.1 0.25	V V
IIN	Input Current (Except OSC IN)	$V_{IN} = V_{CC} \text{ or } GND$		±1.0	μΑ
loz	Output TRI-STATE® Current	$V_{OUT} = V_{CC} \text{ or } GND$		±5.0	μA
I <sub>LKG</sub>	Output High Leakage Current MFO, INTR Pins	$V_{OUT} = V_{CC}$ or GND Outputs Open Drain		±5.0	μΑ
ICC	Quiescent Supply Current (Note 7)	$\begin{array}{l} F_{OSC} = 32.768 \text{ kHz} \\ V_{IN} = V_{CC} \text{ or GND (Note 5)} \\ V_{IN} = V_{CC} \text{ or GND (Note 6)} \\ V_{IN} = V_{IH} \text{ or } V_{IL} \text{ (Note 6)} \end{array}$		250 1.0 12.0	μA mA mA
		F <sub>OSC</sub> = 4.194304 MHz or 4.9152 MHz V <sub>IN</sub> = V <sub>CC</sub> or GND (Note 6) V <sub>IN</sub> = V <sub>IH</sub> or V <sub>IL</sub> (Note 6)		8 20	mA mA
Icc	Quiescent Supply Current (Single Supply Mode) (Note 7)	$\begin{array}{l} V_{BB} = GND \\ V_{IN} = V_{CC} \mbox{ or } GND \\ F_{OSC} = 32.768 \mbox{ kHz} \\ F_{OSC} = 4.9152 \mbox{ MHz} \mbox{ or } \\ 4.194304 \mbox{ MHz} \end{array}$		40 7.5	μA mA
I <sub>BB</sub>	Standby Mode Battery Supply Current (Note 7)	$\label{eq:VCC} \begin{array}{l} V_{CC} = GND \\ OSC  OUT =  open  circuit, \\ other  pins =  GND \\ F_{OSC} =  32.768  \text{kHz} \\ F_{OSC} =  4.9152  \text{MHz}  \text{or} \\ 4.194304  \text{MHz} \end{array}$		10 400	μΑ μΑ
IBLK	Battery Leakage	$\begin{array}{l} 2.2V \leq V_{BB} \leq 4.0V \\ \text{other pins at GND} \\ V_{CC} = \text{GND}, V_{BB} = 4.0V \\ V_{CC} = 5.5V, V_{BB} = 2.2V \end{array}$	-5	1.5	μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: For F\_{OSC} = 4.194304 or 4.9152 MHz, V\_{BB} minimum = 2.8V. In battery backed mode, V\_{BB}  $\leq$  V\_{CC} -0.4V.

Single Supply Mode: Data retention voltage is 2.2V min. In single Supply Mode (Power connected to  $V_{CC}$  pin) 4.5V  $\leq$   $V_{CC}$   $\leq$  5.5V.

Note 4: This parameter (VIH) is not tested on all pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

2-52

## 8572A

## **AC Electrical Characteristics**

 $V_{CC}$  = 5V  $\pm$  10%,  $V_{BB}$  = 3V,  $V_{\overline{PFAIL}}$  >  $V_{IH},$   $C_L$  = 100 pF (unless otherwise specified)

----

Symbol	Parameter	Min	Max	Units
AD TIMING				
t <sub>AR</sub>	Address Valid Prior to Read Strobe	20		ns
t <sub>RW</sub>	Read Strobe Width (Note 8)	80		ns
tCD	Chip Select to Data Valid Time		80	ns
tRAH	Address Hold after Read (Note 9)	3		ns
t <sub>RD</sub>	Read Strobe to Valid Data		70	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		60	ns
t <sub>RCH</sub>	Chip Select Hold after Read Strobe	0		ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses	50		ns
RITE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	20		ns
twah	Address Hold after Write Strobe (Note 9)	3		ns
tcw	Chip Select to End of Write Strobe	90		ns
tww	Write Strobe Width (Note 10)	80		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	50		ns
twdh	Data Hold after Write Strobe (Note 9)	3		ns
twch	Chip Select Hold after Write Strobe	0		ns
FERRUPT TIMI	NG			
t <sub>ROLL</sub>	Clock Rollover to INTR Out is Typically 16.5 µs			

Note 8: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when both signals are low and terminates when either signal returns high.

Note 9: Hold time is guaranteed by design but not production tested. This limit is not used to calculate outgoing quality levels.

Note 10: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

## **AC Test Conditions**

Input Pulse Levels	GND to 3.0V
Input Rise and Fall Times	6 ns (10%–90%)
Input and Output Reference Levels	1.3V
TRI-STATE Reference	Active High + 0.5V
Levels (Note 12)	Active Low -0.5V

Note 11:  $C_L = 100 \text{ pF}$ , includes jig and scope capacitance.


- Note 12: S1 =  $V_{CC}$  for active low to high impedance measurements. S1 = GND for active high to high impedance measurements.
  - S1 = open for all other timing measurements.

## Capacitance (T<sub>A</sub> = 25°C, f = 1 MHz)

Symbol	Parameter (Note 13)	Тур	Units
CIN	Input Capacitance	5	pF
COUT	Output Capacitance	7	pF

Note 13: This parameter is not 100% tested.

Note 14: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.



TL/F/9980-2

2

# DP8572A/DP8572AM

## 8572AM—Military Version

## Absolute Maximum Ratings (Notes 1 & 2)

The 883 specifications are written to reflect the current (at the time of printing) Rel Electrical Test Specifications (RETS) established by National Semiconductor for this product. For a copy of the latest version of the RETS please contact your local National Semiconductor sales office or distributor.

Supply Voltage (V <sub>CC</sub> )	-0.5V to +7.0V
DC Input Voltage (VIN)	$-0.5V$ to $V_{CC}+0.5V$
DC Output Voltage (V <sub>OUT</sub> )	0.5V to V_{CC}+0.5V
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.	) 260°C

## **DC Electrical Characteristics**

 $V_{CC} = 5.0V \pm 10\%$   $V_{DD} = 3V$ 

## **Operation Conditions**

 $\nabla$ 

•	Min	Max	Unit	
Supply Voltage (V <sub>CC</sub> ) (Note 3)	4.5	5.5	V	
Supply Voltage (V <sub>BB</sub> ) (Note 3)	2.2	$V_{CC}-0.4$	. <b>V</b>	
DC Input or Output Voltage (V <sub>IN</sub> , V <sub>OUT</sub> )	0.0	V <sub>CC</sub>	v	
Operating Temperature (T <sub>A</sub> )	-55	+ 125	°C	
Electro-Static Discharge Rating Typical Values		1	kV	
<i>e</i> JA DIP Board Socket			C/W C/W	

Symbol	Parameter	Vcc	Conditions	Min	Max	Units
VIH	High Level Input Voltage (Note 4)		All Inputs Except OSC IN. OSC IN with External Clock	2.0 V <sub>BB</sub> — 0.1		v v
V <sub>IL</sub>	Low Level Input Voltage		All Inputs Except OSC IN. OSC IN with External Clock		0.8 0.1	v v
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT)	5.5V 5.5V	$I_{OUT} = -20 \mu A$ $I_{OUT} = -4.0 m A$	V <sub>CC</sub> - 0.1 3.5		v v
V <sub>OL</sub>	Low Level Output Voltage (Excluding OSC OUT)	5.5V 5.5V	$I_{OUT} = 20 \ \mu A$ $I_{OUT} = 4.0 \ m A$		0.1 0.25	v v
I <sub>IN</sub>	Input Current (Except OSC IN)	5.5V	$V_{IN} = V_{CC} \text{ or } GND$		±1.0	. μΑ
loz	Output TRI-STATE Current	5.5V	$V_{OUT} = V_{CC} \text{ or GND}$		±5.0	μA
lcc	Quiescent Supply Current (Note 7)	5.5V 5.5V 5.5V	$\begin{split} F_{OSC} &= 32.768 \text{ kHz} \\ V_{IN} &= V_{CC} \text{ or GND (Note 5)} \\ V_{IN} &= V_{CC} \text{ or GND (Note 6)} \\ V_{IN} &= V_{IH} \text{ or } V_{IL} \text{ (Note 6)} \end{split}$		275 1.0 12.0	μA mA mA
		5.5V 5.5V	$\begin{array}{l} F_{OSC} = \ 4.9152 \ MHz \\ V_{IN} = \ V_{CC} \ or \ GND \ (Note \ 6) \\ V_{IN} = \ V_{IH} \ or \ V_{IL} \ (Note \ 6) \end{array}$		8 20	mA mA
lcc	Quiescent Supply Current (Single Supply Mode)5.5V (Note 7)	5.5V	$\label{eq:VBB} \begin{array}{l} V_{BB} = GND, V_{IN} = V_{CC} \text{ or } GND \\ F_{OSC} = 32.768 \ kHz \\ F_{OSC} = 4.9152 \ MHz \end{array}$		40 7.5	μA mA
I <sub>BB</sub>	Standby Mode Battery Supply Current (Note 7)	0V 0V	$\begin{array}{l} \text{OSC OUT} = \text{Open Circuit,} \\ \text{Other Pins} = \text{GND} \\ \text{F}_{\text{OSC}} = 32.768 \text{ kHz} \\ \text{F}_{\text{OSC}} = 4.9152 \text{ MHz} \end{array}$		10 400	μΑ μΑ
BLK	Battery Leakage	5.5V 5.5V 5.5V	2.2V ≤ V <sub>BB</sub> ≤ 4.0V 25°C -55°C + 125°C	-5 -5 -5	1.5 3.5 3.5	μΑ μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: For  $F_{OSC}$  = 4.194304 or 4.9152 MHz,  $V_{BB}$  minimum = 2.8V. In battery backed mode,  $V_{BB} \le V_{CC}$  - 0.4V.

Single Supply Mode: Data retention voltage is 2.2V min. In single Supply Mode (Power connected to V\_{CC} pin) 4.5V  $\,\leq\,$  V\_{CC}  $\,\leq\,$  5.5V.

Note 4: This parameter (VIH) is not tested on all pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

## 8572AM—Military Version

## **AC Electrical Characteristics**

 $V_{CC}$  = 4.5V and 5.5V,  $V_{BB}$  = 3V,  $V_{\overline{PFAIL}}$  >  $V_{IH},\,C_L$  = 100 pF (unless otherwise specified)

--- 57

~ ,

Symbol	Parameter	Min	Max	Units
AD TIMING				
t <sub>AR</sub>	Address Valid Prior to Read Strobe	20		ns
t <sub>RW</sub>	Read Strobe Width (Note 8)	80		ns
t <sub>CD</sub>	Chip Select to Data Valid Time		80	ns
t <sub>RD</sub>	Read Strobe to Valid Data		70	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		60	ns
t <sub>RCH</sub>	Chip Select Hold after Read Strobe			ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses 50			ns
ITE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	20		ns
t <sub>CW</sub>	Chip Select to End of Write Strobe	90		ns
tww	Write Strobe Width (Note 9)	80		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	50		ns
twcH	Chip Select Hold after Write Strobe	0		ns

Note 8: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when both signals are low and terminates when either signal returns high.

Note 9: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

## **AC Test Conditions**

Input Pulse Levels	GND to 3.0V
Input Rise and Fall Times	6 ns (10%–90%)
Input and Output	1.3V
Reference Levels	1.01
TRI-STATE Reference	Active High + 0.5V
Levels (Note 11)	Active Low -0.5V

Note 10:  $C_L = 100 \text{ pF}$ , includes jig and scope capacitance.

Note 11: S1 =  $V_{CC}$  for active low to high impedance measurements. S1 = GND for active high to high impedance measurements.


S1 = open for all other timing measurements.

## Capacitance (T<sub>A</sub> = 25°C, f = 1 MHz)

Symbol	Parameter (Note 12)	Тур	Units
CIN	Input Capacitance	5	рF
COUT	Output Capacitance	7	pF

Note 12: This parameter is not 100% tested.


Note 13: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.



TL/F/9980-24


# Timing Waveforms

DP8572A/DP8572AM



TL/F/9980-3





TL/F/9980-4

# DP8572A/DP8572AN

## General Description (Continued)

The DP8572A's interrupt structure provides three basic types of interrupts: Periodic, Alarm/Compare, and Power Fail. Interrupt mask and status registers enable the masking and easy determination of each interrupt.

## Pin Description

**CS, RD, WR (Inputs):** These pins interface to  $\mu$ P control lines. The  $\overline{CS}$  pin is an active low enable for the read and write operations. Read and Write pins are also active low and enable reading or writing to the RTC. All three pins are disabled when power failure is detected. However, if a read or write is in progress at this time, it will be allowed to complete its cycle.

A0-A4 (Inputs): These 5 pins are for register selection. They individually control which location is to be accessed. These inputs are disabled when power failure is detected.

**OSC IN (Input): OSC OUT (Output):** These two pins are used to connect the crystal to the internal parallel resonant oscillator. The oscillator is always running when power is applied to V<sub>BB</sub> and V<sub>CC</sub>, and the correct crystal select bits in the Real Time Mode Register have been set.

**MFO (Output):** The multi-function output can be used as a second interrupt output for interrupting the  $\mu$ P. This pin can also provide an output for the oscillator. The MFO output is configured as push-pull, active high for normal or single power supply operation and as an open drain during standby mode (V<sub>BB</sub> > V<sub>CC</sub>). If in battery backed mode and a pullup resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>.

**INTR** (Output): The interrupt output is used to interrupt the processor when a timing event or power fail has occurred and the respective interrupt has been enabled. The INTR output is permanently configured active low, open drain. If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>. The output is a DC voltage level. To clear the INTR, wite a 1 to the appropriate bit(s) in the Main Status Register.

**D0–D7 (Input/Output):** These 8 bidirectional pins connect to the host  $\mu$ P's data bus and are used to read from and write to the RTC. When the PFAIL pin goes low and a write is not in progress, these pins are at TRI-STATE.


**PFAIL** (Input): In battery backed mode, this pin can have a digital signal applied to it via some external power detection logic. When  $\overrightarrow{\text{PFAIL}} = \text{logic 0}$  the RTC goes into a lockout mode, in a minimum of 30  $\mu$ s or a maximum of 63  $\mu$ s unless lockout delay is programmed. In the single power supply mode, this pin is not useable as an input and should be tied to V<sub>CC</sub>. Refer to section on Power Fail Functional Description.

 $\label{eq:VBB} \begin{array}{l} \textbf{V}_{BB} \ (\textbf{Battery Power Pin):} \ \text{This pin is connected to a backup power supply. This power supply is switched to the internal circuitry when the V_{CC} becomes lower than V_{BB}. Utilizing this pin eliminates the need for external logic to switch in and out the back-up power supply. If this feature is not to be used then this pin must be tied to ground, the RTC programmed for single power supply only, and power applied to the V_{CC} pin. \end{array}$ 


 $\mathbf{V_{CC}}$ : This is the main system power pin.

GND: This is the common ground power pin for both  $V_{BB}$  and  $V_{CC}\!$ 


## **Connection Diagrams**



Top View



**Plastic Chip Carrier** 



**Top View** 

Order Number DP8572AV See NS Package Number V28A

## **Functional Description**

The DP8572A contains a fast access real time clock, interrupt control logic, power fail detect logic, and CMOS RAM. All functions of the RTC are controlled by a set of seven registers. A simplified block diagram that shows the major functional blocks is given in *Figure 1*.

The blocks are described in the following sections:

- 1. Real Time Clock
- 2. Oscillator Prescaler
- 3. Interrupt Logic
- 4. Power Failure Logic
- 5. Additional Supply Management

The memory map of the RTC is shown in the memory addressing table. The memory map consists of two 31 byte pages with a main status register that is common to both pages. A control bit in the Main Status Register is used to select either page. *Figure 2* shows the basic concept. Page 0 contains all the clock timer functions, while page 1 has scratch pad RAM. The control registers are split into two separate blocks to allow page 1 to be used entirely as scratch pad RAM. Again a control bit in the Main Status Register is used to select either control register block.

	Page Select = 0	· · · · · · · · · · · · · · · · · · ·		
· 1F	RAM/TEST Register		Page Select = 1	<u> </u>
1E	RAM	11	RAM	· · ·
1D	Months Time Save RAM	1	RAM	
1C	Day of Month Time Save RA	M 11	RAM	
1B	Hours Time Save RAM	10	RAM	
1 <b>A</b>	Minutes Time Save RAM	11	B RAM	
19	Seconds Time Save RAM	. 1/	RAM	
18	Day of Week Compare RAM	1	RAM	
17	Months Compare RAM	11	RAM	
16	Day of Month Compare RAM	1	7 RAM	
15	Hours Compare RAM	. 10	S RAM	
14	Minutes Compare RAM		5 RAM	
13	Seconds Compare RAM	1	RAM	
12	N/A	13	S RAM	
11	N/A	1 12	2 RAM	
10	N/A	1	1 RAM	
OF	N/A	10	RAM	
OE	Day of Week Clock Counter	0	RAM	
OD	100's Julian Clock Counter	0	RAM	
OC	Units Julian Clock Counter	01	RAM	
OB	Years Clock Counter	-00	RAM	
0A	Months Clock Counter	01	RAM	
09	Day of Month Clock Counter	0/	RAM	
08	Hours Clock Counter	0	RAM	
07	Minutes Clock Counter	08	RAM	
06	Seconds Clock Counter	. 01	7 RAM	
05	1/100 Second Counter	0	S RAM	
			5 RAM	
		04	RAM	
Register Selec	et = 0	Register Select = 1 03	S RAM	
Time Save Co	ntrol Register 04 Interru	pt Control Register 1 0:	2 RAM	
Periodic Flag	g Register 03 Interru	pt Control Register 0 0	1 RAM	
N//	A 02 Out	put Mode Register		
N//		Time Mode Register		1.1
<b>a</b>		1		
	00	Main Status Register		
	FIGURE 2. DI	P8572A Internal Memory	Мар	

FIGURE 2. DP8572A Internal Memory Map

TL/F/9980-7

#### Functional Description (Continued) INITIAL POWER-ON of BOTH VBB and VCC

 $V_{BB}$  and  $V_{CC}$  may be applied in any sequence. In order for the power fail circuitry to function correctly, whenever power is off, the  $V_{CC}$  pin must see a path to ground through a maximum of 1 MΩ. The user should be aware that the control registers will contain random data. The first task to be carried out in an initialization routine is to start the oscillator by writing to the crystal select bits in the Real Time Mode Register. If the DP8572A is configured for single supply mode, an extra 50  $\mu$ A may be consumed until the crystal select bits are programmed. The user should also ensure that the RTC is not in test mode (see register descriptions).

#### REAL TIME CLOCK FUNCTIONAL DESCRIPTION

As shown in *Figure 2*, the clock has 10 bytes of counters, which count from 1/100 of a second to years. Each counter counts in BCD and is synchronously clocked. The count sequence of the individual byte counters within the clock is shown later in Table VII. Note that the day of week, day of month, day of year, and month counters all roll over to 1. The hours counter in 12 hour mode rolls over to 1 and the AM/PM bit toggles when the hours rolls over to 12 (AM = 0, PM = 1). The AM/PM bit is bit D7 in the hours counter.

All other counters roll over to 0. Also note that the day of year counter is 12 bits long and occupies two addresses. Upon initial application of power the counters will contain random information.

#### READING THE CLOCK: VALIDATED READ

Since clocking of the counter occurs asynchronously to reading of the counter, it is possible to read the counter while it is being incremented (rollover). This may result in an incorrect time reading. Thus to ensure a correct reading of the entire contents of the clock (or that part of interest), it must be read without a clock rollover occurring. In general this can be done by checking a rollover bit. On this chip the periodic interrupt status bits can serve this function. The following program steps can be used to accomplish this.

- 1. Initialize program for reading clock.
- 2. Dummy read of periodic status bit to clear it.
- 3. Read counter bytes and store.
- 4. Read rollover bit, and test it.
- 5. If rollover occured go to 3.
- 6. If no rollover, done.

To detect the rollover, individual periodic status bits can be polled. The periodic bit chosen should be equal to the highest frequency counter register to be read. That is if only SECONDS through HOURS counters are read, then the SECONDS periodic bit should be used.

#### **READING THE CLOCK: INTERRUPT DRIVEN**

Enabling the periodic interrupt mask bits cause interrupts just as the clock rolls over. Enabling the desired update rate and providing an interrupt service routine that executes in less than 10 ms enables clock reading without checking for a rollover.

#### **READING THE CLOCK: LATCHED READ**

Another method to read the clock that does not require checking the rollover bit is to write a one into the Time

Save Enable bit (D7) of the Time Save Control Register, and then to write a zero. Writing a one into this bit will enable the clock contents to be duplicated in the Time Save RAM. Changing the bit from a one to a zero will freeze and store the contents of the clock in Time Save RAM. The time then can be read without concern for clock rollover, since internal logic takes care of synchronization of the clock. Because only the bits used by the clock counters will be latched, the Time Save RAM should be cleared prior to use to ensure that random data stored in the unused bits do not confuse the host microprocessor. This bit can also provide time save at power failure, see the Additional Supply Management Functions section. With the Time Save Enable bit at a logical 0, the Time Save RAM may be used as RAM if the latched read function is not necessary.


# INITIALIZING AND WRITING TO THE CALENDAR-CLOCK

Upon initial application of power to the RTC or when making time corrections, the time must be written into the clock. To correctly write the time to the counters, the clock would normally be stopped by writing the Start/Stop bit in the Real Time Mode Register to a zero. This stops the clock from counting and disables the carry circuitry. When initializing the clock's Real Time Mode Register, it is recommended that first the various mode bits be written while maintaining the Start/Stop bit reset, and then writing to the register a second time with the Start/Stop bit set.

The above method is useful when the entire clock is being corrected. If one location is being updated the clock need not be stopped since this will reset the prescaler, and time will be lost. An ideal example of this is correcting the hours for daylight savings time. To write to the clock "on the fly" the best method is to wait for the 1/100 of a second periodic interrupt. Then wait an additional 16  $\mu$ s, and then write the data to the clock.

# PRESCALER/OSCILLATOR FUNCTIONAL DESCRIPTION

Feeding the counter chain is a programmable prescaler which divides the crystal oscillator frequency to 32 kHz and further to 100 Hz for the counter chain (see *Figure 3*). The crystal frequency that can be selected are: 32 kHz, 32.768 kHz, 4.9152 MHz, and 4.194304 MHz.



The oscillator is programmed via the Real Time Mode Register to operate at various frequencies. The crystal oscillator is designed to offer optimum performance at each frequency. Thus, at 32.768 kHz the oscillator is configured as a low frequency and low power oscillator. At the higher frequencies the oscillator inverter is reconfigured. In addition to the inverter, the oscillator feedback bias resistor is included on chip, as shown in *Figure 4*. The oscillator input may be driven from an external source if desired. Refer to test mode application note for details. The oscillator stability is enhanced through the use of an on chip regulated power supply.

The typical range of trimmer capacitor (as shown in Oscillator Circuit Diagram *Figure 4*, and in the typical application) at the oscillator input pin is suggested only to allow accurate tuning of the oscillator. This range is based on a typical printed circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases, the **load capacitance** specified by the crystal manufacturer (nominal value 11 pF for the 32.768 crystal) is what determines proper oscillation. This load capcitance is the series combination of capacitance on each side of the crystal (with respect to ground).




FIGURE 4. Oscillator Circuit Diagram

XTAL	Co	Ct	R <sub>OUT</sub> (Switched Internally)
32/32.768 kHz	47 pF	2 pF-22 pF	150 k $\Omega$ to 350 k $\Omega$
4.194304 MHz	68 pF	0 pF-80 pF	500 $\Omega$ to 900 $\Omega$
4.9152 MHz	68 pF	29 pF-49 pF	500 $\Omega$ to 900 $\Omega$

#### INTERRUPT LOGIC FUNCTIONAL DESCRIPTION

The RTC has the ability to coordinate processor timing activities. To enhance this, an interrupt structure has been implemented which enables several types of events to cause interrupts. Interrupts are controlled via two Control Registers in block 1 and two Status Registers in block 0. (See Register Description for notes on paging and also *Figure 5* and Table I.)

The interrupts are enabled by writing a one to the appropriate bits in Interrupt Control Register 0 and/or 1. TABLE I. Registers that are

Applicable to Interrupt Control

Applicable to interrupt control				
Register Name	Register Select	Page Select	Address	
Main Status Register	х	х	00H	
Periodic Flag Register	0	0	03H	
Interrupt Control Register 0	1	0	03H	
Interrupt Control Register 1	1	0	04H	
Output Mode Register	1	0	02H	

The Interrupt Status Flag D0, in the Main Status Register, indicates the state of INTR and MFO outputs. It is set when either output becomes active and is cleared when all RTC interrupts have been cleared and no further interrupts are pending (i.e., both INTR and MFO are returned to their inactive state). This flag enables the RTC to be rapidly polled by the  $\mu$ P to determine the source of an interrupt in a wired—OR interrupt system. (The Interrupt Status Flag provides a true reflection of all conditions routed to the external pins.)

Status for the interrupts are provided by the Main Status Register and the Periodic Flag Register. Bits D1–D5 of the Main Status Register are the main interrupt bits.

These register bits will be set when their associated timing events occur. Enabled Alarm comparisons that occur will set its Main Status Register bit to a one. However, an external interrupt will only be generated if the Alarm interrupt enable bit is set (see *Figure 5*).

Disabling the periodic interrupts will mask the Main Status Register periodic bit, but not the Periodic Flag Register bits. The Power Fail Interrupt bit is set when the interrupt is enabled and a power fail event has occurred, and is not reset until the power is restored. If all interrupt enable bits are 0 no interrupt will be asserted. However, status still can be read from the Main Status Register in a polled fashion (see *Figure 5*).

To clear a flag in bits D2 and D3 of the Main Status Register a 1 must be written back into the bit location that is to be cleared. For the Periodic Flag Register reading the status will reset all the periodic flags.

Interrupts Fall Into Three Categories:

- 1. The Alarm Compare Interrupt: Issued when the value in the time compared RAM equals the counter.
- The Periodic Interrupts: These are issued at every increment of the specific clock counter signal. Thus, an interrupt is issued every minute, second, etc. Each of these interrupts occurs at the roll-over of the specific counter.
- 3. The Power Fail Interrupt: Issued upon recognition of a power fail condition by the internal sensing logic. The power failed condition is determined by the signal on the PFAIL pin. The internal power fail signal is gated with the chip select signal to ensure that the power fail interrupt does not lock the chip out during a read or write.

#### ALARM COMPARE INTERRUPT DESCRIPTON

The alarm/time comparison interrupt is a special interrupt similar to an alarm clock wake up buzzer. This interrupt is generated when the clock time is equal to a value programmed into the alarm compare registers. Up to six bytes can be enabled to perform alarm time comparisons on the counter chain. These six bytes, or some subset thereof, would be loaded with the future time at which the interrupt will occur. Next, the appropriate bits in the Interrupt Control Register 1 are enabled or disabled (refer to detailed description of Interrupt Control Register 1). The RTC then compares these bytes with the clock time. When all the enabled compare registers equal the clock time an alarm interrupt is issued, but only if the alarm compare interrupt is enabled can the interrupt be generated externally. Each alarm compare bit in the Control Register will enable a specific byte for comparison to the clock. Disabling a compare byte is the same as setting its associated counter comparator to an "always equal" state. For example, to generate an interrupt at 3:15 AM of every day, load the hours compare with 0 3 (BCD), the minutes compare with 1 5 (BCD) and the faster counters with 0 0 (BCD), and then disable all other compare registers. So every day when the time rolls over from 3:14:59.99, an interrupt is issued. This bit may be reset by writing a one to bit D3 in the Main Status Register at any time after the alarm has been generated.

If time comparison for an individual byte counter is disabled, that corresponding RAM location can then be used as general purpose storage.

#### PERIODIC INTERRUPTS DESCRIPTION

The Periodic Flag Register contains six flags which are set by real-time generated "ticks" at various time intervals, see *Figure 5.* These flags constantly sense the periodic signals and may be used whether or not interrupts are enabled. These flags are cleared by any read or write operation performed on this register.

To generate periodic interrupts at the desired rate, the associated Periodic Interrupt Enable bit in Interrupt Control Register 0 must be set. Any combination of periodic interrupts may be enabled to operate simultaneously. Enabled periodic interrupts will now affect the Periodic Interrupt Flag in the Main Status Register.

When a periodic event occurs, the Periodic Interrupt Flag in the Main Status Register is set, causing an interrupt to be generated. The  $\mu$ P clears both flag and interrupt by writing a "1" to the Periodic Interrupt Flag. The individual flags in the periodic Interrupt Flag Register do not require clearing to cancel the interrupt.

If all periodic interrupts are disabled and a periodic interrupt is left pending (i.e., the Periodic Interrupt Flag is still set), the Periodic Interrupt Flag will still be required to be cleared to cancel the pending interrupt.

#### POWER FAIL INTERRUPTS DESCRIPTION

The Power Fail Status Flag in the Main Status Register monitors the state of the internal power fail signal. This flag may be interrogated by the  $\mu$ P, but it cannot be cleared; it is cleared automatically by the RTC when system power is restored. To generate an interrupt when the power fails, the Power Fail Interrupt Enable bit in Interrupt Control Register 1 is set. Although this interrupt may not be cleared, it may be masked by clearing the Power Fail Interrupt Enable bit.

#### POWER FAILURE CIRCUITRY FUNCTIONAL DESCRIPTION

Since the clock must be operated from a battery when the main system supply has been turned off, the DP8572A provides circuitry to simplify design in battery backed systems. This switches over to the back up supply, and isolates itself from the host system. *Figure 6* shows a simplified block diagram of this circuitry, which consists of three major sections; 1) power loss logic: 2) battery switch over logic: and 3) isolation logic.

Detection of power loss occurs when  $\overrightarrow{PFAIL}$  is low. Debounce logic provides a 30  $\mu$ s-63  $\mu$ s debounce time, which will prevent noise on the  $\overrightarrow{PFAIL}$  pin from being interpreted as a system failure. After 30  $\mu$ s-63  $\mu$ s the debounce logic times out and a signal is generated indicating that system power is marginal and is failing. The Power Fail Interrupt will then be generated.

### DP8572A/DP8572AM

Functional Description (Continued)

.





FIGURE 5. Interrupt Control Logic Overview

2-62



DP8572A/DP8572AN

#### FIGURE 6. System-Battery Switchover (Upper Left), Power Fail and Lock-Out Circuits (Lower Right)

If chip select is low when a power failure is detected, a safety circuit will ensure that if a read or write is held active continuously for greater than 30 µs after the power fail signal is asserted, the lock-out will be forced. If a lock-out delay is enabled, the DP8572A will remain active for 480 µs after power fail is detected. This will enable the µP to perform last minute bookkeeping before total system collapse. When the host CPU is finished accessing the RTC it may force the bus lock-out before 480 µs has elapsed by resetting the delay enable bit.

The battery switch over circuitry is completely independent of the PFAIL pin. A separate circuit compares V<sub>CC</sub> to the VBB voltage. As the main supply fails, the RTC will continue to operate from the  $V_{CC}$  pin until  $V_{CC}$  falls below the  $V_{BB}$ voltage. At this time, the battery supply is switched in, V<sub>CC</sub> is disconnected, and the device is now in the standby mode. If indeterminate operation of the battery switch over circuit is to be avoided, then the voltage at the V<sub>CC</sub> pin must not be allowed to equal the voltage at the VBB pin.

After the generation of a lock-out signal, and eventual switch in of the battery supply, the pins of the RTC will be configured as shown in Table II. Outputs that have a pull-up resistor should be connected to a voltage no greater than VRB.

TABLE II.	Pin Isolation	during a	Power Failure
-----------	---------------	----------	---------------

Pin	<b>PFAIL</b> Logic 0	Standby Mode V <sub>BB</sub> > V <sub>CC</sub>
CS, RD, WR	Locked Out	Locked Out
A0-A4	Locked Out	Locked Out
D0-D7	Locked Out	Locked Out
Oscillator	Not Isolated	Not Isolated
PFAIL	Not Isolated	Not Isolated
INTR, MFO	Not Isolated	Open Drain

The Interrupt Power Fail Operation bit in the Real-Time Mode Register determine whether or not the interrupts will continue to function after a power fail event.

As power returns to the system, the battery switch over circuit will switch back to V<sub>CC</sub> power as soon as it becomes greater than the battery voltage. The chip will remain in the locked out state as long as PFAIL = 0. When PFAIL = 1

the chip is unlocked, but only after another 30  $\mu$ s min  $\rightarrow$  63  $\mu$ s max debounce time. The system designer must ensure that his system is stable when power has returned.

The power fail circuitry contains active linear circuitry that draws supply current from V<sub>CC</sub>. In some cases this may be undesirable, so this circuit can be disabled by masking the power fail interrupt. The power fail input can perform all lock-out functions previously mentioned, except that no external interrupt will be issued. Note that the linear power fail circuitry is switched off automatically when using V<sub>BB</sub> in standby mode.

# LOW BATTERY, INITIAL POWER ON DETECT, AND POWER FAIL TIME SAVE

There are three other functions provided on the DP8572A to ease power supply control. These are an initial Power On detect circuit, which also can be used as a time keeping failure detect, a low battery detect circuit, and a time save on power failure.

On initial power up the Oscillator Fail Flag will be set to a one and the real time clock start bit reset to a zero. This indicates that an oscillator fail event has occurred, and time keeping has failed.

The Oscillator Fail flag will not be reset until the real-time clock is started. This allows the system to discriminate between an initial power-up and recovery from a power failure. If the battery backed mode is selected, then bit D6 of the Periodic Flag Register must be written low. This will not affect the contents of the Oscillator Fail Flag.

Another status bit is the low battery detect. This bit is set only when the clock is operating under the  $V_{CC}$  pin, and when the battery voltage is determined to be less than 2.1V (typical). When the power fail interrupt enable bit is low, it disables the power fail circuit and will also shut off the low battery voltage detection circuit as well.

To relieve CPU overhead for saving time upon power failure, the Time Save Enable bit is provided to do this automatically. (See also Reading the Clock: Latched Read.) The Time Save Enable bit, when set, causes the Time Save RAM to follow the contents of the clock. This bit can be reset by software, but if set before a power failure occurs, it will automatically be reset when the clock switches to the battery supply (not when a power failure is detected by the PFAIL pin). Thus, writing a one to the Time Save bit enables both a software write or power fail write.

#### SINGLE POWER SUPPLY APPLICATIONS

The DP8572A can be used in a single power supply application. To achieve this, the V<sub>BB</sub> pin must be connected to ground, and the power connected to V<sub>CC</sub> and PFAIL pins. The Oscillator Failed/Single Supply bit in the Periodic Flag Register should be set to a logic 1, which will disable the oscillator battery reference circuit. The power fail interrupt should also be disabled. This will turn off the linear power fail detection circuits, and will eliminate any quiescent power drawn through these circuits. Until the crystal select bits are initialized, the DP8572A may consume about 50  $\mu$ A due to arbitrary oscillator selection at power on.

(This extra 50  $\mu$ A is not consumed if the battery backed mode is selected).

#### DETAILED REGISTER DESCRIPTION

There are 5 external address bits: Thus, the host microprocessor has access to 28 locations at one time. An internal switching scheme provides a total of 61 locations. This complete address space is organized into two pages. Page 0 contains two blocks of control registers, timers, real time clock counters, and special purpose RAM, while page 1 contains general purpose RAM. Using two blocks enables the 9 control registers to be mapped into 5 locations. The only register that does not get switched is the Main Status Register. It contains the page select bit and the register select bit as well as status information.

A memory map is shown in *Figure 2* and register addressing in Table III. They show the name, address and page locations for the DP8572A.

TABLE III. Register/Counter/RAM Addressing for DP8572A


ſ	A0-4	PS	RS	Description
		لنصحف	(Note 2)	
ļ	CONT	ROL REC	ISTERS	
	00	X	· X	Main Status Register
	03	0	0	Periodic Flag Register
	04	0	0	Time Save Control Register
	01	0	1	Real Time Mode Register
	02	0	1	Output Mode Register
	03	0	1	Interrupt Control Register 0
ļ	04	0	1	Interrupt Control Register 1
	COUN	ITERS (C	LOCK CA	LENDAR)
	05		X	1/100, 1/10 Seconds (0-99)
	06	0	X	Seconds (0-59)
	07	0	х	Minutes (0-59)
1	08	0	X	Hours (1–12, 0–23)
1	09	0	· X	Davs of
	1 C 1			Month (1-28/29/30/31)
	.0A	0	X	Months (1-12)
	- 0B: -	· 0 ·	is 'X ti	Years (0-99)
	00	0	: .•X	Julian Date (LSB) (0-99) (Note 3)
	0D 0E	0	x X X X	Julian Date (0-3)
ł				Day of Week (1–7)
ļ	TIME COMPARE RAM			
	13	0	14 <b>X</b> 17 4	Sec Compare RAM (0–59)
	14	0	X	Min Compare RAM (0-59)
	15	0	. X	Hours Compare
				RAM (1–12, 0–23)
	16	0	X	DOM Compare
				RAM (1–28/29/30/31)
ļ	/ 17	0	X	Months Compare RAM (1-12)
	18	0	x	DOW Compare RAM (1-7)
-				
		SAVE RA		· · · · · · · · · · · · · · · · · · ·
	19	0	X	Seconds Time Save RAM
	1A	0	X	Minutes Time Save RAM
	1B	0.~	:= X	Hours Time Save RAM
	10	. 0 / .	<u>X</u> ,	Day of Month Time Save RAM
	1D	0,	., <b>Х</b> .,	Months Time Save RAM
	1E	0	1	RAM
	1F	0	X	RAM/Test Mode Register
ĺ	01–1F	1	x	2nd Page General Purpose RAM

Note 1: PS-Page Select (Bit D7 of Main Status Register)

Note 2: RS-Register Select (Bit D6 of Main Status Register)

Note 3: The LSB counters count 0  $\rightarrow$  99 until the hundreds of days counter reaches 3. Then the LSB counters count to 65 or 66 (if a leap year). The rollover is from 365/366 to 1.

## Functional Description (Continued) MAIN STATUS REGISTER



TL/F/9980-12

The Main Status Register is always located at address 0 regardless of the register block or the page selected.


**D0:** This read only bit is a general interrupt status bit that is taken directly from the interrupt pins. The bit is a one when an interrupt is pending on either the INTR pin or the MFO pin (when configured as an interrupt). This is unlike D3 which can be set by an internal event but may not cause an interrupt. This bit is reset when the interrupt status bits in the Main Status Register are cleared.

**D1-D3:** These three bits of the Main Status Register are the main interrupt status bits. Any bit may be a one when any of the interrupts are pending. Once an interrupt is asserted the  $\mu$ P will read this register to determine the cause. These interrupt status bits are not reset when read. Except for D1, to reset an interrupt a one is written back to the corresponding bit that is being tested. D1 is reset whenever the PFAIL pin = logic 1. This prevents loss of interrupt status when reading the register in a polled mode. D1 and D3 are set regardless of whether these interrupts are masked or not by bits D6 and D7 of Interrupt Control Registers 0 and 1.

D4–D5: General purpose RAM bits.

**D6 and D7:** These bits are Read/Write bits that control which register block or RAM page is to be selected. Bit D6 controls the register block to be accessed (see memory map). The memory map of the clock is further divided into two memory pages. One page is the registers, clock and timers, and the second page contains 31 bytes of general purpose RAM. The page selection is determined by bit D7.

#### PERIODIC FLAG REGISTER



The Periodic Flag Register has the same bit for bit correspondence as Interrupt Control Register 0 except for D6 and D7. For normal operation (i.e., not a single supply application) this register must be written to on initial power up or after an oscillator fail event. D0–D5 are read only bits, D6 and D7 are read/write.

**D0-D5:** These bits are set by the real time rollover events: (Time Change = 1). The bits are reset when the register is read and can be used as selective data change flags.

D6: This bit performs a dual function. When this bit is read, a one indicates that an oscillator failure has occurred and the time information may have been lost. Some of the ways an oscillator failure might be caused are: failure of the crystal, shorting OSC IN or OSC OUT to GND or V<sub>CC</sub>, removal of crystal, removal of battery when in the battery backed mode (when a "0" is written to D6), lowering the voltage at the V<sub>BB</sub> pin to a value less than 2.2V when in the battery backed mode. Bit D6 is automatically set to 1 on initial power-up or an oscillator fail event. The oscillator fail flag is reset by writing a one to the clock start/stop bit in the Real Time Mode Register, with the crystal oscillator.


When D6 is written to, it defines whether the TCP is being used in battery backed (normal) or in a single supply mode application. When set to a one this bit configures the TCP for single power supply applications. This bit is automatically set on initial power-up or an oscillator fail event. When set, D6 disables the oscillator reference circuit. The result is that the oscillator is referenced to V<sub>CC</sub>. When a zero is written to D6 the oscillator reference is enabled, thus the oscillator is referenced to V<sub>BB</sub>. This allows operation in standard battery standby applications.

At initial power on, if the DP8572A is going to be programmed for battery backed mode, the V<sub>BB</sub> pin should be connected to a potential in the range of 2.2V to V<sub>CC</sub> - 0.4V.

For single supply mode operation, the V\_BB pin should be connected to GND and the  $\overrightarrow{\text{PFAIL}}$  pin connected to V\_CC.

D7: Writing a one to this bit enables the test mode register at location 1F (see Table III). This bit should be forced to zero during initialization for normal operation. If the test mode has been entered, clear the test mode register before leaving test mode. (See separate test mode application note for further details.)

#### TIME SAVE CONTROL REGISTER



D0-D4: General purpose RAM bits.


**D5:** The Delay Enable bit is used when a power fail occurs. If this bit is set, a 480  $\mu$ s delay is generated internally before the  $\mu$ P interface is locked out. This will enable the  $\mu$ P to access the registers for up to 480  $\mu$ s after it receives a power fail interrupt. After a power failure is detected but prior to the 480  $\mu$ s delay timing out, the host  $\mu$ P may force immediate lock out by resetting the Delay Enable bit. Note if this bit is a 0 when power fails then after a delay of 30  $\mu$ s min/63  $\mu$ s max the  $\mu$ P cannot read the chip.

**D6:** This read only bit is set and reset by the voltage at the V<sub>BB</sub> pin. It can be used by the  $\mu$ P to determine whether the battery voltage at the V<sub>BB</sub> pin is getting too low. A comparator monitors the battery and when the voltage is lower than 2.1V (typical) this bit is set. The power fail interrupt must be enabled to check for a low battery voltage.

**D7:** Time Save Enable bit controls the loading of real-timeclock data into the Time Save RAM. When a one is written to this bit the Time Save RAM will follow the corresponding clock registers, and when a zero is written to this bit the time in the Time Save RAM is frozen. This eliminates any synchronization problems when reading the clock, thus negating the need to check for a counter rollover during a read cycle.

This bit must be set to a one prior to power failing to enable the Time Save feature. When the power fails this bit is automatically reset and the time is saved in the Time Save RAM.

#### **REAL TIME MODE REGISTER**



D0-D1: These are the leap year counter bits. These bits are written to set the number of years from the previous leap year. The leap year counter increments on December 31st and it internally enables the February 29th counter state. This method of setting the leap year allows leap year to occur whenever the user wishes to, thus providing flexibility in implementing Japanese leap year function.

LY1	LY0	Leap Year Counter
0	0	Leap Year Current Year
0	1	Leap Year Last Year
1	0	Leap Year 2 Years Ago
1	1	Leap Year 3 Years Ago

**D2:** The count mode for the hours counter can be set to either 24 hour mode or 12 hour mode with AM/PM indicator. A one will place the clock in 12 hour mode.

D3: This bit is the master Start/Stop bit for the clock. When a one is written to this bit the real time counter's prescaler and counter chain are enabled. When this bit is reset to zero the contents of the real time counter is stopped and the prescaler is cleared. When the RTC is initially powered up this bit will be held at a logic 0 until the oscillator starts functioning correctly after which this bit may be modified. If an oscillator fail event occurs, this bit will be reset to logic 0.

**D4:** This bit controls the operation of the interrupt output in standby mode. If set to a one it allows Alarm, Periodic, and Power Fail interrupts to be functional in standby mode. Note that the MFO pin is configured as open drain in standby mode.

If bit D4 is set to a zero then bits D0–D5 of Interrupt Control Register 0 and bits D6 and D7 of Interrupt Control Register 1 will be reset when the RTC enters the standby mode (V<sub>BB</sub> > V<sub>CC</sub>). They will have to be re-configured when system (V<sub>CC</sub>) power is restored.


D5: General purpose RAM.

D6 and D7: These two bits select the crystal clock frequency as per the following table:

ХТ1 ХТО		Crystal Frequency
0.	0	32.768 kHz
0	1	4.194304 MHz
1	0	4.9152 MHz
1	1	32.000 kHz

All bits are Read/Write, and any mode written into this register can be determined by reading the register. On initial power up these bits are random.


#### OUTPUT MODE REGISTER



# DP8572A/DP8572AN

## Functional Description (Continued)


**D7:** This bit is used to program the signal appearing at the MFO output, as follows:



**D0–D5:** These bits are used to enable one of the selected periodic interrupts by writing a one into the appropriate bit. These interrupts are issued at the rollover of the clock. For example, the minutes interrupt will be issued whenever the minutes counter increments. In all likelihood the interrupt will be enabled asynchronously with the real time change. Therefore, the very first interrupt will occur in less than the periodic time chosen, but after the first interrupt all subsequent interrupts will be spaced correctly. These interrupts are useful when minute, second, real time reading, or task switching is required. When all six bits are written to a 0 this disables periodic interrupts from the Main Status Register and the DP8572A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then these bits are controlled by D4 of the Real Time Mode Register.

D6 and D7: General Purpose RAM.

#### **INTERRUPT CONTROL REGISTER 1**



TL/F/9980-18

D0-D5: Each of these bits are enable bits which will enable a comparison between an individual clock counter and its associated compare RAM. If any bit is a zero then that clock-RAM comparator is set to the "always equal" state and the associated TIME COMPARE RAM byte can be used as general purpose RAM. However, to ensure that an alarm interrupt is not generated at bit D3 of the Main Status Register, all bits must be written to a logic zero.

D6: In order to generate an external alarm compare interrupt to the  $\mu$ P from bit D3 of the Main Status Register, this bit must be written to a logic 1. If a battery backed mode is selected and the DP8572A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then this bit is controlled by D4 of the Real Time Mode Register.

**D7:** The MSB of this register is the enable bit for the Power Fail Interrupt. When this bit is set to a one an interrupt will be generated to the  $\mu$ P when V<sub>BB</sub> > V<sub>CC</sub>. If a battery backed mode is selected and the DP8572A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then this bit is controlled by D4 of the Real Time Mode Register.

This bit also enables the low battery detection analog circuitry.

in Status F		D5	D4	D3	D2	D1	D0	
	legister PS = 2		ADDRESS = 0	юн				1. Reset by
R/W	R/W	R/W	R/W	R/W <sup>1</sup>	R/W1	R2	R <sup>3</sup>	writing 1 to bit.
Page	Register	RAM	RAM	Alarm	Periodic	Power Fail	Interrupt	2. Set/reset
Select	Select			Interrupt	Interrupt	Interrupt	Status	voltage at
								PFAIL pin.
			·					3. Reset whe
	1. C.		•	ŧ				all pending
								are remov
	Register PS =			ress = 03H				4 Deed Oee
R/W	R/W <sup>4</sup>	R <sup>5</sup>	R5	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	4. Read Osc Write 0 Ba
Test	Osc. Fail/	1 ms	10 ms	100 ms	Seconds	10 Second	Minute	Backed M
Mode	Single Supply	Flag	Flag	Flag	Flag	Flag	Flag	Write 1 Si
						1		Supply Mo 5. Reset by
• .								positive er
÷.,			са. — «*					of read.
	ntrol Register		RS = 0	Address = 0				
R/W	R <sup>6</sup>	R/W	R/W	R/W	R/W	R/W	R/W	<b>,</b>
ime Save	Low Battery	Power Fail						6. Set and re
Enable	Flag	Delay	RAM	RAM	RAM	RAM	RAM	by V <sub>BB</sub> voltage.
	L	Enable		-				] foliago.
al Time Mo	de Register PS	S = 0 R	S = 1 A	ddress = 01H	l			
Crystal	Crystal	BAM	Interrupt EN	Clock	12/24 Hr.	Leap Year	Leap Year	All Bits R/W
Freq. XT1	Freq. XT0		on Back-Up	Start/Stop	Mode	MSB	LSB	
tout Mode	Register PS =	0 RS =	= 1 Addr	ess = 02H		1. A.		
MFO as			1 7.00	000 02.1			· · · · · · · · · · · · · · · · · · ·	1
Crystal	RAM	RAM	RAM	RAM	RAM	RAM	RAM	All Bits R/W
		· · ·			· · · · · · · · · · · · · · · · · · ·	L		J ;
errupt Con	trol Register 0	PS = 0	RS = 1	Address = 0	зн			i di di
		1 ms	10 ms	100 ms	Seconds	10 Second	Minute	
RAM	RAM	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	All Bits R/W
		Enable	Enable	Enable	Enable	Enable	Enable	
errupt Con	trol Register 1	PS = 0	RS = 1	Address = 0	4H			
Power Fail	Alarm	DOW	Month	DOM	Hours	Minute	Second	
Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	Interrupt	All Bits R/W
Enable	Enable	Enable	Enable	Enable	Enable	Enable	Enable	

DP8572A/DP8572AM

## **Application Hints**

Suggested Initialization Procedure for DP8572A in Battery Backed Applications that use the  $V_{BB}$  Pin.

- 1. Enter the test mode by writing a 1 to bit D7 in the Periodic Flag Register.
- Write zero to the RAM/TEST mode Register located in page 0, address HEX 1F.
- 3. Leave the test mode by writing a 0 to bit D7 in the Periodic Flag Register. Steps 1,2,3 guarantee that if the test mode had been entered during power on (due to random pulses from the system), all test mode conditions are cleared. Most important is that the OSC Fail Disable bit is cleared. Refer to AN-589 for more information on test mode operation.
- 4. After power on (V<sub>CC</sub> and V<sub>BB</sub> powered), select the correct crystal frequency bits (D7, D6 in the Real Time Mode Register) as shown in Table IV.

Frequency	D7	D6		
32.768 KHz	0	0		
4.194304 MHz	0	1		
4.9152 MHz	1	0		
32.0 KHz	1	1		

TABLE IV

5. Enter a software loop that does the following:

Set a 3 second(approx) software counter. The crystal oscillator may take 1 second to start.

5.1 Write a 1 to bit D3 in the Real Time Mode Register (try to start the clock). Make sure the crystal select bits remain the same as in step 1. Under normal operation, this bit can be set only if the oscillator is running. During the

software loop, RAM, real time counters, output configuration, interrupt control and timer functions may be initialized.

6. Test bit D6 in the Periodic Flag Register:

IF a 1, go to 5.1. If this bit remains a 1 after 3 seconds, then abort and check hardware. The crystal may be defective or not installed. There may be a short at OSC IN or OSC OUT to V<sub>CC</sub> or GND, or to some impedance that is less than 10 M $\Omega$ .


IF a 0, then the oscillator is running, go to step 7.

7. Write a 0 to bit D6 in the Periodic Flag Register. This action puts the clock chip in the battery backed mode. This mode can be entered only if the OSC fail flag (bit D6 of the Periodic Flag Register) is a 0. Reminder, Bit D6 is a dual function bit. When read, D6 returns oscillator status. When written, D6 causes either the Battery Backed Mode, or the Single Supply Mode of operation.

The only method to ensure the chip is in the battery backed mode is to measure the waveform at the OSC OUT pin. If the battery backed mode was selected successfully, then the peak to peak waveform at OSC OUT is referenced to the battery voltage. If not in battery backed mode, the waveform is referenced to V<sub>CC</sub>. The measurement should be made with a high impedance low capacitance probe (10 M $\Omega$ , 10 pF oscilloscope probe or better). Typical peak to peak swings are within 0.6V of V<sub>CC</sub> and ground respectively.


- 8. Write a 1 to bit D7 of Interrupt Control Register 1. This action enables the PFAIL pin and associated circuitry.
- 9. Write a 1 to bit D4 of the Real Time Mode Register. This action ensures that bit D7 of Interrupt Control Register 1 remains a 1 when  $V_{BB} > V_{CC}$  (Standby Mode).
- 10. Initialize the rest of the chip as needed.

## **Typical** Application




## **Typical Performance Characteristics**










**Operating Current vs** Supply Voltage (Battery Backed Mode F<sub>OSC</sub> = 32.768 kHz) 1400 1200 1000 l<sub>cc</sub> (mA) 800 600 20 3.0 5.0 4.0 6.0 V<sub>CC</sub> (Volts) TL/F/9980-21

Standby Current vs Power Supply Voltage F<sub>OSC</sub> = 4.194304 MHz



TL/F/9980-23



## DP8573A Real Time Clock (RTC)

## **General Description**

The DP8573A is intended for use in microprocessor based systems where information is required for multi-tasking, data logging or general time of day/date information. This device is implemented in low voltage silicon gate microCMOS technology to provide low standby power in battery back-up environments. The circuit's architecture is such that it looks like a contiguous block of memory or I/O ports organized as one block of 32 bytes. This includes the Control Registers, the Clock Counters, the Alarm Compare RAM, and the Time Save RAM.

Time and date are maintained from 1/100 of a second to year and leap year in a BCD format, 12 or 24 hour modes. Day of week and day of month counters are provided. Time is controlled by an on-chip crystal oscillator requiring only the addition of the 32.768 kHz crystal and two capacitors.


Power failure logic and control functions have been integrated on chip. This logic is used by the RTC to issue a power fail interrupt, and lock out the  $\mu$ P interface. The time power fails may be logged into RAM automatically when V<sub>BB</sub> > V<sub>CC</sub>. Additionally, two supply pins are provided. When V<sub>BB</sub>

> V<sub>CC</sub>, internal circuitry will automatically switch from the main supply to the battery supply.

The DP8573A's interrupt structure provides three basic types of interrupts: Periodic, Alarm/Compare, and Power Fail. Interrupt mask and status registers enable the masking and easy determination of each interrupt.

#### Features

- Full function real time clock/calendar — 12/24 hour mode timekeeping
  - 12/24 hour mode times
  - Day of week counter
     Parallel resonant oscillator
- Power fail features
  - Internal power supply switch to external battery
  - Power Supply Bus glitch protection
  - Automatic log of time into RAM at power failure
- On-chip interrupt structure
- Periodic, alarm, and power fail interrupts



2

DP8573A

## Absolute Maximum Ratings (Notes 1 & 2)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Supply Voltage (V <sub>CC</sub> )	-0.5V to +7.0V
DC Input Voltage (V <sub>IN</sub> )	$-0.5V$ to $V_{\mbox{CC}}+0.5V$
DC Output Voltage (V <sub>OUT</sub> )	$-0.5V$ to $V_{CC}$ $+$ 0.5V
Storage Temperature Range	-65°C to +150°C
Power Dissipation (PD)	500 mW
Lead Temperature (Soldering, 10 sec.	) 260°C

## **Operation Conditions**

	Min	Max	Unit
) (Note 3)	4.5	5.5	v
Supply Voltage (V <sub>BB</sub> ) (Note 3)			v
DC Input or Output Voltage (VIN, V <sub>OUT</sub> )		0.0 V <sub>CC</sub>	
ure (T <sub>A</sub> )	-40	+ 85	°C
Electr-Static Discharge Rating		.1 .	kV
		10,300	
1 - C		59°C/W	
t ·		65°C/W	
		80°C/W	
t		88°C/W	
	oltage ure (T <sub>A</sub> )	) (Note 3) 4.5 ) (Note 3) 2.2 oltage 0.0 ure (T <sub>A</sub> ) -40 ge Rating	(Note 3)         4.5         5.5           (Note 3)         2.2         V <sub>CC</sub> -0.4           oltage         0.0         V <sub>CC</sub> ure (T <sub>A</sub> )         -40         +85           ge Rating         1         10,300           tt         55°C/W         65°C/W           80°C/W         80°C/W         80°C/W

## **DC Electrical Characteristics**

 $V_{CC} = 5V \pm 10\%$ ,  $V_{BB} = 3V$ ,  $V_{\overline{PFAIL}} > V_{IH}$ ,  $C_L = 100 \text{ pF}$  (unless otherwise specified)

Symbol	Parameter	Conditions	Min	Max	Units
VIH	High Level Input Voltage (Note 4)	Any Inputs Except OSC IN, OSC IN with External Clock	2.0 V <sub>BB</sub> -0.1		v v
VIL	Low Level Input Voltage	All Inputs Except OSC IN OSC IN with External Clock		0.8 0.1	v v
V <sub>OH</sub>	High Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = -20 \ \mu A$ $I_{OUT} = -4.0 \ m A$	V <sub>CC</sub> -0.1 3.5		V V
V <sub>OL</sub>	Low Level Output Voltage (Excluding OSC OUT)	$I_{OUT} = 20 \ \mu A$ $I_{OUT} = 4.0 \ m A$		0.1 0.25	V V
I <sub>IN</sub>	Input Current (Except OSC IN)	$V_{IN} = V_{CC} \text{ or GND}$		±1.0	μΑ
loz	Output TRI-STATE® Current	$V_{OUT} = V_{CC} \text{ or } GND$ ,		±5.0	μA
I <sub>LKG</sub>	Output High Leakage Current T1, MFO, INTR Pins	$V_{OUT} = V_{CC}$ or GND Outputs Open Drain		±5.0	μΑ
lcc	Quiescent Supply Current (Note 6)	$\begin{array}{l} F_{OSC} = 32.768 \ \text{kHz} \\ V_{IN} = V_{CC} \ \text{or GND} \ (\text{Note 5}) \\ V_{IN} = V_{CC} \ \text{or GND} \ (\text{Note 6}) \\ V_{IN} = V_{IH} \ \text{or } V_{IL} \ (\text{Note 6}) \end{array}$	·	250 1.0 12.0	μA mA mA
ICC	Quiescent Supply Current (Single Supply Mode) (Note 7)	$V_{BB} = GND$ $V_{IN} = V_{CC}$ or GND $F_{OSC} = 32.768$ kHz		40	μΑ
I <sub>BB</sub>	Standby Mode Battery Supply Current (Note 7)	$\label{eq:VCC} \begin{array}{l} V_{CC} = GND \\ OSC  OUT = open circuit, \\ other pins = GND \\ F_{OSC} = 32.768  \text{kHz} \end{array}$		10	μA
I <sub>BLK</sub>	Battery Leakage	$\begin{array}{l} 2.2V \leq V_{BB} \leq 4.0V \\ \text{other pins at GND} \\ V_{CC} = GND \\ V_{CC} = 5.5V \end{array}$	-5	1.5	μΑ μΑ

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur.

Note 2: Unless otherwise specified all voltages are referenced to ground.

Note 3: In battery backed mode,  $V_{BB} \leq V_{CC} - 0.4V$ .

Single Supply Mode: Data retention voltage is 2.2V min.

In single Supply Mode (Power connected to V<sub>CC</sub> pin) 4.5V  $\leq$  V<sub>CC</sub>  $\leq$  5.5V.

Note 4: This parameter (V<sub>IH</sub>) is not tested on all pins at the same time.

Note 5: This specification tests I<sub>CC</sub> with all power fail circuitry disabled, by setting D7 of Interrupt Control Register 1 to 0.

Note 6: This specification tests I<sub>CC</sub> with all power fail circuitry enabled, by setting D7 of Interrupt Control Register 1 to 1.

Note 7: OSC IN is driven by a signal generator. Contents of the Test Register = 00(H) and the MFO pin is not configured as buffered oscillator out.

Symbol	Parameter	Min	Max	Units
DTIMING	· · · · · · · · · · · · · · · · · · ·			
t <sub>AR</sub>	Address Valid Prior to Read Strobe	20		ns
t <sub>RW</sub>	Read Strobe Width (Note 8)	80		ns
tCD	Chip Select to Data Valid Time		80	ns
tRAH	Address Hold after Read (Note 9)	3		ns
t <sub>RD</sub>	Read Strobe to Valid Data		70	ns
t <sub>DZ</sub>	Read or Chip Select to TRI-STATE		60	ns
t <sub>RCH</sub>	Chip Select Hold after Read Strobe	0		ns
t <sub>DS</sub>	Minimum Inactive Time between Read or Write Accesses	50		ns
TE TIMING				
t <sub>AW</sub>	Address Valid before Write Strobe	20		ns
twan	Address Hold after Write Strobe (Note 9)	3		ns
tcw	Chip Select to End of Write Strobe	90		ns
t <sub>WW</sub>	Write Strobe Width (Note 10)	80		ns
t <sub>DW</sub>	Data Valid to End of Write Strobe	50		ns
t <sub>WDH</sub>	Data Hold after Write Strobe (Note 9)	3		ns
twch	Chip Select Hold after Write Strobe	0		ns

Clock rollover to INTR out typically 16.5 µs <sup>t</sup>ROLL

Note 8: Read Strobe width as used in the read timing table is defined as the period when both chip select and read inputs are low. Hence read commences when both signals are low and terminates when either signal returns high.

Note 9: Hold time is guaranteed by design but not production tested. This limit is not used to calculate outgoing quality levels.

Note 10: Write Strobe width as used in the write timing table is defined as the period when both chip select and write inputs are low. Hence write commences when both signals are low and terminates when either signal returns high.

## **AC Test Conditions**

Input Pulse Levels	GND to 3.0V		
Input Rise and Fall Times	6 ns (10%–90%)		
Input and Output	1.3V		
Reference Levels	1.5 V		
TRI-STATE Reference	Active High + 0.5V		
Levels (Note 12)	Active Low -0.5V		

Note 11:  $C_L = 100 \text{ pF}$ , includes jig and scope capacitance.

Note 12: S1 =  $V_{CC}$  for active low to high impedance measurements.

S1 = GND for active high to high impedance measurements.


S1 = open for all other timing measurements.

Capacitance	$T_A = 25^{\circ}C, f = 1 \text{ MHz}$
-------------	--


Symbol	Parameter (Note 14)	Тур	Units
CIN	Input Capacitance	5	pF
COUT	Output Capacitance	7	pF

Note 13: This parameter is not 100% tested.


Note 14: Output rise and fall times 25 ns max (10%-90%) with 100 pF load.



#### **Timing Waveforms**



#### Write Timing Diagram



## **Pin Description**

**CS, RD, WR (Inputs):** These pins interface to  $\mu P$  control lines. The **CS** pin is an active low enable for the read and write operations. Read and Write pins are also active low and enable reading or writing to the RTC. All three pins are disabled when power failure is detected. However, if a read or write is in progress at this time, it will be allowed to complete its cycle.

A0-A4 (Inputs): These 5 pins are for register selection. They individually control which location is to be accessed. These inputs are disabled when power failure is detected.

OSC IN (Input): OSC OUT (Output): These two pins are used to connect the crystal to the internal parallel resonant oscillator. The oscillator is always running when power is applied to  $V_{BB}$  and  $V_{CC}$ .

**MFO (Output):** The multi-function output can be used as a second interrupt (Power fail) output for interrupting the  $\mu$ P. This pin can also provide an output for the oscillator. The MFO output is configured as push-pull, active high for normal or single power supply operation and as an open drain during standby mode (V<sub>BB</sub> > V<sub>CC</sub>). If in battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than V<sub>BB</sub>.

**INTR (Output):** The interrupt output is used to interrupt the processor when a timing event or power fail has occurred and the respective interrupt has been enabled. The INTR output is permanently configured active low, open drain. If in

battery backed mode and a pull-up resistor is attached, it should be connected to a voltage no greater than  $V_{BB}$ . The output is a DC voltage level. To clear the INTR, write a 1 to the appropriate bit(s) in the Main Status Register.


**D0-D7 (Input/Output):** These 8 bidirectional pins connect to the host  $\mu$ P's data bus and are used to read from and write to the RTC. When the PFAIL pin goes low and a write is not in progress, these pins are at TRI-STATE.

**PFAIL** (Input): In battery backed mode, this pin can have a digital signal applied to it via some external power detection logic. When  $\overrightarrow{PFAIL} =$  logic 0 the RTC goes into a lockout mode, in a minimum of 30  $\mu$ s or a maximum of 63  $\mu$ s unless lockout delay is programmed. In the single power supply mode, this pin is not useable as an input and should be tied to V<sub>CC</sub>. Refer to section on Power Fail Functional Description.

V<sub>CC</sub>: This is the main system power pin.

GND: This is the common ground power pin for both  $\mathsf{V}_{BB}$  and  $\mathsf{V}_{CC}.$ 

## **Connection Diagrams**



TL/F/9981-5

Top View Order Number DP8573AN See NS Package Number N24C

## **Functional Description**

The DP8573A contains a fast access real time clock, interrupt control logic, and power fail detect logic. All functions of the RTC are controlled by a set of seven registers. A simplified block diagram that shows the major functional blocks is given in *Figure 1*.

The blocks are described in the following sections:

- 1. Real Time Clock
- 2. Oscillator Prescaler
- 3. Interrupt Logic
- 4. Power Failure Logic
- 5. Additional Supply Management

The memory map of the RTC is shown in the memory addressing table (*Figure 2*). A control bit in the Main Status Register is used to select either control register block.


#### INITIAL POWER-ON of BOTH VBB and VCC

 $V_{BB}$  and  $V_{CC}$  may be applied in any sequence. In order for the power fail circuitry to function correctly, whenever power is off, the  $V_{CC}$  pin must see a path to ground through a maximum of 1  $M\Omega$ . The user should be aware that the control registers will contain random data. The user should ensure that the RTC is not in test mode (see register descriptions).

#### **REAL TIME CLOCK FUNCTIONAL DESCRIPTION**

As shown in *Figure 2*, the clock has 8 bytes of counters, which count from 1/100 of a second to years. Each counter counts in BCD and is synchronously clocked. The count sequence of the individual byte counters within the clock is shown later in Table VII. Note that the day of week, day of month, and month counters all roll over to 1. The hours counter in 12 hour mode rolls over to 12 (AM = 0, PM = 1). The AM/PM bit is bit D7 in the hours counter.

All other counters roll over to 0. Upon initial application of power the counters will contain random information.



TL/F/9981-6



Order Number DP8573AV See NS Package Number V28A




FIGURE 2. DP8573A Internal Memory Map

#### **READING THE CLOCK: VALIDATED READ**

Since clocking of the counter occurs asynchronously to reading of the counter, it is possible to read the counter while it is being incremented (rollover). This may result in an incorrect time reading. Thus to ensure a correct reading of the entire contents of the clock (or that part of interest), it must be read without a clock rollover occurring. In general this can be done by checking a rollover bit. On this chip the periodic interrupt status bits can serve this function. The following program steps can be used to accomplish this.

- 1. Initialize program for reading clock.
- 2. Dummy read of periodic status bit to clear it.
- 3. Read counter bytes and store.
- 4. Read rollover bit, and test it.
- 5. If rollover occured go to 3.
- 6. If no rollover, done.

To detect the rollover, individual periodic status bits can be polled. The periodic bit chosen should be equal to the highest frequency counter register to be read. That is if only SECONDS through HOURS counters are read, then the SECONDS periodic bit should be used.

#### **READING THE CLOCK: INTERRUPT DRIVEN**

Enabling the periodic interrupt mask bits cause interrupts just as the clock rolls over. Enabling the desired update rate and providing an interrupt service routine that executes in less than 10 ms enables clock reading without checking for a rollover.

#### READING THE CLOCK: LATCHED READ

Another method to read the clock that does not require checking the rollover bit is to write a one into the Time Save Enable bit (D7) of the Time Save Control Register, and then to write a zero. Writing a one into this bit will enable the clock contents to be duplicated in the Time Save RAM. Changing the bit from a one to a zero will freeze and store the contents of the clock in Time Save RAM. The time then can be read without concern for clock rollover, since internal logic takes care of synchronization of the clock. Because only the bits used by the clock counters will be latched, the Time Save RAM should be cleared prior to use to ensure that random data stored in the unused bits do not confuse the host microprocessor. This bit can also provide time save at power failure, see the Additional Supply Management Functions section. With the Time Save Enable bit at a logical 0, the Time Save RAM may be used as RAM if the latched read function is not necessary.


# INITIALIZING AND WRITING TO THE CALENDAR-CLOCK

Upon initial application of power to the TCP or when making time corrections, the time must be written into the clock. To correctly write the time to the counters, the clock would normally be stopped by writing the Start/Stop bit in the Real Time Mode Register to a zero. This stops the clock from counting and disables the carry circuitry. When initializing the clock's Real Time Mode Register, it is recommended that first the various mode bits be written while maintaining the Start/Stop bit reset, and then writing to the register a second time with the Start/Stop bit set.

The above method is useful when the entire clock is being corrected. If one location is being updated the clock need not be stopped since this will reset the prescaler, and time will be lost. An ideal example of this is correcting the hours for daylight savings time. To write to the clock "on the fly" the best method is to wait for the 1/100 of a second periodic interrupt. Then wait an additional 16  $\mu$ s, and then write the data to the clock.

# PRESCALER/OSCILLATOR FUNCTIONAL DESCRIPTION

Feeding the counter chain is a programmable prescaler which divides the crystal oscillator frequency to 32 kHz and further to 100 Hz for the counter chain (see *Figure 3*).



TL/F/9981-8

#### FIGURE 3. Programmable Clock Prescaler Block

In addition to the inverter, the oscillator feedback bias resistor is included on chip, as shown in *Figure 4*. The oscillator input may be driven from an external source if desired. Refer to test mode application note for details. The oscillator stability is enhanced through the use of an on chip regulated power supply.

The typical range of trimmer capacitor (as shown in Oscillator Circuit Diagram *Figure 4*, and in the typical application) at the oscillator input pin is suggested only to allow accurate tuning of the oscillator. This range is based on a typical printed circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases, the **load capacitance** specified by the crystal manufacturer (nominal value 11 pF for the 32.768 crystal) is what determines proper oscillation. This load capcitance is the series combination of capacitance on each side of the crystal (with respect to ground).




FIGURE 4. Oscillator Circuit Diagram

XTAL	Co	Ct	R <sub>OUT</sub>
32.768 kHz	47 pF	2 pF-22 pF	150 k $\Omega$ to 350 k $\Omega$

#### INTERRUPT LOGIC FUNCTIONAL DESCRIPTION

The RTC has the ability to coordinate processor timing activities. To enhance this, an interrupt structure has been implemented which enables several types of events to cause interrupts. Interrupts are controlled via two Control Registers in block 1 and two Status Registers in block 0. (See Register Description for notes on paging and Table I.)

The interrupts are enabled by writing a one to the appropriate bits in Interrupt Control Register 0 and/or 1.

TABLE I. Registers that are Applicable to Interrupt Control

Register Name	Register Select	Address
Main Status Register	x	00H
Periodic Flag Register	0	03H
Interrupt Control Register 0	1	03H
Interrupt Control Register 1	1	04H
Output Mode Register	1	02H

The Interrupt Status Flag D0, in the Main Status Register, indicates the state of INTR and MFO outputs. It is set when either output becomes active and is cleared when all RTC interrupts have been cleared and no further interrupts are pending (i.e., both INTR and MFO are returned to their inactive state). This flag enables the RTC to be rapidly polled by the  $\mu$ P to determine the source of an interrupt in a wired—OR interrupt system. (The Interrupt Status Flag provides a true reflection of all conditions routed to the external pins.)

Status for the interrupts are provided by the Main Status Register and the Periodic Flag Register. Bits D1-D5 of the Main Status Register are the main interrupt bits.

These register bits will be set when their associated timing events occur. Enabled Alarm comparisons that occur will set its Main Status Register bit to a one. However, an external interrupt will only be generated if the Alarm interrupt enable bit is set (see *Figure 5*).

Disabling the periodic interrupts will mask the Main Status Register periodic bit, but not the Periodic Flag Register bits. The Power Fail Interrupt bit is set when the interrupt is enabled and a power fail event has occurred, and is not reset until the power is restored. If all interrupt enable bits are 0 no interrupt will be asserted. However, status still can be read from the Main Status Register in a polled fashion (see Figure 5).

To clear a flag in bits D2 and D3 of the Main Status Register a 1 must be written back into the bit location that is to be cleared. For the Periodic Flag Register reading the status will reset all the periodic flags.

Interrupts Fall Into Three Categories:

- 1. The Alarm Compare Interrupt: Issued when the value in the time compared RAM equals the counter.
- The Periodic Interrupts: These are issued at every increment of the specific clock counter signal. Thus, an interrupt is issued every minute, second, etc. Each of these interrupts occurs at the roll-over of the specific counter.

DP8573A

3. The Power Fail Interrupt: Issued upon recognition of a power fail condition by the internal sensing logic. The power failed condition is determined by the signal on the PFAIL pin. The internal power fail signal is gated with the chip select signal to ensure that the power fail interrupt does not lock the chip out during a read or write.

#### ALARM COMPARE INTERRUPT DESCRIPTON

The alarm/time comparison interrupt is a special interrupt similar to an alarm clock wake up buzzer. This interrupt is generated when the clock time is equal to a value programmed into the alarm compare registers. Up to six bytes can be enabled to perform alarm time comparisons on the counter chain. These six bytes, or some subset thereof, would be loaded with the future time at which the interrupt will occur. Next, the appropriate bits in the Interrupt Control Register 1 are enabled or disabled (refer to detailed description of Interrupt Control Register 1). The RTC then compares these bytes with the clock time. When all the enabled compare registers equal the clock time an alarm interrupt is issued, but only if the alarm compare interrupt is enabled can the interrupt be generated externally. Each alarm compare bit in the Control Register will enable a specific byte for comparison to the clock. Disabling a compare byte is the same as setting its associated counter comparator to an "always equal" state. For example, to generate an interrupt at 3:15 AM of every day, load the hours compare with 0 3 (BCD), the minutes compare with 1 5 (BCD) and the faster counters with 0 0 (BCD), and then disable all other compare registers. So every day when the time rolls over from 3:14:59.99, an interrupt is issued. This bit may be reset by writing a one to bit D3 in the Main Status Register at any time after the alarm has been generated.

If time comparison for an individual byte counter is disabled, that corresponding RAM location can then be used as general purpose storage.

#### PERIODIC INTERRUPTS DESCRIPTION

The Periodic Flag Register contains six flags which are set by real-time generated "ticks" at various time intervals, see *Figure 5*. These flags constantly sense the periodic signals and may be used whether or not interrupts are enabled. These flags are cleared by any read or write operation performed on this register.

To generate periodic interrupts at the desired rate, the associated Periodic Interrupt Enable bit in Interrupt Control Register 0 must be set. Any combination of periodic interrupts may be enabled to operate simultaneously. Enabled periodic interrupts will now affect the Periodic Interrupt Flag in the Main Status Register.

When a periodic event occurs, the Periodic Interrupt Flag in the Main Status Register is set, causing an interrupt to be generated. The  $\mu$ P clears both flag and interrupt by writing a "1" to the Periodic Interrupt Flag. The individual flags in the periodic Interrupt Flag Register do not require clearing to cancel the interrupt.

If all periodic interrupts are disabled and a periodic interrupt is left pending (i.e., the Periodic Interrupt Flag is still set), the Periodic Interrupt Flag will still be required to be cleared to cancel the pending interrupt.

DP8573A

Functional Description (Continued)

4




FIGURE 5. Interrupt Control Logic Overview

2-78

#### POWER FAIL INTERRUPTS DESCRIPTION

The Power Fail Status Flag in the Main Status Register monitors the state of the internal power fail signal. This flag may be interrogated by the  $\mu$ P, but it cannot be cleared; it is cleared automatically by the RTC when system power is restored. To generate an interrupt when the power fails, the Power Fail Interrupt Enable bit in Interrupt Control Register 1 is set. Although this interrupt may not be cleared, it may be masked by clearing the Power Fail Interrupt Enable bit.

# POWER FAILURE CIRCUITRY FUNCTIONAL DESCRIPTION

Since the clock must be operated from a battery when the main system supply has been turned off, the DP8573A provides circuitry to simplify design in battery backed systems. This switches over to the back up supply, and isolates itself from the host system. *Figure 6* shows a simplified block diagram of this circuitry, which consists of three major sections; 1) power loss logic: 2) battery switch over logic: and 3) isolation logic.

Detection of power loss occurs when  $\overrightarrow{\text{PFAIL}}$  is low. Debounce logic provides a 30  $\mu$ s-63  $\mu$ s debounce time, which will prevent noise on the  $\overrightarrow{\text{PFAIL}}$  pin from being interpreted as a system failure. After 30  $\mu$ s-63  $\mu$ s the debounce logic times out and a signal is generated indicating that system power is marginal and is failing. The Power Fail Interrupt will then be generated.

If chip select is low when a power failure is detected, a safety circuit will ensure that if a read or write is held active continuously for greater than 30  $\mu$ s after the power fail signal is asserted, the lock-out will be forced.

The battery switch over circuitry is completely independent of the  $\overline{\text{PFAIL}}$  pin. A separate circuit compares  $V_{CC}$  to the  $V_{BB}$  voltage. As the main supply fails, the RTC will continue to operate from the  $V_{CC}$  pin until  $V_{CC}$  falls below the  $V_{BB}$  voltage. At this time, the battery supply is switched in,  $V_{CC}$  is

disconnected, and the device is now in the standby mode. If indeterminate operation of the battery switch over circuit is to be avoided, then the voltage at the V<sub>CC</sub> pin must not be allowed to equal the voltage at the V<sub>BB</sub> pin.

After the generation of a lock-out signal, and eventual switch in of the battery supply, the pins of the RTC will be configured as shown in Table II. Outputs that have a pull-up resistor should be connected to a voltage no greater than  $V_{BB}.$ 


TARLE II	Pin Isolation	during a	Power Failure
I ADLE II.	Pin Isolauol	i uui iliy a	Power railure

Pin	PFAIL = Logic 0	Standby Mode V <sub>BB</sub> > V <sub>CC</sub>
CS, RD, WR	Locked Out	Locked Out
A0-A4	Locked Out	Locked Out
D0-D7	Locked Out	Locked Out
Oscillator	Not Isolated	Not Isolated
PFAIL	Not Isolated	Not Isolated
INTR, MFO	Not Isolated	Open Drain

The Interrupt Power Fail Operation bit in the Real-Time Mode Register determines whether or not the interrupts will continue to function after a power fail event.

As power returns to the system, the battery switch over circuit will switch back to V<sub>CC</sub> power as soon as it becomes greater than the battery voltage. The chip will remain in the locked out state as long as  $\overrightarrow{PFAIL} = 0$ . When  $\overrightarrow{PFAIL} = 1$  the chip is unlocked, but only after another 30  $\mu$ s min  $\rightarrow 63$   $\mu$ s max debounce time. The system designer must ensure that his system is stable when power has returned.

The power fail circuitry contains active linear circuitry that draws supply current from  $V_{CC}$ . In some cases this may be undesirable, so this circuit can be disabled by masking the power fail interrupt. The power fail input can perform all lock-out functions previously mentioned, except that no ex-



and Lock-Out Circuits (Lower Right)

4

ternal interrupt will be issued. Note that the linear power fail circuitry is switched off automatically when using  $V_{BB}$  in standby mode.

#### INITIAL POWER ON DETECT AND POWER FAIL TIME SAVE

There are two other functions provided on the DP8573A to ease power supply control. These are an initial Power On detect circuit, which also can be used as a time keeping failure detect, and a time save on power failure.

On initial power up the Oscillator Fail Flag will be set to a one and the real time clock start bit reset to a zero. This indicates that an oscillator fail event has occurred, and time keeping has failed.

The Oscillator Fail flag will not be reset until the real-time clock is started. This allows the system to discriminate between an initial power-up and recovery from a power failure. If the battery backed mode is selected, then bit D6 of the Periodic Flag Register must be written low. This will not affect the contents of the Oscillator Fail Flag.

To relieve CPU overhead for saving time upon power failure, the Time Save Enable bit is provided to do this automatically. (See also Reading the Clock: Latched Read.) The Time Save Enable bit, when set, causes the Time Save RAM to follow the contents of the clock. This bit can be reset by software, but if set before a power failure occurs, it will automatically be reset when the clock switches to the battery supply (not when a power failure is detected by the PFAIL pin). Thus, writing a one to the Time Save bit enables both a software write or power fail write.

#### SINGLE POWER SUPPLY APPLICATIONS

The DP8573A can be used in a single power supply application. To achieve this, the  $V_{BB}$  pin must be connected to ground, and the power connected to  $V_{CC}$ . The Oscillator Failed/Single Supply bit in the Periodic Flag Register should be set to a logic 1, which will disable the oscillator battery reference circuit. The power fail interrupt should also be disabled. This will turn off the linear power fail detection circuits, and will eliminate any quiescent power drawn through these circuits.

#### **DETAILED REGISTER DESCRIPTION**

There are 5 external address bits: Thus, the host microprocessor has access to 28 locations at one time. An internal switching scheme provides a total of 30 locations.


The only register that does not get switched is the Main Status Register. It contains the register select bit as well as status information.

A memory map is shown in *Figure 2* and register addressing in Table III. They show the name, address and page locations for the DP8573A.

TABLE III. Register/Counter/RAM Addressing for DP8573A

A0-4	RS (Note 1)	Description					
CON	TROL REC	BISTERS					
00	х	Main Status Register					
01	0	N/A					
02	0	N/A					
03	0	Periodic Flag Register					
04	0	Time Save Control Reg	ister				
01	1	Real Time Mode Regist	er				
02	1	Output Mode Register	· .				
03	1	Interrupt Control Regist					
04	1	Interrupt Control Regist	er 1				
COU	NTERS (C	LOCK CALENDAR)	. •				
05	х	1/100, 1/10 Seconds	(0-99)				
06	Х	Seconds	(0-59)				
07	Х	Minutes	(0-59)				
08	Х	Hours	(1-12, 0-23)				
. 09	Х	Days of Month	(1-28/29/30/31)				
0A	Х	Months	(1–12)				
0B	Х	Years	(0-99)				
0C	х	RAM					
0D -	х	D0, D1 bits only					
0E	<b>X</b> 1	Day of Week	(1–7)				
0F	х	N/A					
10	Х	N/A					
11	Х	N/A					
12	<b>X</b> .	N/A					
TIME	COMPAR	E RAM					
13	х	Sec Compare RAM	(0-59)				
14	х	Min Compare RAM	(0-59)				
15	x	Hours Compare RAM	(1-12, 0-23)				
16	Х	DOM Compare RAM	(1-28/29/30/31)				
17	X	Months Compare RAM	(1-12)				
18	х	DOW Compare RAM	(1-7)				
TIME	SAVE RA	M					
19	х	Seconds Time Save RA	м				
1A	x	Minutes Time Save RAM	M				
1B	x	Hours Time Save RAM					
1C	X	Day of Month Time Sav	e RAM				
1D	х	Months Time Save RAM	1				
1E	1	RAM					
1F	x	RAM/Test Mode Regist	ter				

Note 1: RS-Register Select (Bit D6 of Main Status Register)



TL/F/9981-12

The Main Status Register is always located at address 0 regardless of the register block selected.


**D0:** This read only bit is a general interrupt status bit that is taken directly from the interrupt pins. The bit is a one when an interrupt is pending on either the  $\overline{INTR}$  pin or the MFO pin (when configured as an interrupt). This is unlike D3 which can be set by an internal event but may not cause an interrupt. This bit is reset when the interrupt status bits in the Main Status Register are cleared.

**D1-D3:** These three bits of the Main Status Register are the main interrupt status bits. Any bit may be a one when any of the interrupts are pending. Once an interrupt is asserted the  $\mu$ P will read this register to determine the cause. These interrupt status bits are not reset when read. Except for D1, to reset an interrupt a one is written back to the corresponding bit that is being tested. D1 is reset whenever the PFAIL pin = logic 1. This prevents loss of interrupt status when reading the register in a polled mode. D1 and D3 are set regardless of whether these interrupts are masked or not by bits D6 and D7 of Interrupt Control Registers 0 and 1.

D4, D5 and D7: General purpose RAM bits.

**D6:** Bit D6 controls the register block to be accessed (see memory map).

#### PERIODIC FLAG REGISTER



The Periodic Flag Register has the same bit for bit correspondence as Interrupt Control Register 0 except for D6 and D7. For normal operation (i.e., not a single supply application) this register must be written to on initial power up or after an oscillator fail event. D0–D5 are read only bits, D6 and D7 are read/write.

**D0-D5:** These bits are set by the real time rollover events: (Time Change = 1). The bits are reset when the register is read and can be used as selective data change flags.

**D6:** This bit performs a dual function. When this bit is read, a one indicates that an oscillator failure has occurred and the time information may have been lost. Some of the ways an oscillator failure might be caused are: failure of the crystal, shorting OSC IN or OSC OUT to GND or V<sub>CC</sub>, removal of crystal, removal of battery when in the battery backed mode (when a "0" is written to D6), lowering the voltage at the V<sub>BB</sub> pin to a value less than 2.2V when in the battery

backed mode. Bit D6 is automatically set to 1 on initial power-up or an oscillator fail event. The oscillator fail flag is reset by writing a one to the clock start/stop bit in the Real Time Mode Register, with the crystal oscillating.


When D6 is written to, it defines whether the TCP is being used in battery backed (normal) or in a single supply mode application. When set to a one this bit configures the TCP for single power supply applications. This bit is automatically set on initial power-up or an oscillator fail event. When set, D6 disables the oscillator reference circuit. The result is that the oscillator referenced to  $V_{CC}$ . When a zero is written to D6 the oscillator reference is enabled, thus the oscillator is referenced to  $V_{BB}$ . This allows operation in standard battery standby applications.

At initial power on, if the DP8573A is going to be programmed for battery backed mode, the  $V_{BB}$  pin should be connected to a potential in the range of 2.2V to  $V_{CC}-0.4V.$ 

For single supply mode operation, the V<sub>BB</sub> pin should be connected to GND and the  $\overline{\text{PFAIL}}$  pin connected to V<sub>CC</sub>.

**D7:** Writing a one to this bit enables the test mode register at location 1F (see Table III). This bit should be forced to zero during initialization for normal operation. If the test mode has been entered, clear the test mode register before leaving test mode. (See separate test mode application note for further details.)

#### TIME SAVE CONTROL REGISTER



TL/F/9981-14


D0-D5: General purpose RAM bits.

D6: Not Available, appears as logic 0 when read.

**D7:** Time Save Enable bit controls the loading of real-timeclock data into the Time Save RAM. When a one is written to this bit the Time Save RAM will follow the corresponding clock registers, and when a zero is written to this bit the time in the Time Save RAM is frozen. This eliminates any synchronization problems when reading the clock, thus negating the need to check for a counter rollover during a read cycle.

This bit must be set to a one prior to power failing to enable the Time Save feature. When the power fails this bit is automatically reset and the time is saved in the Time Save RAM.

#### REAL TIME MODE REGISTER





**D0-D1:** These are the leap year counter bits. These bits are written to set the number of years from the previous leap year. The leap year counter increments on December 31st and it internally enables the February 29th counter state. This method of setting the leap year allows leap year to occur whenever the user wishes to, thus providing flexibility in implementing Japanese leap year function.

LY1	LY0	Leap Year Counter
0	· 0	Leap Year Current Year
0	1	Leap Year Last Year
1	0	Leap Year 2 Years Ago
1	1	Leap Year 3 Years Ago

**D2:** The count mode for the hours counter can be set to either 24 hour mode or 12 hour mode with AM/PM indicator. A one will place the clock in 12 hour mode.


D3: This bit is the master Start/Stop bit for the clock. When a one is written to this bit the real time counter's prescaler and counter chain are enabled. When this bit is reset to zero the contents of the real time counter is stopped. When the RTC is initially powered up this bit will be held at a logic 0 until the oscillator starts functioning correctly after which this bit may be modified. If an oscillator fail event occurs, this bit will be reset to logic 0.

D4: This bit controls the operation of the interrupt output in standby mode. If set to a one it allows Alarm, Periodic, and Power Fail interrupts to be functional in standby mode. Note that the MFO pin is configured as open drain in standby mode.

If bit D4 is set to a zero then bits D0–D5 of Interrupt Control Register 0 and bits D6 and D7 of Interrupt Control Register 1 will be reset when the RTC enters the standby mode. They will have to be re-configured when system ( $V_{CC}$ ) power is restored.

D5-D7: General purpose RAM bits.

#### **OUTPUT MODE REGISTER**




D0-D6: General purpose RAM bits.

**D7:** This bit is used to program the signal appearing at the MFO output, as follows:

D7	MFO Output Signal
0	Power Fail Interrupt
1	Buffered Crystal Oscillator

#### **INTERRUPT CONTROL REGISTER 0**




TL/F/9981-17

**D0-D5:** These bits are used to enable one of the selected periodic interrupts by writing a one into the appropriate bit. These interrupts are issued at the rollover of the clock. For example, the minutes interrupt will be issued whenever the minutes counter increments. In all likelihood the interrupt will be enabled asynchronously with the real time change. Therefore, the very first interrupt will occur in less than the periodic time chosen, but after the first interrupt all subsequent interrupts will be spaced correctly. These interrupts are useful when minute, second, real time reading, or task switching is required. When all six bits are written to a 0 this disables periodic interrupts from the Main Status Register and the interrupt pin. If battery backed mode is selected and the DP8573A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then these bits are controlled by D4 of the Real Time Mode Register.

D6 and D7: General purpose RAM.

#### **INTERRUPT CONTROL REGISTER 1**



**D0-D5:** Each of these bits are enable bits which will enable a comparison between an individual clock counter and its associated compare RAM. If any bit is a zero then that clock-RAM comparator is set to the "always equal" state and the associated TIME COMPARE RAM byte can be used as general purpose RAM. However, to ensure that an alarm interrupt is not generated at bit D3 of the Main Status Register, all bits must be written to a logic zero.

**D6:** In order to generate an external alarm compare interrupt to the  $\mu$ P from bit D3 of the Main Status Register, this bit must be written to a logic 1. If battery backed mode is selected and the DP8573A is in standby (V<sub>BB</sub> > V<sub>CC</sub>), then this bit is controlled by D4 of the Real Time Mode Register.

D7: The MSB of this register is the enable bit for the Power Fail Interrupt. When this bit is set to a one an interrupt will be generated to the  $\mu P$  when  $V_{BB} > V_{CC}$ . If battery backed mode is selected and the DP8573A is in standby ( $V_{BB} > V_{CC}$ ), then this bit is controlled by D4 of the Real Time Mode Register.

Contro					-		_	
D7	D6	D5	D4	D3	D2	D1	D0	1. Boost by
	Register PS = 2				5 0 0 1	-1	- 2	<ol> <li>Reset by writing</li> </ol>
R/W	R/W	R/W	R/W	R/W <sup>1</sup>	R/W <sup>1</sup>	R <sup>2</sup>	R <sup>3</sup>	1 to bit.
RAM	Register	BAM	BAM	Alarm	Periodic	Power Fail	Interrupt	2. Set/reset b
	Select			Interrupt	Interrupt	Interrupt	Status	voltage at
								PFAIL pin.
								3. Reset when
								all pending interrupts
								are remove
eriodic Flag	r <b>Register</b> PS =	= 0 RS =	= 0 Addr	ess = 03H				
R/W	R/W <sup>4</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	R <sup>5</sup>	4. Read Osc 1 Write 0 Bat
Test	Osc. Fail/	1 ms	10 ms	100 ms	Seconds	10 Second	Minute	Backed Mc
Mode	Single Supply	Flag	Flag	Flag	Flag	Flag	Flag	Write 1 Sin
								Supply Mo
								5. Reset by
ime Save Co	ontrol Register	PS = 0	RS = 0 Addr	ress = 04H				positive ed of read.
<b>ime Save Co</b> Time Save								of read.
	ntrol Register	PS = 0 RAM	RS = 0 Addr RAM	ress = 04H RAM	RAM	RAM	RAM	
Time Save Enable	N/A	RAM	RAM	RAM		RAM	RAM	of read.
Time Save Enable		RAM	RAM	RAM ddress = 01H				of read.
Time Save Enable	N/A	RAM	RAM RS = 1 A Interrupt EN	RAM ddress = 01H Clock	12/24 Hr.	Leap Year	Leap Year	]
Time Save Enable Ieal Time Mo	N/A ode Register PS	RAM S = 0 R	RAM	RAM ddress = 01H				of read.
Time Save Enable Real Time Mo RAM	N/A ode Register PS	RAM S = 0 R RAM	RAM RS = 1 A Interrupt EN on Back-Up	RAM ddress = 01H Clock	12/24 Hr.	Leap Year	Leap Year	of read.
Time Save Enable Ieal Time Mo RAM Dutput Mode	N/A ode Register PS RAM Register PS =	RAM S == 0 R RAM	RAM RS = 1 A Interrupt EN on Back-Up = 1 Addr	RAM ddress = 01H Clock Start/Stop ess = 02H	12/24 Hr. Mode	Leap Year MSB	Leap Year LSB	of read. All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM	N/A ode Register PS RAM	RAM S = 0 R RAM	RAM RS = 1 A Interrupt EN on Back-Up	RAM ddress = 01H Clock Start/Stop	12/24 Hr.	Leap Year	Leap Year	of read.
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal	N/A Dede Register PS RAM Register PS = RAM	RAM S = 0 R RAM = 0 RS = RAM	RAM IS = 1 A Interrupt EN on Back-Up = 1 Addr RAM	RAM ddress = 01H Clock Start/Stop ess = 02H RAM	12/24 Hr. Mode RAM	Leap Year MSB	Leap Year LSB	of read. All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal	N/A ode Register PS RAM Register PS =	RAM S = 0 R RAM = 0 RS = RAM	RAM RS = 1 A Interrupt EN on Back-Up = 1 Addr	RAM ddress = 01H Clock Start/Stop ess = 02H	12/24 Hr. Mode RAM	Leap Year MSB	Leap Year LSB	of read. All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal	N/A ode Register PS RAM Register PS = RAM htrol Register 0	RAM S = 0 R RAM 0 RS = RAM 0 PS = 0 1 ms	RAM IS = 1 A Interrupt EN on Back-Up = 1 Addr RAM RS = 1 10 ms	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms	12/24 Hr. Mode RAM 3H Seconds	Leap Year MSB RAM 10 Second	Leap Year LSB RAM Minute	of read. All Bits R/W All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal	N/A Dede Register PS RAM Register PS = RAM	RAM S = 0 R RAM 0 RS = RAM 0 PS = 0 1 ms Interrupt	RAM IS = 1 A Interrupt EN on Back-Up = 1 Addr RAM RS = 1 10 ms Interrupt	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms Interrupt	12/24 Hr. Mode RAM 3H Seconds Interrupt	Leap Year MSB RAM 10 Second Interrupt	Leap Year LSB RAM Minute Interrupt	of read. All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal nterrupt Cor	N/A ode Register PS RAM Register PS = RAM htrol Register 0	RAM S = 0 R RAM 0 RS = RAM 0 PS = 0 1 ms	RAM IS = 1 A Interrupt EN on Back-Up = 1 Addr RAM RS = 1 10 ms	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms	12/24 Hr. Mode RAM 3H Seconds	Leap Year MSB RAM 10 Second	Leap Year LSB RAM Minute	of read. All Bits R/W All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal Interrupt Cor RAM	N/A ode Register PS RAM Register PS = RAM htrol Register 0	RAM S = 0 R RAM 0 RS = RAM 0 PS = 0 1 ms Interrupt Enable	RAM IS = 1 A Interrupt EN on Back-Up = 1 Addr RAM RS = 1 10 ms Interrupt	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms Interrupt	12/24 Hr. Mode RAM 3H Seconds Interrupt Enable	Leap Year MSB RAM 10 Second Interrupt	Leap Year LSB RAM Minute Interrupt	of read. All Bits R/W All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal Interrupt Cor RAM	N/A Dete Register PS RAM Register PS = RAM htrol Register 0 RAM	RAM S = 0 R RAM 0 RS = RAM 0 PS = 0 1 ms Interrupt Enable	RAM RS = 1 A Interrupt EN on Back-Up = 1 Addr RAM RS = 1 10 ms Interrupt Enable	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms Interrupt Enable	12/24 Hr. Mode RAM 3H Seconds Interrupt Enable	Leap Year MSB RAM 10 Second Interrupt	Leap Year LSB RAM Minute Interrupt	of read. All Bits R/W All Bits R/W All Bits R/W
Time Save Enable Real Time Mo RAM Dutput Mode MFO as Crystal nterrupt Cor RAM	N/A Dede Register PS RAM Register PS = RAM htrol Register 0 RAM htrol Register 1	RAM S = 0 R RAM 0 RS = RAM 0 PS = 0 1 ms Interrupt Enable PS = 0	RAM Interrupt EN on Back-Up = 1 Addr RAM RS = 1 10 ms Interrupt Enable RS = 1	RAM ddress = 01H Clock Start/Stop ess = 02H RAM Address = 0 100 ms Interrupt Enable Address = 0	12/24 Hr. Mode RAM 3H Seconds Interrupt Enable 4H	Leap Year MSB RAM 10 Second Interrupt Enable	Leap Year LSB RAM Minute Interrupt Enable	of read. All Bits R/W All Bits R/W All Bits R/W

## **Application Hints**

## Suggested Initialization Procedure for DP8573A in Battery Backed Applications that use the $V_{BB}\,\text{Pin}$

- 1. Enter the test mode by writing a 1 to bit D7 in the Periodic Flag Register.
- 2. Write zero to the RAM/TEST mode Register located in page 0, address HEX 1F.
- 3. Leave the test mode by writing a 0 to bit D7 in the Periodic Flag Register. Steps 1, 2, 3 guarantee that if the test mode had been entered during power on (due to random pulses from the system), all test mode conditions are cleared. Most important is that the OSC Fail Disable bit is cleared. Refer to AN-589 for more information on test mode operation.
- 4. Enter a software loop that does the following: Set a 3 second(approx) software counter. The
  - Set a 3 second(approx) software counter. The crystal oscillator may take 1 second to start.

DP8573A

4.1 Write a 1 to bit D3 in the Real Time Mode Register (try to start the clock). Under normal operation, this bit can be set only if the oscillator is running. During the software loop, RAM, real time counters, output configuration, interrupt control and timer functions may be initialized.

## Application Hints (Continued)

5. Test bit D6 in the Periodic Flag Register:


IF a 1, go to 4.1. If this bit remains a 1 after 3 seconds, then abort and check hardware. The crystal may be defective or not installed. There may be a short at OSC IN or OSC OUT to  $V_{CC}$  or GND, or to some impedance that is less than 10  $M\Omega$ .

IF a 0, then the oscillator is running, go to step 7.


6. Write a 0 to bit D6 in the Periodic Flag Register. This action puts the clock chip in the battery backed mode. This mode can be entered only if the OSC fail flag (bit D6 of the Periodic Flag Register) is a 0. Reminder, bit D6 is a dual function bit. When read, D6 returns oscillator status. When written, D6 causes either the Battery Backed Mode, or the Single Supply Mode of operation.


The only method to ensure the chip is in the battery backed mode is to measure the waveform at the OSC OUT pin. If the battery backed mode was selected successfully, then the peak to peak waveform at OSC OUT is referenced to the battery voltage. If not in battery backed mode, the waveform is referenced to V<sub>CC</sub>. The measurement should be made with a high impedance low capacitance probe (10 MΩ, 10 pF oscilloscope probe or better). Typical peak to peak swings are within 0.6V of V<sub>CC</sub> and ground respectively.


- 7. Write a 1 to bit D7 of Interrupt Control Register 1. This action enables the PFAIL pin and associated circuitry.
- 8. Write a 1 to bit D4 of the Real Time Mode Register. This action ensures that bit D7 of Interrupt Control Register 1 remains a 1 when  $V_{BB} > V_{CC}$  (Standby Mode).
- 9. Initialize the rest of the chip as needed.



## **Typical Performance Characteristics**







TL/F/9981-21

2

DP8573A



## **National** Semiconductor

## MM58274C-12 Microprocessor Compatible Real Time Clock

## **General Description**

The MM58274C-12 is fabricated using low threshold metal gate CMOS technology and is designed to operate in bus oriented microprocessor systems where a real time clock and calendar function are required. The on-chip 32.768 kHz crystal controlled oscillator will maintain timekeeping down to 2.2V to allow low power standby battery operation. This device is pin compatible with the MM58174A but continues timekeeping up to tens of years.

## Applications

- Point of sale terminals
- Teller terminals
- Word processors
- Data logging
- Industrial process control


## **Block Diagram**

## **Features**

- Same pin-out as MM58174A, MM58274B, MM58274C, and MM58274
- Timekeeping from tenths of seconds to tens of years in independently accessible registers
- Leap year register
- 12 hour operation only
- Buffered crystal frequency output in test mode for easy oscillator setting
- Data-changed flag allows simple testing for time rollover
- Independent interrupting time with open drain output

TL/F/5602-1

- Fully TTL compatible
- Low power standby operation (10 µA at 2.2V)
- Low cost 16-pin DIP and 20-pin PCC



**FIGURE 1** 

2-86

## Absolute Maximum Ratings (Note 1)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

DC Input or Output Voltage	-0.3V to V <sub>DD</sub> + 0.3V
DC Input or Output Diode Current	±5.0 mA
Storage Temperature, T <sub>STG</sub>	-65°C to +150°C
Supply Voltage, V <sub>DD</sub>	6.5V
Power Dissipation, PD	500 mW
Lead Temperature	
(Soldering, 10 seconds)	260°

## **Operating Conditions**

Operating Condition	ns			MM58274
	Min	Max	Units	82
Operating Supply Voltage	4.5	5.5	v	74
Standby Mode Supply Voltage	2.2	5.5	v	<b>Q</b>
DC Input or Output Voltage	0	V <sub>DD</sub>	v	12
Operating Temperature Range	-40	85	°C	1.0

## Electrical Characteristics $V_{DD} = 5V \pm 10\%$ , T = $-40^{\circ}$ C to $+85^{\circ}$ C unless otherwise stated.

Symbol	Parameter	Conditions	Min	Тур	Max	Units	
VIH	High Level Input Voltage (except XTAL IN)		2.0			v	
VIL	Low Level Input Voltage (except XTAL IN)				0.8	V	
V <sub>OH</sub>	High Level Output Voltage (DB0–DB3)	I <sub>OH</sub> = −20 μA I <sub>OH</sub> = −1.6 mA	V <sub>DD</sub> - 0.1 3.7			v v	
V <sub>OH</sub>	High Level Output Voltage (INT)	l <sub>OH</sub> = −20 μA (In Test Mode)	V <sub>DD</sub> - 0.1			۷ <sub>.</sub>	
V <sub>OL</sub>	Low Level Output Voltage (DB0–DB3, INT)	$I_{OL} = 20 \ \mu A$ $i_{OL} = 1.6 \ m A$			0.1 0.4	v v	
IIL	Low Level Input Current (AD0-AD3, DB0-DB3)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-80	μΑ	
ι.	Low Level Input Current (WR, RD)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		- 190	μΑ	
ΙL	Low Level Input Current (CS)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-550	μA	
<sup>I</sup> оzн	Ouput High Level Leakage Current (INT)	$V_{OUT} = V_{DD}$			2.0	μΑ	
IDD	Average Supply Current	$\begin{array}{l} \mbox{All } V_{\rm IN} = V_{\rm CC} \mbox{ or Open Circuit} \\ V_{\rm DD} = 2.2 \mbox{V} \mbox{ (Standby Mode)} \\ V_{\rm DD} = 5.0 \mbox{V} \mbox{ (Active Mode)} \end{array}$		4	10 1	μA mA	
C <sub>IN</sub>	Input Capacitance			5	10	pF	
COUT	Output Capacitance	(Outputs Disabled)		10		pF	

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur. All voltages referenced to ground unless otherwise noted. Note 2: The DB0-DB3 and AD0-AD3 lines all have active P-channel pull-up transistors which will source current. The CS, RD, and WA lines have internal pull-up resistors to V<sub>DD</sub>.

. .

## **AC Switching Characteristics**

### READ TIMING: DATA FROM PERIPHERAL TO MICROPROCESSOR V\_{DD} = 5V $\pm 0.5$ V, C\_L = 100 pF

Symbol	Parameter		Units		
	r di diffetei	TA	85°C	Units	
		Min	Тур	Max	
t <sub>AD</sub>	Address Bus Valid to Data Valid		390	650	ns
tCSD	Chip Select On to Data Valid		140	300	ns
t <sub>RD</sub>	Read Strobe On to Data Valid		140	300	ns
t <sub>RW</sub>	Read Strobe Width (Note 3, Note 7)			DC	
t <sub>RA</sub>	Address Bus Hold Time from Trailing Edge of Read Strobe	0			ns
t <sub>CSH</sub>	Chip Select Hold Time from Trailing Edge of Read Strobe	0			ns
t <sub>RH</sub>	Data Hold Time from Trailing Edge of Read Strobe	70	160		ns
t <sub>HZ</sub>	Time from Trailing Edge of Read Strobe Until O/P Drivers are TRI-STATE®			250	ns

#### WRITE TIMING: DATA FROM MICROPROCESSOR TO PERIPHERAL $V_{DD}=\,5V\,\pm0.5V$

Symbol	Parameter		Units		
		TA	85°C		
		Min	Тур	Max	
t <sub>AW</sub>	Address Bus Valid to Write Strobe 🖌 (Note 4, Note 6)	400	125		ns
tcsw	Chip Select On to Write Strobe 🖌	250	100		' ns
t <sub>DW</sub>	Data Bus Valid to Write Strobe 🖌	400	220		ns
tww	Write Strobe Width (Note 6)	250	95		ns
twcs	Chip Select Hold Time Following Write Strobe	0			ns
twA	Address Bus Hold Time Following Write Strobe	0		· · · ·	ns
t <sub>WD</sub>	Data Bus Hold Time Following Write Strobe 🖌	100	35		ns
t <sub>AWS</sub>	Address Bus Valid Before Start of Write Strobe	70	20		ns

Note 3: Except for special case restriction: with interrupts programmed, max read strobe width of control register (ADDR 0) is 30 ms. See section on Interrupt Programming.


Note 4: All timings measured to the trailing edge of write strobe (data latched by the trailing edge of WR).

Note 5: Input test waveform peak voltages are 2.4V and 0.4V. Output signals are measured to their 2.4V and 0.4V levels.

Note 6: Write strobe as used in the Write Timing Table is defined as the period when both chip select and write inputs are low, ie.,  $\overline{WS}$ ,  $=\overline{CS} + \overline{WR}$ . Hence write strobe commences when both signals are low, and terminates when the first signal returns high.

Note 7: Read strobe as used in the Read Timing Table is defined as the period when both chip select and read inputs are low, ie.,  $\overline{RS} = \overline{CS} + \overline{RD}$ .

Note 8: Typical numbers are at V\_{CC} = 5.0V and T\_A = 25°C.



2-89

2

## **Functional Description**

The MM58274C-12 is a bus oriented microprocessor real time clock. It has the same pin-out as the MM58174A while offering extended timekeeping up to units and tens of years. To enhance the device further, a number of other features have been added including: 12 hour counting, a testable data-changed flag giving easy error-free time reading and simplified interrupt control.

A buffered oscillator signal appears on the interrupt output when the device is in test mode. This allows for easy oscillator setting when the device is initially powered up in a system.

The counters are arranged as 4-bit words and can be randomly accessed for time reading and setting. The counters output in BCD (binary coded decimal) 4-bit numbers. Any register which has less than 4 bits (e.g., days of week uses only 3 bits) will return a logic 0 on any unused bits. When written to, the unused inputs will be ignored.

Writing a logic 1 to the clock start/stop control bit resets the internal oscillator divider chain and the tenths of seconds counter. Writing a logic 0 will start the clock timing from the nearest second. The time then updates every 100 ms with all counters changing synchronously. Time changing during a read is detected by testing the data-changed bit of the control register after completing a string of clock register reads.

Interrupt delay times of 0.1s, 0.5s, 1s, 5s, 10s, 30s or 60s can be selected with single or repeated interrupt outputs. The open drain output is pulled low whenever the interrupt timer times out and is cleared by reading the control register.

#### **CIRCUIT DESCRIPTION**

The block diagram in *Figure 1* shows the internal structure of the chip. The 16-pin package outline is shown in *Figure 2*.

#### **Crystal Oscillator**


This consists of a CMOS inverter/amplifier with an on-chip bias resistor. Externally a 20 pF capacitor, a 6 pF-36 pF trimmer capacitor and a crystal are suggested to complete the 32.768 kHz timekeeping oscillator circuit.

The 6 pF-36 pF trimmer fine tunes the crystal load impedance, optimizing the oscillator stability. When properly adjusted (i.e., to the crystal frequency of 32.768 kHz), the circuit will display a frequency variation with voltage of less than 3 ppm/V. When an external oscillator is used, connect to oscillator input and float (no connection) the oscillator output.

When the chip is enabled into test mode, the oscillator is gated onto the interrupt output pin giving a buffered oscillator output that can be used to set the crystal frequency when the device is installed in a system. For further information see the section on Test Mode.

#### Divider Chain

The crystal oscillator is divided down in three stages to produce a 10 Hz frequency setting pulse. The first stage is a non-integer divider which reduces the 32.768 kHz input to 30.720 kHz. This is further divided by a 9-stage binary ripple counter giving an output frequency of 60 Hz. A 3-stage Johnson counter divides this by six, generating a 10 Hz output. The 10 Hz clock is gated with the 32.768 kHz crystal frequency to provide clock setting pulses of 15.26  $\mu$ s duration. The setting pulse drives all the time registers on the



device which are synchronously clocked by this signal. All time data and data-changed flag change on the falling edge of the clock setting pulse.

#### **Data-Changed Flag**

The data-changed flag is set by the clock setting pulse to indicate that the time data has been altered since the clock was last read. This flag occupies bit 3 of the control register where it can be tested by the processor to sense data-changed. It will be reset by a read of the control register. See the section, "Methods of Device Operation", for sug-gested clock reading techniques using this flag.

#### Seconds Counters

There are three counters for seconds:

- a) tenths of seconds
- b) units of seconds
- c) tens of seconds.

The registers are accessed at the addresses shown in Table I. The tenths of seconds register is reset to 0 when the clock start/stop bit (bit 2 of the control register) is set to logic 1. The units and tens of seconds are set up by the processor, giving time setting to the nearest second. All three registers can be read by the processor for time output.

#### **Minutes Counters**

There are two minutes counters:

- a) units of minutes
- b) tens of minutes.

Both registers may be read to or written from as required.

#### **Hours Counters**

There are two hours counters:

- a) units of hours
- b) tens of hours.

Both counters may be accessed for read or write operation	S
as desired.	

The tens of hours register has only one active bit and the top three bits are set to logic 0. Data bit 1 of the clock setting register is the AM/PM indicator; logic 0 indicating AM, logic 1 for PM.

Bit 0 of the clock setting register must be written to 0 for correct 12 hour operation.

#### **Days Counters**

There are two days counters:

a) units of days

b) tens of days.

The days counters will count up to 28, 29, 30 or 31 depending on the state of the months counters and the leap year counter. The microprocessor has full read/write access to these registers.

#### **Months Counters**

There are two months counters:

a) units of months

b) tens of months.

Both these counters have full read/write access.

#### Years Counters

There are two years counters:

a) units of years

b) tens of years.

Both these counters have full read/write access. The years will count up to 99 and roll over to 00.

Register Selected		Address	(Binary)	(Hex)	Access	
	AD3	AD2	AD2 AD1			
0 Control Register	0	0	0	. 0	.0	Split Read and Write
1 Tenths of Seconds	0	0	0	1	1 .	Read Only
2 Units Seconds	0	0	1	0	2	R/W
3 Tens Seconds	0	0	1	1	3	<sup>·</sup> R/W
4 Units Minutes	0	1 🕹	0	0	4	R/W
5 Tens Minutes	0	1	0	1	5	R/W
6 Unit Hours	0	1	1	0	6 .	R/W
7 Tens Hours	0	1	1	1	7	R/W
8 Units Days	1	0	0	0	8	R/W
9 Tens Days	1	0	0	1	9	R/W
0 Units Months	1	0	.1	0	Α	R/W
1 Tens Months	1	0	1	1	В	R/W
2 Units Years	1	1	0	0	С	R/W
3 Tens Years	1	1	0	1	D	R/W
4 Day of Week	1	1	1	· 0	E	R/W
5 Clock Setting/	1	1	1	1	F	R/W
Interrupt Registers		1				

#### TABLE I. Address Decoding of Real-Time Clock Internal Registers

2-91

2

#### Day of Week Counter

The day of week counter increments as the time rolls from (11:59 PM to 12:00 AM). It counts from 1 to 7 and rolls back to 1. Any day of the week may be specified as day 1.

#### Clock Setting Register/Interrupt Register

The interrupt select bit in the control register determines which of these two registers is accessible to the processor at address 15. Normal clock and interrupt timing operations will always continue regardless of which register is selected onto the bus. The layout of these registers is shown in Table II.

The clock setting register is comprised of three separate functions:

- a) leap year counter: bits 2 and 3
- b) AM/PM indicator: bit 1
- c) 12-hour mode set: bit 0 (see Table IIA).

The leap year counter is a 2-stage binary counter which is clocked by the months counter. It changes state as the time rolls over from 11:59 on December 31 to 00:00 on January 1.

The counter should be loaded with the 'number of years since last leap year' e.g., if 1980 was the last leap year, a clock programmed in 1983 should have 3 stored in the leap year counter. If the clock is programmed during a leap year, then the leap year counter should be set to 0. The contents of the leap year counter can be read by the  $\mu$ P.

The AM/PM indicator returns a logic 0 for AM and a logic 1 for PM. It is clocked when the hours counter rolls from 11:59 to 12:00.

The 12-hour mode bit is set to logic 0 for 12-hour mode, logic 1 is illegal.

**IMPORTANT NOTE:** Hours mode and AM/PM bits cannot be set in the same write operation. See the section on Initialization (Methods of Device Operation) for a suggested setting routine.

All bits in the clock setting register may be read by the processor.

The interrupt register controls the operation of the timer for interrupt output. The processor programs this register for single or repeated interrupts at the selected time intervals.

The lower three bits of this register set the time delay period that will occur between interrupts. The time delays that can be programmed and the data words that select these are outlined in Table IIB.

Data bit 3 of the interrupt register sets for either single or repeated interrupts; logic 0 gives single mode, logic 1 sets for repeated mode.

Using the interrupt is described in the Device Operation section.

#### **TABLE IIA. Clock Setting Register Layout**

Function		Data Bi	ts Used	Comments	Access	
T unction	DB3			Comments	ACCESS	
Leap Year Counter	х	Х			0 Indicates a Leap Year	R/W
AM/PM Indicator			x		0 = AM 1 = PM	R/W
12-Hour Bit				x	0 = 12-Hour Mode	R/W
					1 = Illegal	

#### **TABLE IIB. Interrupt Control Register**

Function	Comments	Control Word					
	Commenta	DB3	DB2	DB1	DBO		
No Interrupt	Interrupt output cleared, start/stop bit set to 1.	x	0	0	0		
0.1 Second		0/1	0	0	1		
0.5 Second		0/1	0	1	0		
1 Second		0/1	0	1 -	- 1		
5 Seconds	DB3 = 0 for single interrupt	0/1	1	0	0		
10 Seconds	DB3 = 1 for repeated interrupt	0/1	1 .	0	1		
30 Seconds		0/1	1	1	0		
60 Seconds		0/1	1 1	1	1		

Timing Accuracy: single interrupt mode (all time delays):  $\pm 1$  ms Repeated Mode:  $\pm 1$  ms on initial timeout, thereafter synchronous with first interrupt (i.e., timing errors do not accumulate).

#### **Control Register**

There are three registers which control different operations of the clock:

- a) the clock setting register
- b) the interrupt register
- c) the control register.

The clock setting and interrupt registers both reside at address 15, access to one or the other being controlled by the interrupt select bit; data bit 1 of the control register.

The clock setting register programs the timekeeping of the clock. The 12-hour mode and the AM/PM indicator occupy bits 0 and 1, respectively. Data bits 2 and 3 set the leap year counter.

The interrupt register controls the operation of the interrupt timer, selecting the required delay period and either single or repeated interrupt.

The control register is responsible for controlling the operations of the clock and supplying status information to the processor. It appears as two different registers; one with write only access and one with read only access.

The write only register consists of a bank of four latches which control the internal processes of the clock.

The read only register contains two output data latches which will supply status information for the processor. Table III shows the mapping of the various control latches and status flags in the control register. The control register is located at address 0.

The write only portion of the control register contains four latches:

A logic 1 written into the test bit puts the device into test mode. This allows setting of the oscillator frequency as well as rapid testing of the device registers, if required. A more complete description is given in the Test Mode section. For normal operation the test bit is loaded with logic 0.

The clock start/stop bit stops the timekeeping of the clock and resets to 0 the tenths of seconds counter. The time of day may then be written into the various clock registers and the clock restarted synchronously with an external time source. Timekeeping is maintained thereafter.

A logic 1 written to the start/stop bit halts clock timing. Timing is restarted when the start/stop bit is written with a logic 0.

The interrupt select bit determines which of the two registers mapped onto address 15 will be accessed when this address is selected. A logic 0 in the interrupt select bit makes the clock setting register available to the processor. A logic 1 selects the interrupt register.

The interrupt start/stop bit controls the running of the interrupt timer. It is programmed in the same way as the clock start/stop bit; logic 1 to halt the interrupt and reset the timer, logic 0 to start interrupt timing.

When no interrupt is programmed (interrupt control register set to 0), the interrupt start/stop bit is automatically set to a logic 1. When any new interrupt is subsequently programmed, timing will not commence until the start/stop bit is loaded with 0.

In the single interrupt mode, interrupt timing stops when a timeout occurs. The processor restarts timing by writing logic 0 into the start/stop bit.

In repeated interrupt mode the interrupt timer continues to count with no intervention by the processor necessary.

Interrupt timing may be stopped in either mode by writing a logic 1 into the interrupt start/stop bit. The timer is reset and can be restarted in the normal way, giving a full time delay period before the next interrupt.

In general, the control register is set up such that writing 0's into it will start anything that is stopped, pull the clock out of test mode and select the clock setting register onto the bus. In other words, writing 0 will maintain normal clock operation and restart interrupt timing, etc.

The read only portion of the control register has two status outputs:

Since the MM58274C-12 keeps real time, the time data changes asynchronously with the processor and this may occur while the processor is reading time data out of the clock.

Some method of warning the processor when the time data has changed must thus be included. This is provided for by the data-changed flag located in bit 3 of the control register. This flag is set by the clock setting pulse which also clocks the time registers. Testing this bit can tell the processor whether or not the time has changed. The flag is cleared by a read of the control register but not by any write operations. No other register read has any effect on the state of the data-changed flag.

Data bit 0 is the interrupt flag. This flag is set whenever the interrupt timer times out, pulling the interrupt output low. In a polled interrupt routine the processor can test this flag to determine if the MM58274C-12 was the interrupting device. This interrupt flag and the interrupt output are both cleared by a read of the control register.

Access (addr0)	DB3	DB2	DB1	DB0
Read From:	Data-Changed Flag	0	0	Interrupt Flag
Write To:	Test 0 = Normal 1 = Test Mode	Clock Start/Stop 0 = Clock Run 1 = Clock Stop	Interrupt Select 0 = Clock Setting Register 1 = Interrupt Register	Interrupt Start/Stop 0 = Interrupt Run 1 = Interrupt Stop

#### TABLE III. The Control Register Layout

Both of the flags and the interrupt output are reset by the trailing edge of the read strobe. The flag information is held latched during a control register read, guaranteeing that stable status information will always be read out by the processor.

Interrupt timeout is detected and stored internally if it occurs during a read of the control register, the interrupt output will then go low only after the read has been completed.

A clock setting pulse occurring during a control register read will *not* affect the data-changed flag since time data read out before or after the control read will not be affected by the time change.

#### METHODS OF DEVICE OPERATION

#### **Test Mode**

National Semiconductor uses test mode for functionally testing the MM58274C-12 after fabrication and again after packaging. Test mode can also be used to set up the oscillator frequency when the part is first commissioned.

Figure 4 shows the internal clock connections when the device is written into test mode. The 32.768 kHz oscillator is gated onto the interrupt output to provide a buffered output for initial frequency setting. This signal is driven from a TRI-STATE output buffer, enabling easy oscillator setting in systems where interrupt is not normally used and there is no external resistor on the pin.

If an interrupt is programmed, the 32.768 kHz output is switched off to allow high speed testing of the interrupt timer. The interrupt output will then function as normal.

The clock start/stop bit can be used to control the fast clocking of the time registers as shown in *Figure 4*.

#### Initialization

When it is first installed and power is applied, the device will need to be properly initialized. The following operation steps are recommended when the device is set up (all numbers are decimal): 1) Disable interrupt on the processor to allow oscillator setting. Write  $15_{10}$  into the control register: *The clock and interrupt start/stop bits are set to 1, ensuring that the clock and interrupt timers are both halted. Test mode and the interrupt register are selected.* 

2) Write 0 to the interrupt register: Ensure that there are no interrupts programmed and that the oscillator will be gated onto the interrupt output.

3) Set oscillator frequency: All timing has been halted and the oscillator is buffered out onto the interrupt line.

4) Write 5 to the control register. The clock is now out of test mode but is still halted. The clock setting register is now selected by the interrupt select bit.

5) Write 0001 to all registers. This ensures starting with a valid BCD value in each register.

6) Set 12-hour mode: *Write 0 to data bit 0 of the clock setting register.* 

7) Load Real-Time Registers: All time registers (including Leap Years and AM/PM bit) may now be loaded in any order. Note that when writing to the clock setting register to set up Leap Years and AM/PM, the Hours Mode bit must not be altered from the value programmed in step 5.

8) Write 0 to the control register: This operation finishes the clock initialization by starting the time. The final control register write should be synchronized with an external time source.

In general, timekeeping should be halted before the time data is altered in the clock. The data can, however, be altered at any time if so desired. Such may be the case if the user wishes to keep the clock corrected without having to stop and restart it; i.e., winter/summer time changing can be accomplished without halting the clock. This can be done in software by sensing the state of the data-changed flag and only altering time data just after the time has rolled over (data-changed flag set).




FIGURE 4. Test Mode Organization

TL/F/5602-6

#### Reading the Time Registers

Using the data-changed flag technique supports microprocessors with block move facilities, as all the necessary time data may be read sequentially and then tested for validity as shown below.

1) Read the control register, address 0: This is a dummy read to reset the data-changed flag (DCF) prior to reading the time registers.

2) Read time registers: All desired time registers are read out in a block.

3) Read the control register and test DCF: *If DCF is cleared* (*logic 0*), *then no clock setting pulses have after occurred since step 1. All time data is guaranteed good and time reading is complete.* 

If DCF is set (logic 1), then a time change has occurred since step 1 and time data may not be consistent. Repeat steps 2 and 3 until DCF is clear. The control read of step 3 will have reset DCF, automatically repeating the step 1 action.

#### Interrupt Programming

The interrupt timer generates interrupts at time intervals which are programmed into the interrupt register. A single interrupt after delay or repeated interrupts may be programmed. Table IIB lists the different time delays and the data words that select them in the interrupt register.

Once the interrupt register has been used to set up the delay time and to select for single or repeat, it takes no further part in the workings of the interrupt system. All activity by the processor then takes place in the control register. Initializing:

1) Write 3 to the control register (AD0): Clock timing continues, interrupt register selected and interrupt timing stopped.

2) Write interrupt control word to address 15: *The interrupt register is loaded with the correct word (chosen from Table IIB) for the time delay required and for single or repeated interrupts.* 

3) Write 0 or 2 to the control register: *Interrupt timing commences. Writing 0 selects the clock setting register onto the data bus; writing 2 leaves the interrupt register selected. Normal timekeeping remains unaffected.* 

On Interrupt:

Read the control register and test for Interrupt Flag (bit 0). If the flag is cleared (logic 0), then the device is not the source of the interrupt.

If the flag is set (logic 1), then the clock did generate an interrupt. The flag is reset and the interrupt output is cleared by the control register read that was used to test for interrupt.

Single Interrupt Mode:

When appropriate, write 0 or 2 to the control register to restart the interrupt timer.

Repeated Interrupt Mode:

Timing continues, synchronized with the control register write which originally started interrupt timing. No further intervention is necessary from the processor to maintain timing.

In either mode interrupt timing can be stopped by writing 1 into the control register (interrupt start/stop set to 1). Timing for the full delay period recommences when the interrupt start/stop bit is again loaded with 0 as normal.

**IMPORTANT NOTE:** Using the interrupt timer places a constraint on the maximum Read Strobe width which may be applied to the clock. Normally all registers may be read from with a t<sub>RW</sub> down to DC (i.e., CS and RD held continuously low). When the interrupt timer is active however, the maximum read strobe width that can be applied to the control register (Addr 0) is 30 ms.

This restriction is to allow the interrupt timer to properly reset when it times out. Note that it only affects reading of the control register—all other addresses in the clock may be accessed with DC read strobes, regardless of the state of the interrupt timer. Writes to any address are unaffected.


#### NOTES ON AC TIMING REQUIREMENTS

Although the Switching Time Waveforms show Microbus control signals used for clock access, this does not preclude the use of the MM58274C-12 in other non-Microbus systems. *Figure 5* is a simplified logic diagram showing how the control signals are gated internally to control access to the clock registers. From this diagram it is clear that  $\overline{\text{CS}}$  could be used to generate the internal data transfer strobes, with  $\overline{\text{RD}}$  and  $\overline{\text{WR}}$  inputs set up first. This situation is illustrated in *Figure 6*.


The internal data busses of the MM58274C-12 are fully CMOS, contributing to the flexibility of the control inputs. When determining the suitability of any given control signal pattern for the MM58274C-12 the timing specifications in AC Switching Characteristics should be examined. As long as these timings are met (or exceeded) the MM58274C-12 will function correctly.

When the MM58274C-12 is connected to the system via a peripheral port, the freedom from timing constraints allows for very simple control signal generation, as in *Figure 7*. For reading (*Figure 7a*), Address,  $\overline{CS}$  and  $\overline{RD}$  may be activated simultaneously and the data will be available at the port after t<sub>AD</sub>-max (650 ns). For writing (*Figure 7b*), the address and data may be applied simultaneously; 70 ns later  $\overline{CS}$  and  $\overline{WR}$  may be strobed together.

MM58274C-12








TL/F/5602-7

FIGURE 6. Valid MM58274C-12 Control Signals Using Chip Select Generated Access Strobes



## APPLICATION HINTS

#### Time Reading Using Interrupt

In systems such as point of sale terminals and data loggers, time reading is usually only required on a random demand basis. Using the data-changed flag as outlined in the section on methods of operation is ideal for this type of system. Some systems, however, need to sense a change in real time; e.g., industrial timers/process controllers, TV/VCR clocks, any system where real time is displayed.

The interrupt timer on the MM58274C-12 can generate interrupts synchronously with the time registers changing, using software to provide the initial synchronization.

In single interrupt mode the processor is responsible for initiating each timing cycle and the timed period is accurate to  $\pm 1$  ms.

In repeated interrupt mode the period from the initial processor start to the first timeout is also only accurate to  $\pm 1$  ms. The following interrupts maintain accurate delay periods relative to the first timeout. Thus, to utilize interrupt to control time reading, we will use repeated interrupt mode.

In repeated mode the time period between interrupts is exact, which means that timeouts will always occur at the same point relative to the internal clock setting pulses. The case for 0.1s interrupts is shown in *Figure A-1*. The same is true for other delay periods, only there will be more clock setting pulses between each interrupt timeout. If we set up the interrupt timer so that interrupt always times out just after the clock setting pulse occurs (*Figure A-2*), then there is no need to test the data-changed flag as we know that the time data has just changed and will not alter again for another 100 ms.

This can be achieved as outlined below:

1) Follow steps 1 and 2 of the section on interrupt programming. In step 2 set up for repeated interrupt. 2) Read control register AD0: *This is a dummy read to reset the data-changed flag.* 

Read control register AD0 until data-changed flag is set.
 Write 0 or 2 to control register. Interrupt timing commences.

#### Time Reading with Very Slow Read Cycles

If a system takes longer than 100 ms to complete reading of all the necessary time registers (e.g., when CMOS processors are used) or where high level interpreted language routines are used, then the data-changed flag will always be set when tested and is of no value. In this case, the time registers themselves must be tested to ensure data accuracy.

The technique below will detect both time changing *between* read strobes (i.e., between reading tens of minutes and units of hours) and also time changing *during* read, which can produce invalid data.

1) Read and store the value of the *lowest* order time register required.

2) Read out all the time registers required. The registers may be read out in any order, simplifying software requirements.

3) Read the lowest order register and compare it with the value stored previously in step 1. If it is still the same, then all time data is good. If it has changed, then store the new value and go back to step 2.

In general, the rule is that the first and last reads *must* both be of the lowest order time register. These two values can then be compared to ensure that no change has occurred. This technique works because for any higher order time register to change, all the lower order registers must also change. If the lowest order register does not change, then no higher order register has changed either.




FIGURE A-2. Interrupt Timer Synchronized with Clock Setting Pulses



## MM58274C **Microprocessor Compatible Real Time Clock**

## **General Description**

The MM58274C is fabricated using low threshold metal gate CMOS technology and is designed to operate in bus oriented microprocessor systems where a real time clock and calendar function are required. The on-chip 32.768 kHz crystal controlled oscillator will maintain timekeeping down to 2.2V to allow low power standby battery operation. This device is pin compatible with the MM58174A but continues timekeeping up to tens of years. The MM58274C is a direct replacement for the MM58274 offering improved Bus access cycle times.

## Applications

- Point of sale terminals
- Teller terminals
- Word processors
- Data logging
- Industrial process control

## **Block Diagram**

## Features

■ Same pin-out as MM58174A, MM58274B, and MM58274

MM58274C

- Timekeeping from tenths of seconds to tens of years in independently accessible registers
- Leap vear register
- Hours counter programmable for 12 or 24-hour operation
- Buffered crystal frequency output in test mode for easy oscillator setting
- Data-changed flag allows simple testing for time rollover
- Independent interrupting time with open drain output
- Fully TTL compatible
- Low power standby operation (10 µA at 2.2V)
- Low cost 16-pin DIP and 20-pin PCC




FIGURE 1

TL/F/11219-1

## Absolute Maximum Ratings (Note 1)

If Milltary/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

DC Input or Output Voltage	-0.3V to V <sub>DD</sub> + 0.3V
DC Input or Output Diode Current	± 5.0 mA
Storage Temperature, T <sub>STG</sub>	-65°C to +150°C
Supply Voltage, V <sub>DD</sub>	6.5V
Power Dissipation, PD	500 mW
Lead Temperature	
(Soldering, 10 seconds)	260°

## **Operating Conditions**

	Min	Max	Units
Operating Supply Voltage	4.5	5.5	V
Standby Mode Supply Voltage	2.2	5.5	V
DC Input or Output Voltage	0	$V_{DD}$	V
Operating Temperature Range	-40	85	°C

## **Electrical Characteristics** $V_{DD} = 5V \pm 10\%$ , T = $-40^{\circ}$ C to $+85^{\circ}$ C unless otherwise stated.

Symbol	Parameter	Conditions	Min	Тур	Max	Units
VIH	High Level Input Voltage (except XTAL IN)		2.0	1. 		V
V <sub>IL</sub>	Low Level Input Voltage (except XTAL IN)				0.8	۷
VOH	High Level Output Voltage (DB0–DB3)	I <sub>OH</sub> = −20 μA I <sub>OH</sub> = −1.6 mA	V <sub>DD</sub> — 0.1 3.7			v v
V <sub>OH</sub>	High Level Output Voltage (INT)	I <sub>OH</sub> = −20 μA (In Test Mode)	V <sub>DD</sub> - 0.1			V
VOL	Low Level Output Voltage (DB0–DB3, INT)	$I_{OL} = 20 \ \mu A$ $i_{OL} = 1.6 \ m A$			0.1 0.4	v v
Ι <sub>ΙL</sub>	Low Level Input Current (AD0-AD3, DB0-DB3)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-80	μΑ
I <sub>IL</sub>	Low Level Input Current (WR, RD)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-190	μΑ
Ι <sub>ΙL</sub>	Low Level Input Current (CS)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-550	μA
Іогн	Ouput High Level Leakage Current (INT)	V <sub>OUT</sub> = V <sub>DD</sub>	-		2.0	μΑ
I <sub>DD</sub>	Average Supply Current	$\begin{array}{l} \mbox{All } V_{\rm IN} = V_{\rm CC} \mbox{ or Open Circuit} \\ V_{\rm DD} = 2.2 V \mbox{ (Standby Mode)} \\ V_{\rm DD} = 5.0 V \mbox{ (Active Mode)} \end{array}$		4	10 1	μA mA
C <sub>IN</sub>	Input Capacitance			5	10	pF
COUT	Output Capacitance	(Outputs Disabled)		10		pF

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur. All voltages referenced to ground unless otherwise noted. Note 2: The DB0-DB3 and AD0-AD3 lines all have active P-channel pull-up transistors which will source current. The CS, RD, and WR lines have internal pull-up resistors to V<sub>DD</sub>.

5
Z
1
Si Si
2
2
*
- C J

## AC Switching Characteristics

READ TIMING: DATA FROM PERIPHERAL TO MICROPROCESSOR V\_{DD} = 5V  $\pm 0.5$ V, C\_L = 100 pF

Symbol	Parameter		Units		
	rarameter	TA	= -40°C to +	85°C	
		Min	Тур	Max	
t <sub>AD</sub>	Address Bus Valid to Data Valid		390	650	ns
t <sub>CSD</sub>	Chip Select On to Data Valid		140	300	ns
t <sub>RD</sub>	Read Strobe On to Data Valid		140	300	ns
t <sub>RW</sub>	Read Strobe Width (Note 3, Note 7)			DC	
t <sub>RA</sub>	Address Bus Hold Time from Trailing Edge of Read Strobe	0			ns
t <sub>CSH</sub>	Chip Select Hold Time from Trailing Edge of Read Strobe	0			ns
t <sub>RH</sub>	Data Hold Time from Trailing Edge of Read Strobe	70	160		ns
tHZ	Time from Trailing Edge of Read Strobe Until O/P Drivers are TRI-STATE®			250	ns

#### WRITE TIMING: DATA FROM MICROPROCESSOR TO PERIPHERAL $V_{DD}=\,5V\,\pm0.5V$

Symbol	Parameter	Commercial Specification $T_A = -40^{\circ}C \text{ to } +85^{\circ}C$			- Units	
Symbol	i urumeter			85°C	51110	
	_	Min	Тур	Max	]	
t <sub>AW</sub>	Address Bus Valid to Write Strobe 🖌 (Note 4, Note 6)	400	125		ns	
tcsw	Chip Select On to Write Strobe 🖌	250	100		ns	
t <sub>DW</sub>	Data Bus Valid to Write Strobe 🦨	400	220		ns	
tww	Write Strobe Width (Note 6)	250	95		ns	
twcs	Chip Select Hold Time Following Write Strobe	0			ns	
t <sub>WA</sub>	Address Bus Hold Time Following Write Strobe	0			ns	
twD	Data Bus Hold Time Following Write Strobe 🖌	100	35		ns	
taws	Address Bus Valid Before Start of Write Strobe	70	20		ns	

Note 3: Except for special case restriction: with interrupts programmed, max read strobe width of control register (ADDR 0) is 30 ms. See section on Interrupt Programming.


Note 4: All timings measured to the trailing edge of write strobe (data latched by the trailing edge of  $\overline{WR}$ ).

Note 5: Input test waveform peak voltages are 2.4V and 0.4V. Output signals are measured to their 2.4V and 0.4V levels.

Note 6: Write strobe as used in the Write Timing Table is defined as the period when both chip select and write inputs are low, ie.,  $\overline{WS}$ , =  $\overline{CS}$  +  $\overline{WR}$ . Hence write strobe commences when both signals are low, and terminates when the first signal returns high.

Note 7: Read strobe as used in the Read Timing Table is defined as the period when both chip select and read inputs are low, ie.,  $\overline{RS} = \overline{CS} + \overline{RD}$ .

Note 8: Typical numbers are at  $V_{CC} = 5.0V$  and  $T_A = 25^{\circ}C$ .



MM58274C

**Switching Time Waveforms** 

#### FIGURE 2

Order Number MM58274CJ, MM58274CN or MM58274CV See NS Package J16A, N16A, or V20A

## **Functional Description**

The MM58274C is a bus oriented microprocessor real time clock. It has the same pin-out as the MM58174A while offering extended timekeeping up to units and tens of years. To enhance the device further, a number of other features have been added including: 12 or 24 hours counting, a testable data-changed flag giving easy error-free time reading and simplified interrupt control.

A buffered oscillator signal appears on the interrupt output when the device is in test mode. This allows for easy oscillator setting when the device is initially powered up in a system.

The counters are arranged as 4-bit words and can be randomly accessed for time reading and setting. The counters output in BCD (binary coded decimal) 4-bit numbers. Any register which has less than 4 bits (e.g., days of week uses only 3 bits) will return a logic 0 on any unused bits. When written to, the unused inputs will be ignored.

Writing a logic 1 to the clock start/stop control bit resets the internal oscillator divider chain and the tenths of seconds counter. Writing a logic 0 will start the clock timing from the nearest second. The time then updates every 100 ms with all counters changing synchronously. Time changing during a read is detected by testing the data-changed bit of the control register after completing a string of clock register reads.

Interrupt delay times of 0.1s, 0.5s, 1s, 5s, 10s, 30s or 60s can be selected with single or repeated interrupt outputs. The open drain output is pulled low whenever the interrupt timer times out and is cleared by reading the control register.

#### CIRCUIT DESCRIPTION

The block diagram in *Figure 1* shows the internal structure of the chip. The 16-pin package outline is shown in *Figure 2*.

#### **Crystal Oscillator**


This consists of a CMOS inverter/amplifier with an on-chip bias resistor. Externally a 20 pF capacitor, a 6 pF-36 pF trimmer capacitor and a crystal are suggested to complete the 32.768 kHz timekeeping oscillator circuit.

The 6 pF-36 pF trimmer fine tunes the crystal load impedance, optimizing the oscillator stability. When properly adjusted (i.e., to the crystal frequency of 32.768 kHz), the circuit will display a frequency variation with voltage of less than 3 ppm/V. When an external oscillator is used, connect to oscillator input and float (no connection) the oscillator output.

When the chip is enabled into test mode, the oscillator is gated onto the interrupt output pin giving a buffered oscillator output that can be used to set the crystal frequency when the device is installed in a system. For further information see the section on Test Mode.

#### **Divider** Chain

The crystal oscillator is divided down in three stages to produce a 10 Hz frequency setting pulse. The first stage is a non-integer divider which reduces the 32.768 kHz input to 30.720 kHz. This is further divided by a 9-stage binary ripple counter giving an output frequency of 60 Hz. A 3-stage Johnson counter divides this by six, generating a 10 Hz output. The 10 Hz clock is gated with the 32.768 kHz crystal frequency to provide clock setting pulses of 15.26  $\mu$ s duration. The setting pulse drives all the time registers on the



device which are synchronously clocked by this signal. All time data and data-changed flag change on the falling edge of the clock setting pulse.

#### Data-Changed Flag

The data-changed flag is set by the clock setting pulse to indicate that the time data has been altered since the clock was last read. This flag occupies bit 3 of the control register where it can be tested by the processor to sense data-changed. It will be reset by a read of the control register. See the section, "Methods of Device Operation", for suggested clock reading techniques using this flag.

#### Seconds Counters

There are three counters for seconds:

- a) tenths of seconds
- b) units of seconds
- c) tens of seconds.

The registers are accessed at the addresses shown in Table I. The tenths of seconds register is reset to 0 when the clock start/stop bit (bit 2 of the control register) is set to logic 1. The units and tens of seconds are set up by the processor, giving time setting to the nearest second. All three registers can be read by the processor for time output.

#### **Minutes Counters**

There are two minutes counters:

- a) units of minutes
- b) tens of minutes.

Both registers may be read to or written from as required.

#### **Hours Counters**

There are two hours counters:

- a) units of hours
- b) tens of hours.

Both counters may be accessed for read or write operations as desired.

In 12-hour mode, the tens of hours register has only one active bit and the top three bits are set to logic 0. Data bit 1 of the clock setting register is the AM/PM indicator; logic 0 indicating AM, logic 1 for PM.

When 24-hour mode is programmed, the tens of hours register reads out two bits of data and the two most significant bits are set to logic 0. There is no AM/PM indication and bit 1 of the clock setting register will read out a logic 0.

In both 12/24-hour modes, the units of hours will read out four active data bits. 12 or 24-hour mode is selected by bit 0 of the clock setting register, logic 0 for 12-hour mode, logic 1 for the 24-hour mode.

#### **Days Counters**

There are two days counters:

- a) units of days
- b) tens of days.

The days counters will count up to 28, 29, 30 or 31 depending on the state of the months counters and the leap year counter. The microprocessor has full read/write access to these registers.

#### **Months Counters**

There are two months counters:

- a) units of months
- b) tens of months.

Both these counters have full read/write access.

#### **Years Counters**

There are two years counters:

- a) units of years
- b) tens of years.

Both these counters have full read/write access. The years will count up to 99 and roll over to 00.

#### TABLE I. Address Decoding of Real-Time Clock Internal Registers

Register Selected			Address	s (Binary)		(Hex)	Access
•		AD3	AD2	AD1	AD0	(110, X)	Access
0	Control Register	. 0	0	0	0	0	Split Read and Write
1	Tenths of Seconds	0	0	0	1	1	Read Only
2	Units Seconds	0	· 0	1 1	0	2	R/W
3	Tens Seconds	0	0	1	1	3	R/W
4	Units Minutes	0	1	0	0	4	R/W
5	Tens Minutes	0	1	0	1	5	R/W
6	Unit Hours	0	1	1 1	0	6	R/W
7	Tens Hours	0	1	1	1	7	R/W
8	Units Days	1	0	<sup></sup> 0	0	8	R/W
9	Tens Days	1	0	· 0	1	9	R/W
10	Units Months	1	0	1 .	0	A	R/W
11	Tens Months	1	0	1	1	В	R/W
12	Units Years	1	1	0	0	С	R/W
13	Tens Years	1	1	0	1	D	R/W
14	Day of Week	1	1	1	0	E	R/W
15	Clock Setting/	1	1	1	1 1	) F	R/W
	Interrupt Registers						

#### **Day of Week Counter**

The day of week counter increments as the time rolls from 23:59 to 00:00 (11:59 PM to 12:00 AM in 12-hour mode). It counts from 1 to 7 and rolls back to 1. Any day of the week may be specified as day 1.

#### **Clock Setting Register/Interrupt Register**

The interrupt select bit in the control register determines which of these two registers is accessible to the processor at address 15. Normal clock and interrupt timing operations will always continue regardless of which register is selected onto the bus. The layout of these registers is shown in Table II.

The clock setting register is comprised of three separate functions:

a) leap year counter: bits 2 and 3

b) AM/PM indicator: bit 1

c) 12-hour mode set: bit 0 (see Table IIA).

The leap year counter is a 2-stage binary counter which is clocked by the months counter. It changes state as the time rolls over from 11:59 on December 31 to 00:00 on January 1.

The counter should be loaded with the 'number of years since last leap year' e.g., if 1980 was the last leap year, a clock programmed in 1983 should have 3 stored in the leap year counter. If the clock is programmed during a leap year, then the leap year counter should be set to 0. The contents of the leap year counter can be read by the  $\mu$ P.

The AM/PM indicator returns a logic 0 for AM and a logic 1 for PM. It is clocked when the hours counter rolls from 11:59 to 12:00 in 12-hour mode. In 24-hour mode this bit is set to logic 0.

The 12/24-hour mode set determines whether the hours counter counts from 1 to 12 or from 0 to 23. It also controls the AM/PM indicator, enabling it for 12-hour mode and forcing it to logic 0 for the 24-hour mode. The 12/24-hour mode bit is set to logic 0 for 12-hour mode and it is set to logic 1 for 24-hour mode.

**IMPORTANT NOTE:** Hours mode and AM/PM bits cannot be set in the same write operation. See the section on Intialization (Methods of Device Operation) for a suggested setting routine.

All bits in the clock setting register may be read by the processor.

The interrupt register controls the operation of the timer for interrupt output. The processor programs this register for single or repeated interrupts at the selected time intervals.

The lower three bits of this register set the time delay period that will occur between interrupts. The time delays that can be programmed and the data words that select these are outlined in Table IIB.

Data bit 3 of the interrupt register sets for either single or repeated interrupts; logic 0 gives single mode, logic 1 sets for repeated mode.

Using the interrupt is described in the Device Operation section.

TABLE IIA. Clock Setting Register Layout	
--	--

Function		Data B	its Used		Comments	Access
, anoton	DB3	DB2	DB1	DB0	Comments	A00033
Leap Year Counter	х	X			0 Indicates a Leap Year	R/W
AM/PM Indicator (12-Hour Mode)			X		0 = AM 1 = PM	R/W
					0 in 24-Hour Mode	
12/24-Hour Select Bit				X	0 = 12-Hour Mode	R/W
					1 = 24-Hour Mode	

#### TABLE IIB. Interrupt Control Register

		· · · · · · · · · · · · · · · · · · ·						
Function	Comments	Control Word						
1 dilotion		DB3	DB2	DB1	DB0			
No Interrupt	Interrupt output cleared, start/stop bit set to 1.	x	0	0	0			
0.1 Second		0/1	0	0	1			
0.5 Second		0/1	0	1	0			
1 Second	DB3 = 0 for single interrupt	0/1	0	1	1			
5 Seconds		0/1	1	0	0			
10 Seconds	DB3 = 1 for repeated interrupt	0/1	1	0	1			
30 Seconds		0/1	1 .	1	0			
60 Seconds		0/1	1	1	1			

Timing Accuracy: single interrupt mode (all time delays):  $\pm 1$  ms Repeated Mode:  $\pm 1$  ms on initial timeout, thereafter synchronous with first interrupt (i.e., timing errors do not accumulate). 2

#### **Control Register**

There are three registers which control different operations of the clock:

- a) the clock setting register
- b) the interrupt register
- c) the control register.

The clock setting and interrupt registers both reside at address 15, access to one or the other being controlled by the interrupt select bit; data bit 1 of the control register.

The clock setting register programs the timekeeping of the clock. The 12/24-hour mode select and the AM/PM indicator for 12-hour mode occupy bits 0 and 1, respectively. Data bits 2 and 3 set the leap year counter.

The interrupt register controls the operation of the interrupt timer, selecting the required delay period and either single or repeated interrupt.

The control register is responsible for controlling the operations of the clock and supplying status information to the processor. It appears as two different registers; one with write only access and one with read only access.

The write only register consists of a bank of four latches which control the internal processes of the clock.

The read only register contains two output data latches which will supply status information for the processor. Table III shows the mapping of the various control latches and status flags in the control register. The control register is located at address 0.

The write only portion of the control register contains four latches:

A logic 1 written into the test bit puts the device into test mode. This allows setting of the oscillator frequency as well as rapid testing of the device registers, if required. A more complete description is given in the Test Mode section. For normal operation the test bit is loaded with logic 0.

The clock start/stop bit stops the timekeeping of the clock and resets to 0 the tenths of seconds counter. The time of day may then be written into the various clock registers and the clock restarted synchronously with an external time source. Timekeeping is maintained thereafter.

A logic 1 written to the start/stop bit halts clock timing. Timing is restarted when the start/stop bit is written with a logic 0.

The interrupt select bit determines which of the two registers mapped onto address 15 will be accessed when this address is selected. A logic 0 in the interrupt select bit makes the clock setting register available to the processor. A logic 1 selects the interrupt register.

The interrupt start/stop bit controls the running of the interrupt timer. It is programmed in the same way as the clock start/stop bit; logic 1 to halt the interrupt and reset the timer, logic 0 to start interrupt timing.

When no interrupt is programmed (interrupt control register set to 0), the interrupt start/stop bit is automatically set to a logic 1. When any new interrupt is subsequently programmed, timing will not commence until the start/stop bit is loaded with 0.

In the single interrupt mode, interrupt timing stops when a timeout occurs. The processor restarts timing by writing logic 0 into the start/stop bit.

In repeated interrupt mode the interrupt timer continues to count with no intervention by the processor necessary.

Interrupt timing may be stopped in either mode by writing a logic 1 into the interrupt start/stop bit. The timer is reset and can be restarted in the normal way, giving a full time delay period before the next interrupt.

In general, the control register is set up such that writing 0's into it will start anything that is stopped, pull the clock out of test mode and select the clock setting register onto the bus. In other words, writing 0 will maintain normal clock operation and restart interrupt timing, etc.

The read only portion of the control register has two status outputs:

Since the MM58274C keeps real time, the time data changes asynchronously with the processor and this may occur while the processor is reading time data out of the clock.

Some method of warning the processor when the time data has changed must thus be included. This is provided for by the data-changed flag located in bit 3 of the control register. This flag is set by the clock setting pulse which also clocks the time registers. Testing this bit can tell the processor whether or not the time has changed. The flag is cleared by a read of the control register but not by any write operations. No other register read has any effect on the state of the data-changed flag.

Data bit 0 is the interrupt flag. This flag is set whenever the interrupt timer times out, pulling the interrupt output low. In a polled interrupt routine the processor can test this flag to determine if the MM58274C was the interrupting device. This interrupt flag and the interrupt output are both cleared by a read of the control register.

Access (addr0) DB3		DB2	DB1	DB0	
Read From:	Data-Changed Flag	0	0	Interrupt Flag	
Write To:	Test 0 = Normal 1 = Test Mode	Clock Start/Stop 0 = Clock Run 1 = Clock Stop	Interrupt Select 0 = Clock Setting Register 1 = Interrupt Register	Interrupt Start/Stop 0 = Interrupt Run 1 = Interrupt Stop	

#### TABLE III. The Control Register Layout

Both of the flags and the interrupt output are reset by the trailing edge of the read strobe. The flag information is held latched during a control register read, guaranteeing that stable status information will always be read out by the processor.

Interrupt timeout is detected and stored internally if it occurs during a read of the control register, the interrupt output will then go low only after the read has been completed.

A clock setting pulse occurring during a control register read will *not* affect the data-changed flag since time data read out before or after the control read will not be affected by the time change.

#### METHODS OF DEVICE OPERATION

#### **Test Mode**

National Semiconductor uses test mode for functionally testing the MM58274C after fabrication and again after packaging. Test mode can also be used to set up the oscillator frequency when the part is first commissioned.

Figure 4 shows the internal clock connections when the device is written into test mode. The 32.768 kHz oscillator is gated onto the interrupt output to provide a buffered output for initial frequency setting. This signal is driven from a TRI-STATE output buffer, enabling easy oscillator setting in systems where interrupt is not normally used and there is no external resistor on the pin.

If an interrupt is programmed, the 32.768 kHz output is switched off to allow high speed testing of the interrupt timer. The interrupt output will then function as normal.

The clock start/stop bit can be used to control the fast clocking of the time registers as shown in *Figure 4*.

#### Initialization

When it is first installed and power is applied, the device will need to be properly initialized. The following operation steps are recommended when the device is set up (all numbers are decimal): 1) Disable interrupt on the processor to allow oscillator setting. Write  $15_{10}$  into the control register: *The clock and interrupt start/stop bits are set to 1, ensuring that the clock and interrupt timers are both halted. Test mode and the interrupt register are selected.* 

2) Write 0 to the interrupt register: Ensure that there are no interrupts programmed and that the oscillator will be gated onto the interrupt output.

3) Set oscillator frequency: All timing has been halted and the oscillator is buffered out onto the interrupt line.

4) Write 5 to the control register: The clock is now out of test mode but is still halted. The clock setting register is now selected by the interrupt select bit.


5) Write 0001 to all registers. This ensures starting with a valid BCD value in each register.

6) Set 12/24 Hours Mode: Write to the clock setting register to select the hours counting mode required.

7) Load Real-Time Registers: All time registers (including Leap Years and AM/PM bit) may now be loaded in any order. Note that when writing to the clock setting register to set up Leap Years and AM/PM, the Hours Mode bit must not be altered from the value programmed in step 5.

8) Write 0 to the control register: This operation finishes the clock initialization by starting the time. The final control register write should be synchronized with an external time source.

In general, timekeeping should be halted before the time data is altered in the clock. The data can, however, be altered at any time if so desired. Such may be the case if the user wishes to keep the clock corrected without having to stop and restart it; i.e., winter/summer time changing can be accomplished without halting the clock. This can be done in software by sensing the state of the data-changed flag and only altering time data just after the time has rolled over (data-changed flag set).



**FIGURE 4. Test Mode Organization** 

TL/F/11219-7

#### **Reading the Time Registers**

Using the data-changed flag technique supports microprocessors with block move facilities, as all the necessary time data may be read sequentially and then tested for validity as shown below.

1) Read the control register, address 0: This is a dummy read to reset the data-changed flag (DCF) prior to reading the time registers.

2) Read time registers: All desired time registers are read out in a block.

3) Read the control register and test DCF: *If DCF is cleared* (*logic 0*), then no clock setting pulses have after occurred since step 1. All time data is guaranteed good and time reading is complete.

If DCF is set (logic 1), then a time change has occurred since step 1 and time data may not be consistent. Repeat steps 2 and 3 until DCF is clear. The control read of step 3 will have reset DCF, automatically repeating the step 1 action.

#### Interrupt Programming

The interrupt timer generates interrupts at time intervals which are programmed into the interrupt register. A single interrupt after delay or repeated interrupts may be programmed. Table IIB lists the different time delays and the data words that select them in the interrupt register.

Once the interrupt register has been used to set up the delay time and to select for single or repeat, it takes no further part in the workings of the interrupt system. All activity by the processor then takes place in the control register. Initializing:

1) Write 3 to the control register (AD0): Clock timing continues, interrupt register selected and interrupt timing stopped.

2) Write interrupt control word to address 15: *The interrupt register is loaded with the correct word (chosen from Table IIB) for the time delay required and for single or repeated interrupts.* 

3) Write 0 or 2 to the control register: Interrupt timing commences. Writing 0 selects the clock setting register onto the data bus; writing 2 leaves the interrupt register selected. Normal timekeeping remains unaffected.

On Interrupt:

Read the control register and test for Interrupt Flag (bit 0). If the flag is cleared (logic 0), then the device is not the source of the interrupt.

If the flag is set (logic 1), then the clock did generate an interrupt. The flag is reset and the interrupt output is cleared by the control register read that was used to test for interrupt.

Single Interrupt Mode:

When appropriate, write 0 or 2 to the control register to restart the interrupt timer.

Repeated Interrupt Mode:

Timing continues, synchronized with the control register write which originally started interrupt timing. No further intervention is necessary from the processor to maintain timing.

In either mode interrupt timing can be stopped by writing 1 into the control register (interrupt start/stop set to 1). Timing for the full delay period recommences when the interrupt start/stop bit is again loaded with 0 as normal.

**IMPORTANT NOTE:** Using the interrupt timer places a constraint on the maximum Read Strobe width which may be applied to the clock. Normally all registers may be read from with a  $t_{RW}$  down to DC (i.e.,  $\overline{CS}$  and  $\overline{RD}$  held continuously low). When the interrupt timer is active however, the maximum read strobe width that can be applied to the control register (Addr 0) is 30 ms.


This restriction is to allow the interrupt timer to properly reset when it times out. Note that it only affects reading of the control register—all other addresses in the clock may be accessed with DC read strobes, regardless of the state of the interrupt timer. Writes to any address are unaffected.

#### NOTES ON AC TIMING REQUIREMENTS


Although the Switching Time Waveforms show Microbus control signals used for clock access, this does not preclude the use of the MMS8274C in other non-Microbus systems. *Figure 5* is a simplified logic diagram showing how the control signals are gated internally to control access to the clock registers. From this diagram it is clear that  $\overline{CS}$  could be used to generate the internal data transfer strobes, with  $\overline{RD}$  and  $\overline{WR}$  inputs set up first. This situation is illustrated in *Figure 6*.

The internal data busses of the MM58274C are fully CMOS, contributing to the flexibility of the control inputs. When determining the suitability of any given control signal pattern for the MM58274C the timing specifications in AC Switching Characteristics should be examined. As long as these timings are met (or exceeded) the MM58274C will function correctly.

When the MM58274C is connected to the system via a peripheral port, the freedom from timing constraints allows for very simple control signal generation, as in *Figure 7*. For reading (*Figure 7a*), Address, CS and RD may be activated simultaneously and the data will be available at the port after  $t_{AD}$ -max (650 ns). For writing (*Figure 7b*), the address and data may be applied simultaneously; 70 ns later  $\overrightarrow{CS}$  and  $\overrightarrow{WR}$  may be strobed together.



2



#### **APPLICATION HINTS**

#### **Time Reading Using Interrupt**

In systems such as point of sale terminals and data loggers, time reading is usually only required on a random demand basis. Using the data-changed flag as outlined in the section on methods of operation is ideal for this type of system. Some systems, however, need to sense a change in real time; e.g., industrial timers/process controllers, TV/VCR clocks, any system where real time is displayed.

The interrupt timer on the MM58274C can generate interrupts synchronously with the time registers changing, using software to provide the initial synchronization.

In single interrupt mode the processor is responsible for initiating each timing cycle and the timed period is accurate to  $\pm 1$  ms.

In repeated interrupt mode the period from the initial processor start to the first timeout is also only accurate to  $\pm 1$  ms. The following interrupts maintain accurate delay periods relative to the first timeout. Thus, to utilize interrupt to control time reading, we will use repeated interrupt mode.

In repeated mode the time period between interrupts is exact, which means that timeouts will always occur at the same point relative to the internal clock setting pulses. The case for 0.1s interrupts is shown in *Figure A-1*. The same is true for other delay periods, only there will be more clock setting pulses between each interrupt timeout. If we set up the interrupt timer so that interrupt always times out just after the clock setting pulse occurs (*Figure A-2*), then there is no need to test the data-changed flag as we know that the time data has just changed and will not alter again for another 100 ms.

This can be achieved as outlined below:

1) Follow steps 1 and 2 of the section on interrupt programming. In step 2 set up for repeated interrupt. 2) Read control register AD0: *This is a dummy read to reset the data-changed flag.* 

Read control register AD0 until data-changed flag is set.
 Write 0 or 2 to control register. Interrupt timing commences.

#### **Time Reading with Very Slow Read Cycles**

If a system takes longer than 100 ms to complete reading of all the necessary time registers (e.g., when CMOS processors are used) or where high level interpreted language routines are used, then the data-changed flag will always be set when tested and is of no value. In this case, the time registers themselves must be tested to ensure data accuracy.

The technique below will detect both time changing *between* read strobes (i.e., between reading tens of minutes and units of hours) and also time changing *during* read, which can produce invalid data.

1) Read and store the value of the *lowest* order time register required.

2) Read out all the time registers required. The registers may be read out in any order, simplifying software requirements.

3) Read the lowest order register and compare it with the value stored previously in step 1. If it is still the same, then all time data is good. If it has changed, then store the new value and go back to step 2.

In general, the rule is that the first and last reads *must* both be of the lowest order time register. These two values can then be compared to ensure that no change has occurred. This technique works because for any higher order time register to change, all the lower order registers must also change. If the lowest order register does not change, then no higher order register has changed either.





FIGURE A-1. Time Delay from Clock Setting Pulses to Interrupt is Constant



2



National Semiconductor

## MM58174A Microprocessor-Compatible Real-Time Clock

## **General Description**

The MM58174A is a low-threshold metal-gate CMOS circuit that functions as a real-time clock and calendar in bus-oriented microprocessor systems. The device includes an interrupt timer which may be programmed to one of three times. Timekeeping is maintained down to 2.2V to allow low power standby battery operation. The timebase is generated from a 32768 Hz crystal-controlled oscillator.


## Features

- Microprocessor compatible
- Tenths of seconds, seconds, tens of seconds, minutes, tens of minutes, day of week, days, tens of days, months, tens of months, independent registers
- Automatic leap year calculation
- Internal pull-ups to safeguard data
- Protection for read during data changing
- Independent interrupt system with open drain output

- TTL compatible
- Low power standby operation (2.2V, 10 µA)
- Low cost internally biased oscillator
- Low cost 16-pin dual-in-line package
- Available for commercial and military temperature ranges

## Applications

- Point-of-sale terminals
- Word processors
- Teller terminals
- Event recorders
- Microprocessor-controlled instrumentation
- Microprocessor time clock
- TV/VCR reprogramming
- Intelligent telephone



## **Absolute Maximum Ratings**

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Storage Temperature	-65°C to +150°C
V <sub>DD</sub> -V <sub>SS</sub>	6.5V
Lead Temperature (Soldering, 10 second	s) 300°C

## **Electrical Characteristics** $T_A = -40^{\circ}C$ to $+85^{\circ}C$ , $V_{SS} = 0V$

Symbol	Parameter	Conditions	Min	Тур	Max	Units
V <sub>DD</sub>	Supply Voltage	Standby Mode (no READ or WRITE Instructions)	2.2		5.5	v
		Operational Mode	4.5		5.5	<u>v</u>
IDD	Supply Current	$V_{DD} = 2.2V$ (Standby) $V_{DD} = 5V$ (Operating)			10 1	μA mA
	Input Logic Levels for Signals: AD0–AD3, DB0–DB3, WR, RD, CS Logic ''1'' Logic ''0''	V <sub>DD</sub> = 5V	2		0.8	v v
_	Input Capacitance				10	pF
	Input Current Levels	$V_{DD} = 5V$				
	Current to V <sub>SS</sub> for Signals: AD0–AD3, DB0–DB3, <del>RD</del>	V <sub>IN</sub> = V <sub>DD</sub>			30	μA
	Internal Resistor to V <sub>DD</sub> for Signals: WR CS		30 30	100 100	ì	kΩ kΩ
	Output Logic Levels for Signals: DB0–DB3	V <sub>DD</sub> = 5V				
	Logic "1" Logic "0"	$l_{OH} = -0.1 \text{ mA}$ $l_{OL} = 1.6 \text{ mA}$	2.4		0.4	v v
	INTERRUPT (Open Drain) Logic "0"	For $I_{DS} = 1.6 \text{ mA}$			0.4	v
	Off Leakage	V <sub>OUT</sub> = 5V			5	μΑ

2

## **Functional Description**

The MM58174 is a microprocessor bus-oriented real-time clock. The circuit includes addressable real-time counters for tenths of seconds through months and a write only register for leap year calculation. The counters are arranged as bytes of four bits each. When addressed a byte will appear on the data I/O bus so that each word can be accessed independently. If any byte does not contain four bits (e.g., days of the week uses only 3 bits), the unused bits will be unrecognized during a write operation and tied to V<sub>SS</sub> during a read operation.

The addressable reset latch causes the pre-scaler, tenths of seconds, seconds, and tens of seconds to be held in a reset condition. If a register is updated during a read operation the I/O data is prevented from updating and a subsequent read will return the illegal b.c.d. code '1111'. The interrupt timer may be programmed for intervals of 0.5 second, 5 seconds, or 60 seconds and may be coded as a single or repeated operation. The open drain interrupt output is pulled to V<sub>SS</sub> when the timer times out and reading the interrupt register provides the internal selected information.

## **Circuit Description**

The block diagram shown in *Figure 1* shows the structure of the CMOS clock chip. A 16-pin DIL package is used.

#### **CRYSTAL OSCILLATOR**

This consists of a CMOS inverter/amplifier with on-chip bias resistor and capacitors. A single 6 pF-36 pF trimmer is all that is required to fine tune the crystal (see *Figure 2*). However, for improved stability, some crystals may require a capacitor of typical value 20 pF to be added between pin 14 and ground. The output of the oscillator is blocked by the start/stop F/F.

#### NON-INTEGER DIVIDER

This counter divides the incoming 32,768 Hz frequency by 15/16 down to 30,720 Hz.

#### **FIXED DIVIDER (512)**

This is a standard 9-stage binary ripple counter. Output frequency is 60 Hz. This counter is reset to zero by start/stop F/F.

#### **FIXED DIVIDER (6)**

This is a 3-stage Johnson counter with a 10 Hz output signal. This counter is reset to zero state by the start/stop F/F.

#### SYNCHRONIZATION STAGE

Both 10 Hz and 32,768 Hz clocks are fed into this section. It is used to generate a pulse of 15.25  $\mu$ s width on the rising edge of each 10 Hz pulse.


This pulse is used to increment all the seconds, minutes, hours, days, months, and year counter and also to set the data changed F/F.

#### DATA CHANGED F/F

This is set by the rising edge of each 10 Hz pulse to indicate that the clock value has changed since the last read operation. It is reset by any clock read command.

The flip flop sets all data bus bits to a "1" during RD time indicating that a register has been updated. This transient condition may occur at the end of the Read Data strobe. Hence, invalid data may still be read from the clock, if the strobe width was less than 3  $\mu$ s.

## **Connection Diagram**



Top View Order Number MM58174AN See NS Package Number N16A

The possibility may be overcome by implementing a further read of the tenths of seconds register at the end of every series of reads (starting with a read at the tenths of seconds register) and checking for unchanged data.

#### SECONDS COUNTERS

There are three counters for Seconds:

- a) tenths of seconds
- b) units of seconds
- c) tens of seconds

The outputs of all three counters can be separately multiplexed on to the command 4-bit output bus. Table I shows the address decoding for each counter. All three counters are reset to zero by the start/stop F/F.

#### **MINUTES COUNTERS**

There are two Minutes counters:

- a) units of minutes
- b) tens of minutes

Both counters are parallel loaded with data from the 4-bit input bus when addressed by the microprocessor and a Write Data Strobe pulse given. Similarly, the output of both counters can be read separately onto the common 4-bit output bus (Table I).

#### HOURS COUNTERS

There are two Hours counters which will count in a 24-hour mode:

a) units of hours

b) tens of hours


Both counters have identical parallel load and read multiplex features to the Minutes counters.

#### SEVEN DAY COUNTER

There is a 7-state counter which increments every 24 hours. It will have identical parallel load and read multiplex capabilities to the Minutes and Hours counters. The counter counts cyclically from 1–7.

# MM58174A

## Circuit Description (Continued)



#### DAYS COUNTER

There are two Days counters:

a) units of days

b) tens of days

The Days counters will count up to 28, 29, 30, or 31 days depending on the state of the Months counters and the Years Status Register. Days counters have parallel load and read multiplex capabilities.

#### MONTHS COUNTERS

There are two Months counters:

a) units of months

b) tens of months

The Months counters have parallel load and read multiplex capabilities.

#### YEARS STATUS REGISTER


The Years Status register is a shift register of 4 bits. It will be shifted every year on December 31st. The status register must be set in accordance with Table III. No readout capability is provided.

#### CHIP SELECT (CS)

An external chip select is provided. The chip enable is active low.

#### COUNTER AND REGISTER SELECTION

Table I shows the coding on the address lines AD0-AD3 which select the registers in the circuit to be either parallel loaded or read on to the output bus.



#### START/STOP (RESET) LATCH

A logic "1" on DB0 at chip address 14 (E) will start the clock running, a logic "0" will stop the clock. This function allows the loading of time data into the clock and its precise starting. The clock starts at 0.1 seconds.

#### TEST MODE

This mode is incorporated to facilitate production testing of the circuit. In this mode, the 32,768 Hz clock is fed forward as shown in *Figure 3*. For normal operation, the circuit must be set to the non-test mode as part of the system initialization. This is accomplished by writing a logic "0" to DB3 at AD0.

Selected Counter		Address Bits				Mode
		AD3	AD2	AD1	AD0	Mode
0	Test Only	0	0	0	0	Write Only
1	Tenths of Secs.	0	0	0	1	Read Only
2	Units of Secs.	0	0	1	0	Read Only
3	Tens of Secs.	0	0	1	1	Read Only
4	Units of Mins.	0	1	0	0	Read or Write
5	Tens of Mins.	0	1	0	1	Read or Write
6	Units of Hours	0	1	1	0	Read or Write
7	Tens of Hours	0	1	1	1	Read or Write
8	Units of Days	1	0	0	0	Read or Write
9	Tens of Days	1	0	0	1	Read or Write
10	Day of Week	1	0	1	0	Read or Write
11	Units of Months	1	0	1	1	Read or Write
12	Tens of Months	1	1	0	0	Read or Write
13	Years	1	1	0	1	Write Only
14	Stop/Start	1	1	1	0	Write Only
15	Interrupt	1	1	1	1	Read or Write

#### **TABLE I. Address Decoding for Internal Registers**

## Circuit Description (Continued)

#### **TABLE IIa. Interrupt Selection Data**

Mode: Address 15, Write Mode										
Function	DB3	DB2	DB1	DB0						
No Interrupt	х	0	0	0						
Int. at 60 Sec. Intervals*	0/1	1	0	0						
Int. at 5.0 Sec. Intervals*	0/1	0	1	0						
Int. at 0.5 Sec. Intervals*	0/1	0	0	1						

\*+ 16.6 ms

DB3 = 0, single interrupt

DB3 = 1, repeated interrupt

#### TABLE IIb. Interrupt Read Back (Status)

Mode: Address 15, Read Mode										
Interrupt Status DB3 DB2 DB1 DB0										
Reset	x	0	0	0						
60 Sec. Signal	X	1	0	0						
5.0 Sec. Signal	X	0	1	0						
0.5 Sec. Signal	X	0	0	1						

X = don't care state

#### **TABLE III. Years Status Register**

Mode: Address 13, Write Mode										
•	DB3	DB2	DB1	DB0						
Leap Year	1	0	0	0						
Leap Year-1	0	1	0	0						
Leap Year-2	0	0	1	0						
Leap Year-3	0	0	0	1						

Note: Leap year counter rolls over on December 31 @ 23:59:59.

#### INTERRUPT SYSTEM

The interrupt output and its frequency of operation is enabled by writing to address 15 (see Table IIa). To ensure correct operation, the interrupt should be serviced within 16.6 ms.

The interrupt is initialized by writing "0" to address 15 and reading the interrupt, i.e., reading at address 15 three times. Initialization must be performed at power on and also if the interrupt is not serviced correctly within 16.6 ms.

#### SERVICING THE INTERRUPT

In a typical system the open drain interrupt output is wired to the processor interrupt system. Hence, when the interrupt timer times out, the interrupt output is pulled low and the processor is interrupted.

The processor may then reset the interrupt by utilizing the following procedure:


Read Address 15 three times.

This resets the interrupt output and restarts the interrupt timer when in the repeat mode.

It is recommended that the interrupt output is connected to a unique processor port.

#### CRYSTAL PARAMETERS

Figure 4 is an electrical representation of the crystal along with some typical values. The 32.768 kHz crystal is an NT CUT (tuning fork type) or XY BAR for use in a parallel resonant Pierce oscillator.



#### FIGURE 4. Typical Crystal Parameters

#### DEVICE INITIALIZATION AND OSCILLATOR SETTING

When first installed or if the battery back-up has failed, the MM58174A will require to be properly initialized. The following sequence is a suggested flow of operations to achieve this.

	Action	Result
1)	Apply power.	Clears interrupt timer
2)	Write "0" to address 15.	chain.
3)	Read 3 times from address 15.	Clears interrupt output logic.
4)	Write "0" on DB3 to address 0.	Clears test mode.
5)	Write "0" on DB0 to address 14.	Stops clock running.
6)	Set up timekeeping registers.	Load real-time into device time registers, minutes to leap years.
7)	Write "1" on DB0 to address 14.	Starts timekeeping synchronized to an external time source.
8)	Program and start interrupts.	Commence interrupt timing, if so required.

#### **OSCILLATOR SETTING**

Directly connecting a frequency meter to the Crystal Out pin (14) will not allow correct frequency setting because of the extra capacitive loading of the meter. One possibility for setting is to use a high impedance probe or a CMOS buffer to keep the loading as low as possible (e.g., 100 x 2 pF probe). Alternatively, a buffered output of 16.384 kHz OSC/2 can be produced on DB0 by applying the following procedure:

	Action	Result
1)	Write a "1" on DB3 to address 0.	Selects test mode.
2)	Write a "1" on DB0 to address 14.	Starts clock timing.
3)	Read at address 1 (tenths of secs).	"Data Changed" signal is read.
4)	Read at address 1 and HOLD the strobe LOW.	16.384 kHz appears on DB0.

5) Adjust trimmer capacitor.

There must be no extra activity on the RD line between steps 3 and 4 or only the normal "Data Changed" signal will be observed on the data bus. Thus if the normal host processor system is being used to generate the chip waveforms, proper care must be taken.

# **Timing Waveforms**

#### READ MODE

*Figure 6* gives detailed timing for the transfer of data from peripheral to microprocessor. See Table IV.

All times are measured from (or to) valid logic "0" level = 0.8V or valid logic "1" level = 2.0V.

#### WRITE MODE

*Figure 7* gives detailed timing for the transfer of data from microprocessor to peripheral. See Table V.

ADDRESS VALID

tww | twa

DATA VALID

tACSO

tcsw

FIGURE 7. Write Cycle Waveforms


taw

t<sub>D₩</sub>

t<sub>ACS1</sub>

t<sub>WD</sub>

TL/F/6681-8



MICROPROCESSOR BUS

TL/F/6681-6




A3-A0


cs


WR


D3-D0











MM58174A

# **Operating Conditions** MM58174AN $T_A = -40^{\circ}$ C to 85°C, $V_{DD} = 5V$

Symbol		MM58	174AN		11-14-	
Symbol	Parameter	Min	Max	Тур	Units	Comments
t <sub>ACS0</sub>	Address Bus Valid to Chip Select ON ( $\overline{CS} = 0$ )	0			ns	
t <sub>CSR</sub>	Chip Select ON to Read Strobe	0			ns ,	
t <sub>RD</sub>	Read Cycle Access Time from Read Strobe to Data Bus Valid		900	450	ns	C <sub>L</sub> = 100 pF
t <sub>RH</sub>	Data Hold Time from Trailing Edge of Read Strobe	0	330		ns	
t <sub>RA</sub>	Address Bus Hold Time from Trailing Edge of Read Strobe	70		500	ns	
t <sub>ACS1</sub>	Address Change to Chip Select OFF	0	4.11	40	ns	
t <sub>AD</sub>	Address Bus Valid to Data Valid		1850	850	ns	$C_{L} = 100  pR$
t <sub>HZ</sub>	Time from Trailing Edge of Read Strobe until Interface Device Bus Drivers are in TRI-STATE® Mode	0	330		ns	
t <sub>RW</sub>	Read Strobe Width		14		μs	
t <sub>AR</sub>	Address Bus Valid to Read Strobe	500			ns	

#### TABLE IV. Read Timing: Data from Peripheral to Microprocessor

Note 1: In order not to degrade timekeeping accuracy, the number of Read strobes in any one second should be less than 10,000.

Note 2: If address and read occur simultaneously then they must exist for  $t_{AB}$  +  $t_{AD}$ .

#### TABLE V. Write Timing: Data from Microprocessor to Peripheral

Symbol	Parameter	MM5	8174AN	Tur	Units	Comments
Symbol	Parameter	Min	Max	Тур	Units	Comments
t <sub>ACS0</sub>	Address Bus Valid to Chip Select ON ( $\overline{CS} = 0$ )	0			ns	
tcsw	Chip Select ON to Write Strobe	0		450	ns	
t <sub>AW</sub>	Address Bus Valid to Write Strobe	725			ns	
tww	Write Strobe Width	670			ns	
t <sub>DW</sub>	Data Bus Valid before Write Strobe	70			ns	
t <sub>WA</sub>	Address Bus Hold Time following Write Strobe	165			ns	
t <sub>WD</sub>	Data Bus Hold Time following Write Strobe	185		<u> </u>	ns	
t <sub>ACS1</sub>	Address Change to Chip Select OFF ( $\overline{CS} = 1$ )	0			ns	

Note 3: If address and write occur simultaneously, then they must exist for  $t_{AW}$  and  $t_{WW}.$ 



# MM58167B **Microprocessor Real Time Clock**

## **General Description**


The MM58167B is a low threshold metal gate CMOS circuit that functions as a real time clock in bus oriented microprocessor systems. The device includes an addressable real time counter, 56 bits of RAM, and two interrupt outputs. A POWER DOWN input allows the chip to be disabled from the rest of the system for standby low power operation. The time base is a 32.768 Hz crystal oscillator.

## Features

- Microprocessor compatible (8-bit data bus)
- Milliseconds through month counters


- 56 bits of RAM with comparator to compare the real time counter to the RAM data
- 2 INTERRUPT OUTPUTS with 8 possible interrupt signals
- POWER DOWN input that disables all inputs and outputs except for one of the interrupts
- Status bit to indicate rollover during a read
- 32.768 Hz crystal oscillator
- Four-year calendar (no leap year)
- 24-hour clock

# **Connection Diagrams**




**Top View** 

Order Number MM58167BN See NS Package Number N24A



PCC Package



**Top View** 

Order Number MM58167BV See NS Package Number V28A

# **Absolute Maximum Ratings**

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

Storage Temperature	-65°C to +150°C	
V <sub>DD</sub> -V <sub>SS</sub>	6.0V	
Lead Temperature (Soldering, 10 sec.)	300°C	
ESD rating is to be determined.	P	

# **Electrical Characteristics** $v_{SS} = 0V$ , $0^{\circ}C \le T_A \le 70^{\circ}C$

Parameter	Conditions	Min	Max	Units
Supply Voltage				
V <sub>DD</sub>	Outputs Enabled	4.5	5.5	v v
V <sub>DD</sub>	POWER DOWN Mode	2.2	5.5	v
Supply Current				
I <sub>DD</sub> , Dynamic	Outputs TRI-STATE®			
	f <sub>IN</sub> = 32.768 kHz, V <sub>DD</sub> = 5.5V		20	
	$V_{\rm IH} \ge V_{\rm DD} - 0.3V$		20	μΑ
	$V_{IL} \leq V_{SS} + 0.3V$			
I <sub>DD</sub> , Dynamic	Outputs TRI-STATE			
	f <sub>IN</sub> = 32.768 kHz, V <sub>DD</sub> = 5.5V		5	mA
	$V_{IH} = 2.0V, V_{IL} = 0.8V$			
Input Voltage				
Logical Low		0.0	0.8	V
Logical high		2.0	V <sub>DD</sub>	V
Input Leakage Current	$V_{SS} \le V_{IN} \le V_{DD}$	-1	1	μΑ
Output Impedance	I/O and INTERRUPT OUT			
Logical Low	$V_{DD} = 4.5V, I_{OL} = 1.6 \text{ mA}$		0.4	V
Logical High	$V_{DD} = 4.5V, I_{OH} = -400 \mu A$	2.4		V
·	$I_{OH} = -10 \mu A$	0.8 V <sub>DD</sub>		V
TRI-STATE	$V_{SS} \le V_{OUT} \le V_{DD}$	-1	11	μΑ
Output Impedance	RDY and STANDBY INTERRUPT			
	(Open Drain Devices)			
Logical Low, Sink	$V_{DD} = 4.5V, I_{OL} = 1.6 \text{ mA}$		0.4	v
Logical High, Leakage	$V_{OUT} \le V_{DD}$		10	μΑ

# **Functional Description**

#### **Real Time Counter**

The real time counter is divided into 4-bit digits with 2 digits being accessed during any read or write cycle. Each digit represents a BCD number and is defined in Table I. Any unused bits are held at a logical zero during a read and ignored during a write. An unused bit is any bit not necessary to provide a full BCD number. For example tens of hours cannot legally exceed the number 2, thus only 2 bits are necessary to define the tens of hours. The other 2 bits in the tens of hours digit are unused. The unused bits are designated in Table I as dashes.

The addressable portion of the counter is from milliseconds to months. The counter itself is a ripple counter. The ripple delay is less than 60  $\mu$ s above 4.5V and 300  $\mu$ s at 2.2V.

#### RAM

56 bits of RAM are contained on-chip. These can be used for any necessary power down storage or as an alarm latch for comparison to the real time counter. The data in the RAM can be compared to the real time counter on a digit basis. The only digits that are not compared are the unit ten thousandths of seconds and tens of days of the week (these are unused in the real time counter). If the two most significant bits of any RAM digit are ones, then this RAM location will always compare. The rule of thumb for an "alarm" interrupt is: All nibbles of higher order than specified are set to C hex (always compare). All nibbles lower than specified are set to "zero". As an example, if an alarm is to occur everyday at 10:15 a.m., configure the bits in RAM as shown in Table II.

The RAM is formatted the same as the real time counter, 4 bits per digit, 14 digits, however there are no unused bits.

The unused bits in the real time counter will compare only to zeros in the RAM.

An address map is shown in Table III.

#### Interrupts and Comparator

There are two interrupt outputs. The first is the INTERRUPT OUTPUT (a true high signal). This output can be programmed to provide 8 different output signals. They are: 10 Hz, once per second, once per minute, once per hour, once a day, once a week, once a month, and when a RAM/ real time counter comparison occurs. To enable the output a one is written into the interrupt control register at the bit location corresponding to the desired output frequency (Figure 1). Once one or more bits have been set in the interrupt control register, the corresponding counter's rollover to its reset state will clock the interrupt status register and cause the interrupt output to go high. To reset the interrupt and to identify which frequency caused the interrupt, the interrupt status register is read. Reading this register places the contents of the status register on the data bus. The interrupting frequency will be identified by a one in the respective bit position. Removing the read will reset the interrupt.

The second interrupt is the STANDBY INTERRUPT (open drain output, active low). This interrupt occurs when enabled and when a RAM/real time counter comparison occurs. The STANDBY INTERRUPT is enabled by writing a one on the D0 line at address  $16_H$  or disabled by writing a zero on the D0 line. This interrupt is not triggered by the edge of the compare signal, but rather by the level. Thus if the compare is enabled when the STANDBY INTERRUPT is enabled, the interrupt will turn on immediately.

		ТАВ	LE I. Re	al Time	Counter	Format					•
Counter Addressed		D0	Un D1	nits D2	D3	Max BCD Code	D4	Te D5	ns D6	D7	Max BCD Code
Milliseconds	(00 <sub>H</sub> )	_	_		_	0	D4	D5	D6	D7	9
Hundredths and Tenths Sec	(01 <sub>H</sub> )	D0	D1	D2	D3	9	D4	D5	D6	D7	9
Seconds	(02 <sub>H</sub> )	D0	D1	D2	D3	9	D4	D5	D6	-	5
Minutes	(03 <sub>H</sub> )	DO	D1	D2	D3	9	D4	D5	D6	_	5
Hours	(04 <sub>H</sub> )	D0	D1	D2	D3	9	D4	D5	—	_	2
Day of the Week	(05 <sub>H</sub> )	D0	D1	D2		7	_	_	_		0
Day of the Month	(06 <sub>H</sub> )	DO	D1	D2	D3	9	D4	D5	_	_	3
Month	(07 <sub>H</sub> )	DO	D1	D2	D3	9	D4		·		1

(---) indicates unused bits

TABLE II. Clock RAM Bit Map for Alarm Interrupt Everyday at 10:15 a.m.

			Address	-					Da	ata		-	
Function			nuul co.				HI N	ibble			Lo N	ibble	
	4	3	2	1	0	7	6	5	4	3	2	1	0
Milliseconds	0	1	0	0	0	0	0	0	0	No RAM Exists			
Hundredths and Tenths of Seconds	0	1	0	0	1	0	0	0	0	0	0	0	0
Seconds	0	1	0	1	0	0	0	0	0	0	0	0	0
Minutes	0	1	0	1	<sup>`</sup> 1	0	0	0	1	0	1	0	. 1
Hours	0	1	1	0	0	0	0	0	1	0	0	0	0
Day of Week	0	1	1	0	1		No RAI	VI Exists		1	1	Х	Х
Day of Month	0	1	1	1	0	1	1	х	х	1	1	Х	Х
Months	0	1	1	1	1	1	1	x	х	1	1	X	Х

				· · · ·	
TABLE	ш.	Address	Codes	and	Function

A4         A3         A2         A1         A0         Function           0         0         0         0         0         Counter—Milliseconds           0         0         0         0         1         Counter—Hundredths and Tenths           0         0         0         1         0         Counter—Hundredths and Tenths           0         0         0         1         0         Counter—Seconds           0         0         0         1         1         Counter—Minutes           0         0         1         0         Counter—Hours         Counter—Hours           0         0         1         0         Counter—Day of Week         Counter—Day of Month           0         0         1         1         0         Counter—Month           0         0         1         1         1         Counter—Month           0         1         1         1         Counter—Month           0         1         1         1         Counter—Month           0         1         0         0         RAM—Milliseconds           0         1         0         1         RAM—Hundredths and Tenths of	
0         0         0         0         1         Counter-Hundredths and Tenths           0         0         0         1         0         Counter-Seconds           0         0         0         1         1         Counter-Minutes           0         0         1         0         Counter-Mours           0         0         1         0         Counter-Day of Week           0         0         1         1         CounterDay of Month           0         0         1         1         CounterMonth           0         1         0         0         RAMMilliseconds           0         1         0         1         RAMHundredths and Tenths of           0         1         0         1         RAMSeconds           0         1         0         1         RAMMinutes	
0         0         0         1         0         Counter—Seconds           0         0         0         1         1         Counter—Minutes           0         0         1         0         0         Counter—Hours           0         0         1         0         1         Counter—Day of Week           0         0         1         1         0         Counter—Day of Month           0         0         1         1         0         Counter—Day of Month           0         0         1         1         1         Counter—Month           0         1         0         0         RAM—Milliseconds         Month           0         1         0         0         RAM—Hundredths and Tenths of           0         1         0         1         RAM—Seconds           0         1         0         1         RAM—Minutes	
0         0         0         1         1         Counter-Minutes           0         0         1         0         0         Counter-Hours           0         0         1         0         1         Counter-Day of Week           0         0         1         1         0         Counter-Day of Week           0         0         1         1         0         Counter-Day of Month           0         0         1         1         1         Counter-Month           0         1         0         0         RAMMilliseconds         Nonth           0         1         0         0         RAMMilliseconds         Nonth           0         1         0         1         RAMMinutedths and Tenths of           0         1         0         1         RAMSeconds           0         1         0         1         RAMMinutes	s of Seconds
0         0         1         0         0         Counter-Hours           0         0         1         0         1         Counter-Day of Week           0         0         1         1         0         Counter-Day of Week           0         0         1         1         0         Counter-Day of Month           0         0         1         1         1         Counter-Month           0         1         0         0         RAM-Milliseconds           0         1         0         0         RAM-Hundredths and Tenths of           0         1         0         1         RAM-Seconds           0         1         0         1         RAM-Seconds	
0         0         1         0         1         Counter—Day of Week           0         0         1         1         0         Counter—Day of Month           0         0         1         1         1         Counter—Day of Month           0         0         1         1         1         Counter—Month           0         1         0         0         RAM—Milliseconds           0         1         0         0         1         RAM—Hundredths and Tenths of           0         1         0         1         0         RAM—Seconds           0         1         0         1         RAM—Minutes	
0         0         1         1         0         Counter—Day of Month           0         0         1         1         1         Counter—Month           0         1         0         0         0         RAM—Milliseconds           0         1         0         0         1         RAM—Hundredths and Tenths of           0         1         0         1         0         RAM—Hundredths and Tenths of           0         1         0         1         1         RAM—Seconds           0         1         0         1         1         RAM—Seconds	
0         0         1         1         1         CounterMonth           0         1         0         0         0         RAMMilliseconds           0         1         0         0         1         RAMMilliseconds           0         1         0         0         1         RAMHundredths and Tenths of           0         1         0         1         0         RAMSeconds           0         1         0         1         1         RAMMinutes	
0         1         0         0         0         RAM-Milliseconds           0         1         0         0         1         RAM-Hundredths and Tenths of           0         1         0         1         0         RAM-Hundredths and Tenths of           0         1         0         1         0         RAM-Seconds           0         1         0         1         1         RAM-Seconds	
0         1         0         0         1         RAM—Hundredths and Tenths of           0         1         0         1         0         RAM—Seconds           0         1         0         1         1         RAM—Minutes	
0         1         0         1         0         RAM—Seconds           0         1         0         1         1         RAM—Minutes	
0 1 0 1 1 RAM-Minutes	f Seconds
0 1 1 0 0 RAM—Hours	
0 1 1 0 1 RAM—Day of Week	
0 1 1 1 0 RAM—Day of Month	
0 1 1 1 1 1 RAM—Months	
1 0 0 0 0 Interrupt Status Register	
1 0 0 0 1 Interrupt Control Register	
1 0 0 1 0 Counters Reset	
1 0 0 1 1 RAM Reset	
1 0 1 0 0 Status Bit	-
1 0 1 0 1 GO Comand	
1 0 1 1 0 STANDBY INTERRUPT	
1 1 1 1 1 Test Mode	

All others unused

The comparator is a cascaded exclusive NOR. Its output is latched 61  $\mu$ s after the rising edge of the 1 kHz clock signal (input to the milliseconds counter). This allows the counter to ripple through before looking at the comparator. For operation at less than 4.5V, the thousandths of seconds counter should not be included in a compare because of the possibility of having a ripple delay greater than 61  $\mu$ s. (For output timing see Interrupt Timing.)

#### **Power Down Mode**

The POWER DOWN input is essentially a second chip select. It disables all inputs and outputs except for the STANDBY INTERRUPT. When this input is at a logical zero, the device will not respond to any external signals. It will, however, maintain timekeeping and turn on the STANDBY INTERRUPT if programmed to do so. (The programming must be done before the POWER DOWN input goes to a

logical zero.) When switching  $V_{DD}$  to the standby or power down mode, the POWER DOWN input should go to a logical zero at least 1  $\mu$ s before  $V_{DD}$  is switched. When switching  $V_{DD}$  all other inputs must remain between  $V_{SS} - 0.3V$  and  $V_{DD} + 0.3V$ . When restoring  $V_{DD}$  to the normal operating mode, it is necessary to insure that all other inputs are at valid levels before switching the POWER DOWN input back to a logical one. These precautions are necessary to insure that no data is lost or altered when changing to or from the power down mode.

#### **Counter and RAM Resets; GO Command**

The counters and RAM can be reset by writing all 1's (FF) at address  $12_{H}$  or  $13_{H}$  respectively.

A write pulse at address  $15_{\rm H}$  will reset the thousandths, hundredths, tenths, units, and tens of seconds counters. This GO command is used for precise starting of the clock. The data on the data bus is ignored during the write. If the seconds counter is at a value greater than 39 when the GO is issued, the minute counter will increment; otherwise the minute counter is unaffected. This command is not necessary to start the clock, but merely a convenient way to start precisely at a given minute.

#### Status Bit

The status bit is provided to inform the user that the clock is in the process of rolling over when a counter is read. The status bit is set if this 1 kHz clock occurs during or after any counter read. This tells the user that the clock is rippling through the real time counter. Because the clock is rippling, invalid data may be read from the counter. If the status bit is set following a counter read, the counter should be reread.

The status bit appears on D0 when address  $14_{\rm H}$  is read. All the other data lines will zero. The bit is set when a logical one appears. This bit should be read every time a counter read or after a series of counter reads are done. The trailing edge of the read at address  $14_{\rm H}$  will reset the status bit.

#### Using the Rollover Status Bit

If a single read of any clock counter is made, it should be followed by reading the rollover status bit.

Example: Read months, then read rollover status.

If a sequential read of the clock counters is made, then the rollover status bit should be read after the last counter is read.

Example: Read hours, minutes, seconds, then read the rollover status.

#### Oscillator

The oscillator used in the standard Pierce parallel resonant oscillator. Externally, 2 capacitors, a 20 M $\Omega$  resistor and the crystal are required. The 20 M $\Omega$  resistor is connected between OSC IN and OSC OUT to bias the internal inverter in the linear region. For micropower crystals a resistor in series with the oscillator output may be necessary to insure the crystal is not overdriven. This resistor should be approximately 200 k $\Omega$ . The capacitor values should be typically 20 pF–25 pF. The crystal frequency is 32,768 Hz.

The oscillator input can be externally driven, if desired. In this case the oscillator output should be left floating and the oscillator input levels should be within 0.3V of the supplies.

A ground line or ground plane between pins 9 and 10 may be necessary to reduce interference of the oscillator by the A4 address.


#### **Control Lines**

The READ, WRITE, AND CHIP SELECT signals are active low inputs. The READY signal is an open drain output. At the start of each read or write cycle the READY line (open drain) will pull low and will remain low until valid data from a chip read appears on the bus or data on the bus is latched in during a write. READ and WRITE must be accompanied by a CHIP SELECT (see *Figures 3* and 4 for read and write cycle timing).

During a read or write, address bits must not change while chip select and control strobes are low.


#### Test Mode

The test mode is for production testing. It allows the counters to count at a higher than normal rate. In this mode the 32.768 kHz oscillator input is connected directly to the ten thousandths of seconds counter. The chip select and write lines must be low and the address must be held at  $1F_{\rm H}$ .





4



TL/F/6148-4 FIGURE 2

## **Interrupt Timing** $0^{\circ}C \le T_A \le 70^{\circ}C$ , $4.5V \le V_{DD} \le 5.5V$ , $V_{SS} = 0V$

**MM58167B** 

Symbol	Parameter	Min	Max	Units
<sup>t</sup> INTON	Status Register Clock to INTERRUPT OUTPUT (Pin 13) High (Note 1)		5	μs
t <sub>SBYON</sub>	Compare Valid to STANDBY INTERRUPT (Pin 14) Low (Note 1)		5	μs
	Trailing Edge of Status Register Read to INTERRUPT OUTPUT Low		5	μs
tSBYOFF	Trailing Edge of Write Cycle (D0 = 0; Address = 16 <sub>H</sub> ) to STANDBY INTERRUPT Off (High Impedance State)		5	μs

Note 1: The status register clocks are: the corresponding counter's rollover to its reset state or the compare becoming valid. The compare becomes valid 61 µs after the 1/10,000 of a second counter is clocked, if the real time counter data matches the RAM data.

# Read Cycle Timing $0^{\circ}C \leq T_A \leq 70^{\circ}C, 4.5V \leq V_{DD} \leq 5.5V, V_{SS} = 0V$

Symbol	Parameter	Min	Max	Units	
t <sub>AR</sub>	Address Bus Valid to Read Strobe (Note 3)	100		ns	
t <sub>CSR</sub>	Chip Select to Read Strobe (Note 2)	0		ns	
t <sub>RRY</sub>	Read Strobe to Ready Strobe		150	ns	
tRYD	Ready Strobe to Data Valid		800	ns	
t <sub>AD</sub>	Address Bus Valid to Data Valid		1050	ns	
t <sub>RH</sub>	Data Hold Time from Trailing Edge of Read Strobe	0		ns	
<sup>t</sup> HZ	Trailing Edge of Read Strobe to TRI-STATE Mode		250	ns	
t <sub>RYH</sub>	Read Hold Time after Ready Strobe	0		ns	
t <sub>RA</sub>	Address Bus Hold Time from Trailing Edge of Read Strobe	50		ns	
	Rising Edge of Ready to Data Valid		100	ns	

Note 2: When reading, a deselect time of 500 ns minimum must occur between counter reads. Deselect is:  $\overline{CS} = 1$  or (WR) • ( $\overline{RD}$ ) = 1. Note 3: If  $t_{AR} = 0$  and Chip Select, Address Valid or Read are coincident then they must exist for 1050 ns.

# Write Cycle Timing $0^{\circ}C \leq T_{A} \leq 70^{\circ}C, 4.5V \leq V_{DD} \leq 5.5V, V_{SS} = 0V$

Symbol	Parameter	Min	Max	Units ns	
t <sub>AW</sub>	Address Valid to Write Strobe	100			
tcsw	Chip Select to Write Strobe	0		ns	
tow	Data Valid before Write Strobe	100		ns	
t <sub>WRY</sub>	Write Strobe to Ready Strobe		150	ns	
t <sub>RY</sub>	Ready Strobe Width		800	ns	
t <sub>RYH</sub>	Write Hold Time after Ready Strobe	0		ns	
t <sub>WD</sub>	Data Hold Time after Write Strobe	110		ns	
t <sub>WA</sub>	Address Hold Time after Write Strobe	50		ns	


Note 4: If data changes while CS and WR are low, then they must remain coincident for 1050 ns after the data change to ensure a valid write. Data bus loading is 100 pF. Ready output loading is 50 pF and 3 kΩ pull-up.

Input and output AC timing levels:


Logical one = 2.0V

Logical zero = 0.8V

## **Read and Write Cycle Timing Diagrams**




MM58167B



Note 7:  $t_{\phi 2} \ge t_{RS8080} + t_{DL8238} + t_{WRY58167B}$ 

FIGURE 6. 8080 System Interface with Battery Backup



·~ •-

**FIGURE 7** 

2

MM58167B

# National Semiconductor

# NS32FX211 Microprocessor Compatible Real Time Clock

## **General Description**

The NS32FX211 is fabricated using low threshold CMOS technology and is designed to operate in bus oriented microprocessor systems where a real time clock and calendar function are required. The on-chip 32.768 kHz crystal controlled oscillator will maintain timekeeping down to 2.2V to allow low power standby battery operation.


## **Applications**

- Fax machines
- Laser printers
- Word processors
- Data logging
- Industrial process control

# **Connection Diagrams**

## Features

- Low power standby operation (10 µA at 2.2V)
- 16-pin DIP and 20-pin PLCC
- Timekeeping from tenths to seconds to tens of years in independently accessible registers
- Leap year register
- Hours counter programmable for 12 or 24-hour operation
- Fully TTL/CMOS compatible



#### Order Number NS32FX211N, NS32FX211V See NS Package Number N16A or V20A

## Absolute Maximum Ratings (Note 1)

If Military/Aerospace specified devices are required, please contact the National Semiconductor Sales Office/Distributors for availability and specifications.

DC Input or Output Voltage	$-0.3V$ to $V_{DD}$ $+0.3V$
DC Input or Output Diode Current	±5.0 mA
Storage Temperature, (T <sub>STG</sub> )	-65°C to +150°C
Supply Voltage, (V <sub>DD</sub> )	6.5V
Power Dissipation, (PD)	500 mW
Lead Temperature	
(Soldering, 10 seconds)	260°C

# **Operating Conditions**

	Min	Max	Units	
Operating Supply Voltage	4.75	5.25	v	
Standby Mode Supply Voltage	2.2	5.5	v	
DC Input or Output Voltage	0	$V_{DD}$	V	
Operating Temperature Range	0°	70°	°C	

## **Electrical Characteristics** $V_{DD} = 5V \pm 5\%$ , T = 0°C to +70°C unless otherwise stated

Symbol	Parameter	Conditions	Min	Тур	Max	Units
VIH	High Level Input Voltage (except XTAL IN)		2.0			v
VIL	Low Level Input Voltage (except XTAL IN)			-	0.8	V
V <sub>OH</sub>	High Level Output Voltage (DB0–DB3)	$I_{OH} = -20 \ \mu A$ $I_{OH} = -1.6 \ m A$	V <sub>DD</sub> - 0.1 3.7			V V
V <sub>OH</sub>	High Level Output Voltage (INT)	l <sub>OH</sub> = −20 μA (In Test Mode)	V <sub>DD</sub> - 0.1			v
V <sub>OL</sub>	Low Level Output Voltage (DB0–DB3, INT)	l <sub>OL</sub> = 20 μA l <sub>OL</sub> = 1.6 mA			0.1 0.4	V V
IIL	Low Level Input Current (AD0-AD3, DB0-DB3)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-90	μΑ
IIL	Low Level Input Current (WR, RD)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-200	μΑ
կլ	Low Level Input Current (CS)	V <sub>IN</sub> = V <sub>SS</sub> (Note 2)	-5		-570	μΑ
Іогн	Output High Level Leakage Current (INT)	$V_{OUT} = V_{DD}$			2.0	μA
I <sub>DD</sub>	Average Supply Current	$\begin{array}{l} \mbox{All } V_{\rm IN} = V_{\rm CC} \mbox{ or Open Circuit} \\ V_{\rm DD} = 2.2 V \mbox{ (Standby Mode)} \\ V_{\rm DD} = 5.0 V \mbox{ (Static Mode)} \end{array}$		4	10 1	μA mA
C <sub>IN</sub>	Input Capacitance		and an	5	10	pF
COUT	Output Capacitance	(Outputs Disabled)		10		pF

Note 1: Absolute Maximum Ratings are those values beyond which damage to the device may occur. All voltages referenced to ground unless otherwise noted. Note 2: The DB0-DB3 and AD0-AD3 lines all have active P-channel pull-up transistors which will source current. The CS, RD, and WR lines have internal pull-up resistors to V<sub>DD</sub>.

NS32FX211

## **AC Switching Characteristics**

READ TIMING: DATA FROM PERIPHERAL TO MICROPROCESSOR V\_DD = 5V  $\pm 5\%, C_L$  = 100 pF

		Com	cation	Units	
Symbol	Parameter	т,	5°C		
		Min	Тур	Max	
t <sub>AD</sub>	Address Bus Valid to Data Valid		390	650	ns
tCSD	Chip Select On to Data Valid		140	300	ns
t <sub>RD</sub>	Read Strobe On to Data Valid		140	300	ns
t <sub>RW</sub>	Read Strobe Width (Note 3, Note 7)	300		DC	ns
<sup>t</sup> RA	Address Bus Hold Time from Trailing Edge of Read Strobe	0			ns
<sup>t</sup> CSH	Chip Select Hold Time from Trailing Edge of Read Strobe	0			ns
t <sub>RH</sub>	Data Hold Time from Trailing Edge of Read Strobe	70	160		ns
t <sub>HZ</sub>	Time from Trailing Edge of Read Strobe Unitl O/P Drivers are TRI-STATE®			250	ns

#### WRITE TIMING: DATA FROM MICROPROCESSOR TO PERIPHERAL V<sub>DD</sub> = $5V \pm 5\%$

		Com	ation		
Symbol	Parameter	T	°C	Units	
		Min	Тур	Max	
t <sub>AW</sub>	Address Bus Valid to Write Strobe _/	400	125		ns
tcsw	Chip Select On to Write Strobe 🖌	250	100		ns
t <sub>DW</sub>	Data Bus Valid to Write Strobe 🖌	400	220		ns
tww	Write Strobe Width (Note 6)	250	95		ns
twcs	Chip Select Hold Time Following Write Strobe	0			ns
twa	Address Bus Hold Time Following Write Strobe	0			ns
two	Data Bus Hold Time Following Write Strobe 🖌	100	35		ns
t <sub>AWS</sub>	Address Bus Valid before Start or Write Strobe	70	20		ns

Note 3: Except for special case restriction: with interrupts programmed, max read strobe width of control register (ADDR 0) is 30 ms. See section on Interrupt Programming.


Note 4: All timings measured to the trailing edge of write strobe (data latched by the trailing edge of WR).

Note 5: Input test waveform peak voltages are 2.4V and 0.4V. Output signals are measured to their 2.4V and 0.4V levels.

Note 6: Write stobe as used in the Write Timing Table is defined as the period when both chip select and write inputs are low, ie.,  $\overline{WS}$ , =  $\overline{CS}$  +  $\overline{WR}$ . Hence write strobe commences when both signals are low, and terminates when the first signal returns high.

Note 7: Read strobe as used in the Read Timing Table is defined as the period when both chip select and read inputs are low, ie.,  $\overline{RS} = \overline{CS} + \overline{RD}$ .

Note 8: Typical numbers are at  $V_{CC} = 5.0V$  and  $T_A = 25^{\circ}C$ .



## **Functional Description**

The NS32FX211 is a bus oriented microprocessor real time clock.

#### **Crystal Oscillator**

This consists of a CMOS inverter/amplifier with an on-chip bias resistor. Externally a 22 pF capacitor, a 6 pF-40 pF trimmer capacitor and a crystal are suggested to complete the 32.768 kHz timekeeping oscillator circuit.

The 6 pF-40 pF trimmer fine tunes the crystal load impedance, optimizing the oscillator stability. When properly adjusted (i.e., to the crystal frequency of 32.768 kHz), the circuit will display a frequency variation with voltage of less than 3 ppm/V. When an external oscillator is used, connect to oscillator input and float (no connection) the oscillator output.

When the chip is enabled into test mode, the oscillator is gated onto the interrupt output pin giving a buffered oscillator output that can be used to set the crystal frequency when the device is installed in a system.

#### **Divider Chain**

The crystal oscillator is divided down in three stages to produce a 10 Hz frequency setting pulse. The first stage is a non-integer divider which reduces the 32.768 kHz input to 20.720 kHz. This is further divided by a 9-stage binary ripple counter giving an output frequency of 60 Hz. A 3-stage Johnson counter divides this by six, generating a 10 Hz output. The 10 Hz clock is gated with the 32.768 kHz crystal frequency to provide clock setting pulses of 15.26  $\mu$ s duration. The setting pulse drives all the time registers on the device which are synchronously clocked by this signal. All time data and data-changed flag change on the falling edge of the clock setting pulse.

#### **Data-Changed Flag**

The data-changed flag is set by the clock setting pulse to indicate that the time data has been altered since the clock was last read. This flag occupies bit 3 of the control register where it can be tested by the processor to sense data-changed. It will be reset by a read of the control register. See the section, "Methods of Device Operation", for suggested clock reading techniques using this flag.

#### Seconds Counters.


There are three counters for seconds:

- a. tenths of seconds
- b. units of seconds
- c. tens of seconds

The registers are accessed at the addresses shown in Table I. The tenths of seconds register is reset to 0 when the clock start/stop bit (bit 2 of the control register) is set to

# NS32FX21

## Functional Description (Continued)



#### **FIGURE 3. Typical System Connection Diagram**

TL/F/11011-5

logic 1. The units and tens of seconds are set up by the processor, giving time setting to the nearest second. All three registers can be read by the processor for time output.

#### **Minutes Counters**

There are two minutes counters:

a. units of minutes

b. tens of minutes

Both registers may be read to or written from as required.

#### **Hours Counters**

There are two hours counters:

a. units of hours

b. tens of hours

Both counters may be accessed for read or write operations as desired.

In 12-hour mode, the tens of hours register has only one active bit and the top three bits are set to logic 0. Data bit 1 of the clock setting register is the AM/PM indicator; logic 0 indicating AM, logic 1 for PM.

When 24-hour mode is programmed, the tens of hours register reads out two bits of data and the two most significant bits are set to logic 0. There is no AM/PM indication and bit 1 of the clock setting register will read out a logic 0.

In both 12/24-hour modes, the units of hours will read out four active data bits. 12 or 24-hour mode is selected by bit 0

of the clock setting register, logic 0 for 12-hour mode, logic 1 for the 24-hour mode.

#### Days Counters

There are two days counters:

a. units of day

b. tens of days

The days counters will count up to 28, 29, 30 or 31 depending on the state of the months counters and the leap year counter. The microprocessor has full read/write access to these registers.

#### Months Counters

There are two months counters:

- a. units of months
- b. tens of months

Both these counters have full read/write access.

#### Years Counters

There are two years counters:

a. units of years

b. tens of years

Both these counters have full read/write access. The years will count up to 99 and roll over to 00.

#### TABLE I. Address Decoding of Real-Time Clock Internal Registers

<b>Registered Select</b>		Address	(Binary)		- (Hex)	Access
negistered beleet	AD3	AD2	AD1	AD0		AUUUSS
0 Control Register	0	0	0	0	0	Split Read and Write
1 Tenths of Seconds	0	0	0	1	1	Read Only
2 Units Seconds	0	0	1	0	2	R/W
3 Tens Seconds	0	0	1	1	3	R/W
4 Units Minutes	0	1	0	0	4	R/W
5 Tens Minutes	0	1	0	1	5	R/W
6 Unit Hours	0	1	1	0	6	R/W
7 Tens Hours	0	1	1 -	1	7	R/W
8 Units Days	1	0	0	0	8	R/W
9 Tens Days	1	.0	0	1	9	R/W
10 Units Months	1	0 .	1	0	A	R/W
11 Tens Months	1	0	1	1	В	R/W
12 Units Years	1	1	0	0	C C	R/W
13 Tens Years	1	1	0	1	D	R/W
14 Days of Week	1	1	1	0	E	R/W
15 Clock Setting/ Interrupt Registers	· 1	1	1	1	F	R/W

#### **Day of Week Counter**

The day of week counter increments as the time rolls from 23:59 to 00:00 (11:59 PM to 12:00 AM in 12-hour mode). It counts from 1 to 7 and rolls back to 1. Any day of the week may be specified as day 1.

#### **Clock Setting Register/Interrupt Register**

The interrupt select bit in the control register determines which of these two registers is accessible to the processor at address 15. Normal clock and interrupt timing operations will always continue regardless of which register is selected onto the bus. The layout of these registers is shown in Table II.

The clock setting register is comprised of three separate functions:

a. leap year counter: bits 2 and 3

b. AM/PM indicator: bit 1

c. 12/24-hour mode set: bit 0 (see Table IIA).

The leap year counter is a 2-stage binary counter which is clocked by the months counter. It changes state as the time rolls over from 11:59 on December 31 to 00:00 on January 1.

The counter should be loaded with the 'number of years since last leap year' e.g., if 1980 was the last leap year, a clock programmed in 1983 should have 3 stored in the leap year counter. If the clock is programmed during a leap year, then the leap year counter should be set to 0. The contents of the leap year counter can be read by the  $\mu$ P.

The AM/PM indicator returns a logic 0 for AM and a logic 1 for PM. It is clocked when the hours counter rolls from 11:59 to 12:00 in 12-hour mode. In 24-hour mode this bit is set to logic 0.

The 12/24-hour mode set determines whether the hours counter counts from 1 to 12 or from 0 to 23. It also controls the AM/PM indicator, enabling it for 12-hour mode and forcing it to logic 0 for the 24-hour mode. The 12/24-hour mode bit is set to logic 0 for 12-hour mode and it is set to logic 1 for 24-hour mode.

**IMPORTANT NOTE:** Hours mode and AM/PM bits cannot be set in the same write operation. See the section on Initialization (Methods of Device Operation) for a suggested setting routine.

All bits in the clock setting register may be read by the processor.

The interrupt register controls the operation of the timer for interrupt output. The processor programs this register for single or repeated interrupts at the selected time intervals.

The lower three bits of this register set the time delay period that will occur between interrupts. The time delays that can be programmed and the data words that select these are outlined in Table IIB.

Data bit 3 of the interrupt register sets for either single or repeated interrupts; logic 0 gives single mode, logic 1 sets for repeated mode.

Using the interrupt is described in the Device Operation section.

IS32FX211

#### TABLE IIA. Clock Setting Register Layout

Function		Data I	Bits Used	Comments	Access	
	DB3	DB2	DB1	DB0	Commenta	Access
Leap Year Counter	X	X			0 Indicates a Leap Year	R/W
AM/PM Indicator (12-Hour Mode)			X		0 = AM 1 = PM	R/W
					0 in 24-Hour Mode	
12/24-Hour Select Bit				x	0 = 12-Hour Mode	R/W
					1 = 24-Hour Mode	

#### TABLE IIB. Interrupt Control Register

Function	Comments	Control Word				
- unotion	Comments	DB3	DB2	DB1	DB0	
No Interrupt	Interrupt Output Cleared,	X	0	0	0	
	Start/Stop Bit Set to 1.				N 19	
0.1 Second		0/1	0	0	1	
0.5 Second		0/1	0	1	0	
1 Second	DP2 - 0 for Single Internet	0/1	0	1	1	
5 Seconds	DB3 = 0 for Single Interrupt	0/1	1	0	0	
10 Seconds	DB3 = 1 for Repeated Interrupt	0/1	1	0	1	
30 Seconds		0/1	1	1	0	
60 Seconds		0/1	1	1	1	

Timing Accuracy: Single Interrupt Mode (all time delays): ±1 ms

Repeated Mode:  $\pm 1$  ms on Initial Timeout, Thereafter Synchronous with First Interrupt (i.e, timing errors do not accumulate).

#### **Control Register**

There are three registers which control different operations of the clock:

- a. the clock setting register
- b. the interrupt register
- c. the control register

The clock setting and interrupt registers both reside at address 15, access to one or the other being controlled by the interrupt select bit; data bit 1 of the control register.

The clock setting register programs the timekeeping of the clock. The 12/24-hour mode select and the AM/PM indicator for 12-hour mode occupy bits 0 and 1, respectively. Data bits 2 and 3 set the leap year counter.

The interrupt register controls the operation of the interrupt timer, selecting the required delay period and either single or repeated interrupt.

The control register is responsible for controlling the operations of the clock and supplying status information to the processor. It appears as two different registers; one with write only access and one with read only access.

The write only register consists of a bank of four latches which control the internal processes of the clock.

The read only register contains two output data latches which will supply status information for the processor. Table III shows the mapping of the various control latches and status flags in the control register. The control register is located at address 0.

The write only portion of the control register contains four latches:

A logic 1 written into the test bit puts the device into test mode. This allows setting of the oscillator frequency. For normal operation the test bit is loaded with logic 0.

The clock start/stop bit stops the timekeeping of the clock and resets to 0 the tenths of seconds counter. The time of day may then be written into the various clock registers and the clock restarted synchronously with an external time source. Timekeeping is maintained thereafter.

A logic 1 written to the start/stop bit halts clock timing. Timing is restarted when the start/stop bit is written with a logic 0.

The interrupt select bit determines which of the two registers mapped onto address 15 will be accessed when this address is selected.

A logic 0 in the interrupt select bit makes the clock setting register available to the processor. A logic 1 selects the interrupt register.

The interrupt start/stop bit controls the running of the interrupt timer. It is programmed in the same way as the clock start/stop bit; logic 1 to halt the interrupt and reset the timer, logic 0 to start interrupt timing.

When no interrupt is programmed (interrupt control register set to 0), the interrupt start/stop bit is automatically set to a logic 1. When any new interrupt is subsequently programmed, timing will not commence until the start/stop bit is loaded with 0.

In the single interrupt mode, interrupt timing stops when a timeout occurs. The processor restarts timing by writing logic 0 into the start/stop bit.

In repeated interrupt mode the interrupt timer continues to count with no intervention by the processor necessary.

#### TABLE III. The Control Register Layout

Access (addr0) DB3 DB2 DB1 DB0 0 0 Interrupt Flag Read From: Data-Changed Flag Write To: Test Clock Start/Stop Interrupt Select Interrupt Start/Stop 0 = Normal 0 = Clock Run 0 = Clock Setting Register 0 = Interrupt Run 1 = Test Mode 1 = Clock Stop 1 = Interrupt Register 1 = Interrupt Stop

Interrupt timing may be stopped in either mode by writing a logic 1 into the interrupt start/stop bit. The timer is reset and can be restarted in the normal way, giving a full time delay period before the next interrupt.

In general, the control register is set up such that writing 0's into it will start anything that is stopped, pull the clock out of test mode and select the clock setting register onto the bus. In other words, writing 0 will maintain normal clock operation and restart interrupt timing, etc.

The read only portion of the control register has two status outputs:

Since the NS32FX211 keeps real time, the time data changes asynchronously with the processor and this may occur while the processor is reading time data out of the clock.

Some method of warning the processor when the time data has changed must thus be included. This is provided for by the data-changed flag located in bit 3 of the control register. This flag is set by the clock setting pulse which also clocks the time registers. Testing this bit can tell the processor whether or not the time has changed. The flag is cleared by a read of the control register but not by any write operations. No other register read has any effect on the state of the data-changed flag.

Data bit 0 is the interrupt flag. This flag is set whenever the interrupt timer times out, pulling the interrupt output low. In a polled interrupt routine the processor can test this flag to determine if the NS32FX211 was the interrupting device. This interrupt flag and the interrupt output are both cleared by a read of the control register.

Both of the flags and the interrupt output are reset by the trailing edge of the read strobe. The flag information is held latched during a control register read, guaranteeing that stable status information will always be read out by the processor.

Interrupt timeout is detected and stored internally if it occurs during a read of the control register, the interrupt output will then go low only after the read has been completed.

A clock setting pulse occurring during a control register read will *not* affect the data-changed flag since time data read out before or after the control read will not be affected by the time change.

#### Initialization

When it is first installed and power is applied, the NS32FX211 will need to be properly initialized. The following operation steps are recommended when the device is set up (all numbers are decimal):

1) Disable interrupt on the processor to allow oscillator setting. Write 15<sub>10</sub> into the control register: *The clock and interrupt start/stop bits are set to 1, ensuring that the clock and interrupt timers are both halted. Test mode and the interrupt register are selected.*  2) Write 0 to the interrupt register: *Ensure that there are no interrupts programmed and that the oscillator will be gated onto the interrupt output.* 

3) Set oscillator frequency: All timing has been halted and the oscillator is buffered out onto the interrupt line.

4) Write 5 to the control register: *The clock is now out of test* mode but is still halted. The clock setting register is now selected by the interrupt select bit.

5) Write 0001 to all registers. This ensures starting with a valid BCD value in each register.

6) Set 12/24 Hours Mode: Write to the clock setting register to select the hours counting mode required.

7) Load Real-Time Registers: All time registers (including Leap Years and AM/PM bit) may now be loaded in any order. Note that when writing to the clock setting register to set up Leap Years and AM/PM, the Hours Mode bit must not be altered from the value programmed in step 5.

8) Write 0 to the control register: This operation finishes the clock initialization by starting the time. The final control register write should be synchronized with an external time source.

In general, timekeeping should be halted before the time data is altered in the clock. The data can, however, be altered at any time if so desired. Such may be the case if the user wishes to keep the clock corrected without having to stop and restart it; i.e., winter/summer time changing can be accomplished without halting the clock. This can be done in software by sensing the state of the data-changed flag and only altering time data just after the time has rolled over (data-changed flag set).

#### **Reading the Time Registers**

Using the data-changed flag technique supports microprocessors with block move facilities, as all the necessary time data may be read sequentially and then tested for validity as shown below.

1) Read the control register, address 0: This is a dummy read to reset the data-changed flag (DCF) prior to reading the time registers.

2) Read time registers: All desired time registers are read out in a block.

3) Read the control register and test DCF: *If DCF is cleared* (*logic 0*), then no clock setting pulses have after occurred since step 1. All time data is guaranteed good and time reading is complete.

If DCF is set (logic 1), then a time change has occurred since step 1 and time data may not be consistent. Repeat steps 2 and 3 until DCF is clear. The control read of step 3 will have reset DCF, automatically repeating the step 1 action.

NS32FX211

#### Interrupt Programming

The interrupt timer generates interrupts at time intervals which are programmed into the interrupt register. A single interrupt after delay or repeated interrupts may be programmed. Table IIB lists the different time delays and the data words that select them in the interrupt register.

Once the interrupt register has been used to set up the delay time and to select for single or repeat, it takes no further part in the workings of the interrupt system. All activity by the processor then takes place in the control register. Initializing:

1) Write 3 to the control register (AD0): Clock timing continues, interrupt register selected and interrupt timing stopped.

2) Write interrupt control word to address 15: *The interrupt register is loaded with the correct word (chosen from Table IIB) for the time delay required and for single or repeated interrupts.* 

3) Write 0 or 2 to the control register: Interrupt timing commences. Writing 0 selects the clock setting register onto the data bus; writing 2 leaves the interrupt register selected. Normal timekeeping remains unaffected.

#### On Interrupt:

Read the control register and test for Interrupt Flag (bit 0).

If the flag is cleared (logic 0), then the device is not the source of the interrupt.

If the flag is set (logic 1), then the clock did generate an interrupt. The flag is reset and the interrupt output is cleared by the control register read that was used to test for interrupt.

#### Single Interrupt Mode:

When appropriate, write 0 or 2 to the control register to restart the interrupt timer.

#### Repeated Interrupt Mode:

Timing continues, synchronized with the control register write which originally started interrupt timing. No further intervention is necessary from the processor to maintain timing.

In either mode interrupt timing can be stopped by writing 1 into the control register (interrupt start/stop set to 1). Timing for the full delay period recommences when the interrupt start/stop bit is again loaded with 0 as normal.

**IMPORTANT NOTE:** Using the interrupt timer places a constraint on the maximum Read Strobe width which may be applied to the clock. Normally all registers may be read from with a  $t_{RW}$  down to DC (i.e., CS and RD held continuously low). When the interrupt timer is active however, the maximum read strobe width that can be applied to the control register (Addr 0) is 30 ms.

This restriction is to allow the interrupt timer to properly reset when it times out. Note that it only affects reading of the control register—all other addresses in the clock may be accessed with DC read strobes, regardless of the state of the interrupt timer. Writes to any address are unaffected.

#### APPLICATION HINTS

#### Time Reading Using Interrupt

In systems such as point of sale terminals and data loggers, time reading is usually only required on a random demand basis. Using the data-changed flag as outlined in the section on methods of operation is ideal for this type of system. Some systems, however, need to sense a change in real time; e.g., industrial timers/process controllers, TV/VCR clocks, any system where real time is displayed.

The interrupt timer on the NS32FX211 can generate interrupts synchronously with the time registers changing, using software to provide the initial synchronization.

In single interrupt mode the processor is responsible for initiating each timing cycle and the timed period is accurate to  $\pm 1$  ms.

In repeated interrupt mode the period from the initial processor start to the first timeout is also only accurate to  $\pm 1$  ms. The following interrupts maintain accurate delay periods relative to the first timeout. Thus, to utilize interrupt to control time reading, we will use repeated interrupt mode.

In repeated mode the time period between interrupts is exact, which means that timeouts will always occur at the same point relative to the internal clock setting pulses. The case for 0.1s interrupts is shown in *Figure A-1*. The same is true for other delay periods, only there will be more clock setting pulses between each interrupt timeout. If we set up the interrupt timer so that interrupt always times out just after the clock setting pulse occurs (*Figure A-2*), then there is no need to test the data-changed flag as we know that the time data has just changed and will not alter again for another 100 ms.

This can be achieved as outlined below:

1) Follow steps 1 and 2 of the section on interrupt programming. In step 2 set up for repeated interrupt.

2) Read control register AD0: *This is a dummy read to reset the data-changed flag.* 

3) Read control register AD0 until data-changed flag is set.

4) Write 0 or 2 to control register. Interrupt timing commences.

#### Time Reading with Very Slow Read Cycles

If a system takes longer than 100 ms to complete reading of all the necessary time registers (e.g., when CMOS processors are used) or where high level interpreted language routines are used, then the data-changed flag will always be set when tested and is of no value. In this case, the time registers themselves must be tested to ensure data accuracy.

The technique below will detect both time changing *between* read strobes (i.e., between reading tens of minutes and units of hours) and also time changing *during* read, which can produce invalid data.

1) Read and store the value of the *lowest* order time register required.

2) Read out all the time registers required. The registers may be read out in any order, simplifying software requirements.

3) Read the lowest order register and compare it with the value stored previously in step 1. If it is still the same, then all time data is good. If it has changed, then store the new value and go back to step 2.

In general, the rule is that the first and last reads *must* both be of the lowest order time register. These two values can then be compared to ensure that no change has occurred. This technique works because for any higher order time register to change, all the lower order registers must also change. If the lowest order register does not change, then no higher order register has changed either.




FIGURE A-1. Time Delay from Clock Setting Pulses to Interrupt is Constant




FIGURE A-2. Interrupt Timer Synchronized with Clock Setting Pulses

2

NS32FX211





# Section 3 Application Notes



## **Section 3 Contents**

AN-353 MM58167B Real Time Clock Design Guide	3-3
AN-359 The MM58174A Real Time Clock in a Battery Backed-Up Design Provides Reliable	
Clock and Calendar Functions	3-20
AN-365 The MM58274C Adds Reliable Real-Time Keeping to Any Microprocessor System	3-29
AN-588 Calibration of the DP8570A Family	3-45
AN-589 DP8570A Timer Clock Peripheral Test Mode and Test Considerations	3-50
AN-595 Flexible Timers on the DP8570A and DP8571A	3-54
AB-43 Typical DP8570A Interface to the IBM PC/XT for the Purpose of Engineering	
Evaluation	3-60
AN-443 Add a Hardware Clock/Calendar to Your IBM PC	3-62
AN-893 Using External Oscillators for the DP857X Real Time Clocks with the Battery Backed	
Mode Selected	3-83
AN-894 DP8570A Experiments to Test the Low Battery Bit or Generate a Periodic Interrupt	3-86
AN-895 Change the Battery on any DP857X Family Member Using Software without Losing	
Time	3-95

# MM58167B Real Time Clock Design Guide

National Semiconductor Application Note 353 Milt Schwartz



The MM58167B is a real-time 24-hour format clock with input/output structure and control lines that facilitate interfacing to microprocessors. It provides a reliable source of calendar data from milliseconds through months, as well as 6 bytes plus 2 nibbles of RAM, which are available to the user if the alarm (compare) interrupt is not used. The MM58167B features low power consumption (typically 4.5 microamperes at 3-volt supply) during battery backed mode, flexible interrupt structure (alarm and repetitive), and a fast internal update rate (1 kHz). Systems utilizing this device include, personal computers, process control, security, and data acquisition.

This application note covers hardware interface to microprocessors, clock interrupts, oscillator operation, accuracy, calibration techniques, software, and battery back-up considerations.

## Hardware Description Overview

**1.0** *Figure 1* is a functional block diagram of the MM58167B.


It can be subdivided into the following sections:

#### 1.1 Oscillator

The oscillator consists of an internal inverter to which the user connects a 32.768 kHz crystal, bias resistor and capacitors, to form a Pierce parallel resonant circuit.

#### 1.2 Prescaler

The prescaler divides the 32.768 kHz oscillator down to 1 kHz using pulse swallowing techniques. The 1 kHz pulse rate is the incrementing signal for the timekeeping counters.



3

### Hardware Description Overview (Continued)

#### **1.3 Timekeeping Counters**

The timekeeping section consists of a 14-stage BCD counter, each stage having read/write capability. The counters keep time in a 24-hour format. *Figure 6* shows the counter detail of calendar-date-time format.

#### **1.4 Rollover Status**

A rollover status bit (read only) informs the user that invalid data may have been read, due to the counters being incremented during a counter read or between successive counter reads. This situation occurs because the counters are clocked asynchronously with respect to the microprocessor.

#### 1.5 RAM

14 nibbles of RAM are provided for alarm (compare) interrupt or general storage. The nibbles are packed 2 per address except for 2 locations, address 08 and 0D (HEX). The nibble at address 08 appears in the high order 4 bits, while the nibble at address 0D appears in the low order 4 bits. See memory map *Figure 2* for details.

Address In HEX	D7 D6 D5 D4	D3 D2 D1 D0			
8	Milliseconds	No RAM Exists			
9	Tenths of Seconds	Hundredths of Seconds			
A	Tens of Seconds	Units of Seconds			
В	Tens of Minutes	Units of Minutes			
С	Tens of Hours	Units of Hours			
D	No RAM Exists	Day of Week Units Day of Month			
E	Tens Day of Month				
F	Tens of Months	Units of Months			

#### FIGURE 2. RAM Memory Map

#### 1.6 Comparator

A 46-bit comparator compares values in RAM against the counters to provide an alarm (compare) interrupt. When a compare occurs, the main interrupt will be activated if the D0 bit of the interrupt control register was set. The standby interrupt will be activated if a "1"was written to address 16 hex.

#### 1.7 Interrupt Hardware

Interrupt hardware consists of two interrupt outputs. The main interrupt and the standby interrupt. The main interrupt is an active high push-pull output. The standby interrupt is an active low open drain output. For the main interrupt, an 8-bit control register allows the user to select from 1 to 7 interrupt rates, as well as an alarm. An 8-bit status register informs the user which of the 8 interrupts occurred. A one-bit control register enables/disables the standby interrupt. The standby interrupt is activated only for the alarm condition. A 46-bit comparator matches the timekeeping counters against RAM for the alarm interrupt.

#### 1.8 Input/Output and Control Lines

The input/output structure consists of a 5-bit address bus and 8-bit bidirectional data bus. The control lines are chip select, power down, read and write. In addition, a ready output is provided for those microprocessors that have wait-state capability and meet the timing requirements of the ready signal. The power down input acts as a chip select of opposite polarity. It differs from the chip select in that it will TRI-STATE® the main interrupt output while the chip select does not TRI-STATE the interrupt. The power down input is intended to facilitate deselecting the chip for battery backed operation. Chip select, read and write are active low controls. The ready output is active low open drain and is caused by chip select and the negative-going-edge of read or write (it is an internal one-shot). If the ready output is not used as a control line when interfacing to a microprocessor, it may be left open circuit.

### **Detail Descriptions**

#### OSCILLATOR

Figure 3 represents the internal and external circuitry that comprise the oscillator. The inverter, which is the heart of the oscillator, is designed to consume minimum power. The inverter has a typical gain of 30 at 1 kHz and 4 at 30 kHz. The oscillator input may be driven from an external source. If this is desired, the input should swing rail-to-rail and be approximately a 50% duty cycle. The oscillator output pin is open circuit for this case. The external oscillator circuit may be constructed using a CMOS inverter or N-FET (see Figures 4a and 4b). Referring to Figure 3, the external 20 M\Omega resistor biases the inverter in its active region. The internal feedback resistor may be too large in value to guarantee reliable biasing.

The external series resistor is to protect the crystal from being overdriven and possibly damaged. Manufacturers of these crystals specify maximum power that the crystal can dissipate. It is this rating which determines what value of series resistor should be used. The two external capacitors are effectively in series with each other (from an A.C. viewpoint). This total value comprises the load capacitance (typically 9 to 13 picofarad) specified by the crystal manufacturer at the crystal's oscillating frequency. The rule of thumb in choosing these capacitors is:

1/load capacitance = 1/C1 + 1/C2

C2 is greater than C1 (typically two to four times)

C1 is usually trimmed to obtain the 32768 Hertz frequency.


The start-up time of this oscillator may vary from two to seven seconds (empirical observation) and is due to the high "Q" of the crystal. Typical waveform values monitored at the oscillator output are observed to be 3 volts peak to peak riding on a 2.5 volt D.C. level (for V + = 5 volts).

#### CHOOSING THE CRYSTAL

The below parameters describe the crystal to be used Parallel Resonant, tuning fork (N cut) or XY Bar

Q>=35,000	
Load Capacitance (CL)	9 to 13 Picofarad
Power Rating	20 Microwatt Max.
Accuracy	User Choice
Temperature Coefficient	User Choice





#### FIGURE 4a

When used with a crystal, the accuracy of the oscillator circuit over voltage and temperature is about +/- 10 PPM. Voltage variations cause about 50% of the inaccuracy and temperature variations account for the other half. This inaccuracy results in an error of about 5 minutes per year. Errors due to external components must be taken into account by the user. If an external oscillator is used, then it determines the accuracy of the clock. The oscillator input pin (pin 10), is a high impedance node that is susceptible to 'noise'. The usual result is the clock gains time at a high rate (on the order of seconds per hour or greater). This noise is usually the result of coupling from pin 9 which is a low order address bit if tied directly to a microprocessor bus. Suggestions to alleviate this condition are:


- 1. Gate pin 9 with chip select.
- Use a slow rise and fall time non inverting buffer such as a CMOS to drive pin 9. If this choice is made, similar CMOS should drive the write and read strobes to avoid timing conflicts.

- TL/F/5727-4 FIGURE 4b 3. Use an external oscillator and drive pin 10 with a
- low impedance device (CMOS or transistor), leave pin 11 open circuit.
- 4. Connect all oscillator components as close as possible to pins 10 and 11.

#### CALIBRATION

To calibrate the oscillator the following method is suggested. The one second repetitive interrupt is activated. This is done by first connecting the interrupt (pin 13) of the clock to the interrupt of the microprocessor. Next a short program is written that sets bit D2 of the interrupt control register, and then enters a loop that wastes time while awaiting an interrupt. The interrupt service routine only needs to read the interrupt status register, which clears the interrupt, and then returns. The result is a 1 second periodic signal at pin 13. The flow chart of *Figure 5* is an example of the detail steps. A time event meter is used to measure the time interval between successive positive going edges of the interrupt will be 1 second when the oscillator is at 32,768 Hertz. AN-353

#### **Detail Descriptions** (Continued)



#### FIGURE 5. Flow Chart for Calibration Using the 1 Hz Repetitive Interrupt

If the 32,768 Hertz is to be measured directly, then a HI impedance LO capacitance amplifier or comparator or CMOS gate should be connected to the oscillator output pin to prevent the measuring instrument from offsetting the frequency of the oscillator. This addition is permanently a part of the oscillator circuit and must be battery backed if the clock is battery backed. The reason for battery backing this buffer is to ensure that its input impedance does not change during the power down operation which could result in the oscillator stopping or being offset in frequency.

#### PRESCALER OPERATION

The 32,768 Hertz signal is divided to an even 32,000 Hertz using pulse swallowing techniques. This is accomplished by


dropping three pulses every 128 counts of the 32,768 Hertz signal. The resulting 32 kHz is then divided to produce 1 kHz which is the internal incrementer for the rest of the timekeeper. This 1 kHz waveform is nonmonotonic with respect to individual periods. As a result, there are 750 short and 250 long periods within a one second interval.

The short period is 1/1024 seconds, and the long period is [1/1024 + 3/32768] seconds. As a result, the milliseconds, hundredths and tenths of seconds "jitter". The inaccuracy on an individual period basis is about 91 microseconds. The period and number of clock edges are correct over one second within the accuracy of the crystal oscillator. The ten thousandths of seconds counter referred to in the data sheet counts milliseconds. The 1 second and slower signals are jitter free. Refer to *Figure 6* for counter block diagram.

#### TIMEKEEPING COUNTERS


The timekeeping counters are intended to work with valid BCD values. In general, if illegal codes are entered then no guarantee is given for recovery. As shown in *Figure 6*, the timekeeping stages are arranged as a ripple counter. The month, day of month, and day of week counters count 1 through N. The milliseconds through hours counters count 0 through N. The rollover of a counter stage increments the next higher order counter. This rollover takes place when the highest allowed value plus one is decoded. For example, in a 30-day month, the day of month counter would decode the value 31, reset to one and increment the month counter, the counter will reset when the write is removed and "may" increment the next higher order counter.


For example, if February 29 is written to the clock, the read back will be a "1" in the day of month counter and the month may read "3". However, for leap year use, February 31 may be written. If this is done on Mar 1 at 0 (hours through milliseconds), then the clock will read March 1 after 24 hours. In this way, the value Feb 31 could be used as an indication that the date is really Feb 29. Refer to *Figures 7A 7B*, and *7C* for flowcharts of a program and alarm interrupt bit map that take leap year into account. Note that the software implemented leap year counter is accurate at least through the year 2048. For a perpetual calendar, a more sophisticated algorithm would be needed.



3-7

3





1.4



TL/F/5727-11


AN-353

Function		Address				DATA							
	Address					Hi Nibble				Lo Nibble			
	4	3	2	1	0	7	6	5	4	3	2	· 1	0
Milliseconds	0	1	0	0	0	0	0	0	0	No RAM Exists			
Hundredths and Tenths of Seconds	0	1	0	0	1	0	0	0	0	0	0	0	0
Seconds	0	i 1	0	1	0	0	0	0	0	0	0	0	0
Minutes	0	1	0	1	1	0	0	0	0	0	0	0	0
Hours	0	1	1	0	0	0	0	0	0	0	0	0	0
Day of Week	0	1	. 1	0	1	No RAM Exists			1	1	Х	Х	
Day of Month	0	1	1	1	0	0	0	0	0	0	0	0	1
Months	0	1	1	1	1	0	0	. 0	0	0	0	1	1

FIGURE 7C. Clock RAM Bit Map For Alarm Interrupt on March 1@ 0 Hrs

#### INTERRUPTS

The MM58167B has two interrupt output pins. The main interrupt (pin 13) is active "high", and is active when the power down pin is "high". When power down (pin 23) is low, the main interrupt output is TRI-STATE. The second interrupt is the "standby interrupt" and is an active low open drain requiring a pull up resistor to VDD. This interrupt is always powered. Refer to *Figure 8* for typical sink current versus voltage out characteristics. Separate control bits exist for the two interrupts. The main interrupt offers two modes of operation which may be combined. Mode 1 is the interactive repetitive interrupt. For this case, a logic 1 is written to one or more bits in the control register (address 11 hex) from D1 through D7, a logic 0 is written into the D0 position. Refer to *Figure 9* for bit configuration of the interrupt control and status registers.



#### FIGURE 8. Typical Curve of I vs V of Standby Interrupt


TI /F/5727-12


As a result, the clock chip provides an interactive repetitive interrupt, that occurs when the selected counter rolls over. That is, the user must clear the interrupt so the next one can be recognized. This is done by reading the interrupt status register (address 10 hex). This read results in the user obtaining the interrupt status (which interrupt occurred) and the clearing of the interrupt output as well as the status register. It is the positive-going-edge of the read strobe which causes the preceding. This clearing action precludes polling the status register. For precision timing, the positive-going-edge of the repetitive interrupt should be used as a trigger. The one-per-second through one-per-month repetitive interrupts will be as accurate as the setting of the crystal oscillator. The ten-per-second interrupt will be accurate to about 91 microseconds. Refer to prescaler description for more detail.

The second mode of main interrupt is the "compare" or "alarm". In this case, a specific value is entered in the RAM of the clock. When the time keeping counter(s) match that value, the interrupt becomes active. Refer to *Figure 11* for a typical example. *Figures 9* and *10* show internal interrupt logic and waveforms. In addition to a specific one time interrupt (alarm), a repetitive interrupt can be achieved by reprogramming the selected RAM location with a future event value. The rule of thumb for an "alarm" interrupt is: All nibbles of higher order than specified are set to C hex (always compare). All nibbles lower than specified are set to "zero".

A programming example of the fastest interrupt rate obtainable (500 per second) is given in *Figure 12*. This program written in NSC800<sup>TM</sup> code (Z80) sets "always compare" conditions (CC hex) in RAM locations 9 through C, E and F. RAM location D which corresponds to the day of the week counter (a single digit), is set to C. RAM location 8 is set to 0. When the first interrupt occurs, the service routine reads the status register and sets the value 2 into RAM location 8. At succeeding interrupts, the values 4, 6, 8 are set into location 8 and the sequence repeats.

If an interrupt is activated and the interrupt occurs during battery backed operation (power down), the main interrupt output will be active high when system power returns.





#### FIGURE 12. NSC800 Assembly Code for 500 Hz Interrupt

				ORG 080	он		*	
4092			DFCFT	EQU 04092	2			
4092			CONT	EQU 04092 EQU 04091				
4090			STAT	EQU 04090				
408F			MON	EQU 0408F	H Constant			
408E			DOM	EQU 0408E	н			
408D			DOW	EQU 0408D		•		
408C			HRS	EQU 0408C		and the second		
408B 408A			MIN SEC	EQU 0408B EQU 0408A				
4088			HT	EQU 0408A EQU 04089			. •	
4088			MIL	EQU 04088				
1010			VEC1	EQU 0101C				
101D			VEC2	EQU 0101D	н			1
0800'	3E 00		INIT:	LD	A.0	OFT UD INTO	T FOR NSC888	
0802'	32 101C		INIT:	LD	(VEC1),A	SEI OF INIK	FI FUR NSC888	
0805'	3E 09			LD	A,009H	•		
0807'	32 101D			LD	(VEC2),A			
080A'	3E 08			LD	A,8	•		
0800'	D3 BB			OUT	(OBBH),A	•	. •	
080E'	31 1FFF			LD	SP,01FFFH	INIT STACK	POINTER	
0811'	3E FF			LD	A,OFFH			
0813'	32 4092			LD	(Reset),A	RESET ALL CI	LOCK COUNTERS	
0816'	3E 00			LD	A,0			
0818'	32 4091			LD	(CONT),A	CLEAR INTRP		
081B' 081E'	3A 4090 3E CC			LD LD	A, (STAT)	SET RAM FOR	ENDING INTRPT	
0820'	32 408F			LD	A,OCCH (MON),A	;SEI AAM FUA	INIKII	
0823'	32 408F			LD	(DOM),A			
0826	32 408D			LD	(DOW),A			
0829	32 408C			LD	(HRS),A			
0820'	32 408B			LD	(MIN),A			
082F'	32 408A			ГD	(SEC),A			
0832	32 4089			LD	(HT),A			
0835'	3E 00			LD	A,0			
0837'	32 4088 3E 01			LD LD	(MIL),A			
083A' 083C'	32 4091			LD	A,1 (CONT), A	SET COMPARI	TNTEPT	
083E'	FB			EI	(0011), A	,DEI COMINI		
0840'	00		NOP:	NOP				
0841'	C3 0840			JP	NOP	WASTE TIME	WAITING	
					-	;INTERRUPT		
						ETS THE VALUE IN . IF YES THEN SE		
					EAR INTERRUPT		LINAM	
					O RAM MILLISE			
					T AND RETURN.			
						DS IS "HIGH" O	RDER NIBBLE	
			;ONLY					
				ORG 090	0 <sup>1</sup>			
				0113 030		· • •		
0900'	3A 4088		LD	A,(MIL)		GET RAM MIL	LSEC	
0903'	E6 FO		AND	OFOH		;MASK		
0905'	FE 80		CP	080H		; ? RAM=8		
0907'	CA 0912'		JP	Z,ZERO				
090A'	C6 20		ADD	A,020H				
090C' 090F'	32 4088		LD	(MIL),A				
090F' 0912'	C3 0917' 3E 00	ZERO:	JP LD	RETRN				
0912	32 4088	LERU:	LD	A,O (MIL),A				
0917'	3A 4090	RETRN:		A, (STAT		CLEAR INTRP:	r	
091A'	FB		EI			,	-	
091B'	C9		RET					
					END			

AN-353

NAME ('I500Hz') TITLE 58167 500HZ REPETITIVE INTERRUPT (10/13/83)

:THIS PROGRAM IS FOR USE WITH THE 58167 FOWER DOWN BOARD :INTERFACED TO THE NSC888 BOARD. CODE IS NSC800. :A 500HZ SIGNAL IS GENERATED AT THE INTERRUPT PIN (13). :THIS SIGNAL IS GENERATED USING THE COMPARE INTERRUPT :AND UPDATING THE 'RAM' FOR THE NEXT INTERRUPT · 🕶

#### STANDBY INTERRUPT

A "1" written to address 16 hex enables the standby interrupt and a "0" disables it. This interrupt also becomes active when a match exists between time keeping counter(s) and a value written into RAM. The standby interrupt can be cleared as soon as it is recognized. The user should ensure that a delay of one millisecond or greater exists prior to reenabling the standby interrupt. This delay is necessary because of the internal signal level which causes the interrupt. If this delay does not occur, then the standby interrupt becomes reactivated until the internal latched compare goes away, which occurs at the next 1 kHz clock. *Figure 10* illustrates interrupt timing.

#### RAM

RAM is organized as shown in *Figure 2*. There are 4 bits of RAM for each BCD counter. The RAM may be used as general purpose or for an alarm interrupt. It is possible under certain conditions to perform the compare interrupt and use selected bits of the RAM for general purpose storage. Any RAM position that is set for the 'always compare' condition allows the user to manipulate the 2 LO order bits in each nibble. However, the 2 high order bits in each nibble position must be maintained as logic 1'S. For example, the user may have an alarm interrupt that does not use the day of the week as a condition for interrupt. Therefore the 2 low order bits might be used as a 4 state software counter to keep track of leap year. Reading and writing the RAM is the same as any standard RAM.

#### HARDWARE INTERFACE CONSIDERATIONS

There are four basic methods of interfacing the MM58167B to a microprocessor. They are memory mapped, microproc-

essor ports (for single chip microprocessors like the 8048), peripheral adapter, and separate latches. The advantage of memory mapped interface is use of all memory reference instructions. The disadvantages are the processor may need to be "wait-stated" and the environment is noisier with respect to the crystal oscillator. Refer to *Figure 13* for typical bus interface.

Microprocessors that have separate ports (16 are sufficient) offer the capability to interface directly without "wait-stating", or additional device count. Eight of the port bits (data) need to be bidirectional for this interface. *Figure 14* indicates port interface. Programmable peripheral interface devices such as the 8255A or NSC810 afford the user the advantage of timing control by data bit manipulation, as well as a less noisy environment with respect to the oscillator circuit. *Figure 15* depicts the 8255A and NSC810 interface.

External latches may be used in place of the programmable peripheral interface device. This results in higher package count but easier troubleshooting. Also, the latches do not have to be manipulated through a control register. *Figure 16* illustrates the external latch approach. For the peripheral approaches, address, data, chip select, read and write strobes are manipulated by controlling the data bus bits via program execution. The peripheral interface approach facilitates calibration of the oscillator because the chip select, read strobe, and address lines can be set to steady state logic levels. Refer to calibration techniques for more detail.






FIGURE 13. Typical µP Bus Interface








TL/F/5727-17

FIGURE 15. MM58167B Interfaced to  $\mu$ P Through Peripheral Adapter




TL/F/5727-18

### POWER DOWN/BATTERY BACKED CONSIDERATIONS

Battery back up of the clock may be considered by the user to maintain time during power failure, provide a "wake-up" alarm, save the time that power failure occurred, calculate how long power failure lasted. The first step in providing a battery backed system is to isolate the system supply from the battery. This is to ensure that the battery is not discharged by the system supply when power failure occurs. Figure 17 shows two techniques to achieve isolation. Figure 17A is implemented using diodes to isolate. In one case a Schottky diode is used to guarantee minimum voltage drop loss, while in the other case an adjustable voltage regulator (LM317) is used from a higher voltage and regulated to about 5.7 volts. A 1N914 diode in series with the regulator achieves the 5 volts for the clock. The Schottky diode has a drop of about 0.3 volts. Thus the V+ of the clock is typically at 4.7 volts. The user must be cautious about input signals not exceeding the 4.7 volt V+, since the clock is a CMOS device. This situation could arise if the devices driving the inputs of the clock were CMOS and received power from the 5 volt system supply. Figure 17B makes use of the low

saturation of a PNP transistor (0.1 volt) to take care of the above situation. The NPN transistor is used to achieve isolation. The zener diode ensures that the circuit stops conducting and appears open circuit before the battery switches in. Some basic considerations must be adhered to in a power down situation where the real time clock is battey backed. One is to ensure no spurious write strobes accompanied by a chip select occur during power down or power up. Another is to guarantee the system is stable when selecting/dese-

is to guarantee the system is stable when selecting/deselecting the clock. Also, any legitimate write-in-progress should be completed. To accomplish this, hardware is implemented such that early power failure is detected (usually a comparator detects DC failure, a retriggerable one-shot detects AC failure) See *Figures 18* and *19*. At this point the clock chip is deselected. The worst case is the power fails faster than the detection circuit can cause deselection. When power returns, the hardware detects power on, but the system must be stable before communication is allowed with the real-time-clock.






FIGURE 19. Sensing AC Line Failure Using Retriggerable One Shot

TL/F/5727-24

The 5-volt system supply rise and fall time characteristics during power turn on and power failure must be known. Care should be taken to allow a legitimate write in progress to be completed. This is necessary because a "short write" could cause erroneous data to be entered to the clock. If the clock is used as a "read only" device (except for initialization of calendar and time), the circuitry to allow a write in progress to be completed does not have to be considered. For this situation, a switch in series with the write strobe could be implemented such that the write line to the clock is "tied high" after initialization.

To sense system DC power failure a comparator and voltage reference may be used. Figure 20, detail 1, shows the comparator and voltage reference configured such that the comparator output is "low" when 5-volt system power is greater than 4.6 volts. If possible, the power fail trip point should be referenced to a lightly loaded (fast collapse) DC supply, preferably higher than the 5-volt system. This would allow early sense of power failure. When using comparators, the output may oscillate as the trip point is approached. The oscillation is caused by noise on the DC line appearing at the input to the comparator when at or near the trip voltage. The cleaner the supply, the less chance of oscillation. In all cases, hysteresis should be used to minimize oscillations. Note that the 20 kohm pull-up resistor is connected to the battery backed node, while the LM139 V+ pin is connected to the 5-volt system supply. Used this way, the comparator does not draw any current except leakage from the battery and the output remains high during power down.

To sense AC failure, a retriggerable one-shot may be used. The RC time out may be adjusted to allow for one or more cycles of 60 Hertz to be missed. Using this approach, the Q output of the one-shot is always high while 60 Hertz is present. When a cycle is missed the one-shot times out and Q goes low. *Figure 19* shows AC sensing. This technique could cause a spurious deselect of the clock if a "glitch" occurs on the AC line resulting in a missed cycle.

For this application, the circuit shown in *Figure 20* was implemented. The MM58167B was interfaced to the NSC800 in memory mapped locations. A demo program was written to exercise the clock, and display time, date and calendar. Power was switched on and off at irregular intervals, to test the battery backed circuitry. The results were that the clock kept correct time. Battery backed current for all circuitry was 10 microamp. For general consideration, this circuitry allows a chip select in progress to be completed.

### **FUNCTIONAL OPERATION OF FIGURE 22**

Power up sequencing consists of the LM139 (comparator) making a high to low transition when the 5-volt system supply exceeds 4.6 volts. This transition triggers the 0.5 second one-shot causing its output to be low and removes the low reset on the D flip-flop through nand gate J. The output of the 2 microsecond one-shot is "don't care" once the comparator switches from high to low. After 0.5 seconds, the system is assumed to be stable, and the D flip-flop output which was reset is clocked high by the low to high transition of the 0.5 second one-shot. Thus, the clock chip is enabled allowing normal communication with the microprocessor.

The power down sequence consists of the comparator making a low to high transition when the 5-volt supply is less than 4.6 volts. If no chip select is present, the D flip-flop is reset through nand gate J, causing pin 23 of the clock to be low (deselected). If a legitimate chip select was in progress, the reset action through nand gate J would be delayed by the low level of the 2-microsecond one-shot.

4 74HCT00 0 SERIAL 5 2 INPUTS 4 WAIT STATE GENERATOR 74LS164 EDGE CONNECTOR P1 FROM P1-40 CLK E -RESET 74HCT00 PIN # SIGNAL 31 A15 74HCT00 10 D TO P1-20 20 4 29 A14 6224 27 A13 1N914 DM8131 11 25 A12 DETAIL 1 13 ٨ 23 A11 5¥ 2N2905 21 15 A10 5٧ ( **(** 19 17 15 A9 ÷ Ţ A8 0.1 Ŧ 18914 A7 4000-43FF 20k TO P1-22 D1 = 3.0V ± 10% 5k LM13 Vina VTRIP SET = 0.5 SEC AT 2.4V ٦**۲** 10k WHEN SYSTEM 1/2 74HC123 3 2N2222 200\* + 50k LM385-2.5 G  $\odot$ ÷ ÷ 4080 - 40FF 74LS138 → CS1 ÷ в  $\odot$ I ADIRAN 10 Ī 16 Ţ 100 pF 74HC74 12 \$4 2 -1(\* 13 11 厕 A6 20 20 F F A5 9 A4 1/2 74HC123 201 A RESET1 7 A3 5 G AZ 3 A1 (A A0 MM581878 TEXTOOL Z1F SOCKET ۱ 16 D7 14 D6 12 DS INTERRUPT 10 D4 13 4 C 8 D3 6 D2 4 D1 2 DO 39 **9**0 37 WR 2N2222 24 ALE Ī 22 pF 22 ĈŜ Ī ► TO P1-34 34 RSTA 40 20 CLX WAIT ALL 100k TL/F/5727-23 FIGURE 20. Detailed Schematic of Power Down Circuitry, and Interface to NSC888 Board

**E36-NA** 

÷

1

A wait state generator was implemented using the chip select as the sensing signal. This was necessary to comply with NSC800 wait state timing. The wait generator provides 2 microseconds of access time, which is more than adequate to meet clock chip timing requirements. Pull-down resistors were added to all clock input pins to guarantee no floating inputs during power down. This ensures that the CMOS clock does not draw excessive current from the battery during power down. A diode isolates 5-volt system from the battery (A 3.4-volt Tadiran nonrechargeable lithium cell was used in this application). The battery is isolated from the 5-volt supply using a circuit comprised of PNP and NPN transistors along with a zener diode. The zener diode value was selected such that the combined voltage drop of the zener and the base emitter of the NPN transistor was greater than the battery voltage. This ensures no current will be drawn from the battery by the 5-volt supply when power failure occurs.

The battery is non rechargeable, but allows up to 10 microamps of charge current without damaging the cell. An LM139 voltage comparator and LM385-2.5 voltage reference were used to sense the 5-volt system supply. The trip point was adjusted such that when the 5-volt supply dropped to 4.6 volts, the comparator output showed oscillation, but caused no malfunction. The duration of the oscillation was about 100 microseconds. Burst noise on the 5-volt supply was about 0.5 volts peak to peak. For the circuitry implemented, the 5-volt supply should fall no faster than 1 volt per millisecond. This rate allows 100 microseconds for deselect to take place while the supply is falling from 4.6 volts to 4.5 volts. Thus, deselect occurs while the system is stable.

### **Miscellaneous**

### TEST MODE

The test mode applies the oscillator output to the input of the millisecond counter. This affords faster testing of the chip. This mode is intended for factory testing, where a programmable pulse generator is used. A pulse rate of 50 kHz may be used in this mode. The pulse should swing rail to rail and be a square wave. Apply the pulses to the oscillator input pin, leaving the oscillator output pin open circuit. The basic sequence would be to write values to the counters, enter test mode and apply a known number of pulses. Next, read the counters using normal read sequence.

### GO COMMAND

A write to address 15 hex (data is a "don't care") will clear the seconds through milliseconds counters. If the value in the seconds counter is equal to or greater than 40 when the GO command is executed, then the minute counter will be incremented.

### **RESET COMMAND**

Writing the value FF hex to address 12 hex causes the hours through milliseconds counters to be reset to zero. The day of week, day of month, and month counters are set to 1. Writing the value FF hex to address 13 hex causes the RAM to be cleared.

### **GENERAL TIMING CONSIDERATIONS:**

To guarantee a valid read/write without using the ready output, the following criteria must be met.

### **Read Operation**

When reading, a deselect time of 500 nanoseconds must occur between counter reads. Read strobe width must not exceed 800 microseconds. The deselect condition is:  $\overline{CS} = 1$  or ( $\overline{RD}$ ) • ( $\overline{WR}$ ) = 1.

- 1. Address setup before RD = 100 ns min
- 2. CS to RD=0 min
- 3. Read strobe width = 950 ns min
- 4. Address hold after read = 50 ns min
- 5. Deselect time = 500 ns min

### Write Operation

- 1. Address set up before WR = 100 ns min
- 2. CS to WR=0 ns min
- 3. WR and data must be coincident for 950 ns min
- 4. Data hold after WR = 110 ns min
- 5. Address hold after WR = 50 ns min

If the ready output is used to guarantee read write operation, then the following recommendations are made. Referencing the April 1982 data sheet, during a read, the ready line makes its positive transition 100 nanoseconds before data is valid. (Not shown in the data sheet.) The user should not use this signal to latch data into an external latch. If this signal is used to wait state a microprocessor, then a critical examination of the microprocessor timing with respect to when it terminates its wait stated cycle must be made. This examination must also include any set-up time the processor needs prior to reading data. Also, note that the ready output (per the data sheet) negative-going-edge occurs 150 nanoseconds after the read or write strobe has gone low. Check microprocessor timing to ensure that the ready signal would be recognized as a "wait-signal".

It is not advised to perform sequential reading by connecting chip select and read low and cycling through the counters by changing address lines. The reason is that it is possible to cause an internal latch to "flip," the result being an error in timekeeping.

### SOFTWARE CONSIDERATIONS

### **Reading the Counters**

A read of one counter plus the rollover status bit or all the counters plus the rollover bit must be done within 800 microseconds. If the rollover status bit is a "1" then a complete read of counter(s) must be performed again. The 800 microsecond value is conservative. If the time between the read of any counter(s) and the rollover status bit exceeds 800 microseconds, then the status bit will always be set. The order of reading must be counter(s) first, then rollover status bit. This is because the positive going edge of the read strobe clears the status bit. Refer to Figure 23. The status bit is enabled for a period of 150 microsecond maximum at a rate of 1 kHz. If during this 150 microsecond period a counter(s) read occurs, the status bit will be set. This is true no matter how often the rollover status is read during that time period. Each rollover status read resets the status bit, but any counter read within the 150 microsecond period will set the rollover status bit. If the counters are read after a repetitive interrupt, then allow 150 microseconds (conservative) from the sense of the interrupt to the read of the counters (ripple delay time) and the data will be valid. If the counters are read after a compare interrupt, the read can occur immediately and will be valid.

### Writing the Counters

The counters may be written to in any order, because the write overrides the internal increment. If it is desired to write all the counters without increments occurring in between writes, then the complete write operation must be performed within 800 microseconds. As long as valid BCD values (with respect to the specific counter) are written, no other counter is affected by the write. In general, writing the high order to low order counters is the conservative approach. This method is less susceptible to increments between writes for cases where the writing takes greater than 800 microseconds. For initialization of time, if the "GO" command is issued prior to any write, then 10 milliseconds are available to write from months through tenths and hundredths of seconds without any effect due to internal incrementing.

### BIBLIOGRAPHY

MM58167B Microprocessor Real Time Clock Data Sheet April 1982.

"Crystal Oscillator Design And Temperature Compensation" By Marvin E. Frerking.

National Semiconductor Application Note AN-313 D.C. Electrical Characterization Of High Speed CMOS Logic. LM-139 Quad Voltage Comparator Data Sheet.




FIGURE 21. Rollover Status Bit Logic

AN-353

## he MM58174A Real Time Clock in a Battery Backed-Up Design Provides Reliable Clock and Calendar Functions

National Semiconductor Application Note 359 Steve Munich

### INTRODUCTION

National Semiconductor's MM58174A microprocessor real time clock is a reliable and economical solution to adding clock and calendar timekeeping to any system. This metal-gate CMOS circuit (*Figure 1*) will operate with a supply voltage as low as 2.2V, allowing easy implementation of battery back-up circuitry to maintain timekeeping year after year, even when the system's main supply fails. The MM58174A has counters for months, day of month, day of week, hours, minutes, seconds and tenths of seconds, as well as a register for automatic leap year calculations. Also included are periodic and single interrupt capabilities at 0.5, 5 and 60 second intervals.

This application note will describe how to interface the MM58174A to microprocessors with battery backed-up circuitry. Included will be a functional circuit description, trouble-shooting hints, crystal oscillator adjustment and supplier information. Please refer to the data sheet for AC and DC electrical specifications and timing diagrams.


### shown in Table I. Months through minutes registers can be read and written to. Tens of seconds, units of seconds and tenths of seconds registers can only be read and are reset to zero when counting is enabled by the start/stop flip-flop. When properly addressed, a nibble of data appears on the data pins DB0-DB3 when a read occurs, and data is accepted on these pins during a write. Any unused data pins will be ignored during a write operation (e.g., days of week uses only DB2 through DB0). To insure proper counter incrementation and accessing, all timing specifications must be observed. It is particularly important that the $\overline{RD}$ strobe width be less than 15 $\mu$ s for the highest timekeeping accuracy, but never greater than 15 ms.

Address 13 is a write only leap year status register. Writing a "1" to DB3 at this address will cause the time 02/28 23:59 59.9 to roll over to 02/29 00:00 00.0 in one-tenth of a second. If a "1" is instead written to any other data bit, the roll-over will go to 03/01 00:00 00.0 and the leap year will occur as shown in Table II.



### **Reading and Writing the Time**

The MM58174A has BCD counters for tenths of seconds through months, which are accessed by a 4-bit address as



### TABLE I. Address Decoding for Internal Registers


······						
Selected Counter	Address Bits AD3 AD2 AD1 AD0			Mode		
Test Only	0	0	0	0	Write Only	
1 Tenths of Seconds	0	0	0	1	Read Only	
2 Units of Seconds	0	0	1	0	Read Only	
3 Tens of Seconds	0	0	1	1	Read Only	
4 Units of Minutes	0	1	0	0	Read or Write	
5 Tens of Minutes	0	1	0	1	Read or Write	
6 Units of Hours	0	1	1	0	Read or Write	
7 Tens of Hours	0	1	1	1	Read or Write	
8 Units of Days	1	0	0	0	Read or Write	
9 Tens of Days	1	0	0	1	Read or Write	
10 Day of Week	1	0	1	0	Read or Write	
11 Units of Months	1	0	1	1	Read or Write	
12 Tens of Months	1	1	0	0	Read or Write	
13 Years	1	1	0	1	Write Only	
14 Stop/Start	1	1	1	0	Write Only	
15 Interrupt	1	1	1	1	Read or Write	

TABLE II.	Years S	Status	Register
-----------	---------	--------	----------

Mode: Address 13, Write Mode					
DB3 DB2 DB1 DB0					
Leap Year	1	0	0	0	
Leap Year-1	0	1	0	0	
Leap Year-2	0	0	1	0	
Leap Year-3	0	0	0	1	

### **Detecting Changed Data**

It is possible that during a sequential read of months through tenths of seconds a roll-over may occur. If the time at the start of the read is 23:59 59.5 and it rolls over to the time 00:00 00.0, the microprocessor could read back 23:50 00.00 or 23:00 00.0, etc. Wrong data could also be stored in the clock if the clock is running and is updated during a write (the start/stop flip-flop discussed in the next paragraph will help avoid invalid writes). The MM58174A has a datachanged flip-flop which indicates that a tenths of seconds roll-over has occurred. This flip-flop sets all the data lines high each time the tenths of seconds counter is updated. The "F" on the data lines is then cleared by the next low-tohigh transition of any read strobe. In a sequential read of the counters, the tenths of seconds counter may change while the read strobe is low, but an "F" may never be seen before the read strobe comes high. Thus, the "F" may not be detected, although the experimental probability of this occurrence is approximately one in ten thousand reads, in the worst-case. It is essential to restart the whole sequence of reads, beginning from the tens of months register whenever an "F" is encountered on the data lines. A better procedure, outlined in the flowchart of Figure 2, would be to always begin each sequence of reads with the tenths of seconds register and end with this register. If comparing the two values read from this register shows them to be equal, the read is valid. If the compare yields two different values, repeat the same sequence of reads until the same value is read from the tenths of seconds register at the beginning and end of the sequence. It is advisable to use a machine code clock reading routine, or else the time to execute machineinterpreted code may be longer than one-tenth of a second, invalidating all sequential reads.



### Clock Accuracy

Two important factors affect the accuracy of the MM58174A. Any internal counter can jitter by  $-30.5 \ \mu$ s, meaning that the true count can be late by this amount. Also, whenever the clock is restarted (see next section), instead of holding a "0" in the tenths of seconds position for one-tenth of a second, the clock is restarted, one-tenth of a second is lost. Accuracy would be maintained if the clock is restarted 0.1 second after the time reference's minutes change.

### arting and Stopping the Clock

I shows that address 14 accesses the start/stop flip-A "1" on DB0 will start the clock. Writing a "0" to DB0 .m stop it. This flip-flop is used for precise starting and stopping of the clock. It also prevents writing invalid data during a clock roll-over, as mentioned in the last paragraph. Before any sequence of writes, stop the clock. Restart it after the last write is completed.

### Interrupts

14

The interrupt counter is controlled internally by three sequential flip-flops. By sending a sequence of read strobes to these flip-flops, the interrupt counter can be cleared or enabled. Initialization is necessary at power-up because these flip-flops can come up in any state. It is also necessary to re-initialize if an interrupt is not serviced within 16.6 ms. To initialize interrupts on the MM58174A, first write a "0" on the data lines at address 15, then read that address three times. The first read will clear any interrupts set. The second read insures that the counter is reset and the third read enables interrupts. Be sure to disable the microprocessor from accepting interrupts before initialization, because the act of writing "0" to address 15 may cause an interrupt.

Table III indicates which values turn on the 0.5, 5 and 60 second periodic or single interrupts. These values are written at address 15, as shown in Table I. To set a particular interrupt, a write need only occur once. Whenever an interrupt occurs, the signal at pin 13 falls from high to low.

		•	•
TABLE I	II. Interru	ot Selection	and Status

Mode: Address 15, Read or Write Mode						
Function DB3 DB2 DB1 DB0						
No Interrupt	X	0	0	0		
Int. at 60 Sec. Interval <sup>†</sup>	*	1	0	0		
Int. at 5.0 Sec. Interval <sup>†</sup>	*	0	× <b>1</b> –	0		
Int. at 0.5 Sec. Interval†	*	· Q	0	1		

\*0 for single interrupt (write), 1 for periodic interrupt (write).

X = Don't care (read)

<sup>†</sup>Add 16.6 ms to each time interval

To service the interrupt, read address 15 three times. This causes the interrupt output on pin 13 to return high and restarts the interrupt timer if periodic interrupts have been selected. The interrupt register may be read to see which interrupts have been set, but the MM58174A has no status bit indicating that the clock has sent out an interrupt. A version prior to the MM58174A had interrupt acknowledgement capability (the MM58174), so be sure to match data sheets with the correct parts. One final note about interrupts: they are not intended to be generated when the chip is in the sleep mode (see next paragraph). The MM58174A must be running with at least a 4V supply for interrupts to function.

### **Powering Down and Up**

When the supply to pin 16 falls below 5V, timing becomes much more critical because propagation delays increase with a lowering of the power supply voltage. Note that the data sheet has timing specifications for 5V, and although

the part is fully operational down to 4V, your design may not tolerate it. When the supply falls below 4V but stays above 2.2V, the MM58174A is in the sleep mode and only microamps are drawn from the battery. In this mode, the chip is not accessible by reading or writing, but time is being maintained.

On power-up from zero volts  $V_{\mbox{CC}}$  , one must make sure the chip is not in the test mode. This is done by writing a "0" to DB3 at address 0. It is advisable to do this even when coming out of the sleep mode. The test mode is mainly for production testing of the circuit.

There are several things to consider when designing the power-down circuitry. The basic functional requirements are to disable the chips before full power loss or malfunction, and to wait for V<sub>CC</sub> to stabilize before enabling the chip on power-up. A desirable feature would be to allow the read or write in progress to complete. Figures 3 and 4 include a typical power-down circuit which achieves these goals. In general, avoid using TTL since it is not rated below 4.5V. The power-down circuitry's signals to the MM58174A must not be allowed to deviate more than a diode drop above the clock's supply or below ground in order to avoid triggering SCR latch-up. Finally, be sure to use a PNP switch instead of a diode to disconnect the power supply from the battery. This will allow the MM58174A to see a  $V_{CC}$  closer to 5.0V coming from the main supply rather than 4.3V, enhancing timing requirements. See Figures 3 and 4 and the next section for more information on design of power-down circuitry.


### DESIGN IDEAS

Figures 3 and 4 show two possible ways of interfacing the MM58174A to a microprocessor; the former with wait stating and the latter eliminating wait states using the NSC810A RAM/IO timer as a peripheral interference adapter.

### **Real Time Clock Interface with Wait States**

The design of Figure 3 uses wait states to guarantee that the set-up and hold times of the MM58174A are satisfied. If one can afford to constrict his microprocessor throughput while accessing the MM58174A, this design has the advantages of simplified software and somewhat less expensive hardware. Decreased microprocessor throughput is usually not a consideration in most applications unless the clock is continuously being accessed for a real time display, while at the same time the processor is multiplexing the execution of other tasks.

The HC688s of Figure 3 are used to fully decode the 4 bits of address space for the real time clock and to generate chip select and wait states. Each time an address between 4080H and 408FH appears on the address lines of the bus, the second of the cascaded HC688s generates a low strobe that allows the power-down circuitry to create a chip select, and also fires an HC123 one-shot configured to drive a 2 µs wait state onto the wait line of the microprocessor bus. For wait lines of the opposite polarity, the HC123's Q output could be used. A shift register may also be configured to give the proper access time delay.




4

[]

1

:

ω



3-24

ţ

Power is supplied to the parts from a 5.0V supply which is disconnectable by a PNP switch to a battery. When the main supply is on, the PNP in saturation brings the voltage at node B to about 4.8V. The diode near node B is back-biased to keep the battery from discharging and to protect it from damage by isolating it from 5V. If the main supply were to drift far enough downward, the diode would forward-bias, bringing node B to 0.7V below the battery voltage. Since the clock is now in the sleep mode, the only parts needed to be powered by the battery are the clock and the power-down circuitry. An NPN between the bus connection and the WR pin, as shown Figure 3, will reduce power consumption without inverting the signal into this pin. This is made necessary because both CS and WR pins on the MM58174A have internal pull-ups to V<sub>CC</sub> which cause unnecessary current drain if either input were to become grounded. The NPN switch isolates the WR from ground, while the CS input is held high by the power-down circuitry.

### **Power-Down Circuitry Operation**

The power-down circuitry of *Figures 3* and *4* consists of seven HC00 NAND gates and an LM139 low voltage comparator with an assortment of resistors, diodes and capacitors at the differential input.

With the 5.0V supply on, the assortment of diodes, resistors and capacitors at the comparator's differential input creates a low output. But when the supply is off, the battery pulls this output high through the 20 kΩ resistor. On power-up, after a short delay by the diodes and capacitors at the inverting input, the LM139's low level output enables a latch made from HC00 NAND gates to allow a chip select from the 'HC688 (*Figure 3*) or the NSC810A (*Figure 4*) to flow through to pin 1 ( $\overline{\text{CS}}$ ) of the MM58174A.

As power from the 5.0V supply falls below 4.5V, the comparator's output immediately goes high. This threshold voltage is adjustable by the 200 k $\Omega$  potentiometer at the LM139's inverting input. A high output from the comparator to the NAND latch will disable chip selects to the MM58174A.

So as power begins to fail, this circuit will allow reads or writes to the MM58174A to go to completion if the chip is selected before the LM139's output goes high. It is assumed that the MM58174A's  $\overline{\rm CS}$  pin returns high before the supply fails to 4.0V (the minimum V<sub>CC</sub> to access the chip). The length of the chip select strobe determines the limit of how fast the main power supply can drop from 4.5V to 4.0V. In situations where power failure detection is more critical, it is suggested that the comparator's output be connected to the microprocessor's highest priority interrupt so that the necessary software can be accessed.

This power-down circuitry has the advantage of proper operation in the presence of noise. With a slowly falling power supply in a noisy environment, the comparator's output may oscillate momentarily. This oscillation will have no bearing on the chip select signal to the MM58714A in this circuit because the HC00 latch only allows chip selects when the LM139 output is high, and it also does not alter their length once they begin. When the supply falls low enough to stop the comparator from oscillating, chip selects are locked out. One may consider the time that the comparator bounces as a delay before chip access is completely locked out as the standby mode is entered. If the cessation of comparator oscillation is desired, hysteresis can be added. A diagram of this can be found in the LM139 data sheet.

### Real Time Clock Interface without Wait States Using a PIA

Figure 4 shows the details of a design using the NSC800<sup>TM</sup> CMOS microprocessor and the NSC810A peripheral interface adapter. This design has the advantages of lower chip count and the absence of wait states. Similar PIAs, such as the INS8255 or the 8155, could be used with some software adaptation. The power-down circuitry is operationally equivalent to that of *Figure 3*, except that in this design the chip select is created by the PIA. Only the essential connections between the NSC800 and the NSC810A are shown in *Figure 4*.

The NSC800 is an 8-bit CMOS microprocessor combining the features of the Intel 8085 and the Zilog Z80<sup>®</sup>. In this application 8085 code is used to manipulate the control strobes and handle interrupts as detailed in *Figures 5* through *9*. The interconnection between the NSC800 and the NSC810A is straightforward, except for the CE connection on the NSC810A. By tying CE to A13 of the NSC800, chip enabling occurs whenever an IN 2X or an OUT 2X instruction is executed, because the same port address appears on NSC800 lines AD0–AD7 as on A8–A16. Using 2X will raise A13 on the NSC800 high, where X represents a specific port address. This method of enabling is entirely optional. For more information on the NSC800 and NSC810A, refer to the NSC800 Microprocessor Family Handbook.

### Software Description

The ports on the NSC810A are specially configured to control the data, address and control lines. The software allows the port signals to fulfill timing requirements. Port C is used to control the  $\overline{WR}$ ,  $\overline{RD}$  and  $\overline{CS}$  lines, port B is used to control the ddress lines, and port A is used to read and write the data.

The NSC810A is configured into the strobed input mode in the read subroutine in order to get the shortest possible RD strobe. As stated previously, the read strobe must be under 15  $\mu$ s to guarantee proper counter operation. The  $\overline{RD}$ strobe is fed back to the PC2/STB input of the NSC810A in order to latch in the data from the MM58174A. The read subroutine of Figure 5 begins by setting the port C direction. All bits are set for output, except PC2/STB, which is set for input. Port B is set out and port A is set in. Next, all the control strobes from port C are set high using bit set. Before calling the read routine, the MM58174A address to be accessed was loaded into the NSC800's register B, and it is now sent out on port B. Bit clear is used to lower the CS strobe from PC5. The mode definition register is then written to for selecting the strobed mode of the NSC810A. Bit clear is used to lower the RD strobe from port C, and before it is raised again, a MOV instruction puts control values from port C into the accumulator in the shortest time possible. Using these three instructions, the read strobe is held low for about 5  $\mu$ s. The rising edge of the  $\overline{RD}$  strobe is fed into PC2/STB to latch the data into port A, and the IN instruction reads the data. Before exiting the read subroutine, the mode definition register of the NSC810A is again accessed to return the PIA's operation to the basic I/O mode. A wait loop may be added to the read subroutine or elsewhere in the code to limit the number of read strobes to less than 10,000 per second. This specification has been added because

more than 10,000 reads per second can slightly degrade timekeeping accuracy. The write subroutine of *Figure 6* uses the NSC810A ports in the same manner as the read routine; i.e., port A for data, port B for address and port C for control strobes. However, there is no need to latch the data in port A, so the basic I/O mode is used. The write subroutine uses the control strobes from port C by beginning with all three strobes high, manipulating  $\overline{CS}$  and  $\overline{WR}$  low, and finally bringing these port outputs high again. Before calling the write subroutine, the desired address to be accessed is to be stored in the NSC800's register B, and data stored in register A.

		;DATA IS RETURNED INTO REG A
READ:		;SET PORT C
	OUT 026H	;DIRECTION
	MVI A, OFFH	;SET PORT B
	0UT 025H	;DIRECTION OUT
	MVI A, OOH	;SET PORT A
	0UT 024H	;DIRECTION IN
	MVI A, 038H	;SET PC3, PC4 & PC5 HIGH
	OUT O2EH	USING BIT SET
	MOV A, B	;PUT ADDRESS IN A
	OUT 021H	;ADDRESS OUT ON PORT B
	MVI A, O2OH	;BIT CLEAR - PC5
	OUT 02AH	;CHIP SELECT
	MVI A, OlH	SELECT STROBED
	0UT 027H	;MODE
	MVI C, O3OH	;GET READY
	MVI A, OlOH	;BIT CLEAR - PC4
	OUT O2AH	;RD STROBE
	MOV A, C	;LATCH DATA IN PORT A
	OUT 020EH	;& BRING STROBES HIGH
	IN 020H	GET DATA FROM PORT A
	ANI OFH	;MASK-OUT LOWER BITS
	MOV C, A	;SAVE DATA
	MVI A, OOH	RETURN TO
	0UT 027H	;BASIC I/O MODE
	MOV A, C	;RECOVER DATA
	RET	

### FIGURE 5. Read Subroutine

BEFORE CALLING WRITE SUBROUTINE ;STORE 174A ADDRESS IN REG B ;AND DATA IN REG A MOV C, A WRITE: ;SAVE DATA IN REG C MVI A, OFBH OUT 026H ;SET PORT C DIRECTION MVI A, OFFH 0UT 022H ;SET PORT C HIGH 0UT 024H ;SET PORT A DIRECTION OUT 0UT 025H :SET PORT B DIRECTION OUT MOV A, B ;MOVE 174A ADDRESS TO REG A ;ADDRESS OUT FROM PORT B 0UT 021H MVI A, 020H :CHIP SELECT - BIT CLEAR OUT O2AH ;ON PC5 MVI A, O8H ;WRITE STROBE - BIT CLEAR OUT O2AH ;ON PC3 MOV A, C ;RECOVER DATA FROM REG C OUT 020H ;DATA GOES OUT MVI A, OFFH ;SET PORT C 0UT 022H ;HIGH RET **FIGURE 6. Write Subroutine** 

Figure 7 shows the necessary initialization code for the NSC800, NSC810A, and the MM58174A, which use the read and write subroutines. Of greatest importance is the code to insure that the clock is not in the test mode. Notice that a DI instruction is used to disable interrupts before a "0" is written to address 15. Also included is the code to initialize interrupts on the MM58174A. *Figure 8* shows the interrupt service routine, while *Figure 9* shows a method of time setting by first stopping the clock, then restarting it once the setting is complete.

3-26

ORG 1200H ;ORIGINATE @ 1200H LXI SP, O1FH ;LOAD STACK POINTER MVI A, OOH ;ENTER NON-TEST MODE MVI B, OOH ; CALL WRITE LXI H, VECTOR ;"VECTOR" IS INTERRUPT SERVICE ;ROUTINE @ 1016H SHLD 1016H MVI A, 04H ;SET NSC800'S INTERRUPT CON-OUT OBBH ;TROL REGISTER FOR RSTA DI ;DISABLE NSC800 INTERRUPTS MVI A, OOH ;ENABLE INTERRUPTS ON 174A MVI B, OFH ; CALL WRITE ; CALL READ ; CALL READ : CALL READ ΕI :ENABLE NSC800 INTERRUPTS **FIGURE 7. Initialization** VECTOR: MVI B. OFH CALL READ CALL READ CALL READ ΕI RET **FIGURE 8. Interrupt Service Routine** MVI A, OOH ;STOP CLOCK USING MVI B, OEH ;START/STOP FLIP-FLOP CALL WRITE

-

AN-359

(time setting code)

MVI A, O1H MVI B, OEH CALL WRITE

FIGURE 9. Recommended Procedure for Setting Time

### **Oscillator Design**

AN-359

The MM58174A is driven by a standard Pierce oscillator. Figure 10 shows both the internal and external component sizes to be used. For crystals with a power rating of less than 1  $\mu$ W, a 200 k $\Omega$  resistor, in series with the oscillator output, should be used to insure that the crystal is not overdriven. The typical gain for the internal inverter and internal 200 k $\Omega$  series resistor is 20 at 1 kHz input frequency and about 5 at 30 kHz. The oscillator may take from two to seven seconds to begin oscillating due to the high Q of the crystal.

### **Crystal Information**

Choose one of the following crystal types: parallel resonant or tuning fork (NT CUT or XY BAR) with a Q > 35,000 and a frequency of 32,768 kHz. The load capacitance required ranges from 9 pF to 13 pF. The maximum power rating is 20  $\mu$ W. The choice of crystal accuracy and temperature coefficient are left to the user. Two crystals used in our lab are RCD's #RV-38 and Saronix's #NTF3238C.




FIGURE 10. Crystal Oscillator

### **Oscillator Adjustment and External Drive**

A well-tuned oscillator for the MM58174A will have a frequency error of no more than  $\pm$  10 ppm. This would result in the clock being off by  $\pm$ 5 minutes per year. This is a worst-case number, taking into account such factors as temperature variation ( $-40^{\circ}$ C to  $+85^{\circ}$ C) and supply variation (2.2V to 5.5V). The external oscillator components can also contribute to error and this should be taken into account by the user.

Adjusting the trimmer capacitor at pin 15 will minimize the oscillator error. But simply putting a scope probe on the crystal will load the oscillator with at least 10 pF, significantly altering the frequency. There are two good ways of isolating the probe from the oscillator. One method is to put the part in the test mode by writing a "0" to DB3 at AD0, then tune the signal at DB0 to 16,384.00 Hz using an accurate frequency counter. Another method would be to isolate the oscillator from the probe by adding an inverter to the small capacitance at pin 14. This would load the oscillator, but the input capacitance of the gate would not be affected by a probe at the output. The total capacitance on pin 14 should be kept near 15 pF.

To drive the oscillator from an external clock, connect the clock to pin 14 (crystal out) and tie pin 15 (crystal in) high.

### CONCLUSION

The MM58174A can easily be interfaced to a microprocessor to bring the functions of a real time clock and calendar to any system. With a power-fail/back-up circuit, the system will be able to keep accurate time for years, independent of the system power supply.



## The MM58274C Adds Reliable Real-Time Keeping to Any Microprocessor System

### INTRODUCTION

When a Real-Time Clock (RTC) is to be added into a digital system, the designer will face a number of design constraints and problems that do not usually occur in normal systems. Attention to detail in both hardware and software design is necessary to ensure that a reliable and trouble free product is implemented.

The extra circuitry required for an RTC falls into three main groups: a precise oscillator to control real-time couting; a backup power source to maintain time-keeping when the main system power is removed; power failure detection and write protection circuitry. The MM58274C in common with most RTC devices uses an on-chip oscillator circuit and an external watch crystal (frequency 32.768 kHz) as the time reference. A battery is the usual source of backup power, along with circuitry to isolate the battery-backed clock from the rest of the system. Like any CMOS component, the RTC must be protected against data corruption when the main system power fails; a problem that is very often not fully appreciated.

Rather than dealing strictly with any one particular application, this applications note discusses all of the aspects involved in adding a reliable RTC function to a microprocessor system, with descriptions of suitable circuitry to achieve this. Hardware problems, component selection, and physical board layout are examined. The software examples given in the data sheet are explained and clarified, and some other software suggestions are presented. Finally a number of otherwise unrelated topics are lumped together under "Miscellany"; including a discussion on how the MM58274C may be used directly to upgrade an existing MM58174A installation.

### CONTENTS

### **1.0 HARDWARE**

- 1.1 COMPONENT SELECTION
  - 1.1.1 Crystal
  - 1.1.2 Loading Capacitors
  - 1.1.3 Backup Battery:
    - Capacitors

Nickel-Cadmium Cells Alkaline Lithium

Other Cells and Notes Temperature Range

- 1.2 BOARD LAYOUT
  - 1.2.1 Oscillator Connection
  - 1.2.2 Battery Placement
  - 1.2.3 Other Components

National Semiconductor Application Note 365 Peter K. Thomson



### 1.3 POWER SUPPLY ISOLATION SCHEMES

- 1.3.1 The Need for Isolation
- 1.3.2 Isolation Techniques I-5V Supply Only
- 1.3.3 Isolation Techniques II-Negative
- Supply Switched 1.3.4 Other Methods
- 1.4 POWER FAIL PROTECTION
- 1.4 POWER FAIL PROTECTION 1.4.1 Write Protect Switch
  - 1.4.2 5V Sensing
  - 1.4.3 Supply Pre-Sense
  - 1.4.4 Switching Power Supplies
  - 1.4.5 Summary
- 1.4.5 Summa

### 2.0 SOFTWARE

- 2.1 DATA VALIDATION
  - 2.1.1 Post-Read Synchronization
  - 2.1.2 Pre-Read Synchronization
- 2.2 INTERRUPT AS A "DATA-CHANGED" FLAG
- 2.3 WRITING WITHOUT HALTING TIME-KEEPING
- 2.4 THE CLOCK AS A µP WATCHDOG
- 2.5 THE JAPANESE CALENDAR

### 3.0 MISCELLANY

- 3.1 CONNECTION TO NON-MICROBUS SYSTEMS
- 3.2 TEST MODE
- 3.3 TEST MODE AND OSCILLATOR SETTING
- 3.4 UPGRADING AN MM58174A SYSTEM WITH THE MM58274C
- 3.5 WAIT STATE GENERATION FOR FAST µPs
- APPENDIX A-1 Reading Valid Real-Time Data (Reprinted from the MM58274C Data Sheet)

APPENDIX A-2 MM58274C Functional Truth Tables

### **1.0 HARDWARE**

Selecting the correct components for the job and implementing a good board layout is crucial to developing an accurate and reliable Real-Time Clock function. The range of component choices available is large and the suitability of different types depends on the demands of the system.

### **1.1 COMPONENT SELECTION**

With reference to *Figure 1*, the oscillator components and the battery are examined and the suitability of different types is discussed.





FIGURE 1. MM58274C System Installation

TL/F/6737-3

### 1.1.1 Crystal

The oscillator is designed to work with a standard low power NT cut or XY Bar clock crystal of 32.768 kHz frequency. The circuit is a Pierce oscillator and is shown complete in *Figure 2*. The 20 MΩ resistor biases the oscillator into its linear region and ensures oscillator start-up. The 200 kΩ resistor prevents the oscillator amplifier from overdriving the crystal. If very low power crystals are used (i.e., less than 1  $\mu$ W) an external resistor of around 200 kΩ may have to be added to reduce the drive to the crystal.

The oscillator will drive most normal watch crystals, with up to 20  $\mu$ W drive available from the on-chip oscillator.



TL/F/6737-2

### FIGURE 2. Complete Oscillator Diagram

### 1.1.2 Loading Capacitors

Two capacitors are used to provide the correct output loading for the crystal. One is a fixed value capacitor in the range 18 pF–20 pF and the other is a variable 6 pF–36 pF trimmer capacitor. Adjusting the trimmer allows the crystal loading (and hence the oscillator frequency) to be fine tuned for optimal results. The capacitors are the components most likely to affect the overall accuracy of the oscillator and care must be exercised in selection. Ceramic capacitors offer good operating temperature range with close tolerance and low temperature coefficients (typically  $\pm 3$  ppm/K, for good quality examples). If trimming is undesirable a pair of close tolerance ( $\pm 5\%$  or better) capacitors in the range 18 pF-20 pF may be used. The average time-keeping accuracy for this configuration is within  $\pm 20$  seconds per month.

### 1.1.3 Backup Battery

There are a number of different cell types available that can be used for time-keeping retention. Some cells are more suitable than others, and the way in which the system is used also influences the choice of cell. Ideally the standby voltage of the RTC should be kept as low as possible, as the supply current increases with increasing voltage (*Figure 3*). Four different power sources are discussed: capacitors, nickel-cadmium rechargeable cells, alkaline and lithium primary cells.




FIGURE 3. Typical I<sub>DD</sub> ( $\mu$ A) vs V<sub>DD</sub> (V) for MM58274C in Standby Mode (T<sub>A</sub> = 25°C)

### Capacitors

When the system is permanently powered, and any long term removal of system power (i.e., more than a few hours) requires complete restarting, then a 1-2 Farad capacitor may be sufficient to run the clock during the power down. This can keep the clock running for 48-72 hours.

### Nickel-Cadmium Cells

Nickel-cadmium (Ni-Cad) cells can be trickle-charged from the system power supply using a resistor as shown in *Figure 1*. The exact value of resistor used depends on the capacity and number of cells in the battery. Consult the manufacturers data for information on charging rates and times.

A 3- or 4-cell battery should be used to power the clock (the nominal battery voltages are 3.6V for 3 cells in series and 4.8V for 4 cells), with 3 cells preferable. PCB mounting batteries of 100 mAh capacity are available and these will give around 6 months data retention (at normal room temperature). For this cell type to be used the system must spend a large proportion of its time turned on to keep the battery charged (i.e., used daily).

### Alkaline

Alkaline cells are among the least expensive primary cells which are suitable for use in real-time clock applications. They are available in a large range of capacities and shapes and have a very good storage (shelf) life.

Two cells in series will provide a nominal 3V, which is adequate to power the clock (via the isolating diode). The main problem with the alkaline system is that the cell terminal voltage drops slowly over the life of the cell. When the voltage at the clock supply pin drops to 2.2V, the cells must be replaced (battery voltage around 2.6V–2.7V). With present alkaline cells, this point is usually reached when the cells are only  $\frac{1}{2}$  to  $\frac{2}{3}$  discharged.

Provisions must be made either to check the battery voltage at regular intervals or to replace the cells regularly enough to avoid the danger of using discharged cells. Once again the manufacturers data regarding capacity and cell voltage against time must be examined to determine a suitable cell selection. A good alkaline system will supply 1–2 years continuous time-keeping.

### Lithium

Lithium cells are the most suitable for real-time clock applications. A single cell with 3V potential is sufficient to power the system. The cell potential is very stable over use and the storage life is excellent. The energy density of lithium cells is very high, giving enough capacity in a physically small cell to power the clock continuously for at least 5 years (at room temperature using a 1,000 mAh cell).

Several cells which are recommended for RTC use are D2/3A\*, D2A\*, and 1/6DEL/P\*. Each have 1,000 mAh capacity. These cells are available with solder pin connections for PCB mounting, giving a reliable backup supply.

### Other Cells and Notes

There are many other types of cells, both primary and secondary, which may be adapted for RTC use. When selecting a cell type, attention must be paid to: AN-365

- a. Cell capacity and physical size.
- b. Storage (shelf) life.
- c. Voltage variation over use.
- d. Operating temperature range.
- e. The method of battery connection and mounting.

In general, soldered cells are preferable to connector mounted cells. With replaceable batteries, the battery and connector contacts must be kept thoroughly clean. Dirty or corroded contacts can cause the clock to be starved of power, giving erratic and unreliable performance. The ease of operator access for cell replacement should also be considered.

### **Temperature Range**

The performance of any cell will be satisfactory for most office or domestic environments. When "ruggedized" equipment is to be used (i.e., field portable equipment, automotive, etc.) the temperature specification of different cell types should be taken into account when selecting a cell. Lithium cells offer good performance over 0°C-70°C with little loss in capacity. Once again, the manufacturer's data should be examined to determine suitability, especially different cells of the same type can have markedly different characteristics.

Few types of cells will offer any useful capacity at temperatures in or below the range 0°C-10°C, and fewer still will operate over the full military temperature range (-55°C to +125°C). Solid lithium cells and mercury-cadmium cells are two systems which can cover this range.

### **1.2 BOARD LAYOUT**

### **1.2.1 Oscillator Connection**

The oscillator components must be built as close to the pins of the clock chip as is physically possible. The ideal configuration is shown in *Figure 4*. From *Figure 2*, the oscillator circuit, it can be seen that both Osc In and Osc Out are high impedance nodes, susceptible to noise coupling from adjacent lines. Hence the oscillator should, as far as is practicable, be surrounded by a guard ground. The absolute maximum length of PCB tracking on either pin is 2.5 cm (1 inch). Longer tracks increase the parasitic track to track capacitances, increasing the risk of noise coupling and hence reducing the overall oscillator stability.

Where the system operates in humid or very cold environments (below 5°C), condensation or ice may form on the PCB. This has the effect of adding parasitic resistances and capacitances between pins 14 and 15, and also to ground. This variation in loading adversely affects the stability of the oscillator and in extreme cases may cause the oscillator to stop.

**AN-365** 


Keeping the PCB tracks as short as possible will help to minimize the problem, and on its own this may be sufficient. Where the operating conditions are particularly severe, the PCB and oscillator components should be coated with a suitable water repellent material, such as lacquer or silicon grease (suitability being determined by the electrical properties of the materials—high impedance and low dielectric constant).

Figures 2 and 4 show the trimmer placed on Osc Out. The placement of the trimmer capacitor on either Osc In or Osc Out is not critical. Placing the trimmer on Osc Out yields a smaller trim range, but less susceptibility to changes in trimmer capacitance. Placement of the trimmer capacitor on Osc In gives a wider trim span, but slightly greater susceptibility to capacitance changes.

### **1.2.2 Battery Placement**

For the battery, placement is less critical than with the oscillator components. Practical considerations are of greater importance now; i.e., accessibility. The battery should be placed where it is unlikely to be accidentally shorted or disconnected during routine operation and servicing of the equipment.

When replaceable cells are used, connecting a 100  $\mu$ F capacitor across the RTC supply lines will keep the clock operating for 30–40 seconds with the battery disconnected (*Figure 5*). This allows the battery to be replaced regardless of whether or not the main supply is active.



the internal TTL input buffers and causes the µP interface functions of the clock to go to full CMOS logic levels, draw-MM58274 ing no supply current (except for the unavoidable leakage 100 nF DISK current of the internal MOS transistors). For the MM58274C 8 Vss this is achieved by isolating the ground (VSS) supply line VBAT Figures 6a and 6b show the two cases where first VDD (6a)

and then VSS (6b) are open-circuited. The line out from the MM58274C represents any of the Control, Address, or Data lines on the RTC, with the internal pull-up resistor shown. The two diodes and resistor Rs represent the logic device connected to the RTC input and the resistance of the rest of the system with no power applied.

The placement of the other RTC dedicated components

(e.g., supply disconnection and power failure protection

components) is not particularly critical. However, the same

guidelines as applied to the battery should be followed

There are two reasons for disconnecting the clock circuit

1. To prevent the backup battery from trying to power the

2. To minimize the battery current (and extend battery life) by preventing current leakage out of the RTC input pins. The MM58274C inputs have internal pull-up devices which

pull the inputs to V<sub>DD</sub> in power down mode. This turns off

1.2.3 Other Components

when the PCB layout is designed.

1.3.1 The Need for Isolation


from the rest of the system:

from the rest of the system.

**1.3 POWER SUPPLY ISOLATION SCHEMES** 

whole system when the main power fails.

When V<sub>DD</sub> is open-circuit as in Figure 6a, there is a complete current path, shown by the arrows, out of the RTC input and through the external circuitry. This battery current




is a complete waste and serves only to reduce the cell life. Depending on the value of R<sub>S</sub>, the voltage level at the pin may fall low enough to turn on the internal TTL level buffer, wasting further current as the buffer is no longer fully CMOS.

With VSS disconnected (Figure 6b), there is no return path to the battery and the pin is pulled completely up to VDD. The TTL buffer is switched off and no power is lost.

### 1.3.2 Isolation Techniques I—5V Supply Only


Figure 7 shows the isolation circuit suggested in the MM58274C data sheet. This circuit provides complete disconnection where only the system +5V is available for switching control.



### TL/F/6737-8 FIGURE 7. 5V Isolation Circuit

TR2 is the disconnecting device, which is controlled by TR3 and its associated circuitry. TR3 is turned on by its bias chain R2, ZD1, R4 as the system supply rises up to 4.2V. TR3 and R3 then turn on TR2 to connect the clock to the system supply. D1 isolates the backup battery when the system supply is active. The 100 nF disk capacitors decouple the supply during R/W operations and should be included in any disconnection scheme.

TR3 is necessary to prevent R3 and TR2 from leaking battery current in the power down condition. The circuit without TR3 is shown in Figure 8 where TR2 has been replaced by equivalent diodes to clearly show the problem. The circuitry could be simplified by replacing TR3 with a Zener diode (Figure 9). There will be a small loss of current down through TR2 however, as the Zener will pass a small leakage current at below its "knee" voltage. Thus the Zener should be selected for its low current capability.




TL/F/6737-9

with No Power Applied FIGURE 8. Current Leakage in Simplified

R<sub>S</sub> = System Resistance


**Disconnection Schemes** 





### FIGURE 9. Alternative Supply Disconnection Scheme Sensing 5V (Decoupling Capacitors Omitted for Clarity)

Finally TR1 and R1 (*Figure 7*) are optional components which are only required when the interrupt output is used. If interrupts are left programmed when the power fails, the interrupt timer will still time-out setting the interrupt output. Since this is an active low pull-down transistor it effectively shorts directly across TR2, destroying the RTC isolation and discharging the battery into the rest of the system (*Figure 10*). In order to prevent this from occurring, TR1 and R1 are added.




### FIGURE 10. Battery Discharge Path via Unisolated Interrupt Output

None of the disconnection components are at all critical, with general purpose transistors being completely adequate for the task. D1 should be a small-signal silicon or germanium diode.

### 1.3.3 Isolation Techniques II— Negative Supply Switched


....

Where a negative voltage supply is available (either regulated or unregulated) the circuit of *Figure 11* may be used. This is similar in operation to its diode equivalent shown in *Figure 12*, where the voltage drops across the diodes provide the correct potential to the clock. *Figure 11* has the advantage, however, that the clock power is supplied from the ground line by transistor action, rather than via the resistor as in *Figure 12*. Less lower is dissipated in the resistor as only transistor bias current need be drawn.



TL/F/6737-12

FIGURE 11. Negative Voltage Driven Supply Disconnection Scheme (Decoupling Capacitors Omitted for Clarity)



TL/F/6737-13 FIGURE 12. Diode Equivalent Circuit of *Figure 11* 

### 1.3.4 Other Methods

There are many other possibilities for supply disconnection schemes, i.e., relay disconnection. When designing a disconnection scheme, the performance must be analyzed both with the system power applied and with system power absent. Check for leakage paths and undue voltage drops and try to set up so that disconnection and reconnection will take place as near to the backup voltage as possible.

### **1.4 POWER FAIL PROTECTION**

One of the major causes of unreliability in RTC designs is due to inadequate power failure protection. As the system is powered up and down, the  $\mu$ P and surrounding logic can produce numerous spurious signals, including spurious writes and illegal control signals (i.e., RD and WR both active together).

Bipolar logic devices can produce spikes and glitches as the internal biasing switches off around 3V–3.5V, and the transistors operate in their linear region for a short time. Any such spurious signals, if applied to the RTC, could cause the time data to be corrupted. Systems using 74HC logic and CMOS processors are less stringent in their power failure requirements as the devices tend to work right down to around 2V. Some form of write protection is still required, however.

In order to protect the time data, the system must be physically prevented from writing to the clock when the power supply is not stable. The ideal situation is to ban Write access to the clock before the system + 5V starts to fail, and then keep the chip "locked-out" until the power is restored and stabilized. This ideal access control signal is illustrated in *Figure 13*. Three methods of power fail protection are discussed, although there are also many other possibilities.

### 1.4.1 Write Protect Switch

By far the simplest and potentially the most hazard-free method is to use a switch on the WR control line to the clock (*Figure 14*). This is completely adequate, but requires the intervention of an operator to alter time data or program interrupts.

Some thought must be given to ensuring that the operator cannot accidentally leave the WR line switched in. This may be achieved by the physical access method used (i.e., the machine is impossible to operate or switch off when in the time setting mode, because of the placement of access hatches, etc.) or with software. The switch state could be sensed by trying to alter the data in the Tens of Years counter or Interrupt register just prior to leaving the clock setting routine, and refusing to leave the routine until the WR switch has been opened. The switch condition should similarly be checked whenever the system is initialized or reset.

The physical location of the switch should also be considered for ease of accessibility. How easy the switch is to reach will depend on the system; i.e., in some cases a "tamper proof" clock may be required.





FIGURE 13. RTC Access Lockout Definition





### 1.4.2 5V Sensing

The circuit of *Figure 15* senses the system 5V supply and prevents access to the clock if the supply falls below 4.2V–4.3V. This circuit should be used where only the system 5V is available for reference. The LM139 comparator and associated components sense the 5V supply and generate the power fail signal (P.Fail). The 74HC75 and components disconnect the WR line.

R3 and ZD1 provide a reference voltage of 2V-3V for the comparator. R4 and VR1 form a potential divider chain sensing the 5V line, and VR1 is adjusted to switch the comparator output at 4.2V-4.3V. An alternative to VR1 would be to use a pair of close tolerance resistors ( $\pm 2\%$ ) with values selected to suit the Zener diode reference used. The combination of R4, D3 and C2 provide an RC time constant to delay the comparator when sensing the return of 5V (to provide the post-failure delay in *Figure 13*). The LM139 has an open-collector output which is held low when 5V is present and is switched off when 5V fails. This line is pulled high by R5 to flag power failure (P.Fail). Since the comparator is a linear device drawing a bias current, it is powered by the system 5V supply to avoid consuming battery power.

One 74HC75 package contains four latches, of which two are used. These are transparent latches controlled by the "G" input. With G high, the latch is transparent and the Q and  $\overline{Q}$  outputs follow the Data input. When G is low, the state of Q and  $\overline{Q}$  on the falling edge is latched. In this way, F2 prevents P.Fail from locking out the clock if there is a Write cycle in progress. F1 isolates the WR input on the clock when F2 passes the P.Fail signal. C1, R2 and D1 do not slow the advent of P.Fail, but they cause a delay in the release of the function to mask any comparator noise or oscillation as the comparator switches off or on (i.e., during the undefined supply periods).

D2, C3 and R6 smooth the comparator supply and help it to function effectively. The time constants of the RC networks should be selected to suit the power supply of the system that is used. Comparing the functioning of this circuit with the ideal case of *Figure 13* shows that most of the conditions can be satisfied, except that there is no real pre-failure lock-out period. This cannot be achieved without some form of look ahead power failure.

As an alternative to F1 a permanently powered 74HC4066 analog switch could be used as the isolating component (*Figure 16*). The 74HC4066 does not require pull-up resistors on its inputs as there are no internal CMOS buffers inside this device which must be controlled. The resistor on the WR line is for the benefit of the 74HC75.

Note that both of the devices mentioned must be permanently powered from the battery to be useful in this way. Unused gates in any such device must *NOT* be used in combinational logic that is not permanently powered. All unused inputs should be tied to  $V_{DD}$  or  $V_{SS}$  to render them inactive.




FIGURE 15. Power Supply Failure Detection and Write Protection Circuitry

### 1.4.3 Supply Pre-Sense

The same circuit of *Figure 15* can be used with unregulated supplies or other voltage lines which will fail before the 5V line. To achieve this, point X is connected to the sensed voltage instead of 5V, and the R4/VR1 ratio is adjusted to suit. The major benefit here is that advance warning of an impending 5V failure can be detected, allowing a pre-failure lockout signal to be generated.

Less precision is required to sense the unregulated supply than the system 5V supply. Consequently less complex circuitry can be used to do the detection and this is reflected in the circuit of *Figure 17*. Most 5V regulators will operate with an input voltage from 7V to 25V. Typically the input voltage is around 9V to 12V, giving some headroom. In *Figure 17* this voltage is high enough to drive a current through the Zener diode and turn on transistor TR1, holding P.Fail Iow. R<sub>LIM</sub> limits the Zener current. The Zener voltage is selected to switch off before the regulator fails, around 7.5V–8.5V depending on the time constant of the supply. With no current, TR1 switches off and R<sub>P</sub> pulls P.Fail ligh.

When power is re-applied the 5V supply will stabilize before the Zener switches on, removing P.Fail. To provide a longer post-failure lockout period  $R_{LIM}$  could be replaced with two resistors and a diode/capacitor delay as in *Figure 15*.

Figure 18 is another extension of the same basic idea to provide an advance interrupt signal to allow  $\mu$ P housekeeping before the RTC (and CMOS RAM) is locked out. The extra rectifying components D1, Ct and Rt keep  $\overline{NMI}$  off as long as input power is present. Time constant  $\tau_2$  is selected to be at 2–3 times faster than  $\tau_1$ , the supply time constant. The interrupt signal is thus asserted before P.Fail.

### 1.4.4 Switching Power Supplies


Switching power supplies are available which generate power failure signals. This signal may be adequate for direct use as a P.Fail line, but the manufacturer's information should be consulted to determine the suitability of a given power unit. P.Fail must still be gated with the Write signal for the clock, regardless of the actual detection method employed.

### 1.4.5 Summary


The general guidelines for power fail protection are:


- 1. Physically isolate the WR input to the clock. The  $\mu$ P cannot be relied upon to logically operate the isolation mechanism.
- The clock should be isolated before the 5V power line starts to fail, and stay isolated until after it has reestablished.
- Consider the action of the sensing and protection circuitry if the supplies oscillate or if a momentary glitch occurs.
- The Power Fail signal must be gated with Write strobes to the RTC. A foreshortened Write may also cause data corruption.
- 5. Logic components (and ICs in general) should be avoided when designing power failure schemes. Discrete components are far more predictable in their performance when the power supplies are not well defined. The exception to this general rule is when using permanently powered HCMOS logic devices. They will function in a reliable manner down to 2V.

System-powered logic devices cannot be relied on for power failure or Write isolation (not even CMOS).









\*R<sub>S</sub> = Equivalent Resistance of the System.

FIGURE 18. Power Fail Circuit with µP Housekeeping Interrupt

### 2.0 SOFTWARE

### 2.1 DATA VALIDATION

The MM58274C data sheet describes in some detail three different methods of reading the clock and validating the real-time data. These techniques are reproduced in Appendix A-1. Rather than repeating the data sheet examples, this applications note examines the principles that lie behind the techniques suggested.

The basic problem is that the  $\mu$ P must somehow be synchronized with the changes in real-time in order to read valid data. This synchronization can either be done prior to reading the time data (pre-read), or after reading the data (post-read synchronization).

### 2.1.1 Post-Read Synchronization

Using the Data-Changed Flag (DCF) or the lowest order time register as outlined in the appendix: Time Reading using DCF and Time Reading with very slow Read cycles; are both examples of post-read synchronization.

What this means is that the data is read out first, and then verified. This is achieved by defining a random time-slot, started by the first DCF or low order register read, and ended by the second such read. If DCF has not been set during the time-slot or the lowest order register has not changed, then no real-time change occurred during that time-slot. All real-time reads during the time-slot are thus guaranteed.

### 2.1.2 Pre-Read Synchronization

The Interrupt Timer technique uses pre-read synchronization. Once it has been initialized as described, the interrupt timer times out just after the real-time data has changed. Thus the  $\mu P$  is guaranteed a full 100 ms period in which to read the time counters before the next change occurs.

The interrupt timer has to be synchronized with the real-time counters because it is an independent unit which may be started and stopped at any time by the  $\mu$ P. This software synchronization is achieved by using another pre-read technique. The timer is set up and ready to go, but then the  $\mu$ P waits for DCF to occur before issuing the start command. The same technique could be used to actually read the time-data, but post-read synchronization is faster.

### 2.2 INTERRUPT AS A "DATA-CHANGED" FLAG

DCF is set every 100 ms when the 1/10ths of seconds counter is changed. When the time is only being read to the nearest second or minute, it would be useful to have a flag which is only set by a change in the lowest order counter being used.

If the interrupt output from the clock is not being used, the timer can be used as a programmable data-changed flag. To achieve this, the timer is set up and started in exactly the same way as described for interrupt time reading (Appendix A-1). The interrupt output, however, should be left unconnected. When reading the real-time data, the technique used is the same as for the normal Data-Changed Flag except that the Interrupt Flag is tested instead of DCF.

Note that the lowest order real-time register which is to be read out should be used to initially synchronize the counter. The interrupt timer is started when the real-time counter value is seen to change.

### 2.3 WRITING WITHOUT HALTING TIME-KEEPING

For most purposes the RTC should be halted when the time is being set, especially if large numbers of counters are being updated. The clock can also then be re-started in synchronism with an external time reference. If only a few counters are to be altered and the clock is already synchronized, then this can be done without stopping the clock. An example of a minor change which may be undertaken in this way is daylight savings (winter/summer change of hour).

The problem to be overcome when writing in this way is that the write strobe may coincide with a time change pulse. As the time counters are synchronous, the 100 ms clock pulse is fed to each one. Writing to one counter may cause a spurious carry to be generated from that counter, causing the next one up the chain to be incremented.

Since a spurious carry will only affect the next counter if it coincides with a time update pulse, the solution is once again to synchronize clock access with the real-time change. The most suitable method for this is pre-read synchronization. In other words, the  $\mu$ P must wait for DCF to be set before starting to write data to the clock, giving a guaranteed 100 ms period for writing.

The interrupt timer can be used as a  $\mu$ P watchdog circuit, operating on a non-maskable interrupt input to the  $\mu$ P. The timer is set up in either single or repeat interrupt mode for the watchdog period required: 0.1s, 0.5s or 1 second are probably the most useful times for this. Synchronization with real-time is not required.

In the main program loop the  $\mu$ P writes to the clock, stopping and then re-starting the interrupt timer. The timer period selected will depend on how long the main loop takes to execute. As long as the  $\mu$ P continues to execute the loop, no time-outs occur and no interrupts are generated. If the  $\mu$ P fails for some reason to reset the timer, it eventually times out, generating the initializing interrupt to restore operations.

### 2.5 THE JAPANESE CALENDAR

Because the MM58274C has a programmable leap year counter, this allows the possibility of programming for the Japanese Showa calendar. The Japanese calender counts years from the time that the present Japanese Emperor comes to power.

The normal procedure for the MM58274C is to program "the number of years since last leap year." This remains the same whether the clock is loaded with the Gregorian or Showa year. When software is used to calculate the leap year count value from the year, then the formula used must be modified.

The formula for the Gregorian year is:

Leap Year Value = [Gregorian Year/4] REMAINDER

Whereas for the Showa year the formula is:

Leap Year Value = [(Showa Year + 1)/4] REMAINDER

Leap Year Value is the number from 0 to 3 which is written into the leap year counter, and is the REMAINDER of the integer calculations shown above.


### 3.0 MISCELLANY


### 3.1 CONNECTION TO NON Microbus™ SYSTEMS

Adding the MM58274C to non Microbus processors is made fairly straightforward because of the flexibility of the control signal timing. *Figure 19* shows two examples of logic to connect to clock to a 6502/6800 microprocessor bus.

Figure 19a the RD and WR inputs are strobed, generating reasonably typical Microbus type control signals. In *Figure 19b*, CS is used as the strobe signal. There is no particular

advantage to either circuit, they are just variations on the same theme. This circuit flexibility may be used to advantage to save SSI packages in the board design.





TL/F/6737-21

### b) FIGURE 19. 6800/6502 μP Bus Interface


### 3.2 TEST MODE

Test Mode is used by National Semiconductor when the MM58274C is tested during manufacture. It enables the real-time counters to be clocked rapidly through their full count sequence.

The MM58274C counters are clocked synchronously to simplify  $\mu$ P access, with ripple carry signals from each counter to the next. In Test Mode some of these carries are intercepted and permanently asserted causing the counters to count each clock pulse. The prescaler is also bypassed so that the counters count every clock applied to the Osc In pin. The Test Mode counter connection is shown in *Figure 20*.

If Test Mode is to be used for incoming inspection or device verification, then the clock waveform of *Figure 21* should be applied to the oscillator input (Osc In, pin 15). The MM58274C uses semi-dynamic flip-flops in the counters which are only fully static when the oscillator input is high. Thus *Figure 21* shows that the oscillator waveform is normally high, pulsing low to clock the real-time counters. The time data in the counters changes on the rising edge of Osc In.






5....

TL/F/6737-22

### FIGURE 20. Test Mode Interconnection Diagram of Internal Counter Stages



TL/F/6737-23

FIGURE 21. Oscillator Waveform for Counter Clocking in Test Mode

The pulse width limits for reliable clocking are shown on the diagram. When running with a 32 kHz crystal, the normal pulse width is 15.26  $\mu s$ . With no forcing input, the oscillator will self bias to around 2.5V (V\_{DD} = 5V). While a few hundred mV swing above and below this level is sufficient to drive the oscillator, for guaranteed test clocking the input should swing between V\_{IH}  $\geq$  75% V<sub>DD</sub> and V<sub>IL</sub>  $\leq$  25% V<sub>DD</sub>.

### 3.3 TEST MODE AND OSCILLATOR SETTING

When Test Mode is used to set the oscillator frequency, the interrupt timer must be disabled (interrupt register programmed with all 0s) for the oscillator frequency to appear on the interrupt output. No test equipment should be connected directly to either oscillator pin, as the added loading will alter the characteristics of the oscillator making precise tuning impossible. Note that oscillator frequency will vary slightly as the supply varies between operating and standby voltages. Typically this variation will be around  $\pm 6$  seconds per month (V<sub>STANDBY</sub> = 2.4V), slowing at standby voltage. When the clock will spend the greater part of its working life in standby mode, it may prove worthwhile to correct for this in the tuning. This can be done by tuning at standby voltage (by writing the RTC into test mode, then disconnecting it from the system to tune on battery backup). Alternatively, the clock can be slightly overtuned at operational voltage, tuning to 32.7681 kHz.


In a similar way, where the RTC spends equal amounts of time in both operational and standby modes (i.e., powered by day, standby at night), the oscillator may be tuned somewhere between the two conditions. Following these tuning suggestions will not eliminate time-keeping errors, but they will help in minimizing them. Time-keeping accuracy cannot be exactly specified. It depends on the quality of the components used in the oscillator circuit and their physical layout, also the stability of the supply voltage, the variations in ambient temperture, etc. With good components and a reasonably stable environment however, time-keeping accuracy to within 4 seconds/month can be achieved, although 8 seconds/month is somewhat more typical in practical systems.

### 3.4 UPGRADING AN MM58174A SYSTEM WITH THE MM58274C

The MM58274C has the same pin-out as the MM58174A and can be used as a direct replacement, with certain reser-

vations. The two devices are not quite the same in their external circuit appearances, and this is reflected in their applications circuits. In addition, the MM58274C is not software compatible with the MM58174A, requiring a change in the operating system to use the MM58274C.

*Figure 22* shows the circuit diagram for the MM58174A system connection. There are two major differences between this and the MM58274C diagram (*Figure 1*); a) the oscillator circuit and b) the supply disconnection scheme.



### \*Use resistor with Ni-Cad cells only.

FIGURE 22. MM58174A System Installation

AN-365

### a) The Oscillator Circuit

AN-365

The MM58274C normally operates with an 18 pF-20 pF fixed loading capacitor as opposed to the 15 pF of the MM58174A. This is a reflection of the greater internal capacitance of the MM58174A, rather than any change in the characteristics of the oscillator itself. The MM58274C will operate using a 15 pF capacitor, but the oscillator will probably need to be retrimmed.

Operating with a 15 pF capacitor will make the oscillator more sensitive to change in the environment, i.e., temperature, voltage, moisture, etc. This will result in lower accuracy in time-keeping. The oscillator is more prone to stopping at low voltage. Oscillation would normally be maintained down to 1.8V-1.9V (although not guaranteed); with a 15 pF load it may only oscillate down to 2.0V-2.1V. It is thus important to check the battery regularly and replace it before the RTC voltage falls below 2.2V.

Where possible the 15 pF capacitor should be replaced by an 18 pF-20 pF capacitor (anywhere in the range 18 pF-20 pF is adequate), or a second 3 pF-5 pF capacitor may be added in parallel with the 15 pF.

Note: When components have been soldered into the oscillator circuit, allow the circuit to cool to room temperature before attempting to retune the oscillator.

The change of pin of the tuning capacitor (from OSC Out to Osc In) is not critical.

### b) The Supply Disconnection Scheme

The MM58174A uses mostly pull-down devices on its  $\mu$ P inputs to pull the inputs to CMOS levels, and so the 5V power line is disconnected on this device. The two exceptions to this are the  $\overline{CS}$  and  $\overline{WR}$  inputs which have pull-up resistors to inactivate the internal write strobe. As *Figure 5a* shows, there is a leakage path through these pins, which in most MM58174A installations are individually isolated.

The largest penalty in inserting an MM58274C into an MM58174A circuit is the battery current that is lost through the pull-up devices. This will increase the typical supply current from 4  $\mu$ A to 50–100  $\mu$ A and it is up to the individual user to decide whether or not this drain is tolerable in a particular application.

The most important requirement is that the WR input should be electrically isolated or current leakage through pin inputs may force the inputs low enough to cause spurious writes to occur. Since it is already customary to isolate these inputs for the MM58174A, this may not be a problem. Where this has not been done, either the circuit will have to be modified or the  $\overline{WR}$  PCB track can be cut and a switch or some extra circuitry added to allow isolation.

Note that power fail disconnection and input isolation may be achieved using the same components. In *Figure 22* the MM74HC4066 analog switch will do both jobs.

The current drained by the input pull-ups may be minimized with some attention to the data/address driving devices. It is often possible to replace LSTTL devices with standard 7400 series devices and reduce the leakage (at the cost of some increase in operating current). Many 7400 series device outputs lack diodes in the right places to pass leakage currents. LSTTL devices will, for the main part, have these diodes. CMOS devices will always have diodes to both power rails on inputs and outputs.


There is no hard and fast rule for this. Where devices from one manufacturer work, the same part from a different one may not. Some trial and error experimentation may prove worthwhile in selected devices.

### 3.5 WAIT STATE GENERATION FOR FAST µPs

Although the MM58274C has faster access times than the MM58174A, in many cases, the  $\mu$ P will be too fast to directly access the RTC. *Figure 23* shows a circuit which will produce wait states of any length required to enable the RTC to be accessed, using the 74HC74 dual D-type flip-flop.

The RTC  $\overline{\text{CS}}$  signal clocks up a logic 1 on the Q output of the first F/F, removing the Preset from all the other F/Fs and pulling the  $\mu$ P WAIT line low, via the transistor. The other F/Fs 1 to n, form a shift register clocked by the  $\phi_2$  system clock.

After n  $\phi_2$  clocks (where n is the number of flip-flops in the shift register) a logic 0 shifts out from the nth F/F, resetting the main flip-flop. The main F/F then presets the shift register and clears the WAIT signal, ready for the next  $\overline{CS}$  edge to repeat the cycle. On power-up the delay generator will initialize itself after a maximium of n system clocks have occurred so no reset signal is required. Some  $\mu$ Ps demand that a  $\overline{WAIT}$ /READY input is synchronized with  $\phi_2$  of the system clock. This can readily be achieved by selecting the correct  $\phi_2$  edge as the clock signal for the shift register chain.



TL/F/6737-25

Flip-Flop-MM74HC74 D-Type Latch

FIGURE 23. Access Delay Generator (Clocked Wait State Generator)

## will have reset DCF, automatically repeating the step 1 ac-TIME READING USING AN INTERRUPT In systems such as point-of-sale terminals and data loggers, time reading is usually only required on a random demand

basis. Using the data-changed flag as outlined above is ideal for this type of system. Where the µP must respond to any change in real-time (e.g., industrial timers/process controllers, TV/VCR clocks or any system where real-time is displayed) then the interrupt timer may be for time reading. Software is used to synchronize the interrupt timer with the time changing as outlined below:

APPENDIX A-1, READING VALID REAL-TIME DATA

Using the Data-Changed Flag (DCF) technique supports mi-

croprocessors with block move facilities, as all the neces-

sary time data may be read sequentially and then tested for

1. Read the control register, address 0: This is a dummy

2. Read time registers: All desired time registers are read

3. Read the control register and test DCF: If DCF is still

If DCF is set (logic 1), then a time change has occurred

since step 1 and time data may not be consistent. Repeat

steps 2 and 3 until DCF is clear. The control read of step 3

clear (logic 0), then no clock setting pulses have occurred

since step 1. All time data is guaranteed good and time

read to reset the data-changed flag (DCF) prior to reading

TIME READING USING DCF

validity as shown below.

the time registers.

reading is complete.

out in a block.

tion.

- Select the interrupt register (write 2 or 3 to ADDR0).
- 2. Program for repeated interrupts of the desired time interval (see Table IIb in Appendix A-2): Do not start the timer yet.
- 3. Read control register AD0: This is a dummy read to reset the data-changed flag.

- 4. Read control register AD0 repeatedly until data-changed flag is set.
- 5. Write 0 or 2 to control register. Interrupt timing commences.

When interrupt occurs, read out all required time data. There is no need to test DCF as the interrupt "pre-synchronizes" the time reading already. The interrupt flag is automatically reset by reading from ADDR0 to test it. In repeat interrupt mode, the timer continues to run with no further µP intervention necessary.

### TIME READING WITH VERY SLOW READ CYCLES

If a system takes longer than 100 ms to complete reading of all the necessary time registers (e.g., when CMOS processors are used or where high level interpreted language routines are used) then the data-changed flag will always be set when tested and is of no value. In this case, the time registers themselves must be tested to ensure data accuracy.

The technique below will detect both time changing between read strobes (i.e., between reading tens of minutes and units of hours) and also time changing during read, which can produce invalid data.

- 1. Read and store the value of the *lowest* order time register reauired.
- 2. Read out all the time registers required. The registers may be read out in any order, simplifying software requirements.
- 3. Re-read the lowest order register and compare it with the value stored previously in step 1. If it is still the same, then all time data is good. If it has changed, then store the new value and go back to step 2.

In general, the rule is that the first and last reads must both be of the lowest order time register. These two values can then be compared to ensure that no change has occurred. This technique works because for any higher order time register to change, all the lower order registers must also change. If the lowest order register does not change, then no other register has changed either.

### APPENDIX A-2. FUNCTIONAL TRUTH TABLES FOR MM58274C

### **TABLE I. Address Decoding for Internal Registers**

Register Selected			Addre	Access		
	negister selected	AD3	AD3 AD2 AD1		AD0	
0	Control Register	0	0	0	0	Split Read and Write
1	Tenths of Secs	0	0	0	1	Read Only
2	Units Seconds	0	0	- 1	0	R/W
3	Tens Seconds	0	0	1	1	R/W
4	Units Minutes	0	1	0	0	R/W
5	Tens Minutes	0	1	0	1	R/W
6	Units Hours	0	1	1	0	R/W
7	Tens Hours	0	1	1	1	R/W
8	Units Days	1	0	0	0	R/W
9	Tens Days	1	0	0	1	R/W
10	Units Months	1	0	1	0	R/W
11	Tens Months	1	0	1	1 1	R/W
12	Units Years	1	1	0	0	R/W
13	Tens Years	1	1	0	1	R/W
14	Day of Week	1 1	1	1	0	R/W
15	Clock Setting/Interrupt Registers	1	1	1	1	R/W
		•				· · · · · · · · · · · · · · · · · · ·

TABLE IIa. Clock Setting Register Layout						
Function	Data Bits Used				Comments	Access
T difetion	DB3	DB2	DB1	DB0		A00033
Leap Year Counter	Х	X			0 Indicates a Leap Year	R/W
AM/PM Indicator (12 Hour Mode)			x		0 = AM 1 = PM 0 in 24 Hour Mode	R/W
12-24 Hour Select Bit	·			x	0 = 12 Hour Mode 1 = 24 Hour Mode	R/W

### **TABLE IIb. Interrupt Control Register**

Function	Comments	Control Word				
i unedon	Comments		DB2	DB1	DB0	
No Interrupt	Interrupt Output Cleared, Start/Stop Bit Set to 1.	х	0	0	0	
0.1 Second		0/1	0	0	1	
0.5 Second		0/1	0	1	0	
1 Second		0/1	0	1	1	
5 Seconds		0/1	1	0	0	
10 Seconds		0/1	1	0	1	
30 Seconds		0/1	1	1	0	
60 Seconds		0/1	1	1	1	

Timing Accuracy: Single Interrupt Mode (all time delays): ±1 ms Repeated Mode: ±1 ms on initial timeout, thereafter synchronous with first interrupt (i.e., timing errors do not accumulate). DB3 = 0 for Single Interrupt

DB3 = 1 for Repeated Interrupt

### TABLE III. The Control Register Layout

Access (ADDR0)	DB3	DB2	DB1	DB0
Reaf From:	Data Changed Flag	0	0	Interrupt Flag
Write To:	Test 0 = Normal 1 = Test Mode	Clock Start/Stop 0 = Clock Run 1 = Clock Stop	Interrupt Select 0 = Clk. Set Reg. 1 = Int. Reg.	Interrupt Start/Stop 0 = Int. Run 1 = Int. Stop

## Calibration of the DP8570A Family

This application note applies to the DP8570A, DP8571A, DP8572A, and DP8573A. With respect to the DP8573A, only the discussion of the 32.768 kHz oscillator applies.

The intrinsic properties of quartz make it a uniquely simple device for highly accurate and stable frequency generation. Crystals are not a primary frequency standard but used with care can provide stability far in excess of most requirements. Various configurations of oscillator circuits exist to enable the designer to implement such a source. Its performance, however, is largely dependant on the environment and its associated electrical components. Firstly, consider the basic element—the crystal itself.

A quartz crystal is a mechanically moving system and is very dependant on the environment in which it is operating. The encapsulation will therefore critically affect the long term stability and is a major cause of crystal aging. The choice of crystal holder is important; there are four main types:

**TABLE I. Crystal Types** 

Crystal Type	Aging
Solder Sealed	100 ppm/year
Resistance Welded	4 ppm/year
Cold Welded	2 ppm/year
Glass Enclosed	1 ppm/year

The solder seal units have relatively poor aging characteristics and have now been superceded by resistance welded units. The other three types offer good aging characteristics.

The exact frequency of oscillation is also dependent on the ambient temperature, therefore another important feature to bear in mind when choosing a crystal is the Frequency/Temperature characteristic. If a typical manufacturer's specification is consulted it can easily be seen that there is quite a variation in stability for different temperatures; stabilities of  $\pm 20$  ppm over a range of  $-20^\circ$ C to  $+70^\circ$ C are not uncommon.

The capacitors are the components that are most likely to affect the accuracy of the oscillator and care must also be exercised in selection. Since the oscillator plays such an important part in the accuracy of the DP8570A (both timers and real-time selection) it is vital to use good quality examples. There are various types of capacitors available which offer close tolerances and good temperature coefficients. Any of these would be suitable in this application.

TABLE	E II. Ca	pacitor	Types
-------	----------	---------	-------

Capacitor	Typical Tolerance	Typical Temp Coef.
Polycarbonate	5%	50 ppm/°C
Ceramic	10%	30 ppm/°C
Silver Mica	1%	35 ppm/°C

Trimmer capacitors with polypropolene dielectrics give a poorer temp coefficient when compared with those above (typically 300 ppm/°C approx). However, they offer the benefit of allowing the oscillator to be tuned for optimum results.

National Semiconductor Application Note 588 James Petrie



The oscillator components must be built as close as possible to the pins of the device so as to minimize stray capacitance. The oscillator circuit pins are high impedance nodes and are susceptible to noise coupling from adjacent lines, hence the oscillator should also be surrounded by a guard ground. The maximum length of PCB tracks on either pin is 2.5 cm, longer tracks will reduce oscillator stability.

The accuracy and stability of the oscillator is dependent on various factors; principally external components used, ambient temperature and aging. The information given above is included as a guide to the problems encountered in designing a stable oscillator circuit. Manufacturers specifications should be consulted for more comprehensive data before embarking on designs.

*Figures 4a* and *4b* show typical curves of frequency temperature characteristics of tuning fork and A-T cut crystals.

### DP8570 OSCILLATORS

For the DP8570A, the configuration of the crystal oscillator is the standard Pierce parallel resonant oscillator arrangement which has been designed for low power consumption and high stability, this is shown in *Figure 1*. The external components required are a crystal and two capacitors to provide the correct output loading. The configuration recommended is that of a fixed capacitor and a variable trimmer capacitor, adjusting the trimmer allows the crystal loading (and hence the oscillator frequency) to be fine tuned for optimum results. All other components are on-chip.

The DP8570A has three selectable oscillator frequencies which can be used as a clock source, these are split into two groups, there is the high frequency oscillator and the low frequency oscillator. When programmed for low frequency operation, a small low power inverter is selected along with the relevant bias and feedback resistors, similarly for high frequency operation a larger inverter with a different pair of resistors is selected, *Figure 1* illustrates the basic concept.

A fourth option is available, but this is for driving the OSC IN pin with an external 32.768 kHz signal. In this mode the OSC OUT pin is not connected.

The three different crystals frequencies are; 32.768 kHz, 4.194304 MHz or 4.9152 MHz, see data sheet for full explanation of crystal selection. The recommended capacitance values for these crystals are shown in Table 3.

**TABLE III. Oscillator Capacitors** 

	Variable (Osc In)	Fixed (Osc Out)
32.768 KHz	2 pF-22 pF	47 pF
4.194304 MHz	0 pF-80 pF	68 pF
4.9152 MHz	29 pF-49 pF	68 pF

For optimum performance it is recommended that the variable capacitance is placed on OSC IN. The typical value quoted for the trimmer capacitor is the value that the manufacturer quotes for these commercially available types and which will allow accurate tuning of the oscillator. It is not meant to show the range or tolerance of an equivalent fixed value.

3-45

This range is also based on a typical circuit board layout and may have to be changed depending on the parasitic capacitance of the printed circuit board or fixture being used. In all cases the load capacitance specified by the manufacturer is what determines proper oscillation. This load capacitance is the series combination of capacitance on each side of the crystal with respect to ground.

It is perfectly feasible to use two fixed values, however this will not allow optimum setting of the oscillator frequency. For example a 12 pF fixed capacitor with a tolerance of

 $\pm\,10\%$  is a good substitute for the trimmer capacitor in a 32.768 kHz application.

The HF oscillator has been designed primarily for 4 MHz operation therefore greater care should be exercized when choosing external components for 5 MHz operation. The best configuration for the 5 MHz operation is to use a fixed capacitor in parallel with a trimmer capacitor on the OSC IN pin. Note the small variation of the OSC IN capacitance required to ensure correct start-up and oscillation.

TL/F/10356-1




FIGURE 1. DP8570A Oscillator

AN-588

### The crystal frequency can be made available at this pin. Since it is buffered a measuring device can be connected directly to it and the oscillator will remain unaffected. Furpin. ther, this task can be accomplished under software control and without entering test mode.

Adjustment of the oscillator can be carried out using the setup shown in Figure 2, by tuning the capacitance C1 the user can see what effect this variation has on the frequency value.

A calibration routine is necessary to maintain the oscillator

output at the desired accuracy and thus optimize time keeping accuracy. The problem with calibrating these types of

circutis is accessing the oscillator frequency. No test equip-

ment should be connected directly to either oscillator pin, as

the added loading will alter the characteristics of the oscilla-

For the DP8570A, the calibration can be accomplished us-

ing the Multi-Function Output (MFO) pin of the device. The

MFO pin can be programmed for several different functions.

CALIBRATION ROUTINE

1. Buffered Crystal Output

2. Second Interrupt Pin

Timer 0 Output

tor making accurate tuning impossible.

The following sequence of operations is the calibration routine that is required when setting up the oscillator.

- 1. Main Status Register. Write 01xx xxxx. Select RS = 1, PS = 0.
- 2. Output Mode Register. Write 1011 xxxx. Select MFO as buffered oscillator with push/pull and active high configuration
- 3. Real Time Mode Register. Write 0000 0000. Select desired crystal frequency (32.768 kHz).
- 4. Main Status Register. Write 00xx xxxx. Select RS = 0, PS = 0.
- 5. Periodic Flag Register. Write 00xx xxxx. Select Battery backed mode and ensure not in test mode (bit D6 = 1 for single supply mode).
- 6. Monitor the MFO pin with an oscilloscope and observe that the oscillator is functioning at approximately its correct frequency.
- 7. Connect a frequency measuring instrument to the MFO

Care should be exercised when choosing an instrument with which to measure the frequency. To achieve accuracies of 10 ppm or greater high resolution high accuracy instruments only should be used. Instruments recommended are HP 5334A or PHILLIPS PM 6654.

8. Adjust the trimmer capacitor until the desired accuracy is obtained (2 ppm should be achievable). Figure 5 shows the relationship between frequency error or in ppm vs time gained/lost in minutes/year.




FIGURE 2. Calibration Setup

TL/F/10356-2

### **TEST CONSIDERATIONS**

Under test conditions a crystal cannot be used as there is no control over its output, a pulse generator must be used to clock the device in a controlled manner. This presents correlation problems when measuring  $I_{DD}/I_{BB}$  because the clock signal used in testing is a square wave and the values for current consumption will be different. The graphs in *Figure 3* show the values of operating current ( $I_{DD}$ ) and standby current ( $I_{BB}$ ) for different temperatures, voltage and crystal.

The graph that is the most important is I<sub>BB</sub> at 32.768 kHz, the data sheet states that no more than 10  $\mu$ A of standby current will be consumed across temperature for V<sub>BB</sub> = 3V. Typical values at T = 25°C (V<sub>BB</sub> = 3V) as measured on the tester are approximately 4  $\mu$ A, this compares with 6  $\mu$ A as measured with a crystal. If a user wishes to use the 10  $\mu$ A specification, he must limit the battery supply to approximately 3.5V, (see Graph 3a). Graph 3b shows that the standby current does not vary a great deal with temperature.


For the I<sub>CC</sub> measurement a typical value at V<sub>CC</sub> = 5.5V, T = 25°C is 160  $\mu$ A as measured with a tester as opposed to a value of 162  $\mu$ A with a crystal. There is little difference between the two values. The same cannot be said for the high frequency crystals, the tester figure of 210  $\mu$ A for V<sub>CC</sub> = 3V, T = 25°C compared to only 97  $\mu$ A for a crystal. The reason for this is as follows, when forcing with a clock source the current is largely dependent on the capacitance at the OSC OUT pin, the larger the value the larger the current drawn.


During testing the OSC OUT pin cannot be bent out of the test socket therefore there will aways be some value of stray capacitance connected to OSC OUT. Hence, increased current will always be expected.


For the lower frequency crystal the stray capacitance on OSC OUT does not play a major part so the current is greater because of the greater rate of change of the square wave compared to the sine wave output of a crystal.

### CONCLUSION


The calibration of crystal oscillators is fairly straight forward but is of prime importance and as can be seen this task can be accomplished very easily. Regular monitoring of the oscillator frequency can thus be performed with no major disruption to the device's operation.











3

**AN-588** 

# AN-589

# DP8570A Timer Clock Peripheral Test Mode and Test Considerations

Primarily the test mode is used by National Semiconductor to ease the testing of device at manufacture. However, some users may wish to implement testing of devices prior to being used in designs. The purpose of this application note is to give the user insight into what is involved when testing the DP8570A Timer Clock Peripheral (TCP). The complete range of test mode features is presented here along with notes on how to use them. General testing guidelines are also given which should help the user to avoid some of the pitfalls at the design-in stage.

## INTRODUCTION

The real-time clock section of the DP8570A is a series of cascaded registers. To test the correct roll-over of each register in this configuration would take a very long time. For example, if clocked in real-time (100 Hz), testing would take 100 years to complete, obviously this is unacceptable.

Similar problems exist when testing the timers. Each timer is 16 bits wide. If it were to be tested in normal operation, 65536 (2<sup>16</sup>) pulses are required to produce a cycle in the 16th bit in the chain. This will result in an intolerable increase of testing time.

There are further test considerations with the timer prescaler section of the device. These sections contain frequency divider circuits. The easiest way to test these dividers is to measure the frequency of the output and relate it to the frequency of the input. However, with some standard production machines it is difficult to measure frequency. Therefore it will be difficult to check the various outputs of the timer prescaler.

The actual method of testing these prescalers is to apply a set number of pulses to the input of the divider and monitor the output for a change of state. For example, to test the divide by 32000 counter, that number of pulses would have to be applied to produce an output pulse. If the normal timer prescaler configuration is used it will take one full second waiting for the divide by 32000 counter to cycle.

## **TEST MODE FEATURES**

To overcome testing difficulties of the types discussed a test configuration has been designed into the device, which

National Semiconductor Application Note 589 James Petrie



can be implemented via software. Due to the complex nature of the TCP a complete register is required to control the various test functions. This register is situated at RAM location 1F (hex) on page 0 (see datasheet for details of addressing).

The byte associated with this address is normally a general purpose RAM location. When in test mode, the register can be programmed to implement various test configurations. To enable these functions the test mode enable bit (D7) in the Periodic Flag Register (PFR) must be programmed high. For normal operation this bit must be programmed low. The Test Mode Register configuration is shown in *Figure 1*.

D7 <sup>-</sup>	D6	D5	D4	D3	D2	D1	D0
OSF DISABLE	CRB1	CRB0	SRB1	SRB0	ЕМС	CTR TEST	DIR CLOCK


FIGURE 1. Test Mode Register

The functions of the various bits in the test mode register are outlined below. Bits D0,D1 are for the real time and associated sections, while bits D2 to D6 are dedicated for timer use. D7 is for general use.

**DIR CLOCK:** This is the Direct Clock bit. When programmed high, the oscillator dividers (32 kHz and 1 kHz) and the pulse subtractor in the clock prescaler are bypassed. Thus the counters in the real-time section may be clocked directly from a signal presented to the OSC IN pin. To implement the by-pass correctly, the frequency select bits D6,D7 in the Real-Time Mode Register, must be programmed such that the 4 MHz and 5 MHz divider chains are also disabled (see *Figure 2*). The correct programming for this is D6,D7 = 0 or D6,D7 = 1.


The 4 MHz and 5 MHz dividers can be tested in isolation using the following:

The output of these dividers will then be connected directly to the 1/100 second counter.



**CTR TEST:** This is the Counter Test bit. When programmed high this bit re-configures the real-time counters into the test mode configuration (see *Figure 3*). These counters can then be clocked in parallel thus reducing the test time.

Note that the normal maximum operating frequency of these counters is 100 Hz and the low frequency oscillator is designed to work at approximately 32 kHz. Therefore if fast clocking via the OSC IN pin is attempted serious signal degradation will occur, making testing impossible. For these reasons it is recommended that for a  $V_{BB} = 3V$ , a maximum clock rate of 200 kHz (2.5  $\mu$ s pulse width) is used on all tests where the OSC IN pin provides the clock source. When testing the device using clock bursting, the clock must be a return-to-one signal. It is not recommended that the OSC OUT pin be used as a clock source, and must not be connected.



TL/F/10357-2

#### FIGURE 3. Real Time Counters, Test Mode Configuration

**EMC:** This is the Enable MSB Clock bit. When programmed high it enables the most significant bytes (MSBs) of both 16bit counters to be clocked directly. Note that the LSB's of the counters must contain 00(hex) for this to be accomplished correctly. This allows the timers to be tested in two halves, which will give a total of  $2 \times (2^8)$  possible states instead of  $2^{16}$  significantly reducing the test time.

**SRB0:** This is the Signal Route Bit for timer 0 prescaler. When programmed high this bit routes the selected clock to the timer 0 output.

**SRB1:** This is the Signal Route Bit for timer 1 prescaler. When programmed high this bit routes the selected clock to the timer 1 output.

The inclusion of the "SRB" bits means that a more modular approach to timer testing is achieved because the timer prescalers can be tested in isolation.

The clock select bits in the Timer Control Register are used to route the required clock to the multiplexer output "selected clock", of the prescaler, see *Figure 4*. Note that timer 0 output is accessed using the Multifunction Output (MFO) pin, see datasheet for details. However, timer 1 output can be accessed directly using the Timer 1 Output (T1) pin.

**CRB0:** This is the Crystal Route Bit for timer 0 prescaler. When programmed high this bit routes the external crystal frequency to the dividing counters in timer 0 prescaler which are normally driven by the internal 32.0 kHz signal. See *Figure 2*.

**CRB1:** This is the Crystal Route Bit for timer 1 prescaler. When programmed high, this bit routes the external crystal frequency to the dividing counters in timer 1 prescaler which are normally driven by the internal 32.0 kHz signal.

The "CRB" bits allow all the timer prescaler dividers to be clocked directly from the OSC IN pin. This allows fast clocking of these circuits plus allowing a known number of pulses to be input. Note that the frequency select bits in the Real Time Mode register need to be programmed correctly for this section as well (D6,D7 = 0).

**OSF DISABLE:** This is the OSC Fail Disable bit. When programmed high this bit causes the OSC FAIL detect circuitry in the clock prescaler to be disabled.

One of the features of the DP8570A is its ability to detect when an oscillator fail has occurred. Oscillator failure is indicated by reading bit D6 in the Periodic Flag Register. When an oscillator fail is detected four functions are performed.

- 1. The OSC fail flag is set.
- The clock start/stop bit (CSS) in the Real Time Mode register is reset, preserving the time that the oscillator stopped.
- Overrides the lockout circuitry ensuring that the processor interface is not locked out when an oscillator fail has occurred.
- Presets battery bit (D6) in PFR (selects the single power supply mode).

Under test conditions a crystal cannot be used because there is no control over its output. A pulse generator must be used to clock the device in a controlled manner. Obviously, under these single-step conditions the oscillator fail circuitry will detect a lack of oscillation and perform the functions mentioned. Therefore for certain tests it will be necessary to disable the effect of OSC fail (where CSS must remain active for example), this is accomplished using the OSC Fail Disable bit.

To get access to the OSF Disable bit, the test mode enable bit (D7 in the PFR) must be written high first. The order is important. The OSF Disable bit must also be programmed back to zero when testing is complete. This is to avoid drawing excess current in standby mode. When initial power is applied, this bit has been designed to power-up in the inactive state, ensuring that the TCP will not enter a state of permanent lockout when power is applied.

The implications of function 4 are also important when considering the fact that a pulse generator is used to provide the clock source. The amplitude of the output signal should be equal to the power supply of the oscillator (V<sub>OSC</sub>).

When testing the device in battery backed mode, and using single pulses, the following steps are necessary to ensure that the device is in the correct mode.

MSR	00	RS = 0
PFR	80	Test Mode Enable
TST	80	OSC Fail Disable Bit
PFR	80	Battery Bit and Test Mode

The reason the PFR has to be written twice is that the OSC FAIL signal will preset the single supply bit (D6) and has to be disabled before D6 can be written to.

## **Read/Write Considerations**

In the DP8570 the bits in the address space consist not only of normal read/write bits but also flags, read-reset flags, write-1 reset flags and a dual function bit. The user should be aware of these when attempting to read/write to the device.

# **Read/Write Bits**

MSR	D6,D7 Only
TCR0, TCR1	D0-D7
PFR	D7 Only
IRR	D0–D5, D7
RTMR	D0-D7
(Bit D3 will rer is running)	nain at 0 unless in test mode or the oscillator
OMR E	00-D7
ICR0, ICR1 E	00-D7
1/100 sec	D0-D7
SECONDS	D0-D6 (D7 Always 0)
MINUTES	D0-D6 (D7 Always 0)
HOURS 24 hr	D0-D5 (D6,D7 Always 0)
HOURS 12 hr	D0-D4
(D5,D6 Always	s 0, D7 = am/pm Bit)
DAY of MONT	H D0-D5 (D6, D7 Always 0)
MONTH	D0-D4 (D5-D7 Always 0)
YEAR	D0-D7
DAY of YEAR	D0-D7
100's DOY	D0, D1 (D2-D7 Always 0)
DAY of WEEK	D0-D2 (D3-D7 Always 0)

The rest of the address locations are all read/write but certain precautions need to be observed to get a correct response. It is recommended that the control section is reset to all zeros before attempting to write to the rest of page 0 locations.

#### Flags


The flags are read only and are set and reset by events inside the device. They are situated at the following locations.

Batt Low Flag	D6 of IRR
Power Fail Flag	D1 of MSR
Interrupt Status Flag	D0 of MSR
Dual Function	D6 of PFR

When READ, D6 of the PFR will give the contents of the OSC FAIL flag. When WRITTEN, D6 sets up the power supply mode of the DP8570A. Writing a "1" selects single power supply mode, writing a "0" selects the battery backed mode.

The implications of this are quite important because there is no direct way the user can tell which power supply mode is selected. The only way of determining the mode is by monitoring the OSC OUT pin. The amplitude of this signal will be approximately equal to the value of  $V_{OSC}$ .

In battery backed mode the amplitude will be V<sub>BB</sub>, in single supply mode the amplitude will be V<sub>CC</sub>. Most of the time, the OSC OUT pin may be measured using a 10 M $\Omega$ , 10 pF probe. However, when the high frequency oscillator, the oscillator may stop. For this case a higher impedance, lower capacitance probe may be needed.



The only way of determining the mode is by monitoring the OSC OUT pin. The amplitude of this signal will be approximately equal to the value of  $V_{OSC}$ .

In battery backed mode the amplitude will be  $V_{BB}$ , in single supply mode it will be  $V_{CC}$ . This technique is helpful when using either a pulse generator or crystal as the clock source. However, care should be taken if probing OSC OUT when a crystal is used, as the probe capacitance could stop the oscillation. As a minimum, a 10 Meg, 10 pF probe is recommended.

The read-reset flags are situated at D0-D5 of the PFR and are read only. Internal events inside the device set the flags and they are reset when read.

The write-1 reset flags are situated at D2–D5 of the MSR. They can be read as a 1 or 0, and are set by internal events inside the device. Writing a 0 to these bits will have no effect. Writing a 1 will reset these flags. AN-589

#### CONCLUSION

The purpose of this note is to provide some insight into the complexities of testing the DP8570A. It shows how various tests can be carried out efficiently by designing testability into a device. The actual testing implemented by the user can be simple or comprehensive and only those features required need be utilized.

# AN-595

# Flexible Timers on the DP8570A and DP8571A

# **1.0 INTRODUCTION**

The DP8570A/71A/72A/73A family are Real Time Clock devices for use in microprocessor based systems. They are fast access low power devices with power fail protection, standby battery operation, multiple interrupts and RAM. In addition, the DP8570A and DP8571A "Timer Clock Peripherals" have two independent 16-bit binary countdown timers.

This application note deals primarily with using the timers on the DP8570A. It has dedicated timer pins; an external clock pin with up to 10 MHz operation, a hardware gate/hold pin per timer and a timer output pin. Further information is given on the DP8571A which does not have these pins, hence reducing the pin-count, but has the additional feature of being able to cascade the timers. This gives use of a timer of up to 32 bits.

The timers of both Timer Clock Peripherals have four modes of operation, seven crystal derived internal clock frequencies, programmable output/interrupts and standby operation.

#### 2.0 DP8570A TIMERS (Figure 1)

Each timer, T0 and T1, has two 8-bit registers (MSB/LSB) accessed in page 0 of the DP8570A internal memory. The number in these registers is loaded into a 16-bit counter when the timer is started and the counter is decremented by the selected input clock, hence controlling the timer output. Resetting the timer start/stop bit stops the timer and puts its output into its inactive state (high or low depending on how

National Semiconductor Application Note 595 Jim Mitchell



the output is programmed). Every time the start/stop bit is set the initial value in the MSB/LSB registers is reloaded by the next selected timer input clock. A gate signal, however, is also required in mode3 before loading occurs.


Normally when accessing the data at the address of the MSB/LSB registers, only the initial load value will be read. However, if the timer read bit is set, the MSB/LSB of the counter itself will be read. This allows the user to read the counters *on-the-fly*, without disturbing timing.

The user might encounter a problem when the timer read bit is set just as the counter is reloading. In this case there is a possibility of erroneously reading a value FFhex. The user should choose initial register values other than FFhex, reject any FFhex read on-the-fly and try the read operation again.

The T0 and T1 timer start/stop bit and timer read bit are in their respective timer control registers. Each timer control register contains the following bits:

- D0 Timer Start/Stop
- D1 Mode Select M0
- D2 Mode Select M1
- D3 Input Clock Select C0
- D4 Input Clock Select C1
- D5 Input Clock Select C2
- D6 Timer Read
- D7 Count Hold/Gate

The programming of this and other timer related registers is described in Section 3.0.



## 3.0 USING DP8570A TIMERS

The following steps should be considered when using the DP8570A timers.

- a) Mode selection to give desired output waveform.
- b) Input and frequency selections to give countdown rate of timer.
- c) Output and interrupt selections.
- d) Standby conditions (if backed up).

#### 3.1 Mode Selection

Four output waveforms are obtainable from the DP8570A, selected by two bits in the timer control registers (Table I).

M1	мо	Mode
. 0	0	0.
0	1	1
1	0	2
1	1	3

# 3.1.1 MODE 0: Single Pulse Generator (Figure 2)

In this mode, a timer output will become active and its counter will decrement once its start/stop bit is set. As soon as the count reaches zero, the start/stop bit is automatically reset and the output returns to its inactive state. Hence the active time (pulse width) is

Timer Clock Period imes Number in Counter.

The pulse width can be increased by temporarily stopping the clock in two ways. One is to set the timer count hold/gate bit and the other is to put the respective G Input pin to a logic one state. The count-down is resumed once the count hold/gate bit is reset or G input is returned to logic zero.

# 3.1.2 MODE 1: Rate Generator (Figure 3)

In this mode, a timer output will become active and its counter will decrement once its start/stop bit is set. When the count reaches zero, the output goes inactive for one timer clock period. The counter is reloaded with the number in the registers. On the next clock the output goes active again and the sequence continues until the start/stop bit is reset. The period is

Timer Clock Period  $\times$  (Number In Counter + 1)

and the (inactive) pulse width is the timer clock period. As in mode 0, the count-down can be suspended by setting the count hold/gate bit or using the G input pin.

#### 3.1.3 MODE 2: Square Wave generator (Figure 4)

In this mode, a timer output will become active and its counter will decrement once its start/stop bit is set. On the clock after the count reaches zero, the output goes inactive. The counter is reloaded with the number in the registers and the counter will decrement to zero again before returning to the active state. The sequence continues until the start/stop bit is reset. The period is

 $2 \times \text{Timer Clock Period} \times (\text{Number In Counter} + 1)$ 

with a 50% duty cycle. As in mode 0, the count-down can be suspended by setting the count hold/gate bit or using the G input pin.

#### 3.1.4 MODE 3: Retriggerable One Shot (Figure 5)

In mode 3, a timer output will not become active as soon as its start/stop bit is set. A trigger is also required to start a pulse. The trigger is either setting the count hold/gate bit or the rising edge of a pulse on the respective G input pin. (A trigger pulse as short as 25 ns can be used.) This trigger puts the timer output in the active state and initiates the timer count-down sequence. When the count reaches zero, the output goes inactive until another trigger is given. The pulse width is

Timer Clock Period imes Number in Counter.

If another trigger is given while the timer is still decrementing, the initial number from the timer registers is reloaded thus extending the pulse. The DP8570A remains operational in this mode until the start/stop bit is reset.





FIGURE 2. Mode 0—Single Pulse Generator



3




FIGURE 5. Mode 3—Retriggerable One Shot

# 3.2 Input and Frequency Selection

**AN-595** 

The DP8570A has a real time clock which can operate from any of four different crystal frequencies. The crystal frequency is selected in the real time mode register (Table II).

TABLE II. Real Time Mode Register Crystal Select Bits, D7, D6

XT1	ХТО	Crystal Frequency
0	0	32.768 kHz
0	1	4.194304 MHz
1	0	4.9152 MHz
1	1	32.000 kHz

This crystal frequency or a lower frequency derived from it can be used to clock the timers by programming the C2, 1, 0 bits in the timer control registers (Table III) to values 001 to 111 inclusive.

# TABLE III. Timer Control Registers Input Select Bits, D5, D4, D3

C2	C1	CO	Timer Clock
0	0	0	External
0	0	1	Crystal Frequency
0	1	0	(Crystal/Freq.)/4
0	1	1	93.5 μs (10.7 kHz)
1	0	0	1 ms (1 kHz)
1	0	1	10 ms (100 Hz)
1	1	0	0.1s (10 Hz)
1	1	1	1s (1 Hz)

Alternatively, the DP8570A timers can be clocked externally via the TCK pin by writing 000 to these input clock select bits. Falling edges of a 50% duty cycle input on the TCK pin clock the timer(s) at up to 10 MHz.

The other DP8570A timer input pins are G0 and G1 for timers T0 and T1 respectively. Their action depends on the mode selected and is described above.

# 3.3 Output and Interrupt Selections

The T1 pin on the DP8570A is a dedicated output from timer 1, whereas the MFO pin can be configured as the timer 0 output by programming the output mode register (Table IV). TABLE IV. Output Mode Register

# Output Pin Configurations

	D6	MFO	
	0	INTR	
	1	то	
	х	OSC	
		·	
D7	0 (For Tir	ner/INTR Output)	
D6	T0/2nd-INTR		
~-			
	Push-Pull/Open-Drain Active-Hi/Active-Lo		
D4			
50	Pueb-Pul	VOpen-Drain	
	Active-Hi/Active-Lo		
02	Active-Hi	/AGUVE-LU	
D1	Push-Pul	I/Open-Drain	
D0	Active-Hi	/Active-Lo	
	D6 D5 D4 D3 D2 D1	0 1 X D7 0 (For Tir D6 T0/2nd-I D5 Push-Pul D4 Active-Hi D3 Push-Pul D2 Active-Hi D1 Push-Pul	

The output mode register also sets up the T1, MFO and INTR pins as active high or low, push-pull or open-drain outputs individually. Care should be taken not to connect an open drain output to a voltage above the supply voltage in use at the time (i.e., normally V<sub>DD</sub>, but V<sub>BB</sub> in standby).

Whenever a timer goes to its inactive state (except when the start/stop bit is reset), it generates an interrupt, setting a bit in the main status register (*Figure 6*). Interrupt control register 0 includes one bit for each timer (D6, 7 for T0, 1 respectively) to enable the interrupt at an output. The interrupt routing register has one bit per timer (D3, 4 for T0, 1 respectively) to route the interrupt to either the INTR pin or MFO pin (if programmed as a second interrupt pin). The interrupt status bit (D0 of the main status register) is also set when an interrupt (timer, alarm, powerfail or periodic) is pending at an output pin. Writing 1's to the main status register resets interrupts.

#### 3.4 Standby Operation

The DP8570A power supply mode should be programmed on initial power-up by writing to bit D6 of the periodic flag register. Write 1 for single supply mode (hence no standby features) or 0 for battery backed-up mode. If thus configured, the device will enter "standby" mode if V<sub>BB</sub> > V<sub>DD</sub>. (See datasheet for hardware configurations.)

In standby the timers are still operational if bit D5 of the real time mode register is set, and if so, timer (and other) interrupts can be operational in standby if bit D4 is set. The TCK and G input pins, however, are locked out. In standby, MFO, INTR and T1 outputs are automatically configured in as open-drain outputs. When power is restored ( $V_{DD} > V_{BB}$ ) they return to the output mode register configuration.

#### 3.5 Power-Fall Operation

If a low going power loss signal is detected at the PFAIL pin, timer operation is unaffected, but the databus will be locked out.

#### **4.0 PROGRAMMING STEPS**

The following steps are recommended for setting-up DP8570A timer(s) after initial power-up.

a) Main Status Register: PS = 0, RS = 1.

- b) Real Time Mode Register: Set crystal bits (Table II) and standby operation bits.
- c) Main Status Register: PS = 0, RS = 0.
- d) **Periodic Flag Register:** Set bit D6 for single-supply mode or reset it for backed-up mode and reset D7 so that the device is not in test mode.
- e) **T0 and/or T1 Control Register:** Reset start/stop bit (D7) to ensure timers are not running.
- Interrupt Routing Register: Route T0/1 interrupts (0 to INTR, 1 to MFO) if required.
- g) Main Status Register: PS = 0, RS = 1.
- h) Output Mode Register: Configure T1, INTR and MFO Outputs (Table IV).
- i) Interrupt Control Register 0: Set T0/1 interrupt enable bits if required.
- j) MSB/LSB T0/1 Registers: Load values for timer counter(s).
- k) READ: main status register to clear old interrupts.
- I) Main Status Register: PS = 0, RS = 0.
- m) T0 and/or T1 Control Registers: start timer(s) with bits set for mode (Table I) and input clock (Table III).




FIGURE 6. DP8570A Timer Interrupts

TL/F/10372-6

**AN-595** 

If operating timers in a device already powered-up and in a known state, the above order need not be adhered to. Table V gives an example of programming a DP8570A which is already powered-up and operating correctly as a real time clock from some crystal frequency, with power supply configured and not in test mode. This example produces a 10 ms high pulse output (push-pull) every one minute using timer 1.

**TABLE V. Programming Example** 

Write D7–0	Addr.	Reg.	Action
00000000	00000	MSR	PS=RS=0
00000000	00010	TCR1	T1 Stopped
00000010	00000	MSR	RS=1
0xxxxxxx	00011	ICR0	Disable T1 Intr.
00010111	10010	MSB1	} Timer
01101111	10001	LSB1	} Counter = 5999
xxxxxx10	00010	OMR	T1 = p-p, act.hi
00000000	00000	MSR	RS = 0
00101011	00010	TCR1	Start T1: Mode 1,
• .			10 ms Input Clock

(x = Don't care in this example, but may affect other DP8570A operations.)

#### **5.0 SYNCHRONIZATION ERRORS**

As the operation of starting and stopping timers is normally asynchronous to the timer input clock, an error of up to one timer input clock period may occur. Similarly, when using the G input pins or count hold/gate bits, the following synchronization errors can occur depending on timer input clock selected:

External (TCK) + Up to One External Clock Period.

Crystal or Crystal/4 + Up to One Crystal Clock Period.

Other Selections +0 to 32  $\mu$ s.

#### 6.0 DP8571A

The DP8571A differs from the DP8570A in the following ways.

- a) It has no G0 or G1 input pins. The count hold/gate bits are fully functional however.
- b) It has no T1 timer output pin. The T1 timer read bit can be used as in the DP8570A to read the value in the timer counter and interrupts are fully functional also.
- c) The T1 bits in the output mode register (D1, 0) are RAM bits.
- d) It has no TCK input pin.
- e) An added feature of the DP8571A is it cascade mode, activated by programming T0 control register C2–0 input clock select bits to 000.

The C2-0 bits in the T1 control register are programmed to select its input clock (000 is not allowed).

#### 6.1 DP8571A Cascade Operation

In the cascade mode, the output of timer T1 is the input clock for T0 (*Figure 7*). The T1 bits in the output mode register have no effect on T1 and in this mode T1 output should be considered as active-low with falling edges clocking T0.

This mode gives the DP8571A 32-bit counter capability, raising the maximum counter value from 65,535 to 4,294,967,295 (Table VI). If used, for example, as a large hundredths of seconds countdown timer (with 10 ms input clock selected for T1), full range is increased from about 10.9 minutes to over 71 weeks. Also a larger variety of output waveforms can be realised by varying the values in the counters.

TADIE	VI.	Some	Dowore	<b>af 2</b>	for	Reference
INDLC	¥ I.	Some	ruwers	<b>UI 2</b>	101	nelelelice

Power of 2	Decimal Value		
0	1		
4	16		
8	256		
12	4,096		
- 16	65,536		
20	1,048,576		
24	16,777,216		
28	268,435,456		
32	4,294,967,296		

In cascade mode, timers cannot count down in binary from numbers greater than 65,535 if T1 contains any number other than FFFFhex. This is because T1's MSB/LSB register values are reloaded instead of FFFF when T1's count reaches 0000. The following example shows one way of working around this problem.

For countdown from 65,540 (00010004 hex) with cascaded timers:

- a) Reset Timer Control Registers.
- b) Write 00hex to T0 MSB, 01hex to T0 LSB registers and 00hex to T1 MSB, 04hex to T1 LSB registers.
- c) Setup operating conditions for timers (outputs, interrupts, etc.).
- d) Start T0 cascaded from T1, in mode 0-3 as required.
- e) Start T1 with required input, in mode 1-3 as required.
- f) After first T1 input clock (which loads T1 counter) and before the T1 count decrements to 0000hex, write FFhex to both LSB and MSB T1 registers.

The cascaded counters will continue to count down in effect as a single binary counter.

However, in modes 1 and 2, when T0 and T1 both reach 0000hex, the last values written to their LSB/MSB registers will be loaded (i.e. T0 = 0001hex, T1 = FFFhex) unless action is taken to restore T1's original values (0004hex in this case) beforehand. One method would be for T0 to generate an interrupt on reaching 0000hex, which initiates a software routine to write the required values to T1 LSB/ MSB registers before T1 decrements to 0000.

#### 7.0 TEST MODES

Several features are available on the DP8570A/71A to ease testing by setting the test mode enable bit (D7) of the periodic flag register and programming the test register in page 0 as follows.

- a) Set the enable MSB clock bit (D2): allows the two MSB halves of the timer counters to be clocked instead of the LSB halves (LSB must be 00).
- b) Set signal route bits 0 and 1 (D3, 4): routes the T0 and T1 selected input clock signal (inverted) to the output and interrupt logic of the device instead of the timer outputs.

The DP8571A, timer 1 signal route bit does not affect the output of T1 clocking T0, but allows T1 interrupt logic to be driven from its (inverted) clock instead of its output.

c) Set crystal route bits 0 and 1 (D5, 6): The timer input clocks 10.7 kHz to 1 Hz inclusive (Table III) come from prescalers driven from an internal 32 kHz signal. If the crystal route bit is set for a timer, then its prescaler is instead driven directly by the crystal oscillator. Hence, an external signal generator faster than 32 kHz can be used to speed up testing of the timer. Real time mode register crystal select bits should be set to 32 kHz or 32.768 kHz in this case.

(Test modes are featured in detail on National Semiconductor Application Note 589.)




FIGURE 7. DP8571A Cascade Mode, T0 Mode = T1 Mode = 1, Value in Counters: T1 = 3, T0 = 2

**B-43** 

# Typical DP8570A Interface to the IBM PC/XT for the Purpose of Engineering Evaluation

The following information has been provided to assist the reader in developing an evaluation setup for the DP8570A family of Real Time Clocks. This interface was prototyped and debugged for use in an IBM PC/XT or compatible bus computer with an accompanying program written in the C language.

#### Hardware Used

The interface consists of:

DP8570A Timer Clock Peripheral 74ALS521 Address Decoder (I/O Hex 300 to 31F)

74ALS245 Transceiver (Data Bus Buffer)

Lithium Battery (3.4V Nominal)

Standard Pierce Parallel Resonant Crystal

(32.768 kHz, ±20 ppm)

Various Capacitors (±10%)

Various Resistors (1/8W ±10%)

Refer to the complete schematic provided. (Figure 1)

As shown on the schematic, T1, G1, G0 MFO, INTR, and TCK are available for monitoring purposes.

Pins T1, MFO, INTR, and TCK have 3.9k pull-up resistors to V<sub>BB</sub>. These resistors allow operation of T1, MFO, and INTR outputs during power down when in the battery backed mode. The resistor on TCK guarantees this input will not be floating.

National Semiconductor Application Brief 43 Milt Schwartz



Pins G0 and G1 have 10k pull-down resistors to ground. These resistors ensure that Timer 0 and Timer 1 are enabled by the hardware.

A resistor divider was placed at the PFAIL pin in place of an external power fail signal (as suggested in the data sheet). This facilitates bus lockout during a power fail/return. The user may wish to simulate standby mode by changing the voltage at the PFAIL pin. For example, this may be accomplished by connecting a resistor (fixed or variable) in parallel with the 3.4k resistor.

Separate power supplies for  $V_{CC}$  and  $V_{BB}$  may be used in place of the system 5V supply and battery for the purpose of monitoring the supply currents.

## Software

A demo program, TCP, was written in C language and designed to run on MS-DOS or PC-DOS. The program TCP consists of several pop up menus with the initial display as the main menu. This menu lists the available functions which may be called. Each pop up menu prompts for an entry and provides on-screen documentation.




FIGURE 1. DP8570A Timer Clock Peripheral Interface to IBM/XT

TL/F/10402-1

3

**AB-43** 

# Add a Hardware Clock/ Calendar to Your IBM PC

By installing a clock/calendar chip, some interface circuitry, a battery backup system, and two simple programs in your IBM PC, you can add a real-time hardware clock to your computer.

For many personal-computer applications, you need to use time-of-day information to time-stamp files (i.e., to keep track of when you initiated files and when you last updated them), run datebook software, enable autoanswer/autodial modems, and perform other tasks. The IBM PC-DOS maintains a software clock/calendar, but it requires you to enter both date and time from the keyboard every time you power up the computer. However, by adding an inexpensive hardware real-time clock, you can eliminate manual date/time entry.

To add a hardware clock to your PC, you need only a clock/ calendar chip, some interface circuitry, a battery backup system, and two simple programs that let you initialize, read from, and write to the chip. You can use a chip like the MM58274 clock/calendar chip from National Semiconductor as a real-time clock. Although it's fabricated in low-power CMOS, the chip is directly compatible with TTL-level systems. Because of the chip's low current drain in standby mode (10  $\mu$ A at 2.2V), you can use a small lithium battery National Semiconductor Application Note 443 Wesley Lee

-----




for standby operation. If the battery and clock chip are isolated from all other computer circuitry, the chip will continue keeping correct time for years in standby mode.

#### THE MM58274 CLOCK/CALENDAR CHIP

At the heart of the MM58274 are fourteen cascaded counters that provide the timekeeping functions (*Figure 1*). These counters range from tenths of seconds to tens of years; one of them keeps track of the day of the week. A 2-bit register keeps track of the years since the last leap year; you have to set this register during initialization, but it's not otherwise accessible to the user. The fastest counter (tenths of seconds) is clocked by a 10-Hz reference signal that the chip produces by prescaling the 32.768-kHz output of the internal crystal oscillator. As each counter rolls over, the resulting carry pulse clocks the next counter.

Each timing counter is individually addressable for reading or writing; when you place an address (in the range  $1_{\text{HEX}}$  through  $E_{\text{HEX}}$ ) on the MM58274's four address lines, the corresponding counter is connected to the four data lines for a data transfer in BCD format. Unused bits (eg, bit 3 in the tens-of-minutes counter, which counts only from 0 through 5) are forced to zero in the read mode and are ignored in the write mode.




TL/F/8690-1

FIGURE 1. Although it's fabricated in low-power CMOS, the MM58274 clock/calendar chip is directly compatible with TTL-level systems. It includes 14 cascaded counters that provide the timekeeping functions.

-	
~	
-	
- ñ	
-	•
-	
- Cui	,

	TABLE I. I/O Address Map
HEX RANGE	USAGE
000-00F	DMA 8237A-5
020-021	INTERRUPT 8259A
040-043	TIMER 8253-5
060-063	PPI 8255A-5
080-083	DMA PAGE REGISTERS
0AX	NMI MASK REGISTER
0CX	RESERVED
OEX	RESERVED
200-20F	GAME CONTROL
210-217	EXPANSION UNIT
220-24F	RESERVED
278–27F	RESERVED
2C0-2DF	AST "SUPER PAK" CARD
2F0-2F7	RESERVED
2F8-2FF	ASYNCH COMM (SECONDARY)
300-30F	MM58274 REAL-TIME CLOCK
310-31F	OTHER PROTOTYPE CARDS
320-32F	FIXED DISK
378–37F	PRINTER
380-38C	SDLC COMM
380-389	BS COMM (SECONDARY)
3A0-3A9	BS COMM (PRIMARY)
3B0-3BF	IBM MONOCHROME DISPLAY/PRINTER
3C0-3CF	RESERVED
3D0-3DF	COLOR/GRAPHICS
3E0-3E7	RESERVED
3F0-3F7	DISKETTE
3F8-3FF	ASYNCH COMM (PRIMARY)

Note that the timing counters account for only 14 of the chip's 16 addresses. The remaining two— $0_{HEX}$  and  $F_{HEX}$ —are described in *Figures 2* and *3*, respectively. Address  $0_{HEX}$  operates as a control register when written to and as a status register when read from; address  $F_{HEX}$  is the clock-setting or interrupt register, depending on the state of bit DB<sub>2</sub> in the control register. (Note that the 16 MM58274 addresses can be offset from the IBM PC's  $0_{HEX}$  I/O address space. The chip might occupy locations  $300_{HEX}$  to  $30F_{HEX}$  in the computer's I/O space, for example, as Table I shows.)



(a)




FIGURE 2. The MM58274's control register (a), in response to a nibble written to it, determines mode, starts and stops the clock, and selects interrupt frequency. The status register (b), a read-only register, indicates changes in clock data and signals an interrupt. Both registers reside at address 0<sub>HEX</sub>, which may be offset from location 0<sub>HEX</sub> in a host computer's I/O space.




FIGURE 3. The state of bit DB<sub>2</sub> in the control register at address  $0_{HEX}$  selects one of two command registers at address FH<sub>EX</sub>. If the control register's DB<sub>2</sub> equals 0, then F<sub>HEX</sub> becomes the clock-setting register (a). If DB<sub>2</sub> is 1, then F<sub>HEX</sub> becomes the interrupt register (b).


The control register (address 0<sub>HEX</sub>, write mode) selects normal or test mode, clock start and stop functions, and interrupt start and stop functions; the register also determines whether the clock-setting register or the interrupt register will be accessed by the next write to address FHEX. The status register (address 0HEX, read mode) has only two active bits: the Interrupt flag and the Data Changed flag, which is set if any of the timing counters change state during a read operation. Both flags are cleared on completion of a read operation. The clock-setting register (address FHEX, control register bit  $DB_2 = 0$ , write mode) is used only during initialization to set 12- or 24-hr mode, the AM/PM flag (if the clock is in 12-hr mode), and the number of years (zero to three) since the last leap year. The interrupt register (address  $0F_{HEX}$ , control register bit  $DB_2 = 1$ , write mode) determines the interval at which interrupts (if any) are generated.

The I/O channel of the IBM PC is an extension of the 8088 microprocessor bus. The control, address, and data lines of the IBM PC's I/O channel are essentially the same as those of the 8088  $\mu$ P bus, but the PC's I/O channel also has interrupt DMA (direct memory access) functions. In the PC, however, I/O addresses are limited to the range 0<sub>HEX</sub> through 03FF<sub>HEX</sub>, so that only 10 address lines (A<sub>9</sub> through A<sub>0</sub>) need to be decoded. In the *Figure 4* circuit, a 74HCT688 8-bit comparator, via its P<sub>0</sub> through P<sub>7</sub> lines, decodes eight signals: the negative-logic OR of IOR and IOW (the I/O read and write strobes), the DMA strobe (AEN, which is always

low for an I/O operation), and the upper six address bits ( $A_9$  through  $A_4$ ). The base address of the MM58274 is set by the six DIP switches connected to the corresponding Q inputs of the comparator. Address lines  $A_3$  through  $A_0$  are connected directly to the MM58274 address inputs.

The 74HCT688 compares the eight P and Q inputs for equality. When a P = Q condition becomes true, the comparator generates an active-low device-enable strobe (DEN). This signal enables the MM58274, a MM74HCT164 (a wait-state generator), and a 74HCT245 bidirectional bus driver connecting the clock data lines to the IBM bus. Pullup and pulldown resistors on the bus driver force the upper nibble of the IBM bus to  $3_{\text{HEX}}$  during an I/O read operation, thus adding  $30_{\text{HEX}}$  to the BCD output of the clock to convert the BCD number to the corresponding ASCII character.

You don't need to use DIP switches to change the base address of the MM58274 (you could, for instance hard-wire the address), but it's standard practice to include DIP switches on I/O interface cards that are added to any microcomputer. Take care not to assign the same I/O address or addresses to more than one device; if you do, I/O devices will contend for the bus, with unpredictable results. Table 1 shows the standard I/O addresses recognized by PC-DOS version 2 as well as the address space used by the MM58274 (300<sub>HEX</sub> to 30F<sub>HEX</sub>) and, incidentally, by the popular AST Super-Pack card. If you have any other addrin cards in your system, be sure to check the documentation







to determine which addresses they use, so you can avoid I/O address duplication.

# ISOLATION PROLONGS BATTERY LIFE

The battery-isolation circuits in *Figure 4* prevent reverse current from flowing through the battery when the main power supply is on, and they minimize current drain in the battery backup mode. Diode D<sub>3</sub> (*Figure 4*) isolates the battery during system power-up. As long as the system power supply is at least one diode drop (0.6V) above the battery voltage ( $\sim$  3V), diode D<sub>3</sub> is reverse-biased, and no current can flow into or out of the battery. If the supply voltage drops below this level, the battery powers the clock.

To prolong battery life in standby mode, you should eliminate all leakage paths to ground. Don't insert a switch in the +5V bus, though; that alone would be ineffective, as *Figure 5* shows. A ground-disconnect switch ( $Q_2$  in *Figures 4* and 5) eliminates leakage from the RD, WR, and CS pins through the protection diodes. However, even when the ground-disconnect switch is open, a leakage path still exists through the INT pin and an open-drain transistor to ground; thus, a second switch ( $Q_3$ ) is needed to open this path also. When the system powers down, transistor  $Q_1$  shuts off, thereby also shutting off  $Q_2$  (the ground-disconnect switch),  $Q_3$  (the interrupt-disconnect switch), and  $Q_5$  (the power-failure detector). Shutting off these transistors not only isolates the negative terminal of the battery from the system ground bus but also breaks the leakage paths indicated in *Figure 5*.





When  $Q_5$  shuts off, the power-failure circuitry disables the clock chip by forcing the  $\overline{CS}$  (chip select) signal high. The  $\overline{CS}$  signal is the negative-logic AND of  $\overline{DEN}$  (the device-enable signal) and  $\overline{PFD}$ , both of which are active-low. If either one goes high (because the clock is not being addressed, or because system power is low or off), the two sections (IC<sub>4A</sub> and IC<sub>4B</sub> in *Figure 4*) of the 74HCT02 drive the  $\overline{CS}$  input high to disable the clock chip.

#### TIMING CONSIDERATIONS

Your interface circuitry will have to compensate for some incompatibility between the PC and the MM58274. The IBM PC requires that data be read from a device in three clock cycles (630 ns). However, the read-access time of the MM58274 is 850 ns. To slow down the computer, you need a wait-state signal that pulls the I/O CH RDY bus line low for one or more clock cycles. The wait-state generator (Figure 4) consists of an MM74HCT164 shift register, a negativelogic AND gate (IC<sub>4C</sub>, one section of a 74HCT02 NOR chip), and an open-collector inverter (ICIC, one section of a 74LS03). Until the clock is addressed, DEN remains high, clearing the shift register via inverter IC1B; at this time the Q<sub>H</sub> output of the shift register is low. When the clock is addressed, DEN goes low, removing the CLR signal from the shift register and enabling the second input of IC4C so that I/O CH RDY goes low and puts the microprocessor into a wait state. Subsequent clock pulses gradually fill the shift register with ones, starting from the left. The number of wait states generated depends on which output of the shift register you use. This application uses the last tap, so that the microprocessor is delayed for eight clock pulses (8 imes 210 ns). The delay allows plenty of time for MM58274 read and write operations to take place. When the Q<sub>H</sub> output goes high, I/O CH RDY also goes high to terminate the wait state.

Another incompatibility between the IBM PC and the MM58274 occurs in the write-cycle specification,  $t_{WD}$  (Data Bus Hold Time Following Write strobe). The MM58274 requires the system to hold data for 200 ns after the end of the write strobe, whereas the IBM PC holds data on the bus for only 100 ns. However, by disabling the bus driver immediately after writing data to the MM58274, the 3-state capacitance (typically 25 pF) of the bus driver maintains the data on the clock lines for a period of time after the end of the write stobe. When this technique was used experimentally, the typical measured values of the Data Bus Hold Time ranged from 500 to 600 ns.

The time-base reference of the MM58274 is a 32.768-KHz pulse obtained from a crystal-controlled internal oscillator. One side of the crystal is loaded with a 20-pF fixed capacitor tor and the other side with a 6- to 36-pF trimmer capacitor (*Figure 4*). For accurate timekeeping (within 30 sec/month), you must adjust this trimmer capacitor so that the crystal oscillates at the correct frequency. You shouldn't connect measuring instruments directly across the crystal, because

if you were to do so, the capacitance of the leads and instrument would change the oscillator frequency. However, writing  $8_{\rm HEX}$  to the MM58274's control register places MM58274 in the test mode. In the test mode, the crystal oscillator's output is diverted to pin 13 (INT) to provide a buffered signal for an oscilloscope or frequency counter.

#### **PROGRAM THE MM58274 TO PRODUCE INTERRUPTS**

You can program the clock chip to produce a single interrupt or repetitive interrupts at any one of seven intervals from 0.1 to 60 sec by loading the interrupt register (*Figure 3*). To make use of interrupts, connect the INT output from transistor  $Q_5$  (*Figure 4*) to one of the IRQ lines of the IBM PC bus. Six of the eight interrupt levels are reserved for IBM devices; only IRQ<sub>3</sub> and IRQ<sub>5</sub> are available for use with the clock. If you have other add-in cards that use interrupts, however, IRQ<sub>3</sub> and IRQ<sub>5</sub> may be pre-empted, so you won't be able to use interrupts.

To integrate the hardware clock/calendar into your system, you use two 8088 assembly-language programs (the source listings are coded for DOS 2.0). The first, RTCWR (see Listing 1) allows you to put the MM58274 either in test mode to calibrate the crystal clock or in normal mode to initialize time and date. The other routine, RTCRD (see Listing 2) reads the clock, displays the date and time in the upper right corner of the screen, and writes the date and time into the software clock that PC-DOS maintains. Thus, if your AUTOEXEC.BAT file invokes RTCRD, the routine automatically updates the PC-DOS clock from the hardware clock whenever you turn on the system.

Incidentally, RTCWR and RTCRD don't contain routines to perform keyboard input and screen output; they use standard function calls to DOS and BIOS routines (of which a complete listing is given in the *IBM PC Technical Reference Manual*) to perform these functions. Placing a function code in the AH register and executing the appropriate softwareinterrupt instruction invokes these routines. The *PC DOS Programmer's Manual* gives full details on how to make service requests of this kind.

After assembling and linking the RTCWR.ASM and RTCRD.ASM programs, copy the resulting RT-CWR.EXE and RTCRD.EXE files to your system disk. To calibrate the crystal oscillator, connect an oscilloscope or frequency counter between pin 13 of the MM58274 and ground. At the A> prompt, type the following command:

#### RTCWR/C<Return>

The C option puts the clock in the test mode, diverting the 32.768-kHz oscillator output through a buffer to pin 13 of the chip. Adjust the trimmer capacitor until the frequency is correct. Then type "S" to exit from the calibration mode to the time-setting mode. RTCWR will prompt you to select 12- or

24-hr display mode and, if you select 12-hr mode, to set AM or PM. You will then be prompted to enter the number of years since the last leap year, the day of the week, and the current date and time. Each item is written to the MM58274 when you enter it. The clock starts when you press any key, and you exit to PC-DOS. The next time you wish to initialize the hardware, invoke RTCWR *without* the C option, unless you wish to recalibrate the oscillator.

To read the real-time clock, run the program RTCRD.EXE. In short, the program reads the date, places it in a temporary buffer, and displays it. It then reads and displays the time in the same manner. All data reads are validated by means of the Data Changed flag. The program also writes the date and time into the PC-DOS software clock.

RTCRD calls the BIOS display by using the following instruction sequence:

MOV AH, 2
MOV BH, 0
MOV DH, ROW
MOV DL, COL
INT 10H

This call displays the day, date, and time in the upper right corner of the screen. You can change the location of the display by changing the values for row and column (ROW and COL).

Date and time information needs to be validated by means of the Data Changed flag (DCF), because a carry pulse from one counter may ripple through other counters in the chain. It is possible (although statistically improbable) that an incorrect data read may occur during this ripple period. RTCRD assures that data is valid by reading the DCF in the control register twice. The first read, which RTCRD performs before reading any other register, clears the DCF to zero. Then after RTCRD reads all the other registers, it reads the DCF again; if this flag is set, a change in data has occurred and the data read is invalid; otherwise, the data is good.

When you invoke RTCRD from your AUTO-EXEC.BAT file, you ensure that the PC-DOS clock will be automatically updated from the MM58274 whenever you turn the system on or reset it. If you do not have an AUTOEXEC.BAT file, create one as follows:

- Enter COPY CON: AUTOEXEC.BAT and press the Return key.
- Enter RTCRD and press the Return key.
- Press the F6 function key and then the Return key to write an end-of-file mark and save the new AUTOEXEC.BAT file.

If you already have an AUTOEXEC.BAT file, use your normal editor to insert "RTCRD" as the first line in the file.

;	THIS H	PROGRAM WRITES TO THE REAL-TIME CLOCK (MM58274)
;	DATA 1	IS ENTERED FROM THE KEYBOARD AND THEN IS WRITTEN
;	TO THE	E MM58274. ALSO, THE CALIBRATION OF THE CRYSTAL
;	CAN BE	E PERFORMED VIA THIS PROGRAM.
;		
; TABL	E OF EQU	JATES
;		
REGO ·	EQU	300H ;CONTROL REGISTER
REG1	EQU	301H ;TENTHS OF SECONDS
REG2	EQU	302H ;UNITS OF SECONDS
REG3	EQU	303H ;TENS OF SECONDS
REG4	EQU	304H ;UNITS OF MINUTES
REG5	EQU	305H ;TENS OF MINUTES
REG6	EQU	306H ;UNITS OF HOURS
REG7	EQU	307H ;TENS OF HOURS
REG8	EQU	308H ;UNITS OF DAYS
REG9	EQU	309H ;TENS OF DAYS
REG10	EQU	30AH ;UNITS OF MONTHS
REG11	EQU	30BH ;TENS OF MONTHS
REG12	EQU	30CH ;UNITS OF YEARS
REG13	EQU	30DH ;TENS OF YEARS
REG14	EQU	30EH ;DAYS
REG15	EQU	30FH ;CLOCK SETTING AND INTERRUPT REGISTER
;		
STACK	SEGMENT	PARA STACK 'STACK'
	DB	256 DUP(0) ;256 BYTES OF STACK SPACE
STACK 2	ENDS	
;		
DATA S	EGMENT P	PARA PUBLIC 'DATA'
PARM	DB '	8 DUP(0)
BUFF1	DB	16 DUP(0) ;BUFFER SPACE FOR DATE AND TIME
MSGO	DB	'12/24 Hour mode selection:
MSG1	DB	' Enter '0' for 12 hour mode or '
MSG2	DB	' enter 'l' for 24 hour mode.
MSG3	DB	'AM/PM Mode selection. Enter 'A' or 'P'. '
MSG4	DB	'No. of yrs. from last leap year (0-3)
MSG5	DB	'Enter date - (MM/DD/YY)
MSG6	DB	'Enter time - (HR:MM:SS)
MSG7	DB	'Hit any key to start clock
MSG8	DB	' INVALID ENTRY TRY AGAIN '
Mggo	DB	'Enter day- 'l' for Sun, '2' for Mon, etc.'
	DB	'In calibration mode. Adjust trimmer cap. '
MSG9		'so that osc. output = 32.768 KHz. Measure'
MSG9 MSG10	פע	'this is INTR, output (pin 13)
MSG9 MSG10 MSG11	DB DB	
MSG9 MSG10 MSG11 MSG12	DB	'When finished, hit key 's' to set clock '
MSG9 MSG10 MSG11 MSG12 MSG13	DB DB	'When finished, hit key 's' to set clock '
MSG9 MSG10 MSG11 MSG12 MSG13 DATA E	DB DB	'When finished, hit key 's' to set clock '
MSG9 MSG10 MSG11 MSG12 MSG13 DATA E ;	DB DB NDS	
MSG9 MSG10 MSG11 MSG12 MSG13 DATA E ;	DB DB NDS DARD PRO	OGRAM PROLOG
MSG9 MSG10 MSG11 MSG12 MSG13 DATA E ;	DB DB NDS DARD PRO	

```
LISTING 1-RTCWR.ASM (Continued)
CODE SEGMENT PARA PUBLIC 'CODE'
        PUBLIC START
START PROC FAR
                                           START MAIN PROGRAM
        ASSUME CS:CODE
                                           ; .
        PUSH
                DS
                                           :SAVE RETURN ADDR. TO DOS
                AX,0
        MOV
        PUSH
                AX
        MOV
                AX, DATA
                                          :LOAD DATA SEGMENT ADDR.
        MOV
                ES.AX
        ASSUME ES:DATA
;
; MOVE PARAMETERS FROM COMMAND LINE INTO DATA SEGMENT
;
       MOV
                SI,80H
                                           ;MOVE TO PARM. LIST IN PSP
        MOV
                DI, OFFSET PARM
        MOV
                CX.8
        CLD
                                           :SET STRING MOVE FORWARD
        REP
                MOVSB
                                           :MOVE STRING
:
; ESTABLISH NORMAL DATA SEGMENT ADDRESSIBLY
;
        MOV
                DS.AX
        ASSUME DS:DATA
;
; CHECK TO SEE IF WE GO INTO CALIBRATION MODE
;
        CMP
                PARM, 3
                                          ;IS CHAR. LENGTH = 3?
        JNZ
                SET
                                           :NO. BRANCH AND SET CLOCK
:
; CALIBRATE TRIMMER CAPACITOR
;
        CLI
                                           CLEAR INTR OF 8088
       MOV
                                           WRITE TO CONTROL REG.
                AL.OFH
                                              -IN TEST MODE
;
                                              -STOP CLOCK
;
;
                                              -SELECT INTR REG
                                              -STOP INTR
;
       MOV
                DX,REGO
        OUT
                DX,AL
        MOV
                AL.O
                                         GATE OSC. OUTPUT TO INTR. PIN
       MOV
                DX,REG15
        OUT
                DX,AL
                BX, OFFSET MSG10
       MOV
                                        ;DISPLAY MESSAGES
        CALL
                DISPLAY
       MOV
                BX.OFFSET MSG11
                                           :
        CALL
                DISPLAY
       MOV
                BX, OFFSET MSG12
                                           :
        CALL
               DISPLAY
        CALL
                CR_LF
                                        ;TWO <CR> AND <LF>
        CALL
                CR_LF
       MOV
               BX.OFFSET MSG13
        CALL
                DISPLAY
```

LUP8:	MOV	VR.ASM (Continued) AH,0	;FUNCTION=READ CHAR. FROM KEYBOARD
	INT	16H	INVOKE BIOS ROUTINE
	CMP		IS CHAR. AN 'S'
	JE	SET	;YES, BRANCH AND SET CLOCK
	CMP	AL, 's'	IS CHAR. AN 's'?
	JE	SET	YES, BRANCH AND SET CLOCK
	JMP	LUP8	;WAIT, CRYSTAL IS BEING ADJUSTED
; ; INIT:	IALIZE R	TC FOR SETTING IT	
; SET:	STI		
	MOV	AL,07H	WRITE TO CONTROL REG
	;	AL, O'II	-CLOCK STOP
	;		-INTR REG SELECTED
	;		-INTR STOP
	, MOV	DX,REGO	
	OUT	DX,AL	
	MOV	AL,O	
	MOV	DX,REG15	
	OUT	DX,AL	CLEAR INTERRUPT OUTPUT
	MOV	AL,5	
	MOV	DX,REGO	;
	OUT	DX,AL	WRITE TO CNTL REG
;	001	DA,AB	-CLOCK SETTING REG SELECTED
			-CHOCK SHITING NEG SEDECIED
-	RMINE 12	OR 24 HOUR MODE	
; LP1:	мол	BX,OFFSET MSGO	;LOAD STARTING ADDR. OF MSGO
	CALL	DISPLAY	DISPLAY MESSAGE
	MOV	BX, OFFSET MSG1	;LOAD STARTING ADDR. OF MSG1
	CALL	DISPLAY	;DISPLAY MESSAGE
	MOV	BX, OFFSET MSG2	;LOAD STARTING ADDR. OF MSG2
	CALL	DISPLAY	;DISPLAY MESSAGE
LUP1:	CALL	INPCHAR	;INPUT CHAR. FROM KEYBOARD
	CALL	DISPCHAR	;ECHO CHAR.
	CMP	AL,'O'	IS CHAR. FROM KEYBOARD 'O'?
	JE	MD12	YES, JUMP TO 12 HOUR ROUTINE
	CMP	AL,'1'	IS CHAR. FROM KEYBOARD '1'?
	JE	MD24	YES, JUMP TO 24 HOUR ROUTINE
	MOV	BX,OFFSET MSG8	;LOAD STARTING ADDR. OF MSG8
	CALL	DISPLAY	DISPLAY ERROR MESSAGE
	JMP	LUP1	GO BACK AND TRY AGAIN
; • • • • • • •	א פוווסט כ	ODT _ STT ITAD VTAD AND	AN /DM NODE
, 18 12 ;	S ROUN M	ODE - SET LEAP YEAR AND	Amy in myD2
MD12:	CALL	CR_LF	; <cr> AND <lf></lf></cr>
	MOV	AL,O	
	MOV	DX,REG15	
	OUT	DX,AL	;LOAD CODE FOR 12 HOUR MODE
	CALL	AMPM	;SELECT AM OR PM TIME
	CALL	CR_LF	; <cr> AND <lf></lf></cr>

 $\overline{\phantom{a}}$ 

···· •·•

3

LISTING 1-RTCWR.ASM (Continued) ENTER NO. OF YRS. FROM LEAP YR. LEAP. CALL ;<CR> AND <LF> CALL CR\_LF JMP :GOTO TO INPUT DAY ROUTINE DAY : ; IN 12 HOUR MODE - SET LEAP YEAR : MD24: CALL CR\_LF ;<CR> AND <LF> MOV AL,1 MOV DX,REG15 ;LOAD CODE FOR 24 HOUR MODE OUT DX,AL CALL LEAP :ENTER NO. OF YRS. FROM LEAP YR. CALL CR\_LF :<CR> AND <LF> ; ; INPUT DAY OF WEEK - '1' FOR SUN, '2' FOR MON, ETC. ; DAY: MOV BX,OFFSET MSG9 DISPLAY MESSAGE CALL DISPLAY CALL INPCHAR LUP7: :INPUT CHAR. CALL DIPSCHAR :ECHO IT CMP AL, '7' :IS CHAR. OUT OF RANGE? JG ERR2 CMP AL,'l' . ; JL ERR2 MOV DX,REG14 OUT DX,AL :NO, LOAD IN DAY CALL CR\_LF CARRIAGE RTRN AND LINE FEED JMP DATE ERR2: MOV BX, OFFSET MSG8 DISPLAY ERROR MESSAGE CALL DISPLAY JMP LUP7 : : INPUT DATA INTO A BUFFER : DATE: MOV BX, OFFSET MSG5 ;LOAD STARTING ADDR. OF MSG5 CALL DISPLAY DISPLAY MESSAGE CALL BUFFER INPUT DATA INTO A BUFFER CALL :<CR> AND <LF> CR\_LF : ; WRITE DATA OF BUFFER INTO REAL-TIME CLOCK ; MOV BX, OFFSET BUFF1 :MOVE TO STARTING ADDR. OF BUFFER MOV AL.[BX] MOV DX,REG11 WRITE THE TENS OF MONTHS OUT DX,AL INC BX MOV AL,[BX] MOV DX.REG10 OUT DX,AL WRITE THE UNITS OF MONTHS BX INC INC BX MON AL,[BX] MOV DX,REG9

ISTIN									
	OUT	DX,AL			;WRITE	THE TENS OF DAY	S		
	INC	BX							
	MON	AL,[BX]							
	NOM	DX,REG8							
	OUT	DX,AL			;WRITE	THE UNITS OF DA	YS		
	INC	BX	· .						
	INC	BX						•	
	NOM	AL,[BX]				••			
	NOM	DX,REG13							
	OUT	DX,AL			;WRITE	THE TENS OF YEAD	RS		
	INC	BX							
	NOM	AL,[BX]							
	NOM	DX,REG12			. '				
	OUT	DX,AL		- <u> </u>	WRITE;	THE UNITS OF YE.	ARS		
		· · ·	e i		5 S. S.				
INPU	JT TIME O	F DAY INTO A	BUFFER						
						,			
	MON	BX,OFFSET N	ISG6		;LOAD	STARTING ADDR. 0	F MSG6		
	CALL	DISPLAY			;DISPL	AY MESSAGE			
	CALL	BUFFER			;INPUT	DATA INTO BUFFE	R		
	CALL	CR_LF			: <cr></cr>	AND <lf></lf>	. "		
WRII		ME OF DAY INT		-TIME C	LOCK		חד פוודידים		
WRII	THE THE THE THE MOV	ME OF DAY INT		-TIME C	LOCK		. OF BUFFER		
WRII	MOV	ME OF DAY INT BX,OFFSET E		-TIME C	LOCK		. OF BUFFER	• • •	
WRII	MOV MOV	ME OF DAY INT BX,OFFSET E AL,[BX]		-TIME C	LOCK ;Move	TO STARTING ADDR	a an	• • • • • • •	
WRII	MOV MOV MOV	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7		-TIME C	LOCK ;Move	TO STARTING ADDR	a an	• • • •	
WRII	MOV MOV MOV OUT	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL		-TIME C	LOCK ;Move	TO STARTING ADDR	a an	• • • •	
WRII	MOV MOV MOV OUT INC	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX		-TIME C	LOCK ;Move	TO STARTING ADDR	a an		
WRII	MOV MOV MOV OUT INC MOV	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX]		-TIME C	LOCK ;MOVE ;WRITE	TO STARTING ADDR	RS		
WRII	WOA INC MOA WOA WOA WOA	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX		-TIME C	LOCK ;MOVE ;WRITE	TO STARTING ADDR THE TENS OF HOU	RS		
WRII	MOA MOA MOA WOA MOA MOA MOA	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL		-TIME C	LOCK ;MOVE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS		
WRII	MOV MOV MOV MOV MOV MOV MOV	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX		-TIME C	LOCK ;MOVE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS		
WRII	MOV MOV OUT INC MOV OUT INC INC	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX BX BX		-TIME C	LOCK ;MOVE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS		
WRII	MOV MOV MOV MOV MOV MOV MOV MOV MOV	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX BX AL,[BX] DX,REG5 DX,AL		-TIME C	LOCK ;MOVE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS URS		
WRII	WOA WOA WOA WOA WOA WOA WOA WOA WOA WOA	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX BX AL,[BX] DX,REG5 DX,AL BX		-TIME C	LOCK ;MOVE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS URS		
WRII	MOA MOA MOA MOA MOA MOA MOA MOA MOA MOA	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX BX AL,[BX] DX,REG5 DX,AL		-TIME C	LOCK ;MOVE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS URS		
WRII	WOA WOA MOA MOA MOA MOA MOA MOA MOA MOA MOA M	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX BX AL,[BX] DX,REG5 DX,AL BX		-TIME C	LOCK ;MOVE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS URS		
WRII	MOA MOA MOA MOA MOA MOA MOA MOA MOA MOA	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX AL,[BX] DX,REG5 DX,AL BX AL,[BX] DX,REG4 DX,AL		-TIME C	LOCK ;MOVE ;WRITE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU	RS URS UTES		
WRII	WOA WOA WOA WOA WOA WOA WOA WOA WOA WOA	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX AL,[BX] DX,REG5 DX,AL BX AL,[BX] DX,REG4		-TIME C	LOCK ;MOVE ;WRITE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU THE TENS OF MIN	RS URS UTES		·
WRII	MOA MOA MOA MOA MOA MOA MOA MOA MOA MOA	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX AL,[BX] DX,REG5 DX,AL BX AL,[BX] DX,REG4 DX,AL		-TIME C	LOCK ;MOVE ;WRITE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU THE TENS OF MIN	RS URS UTES		
WRII	MOV MOV OUT INC MOV OUT INC MOV OUT INC MOV OUT INC MOV OUT INC	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX AL,[BX] DX,REG5 DX,AL BX AL,[BX] DX,REG4 DX,AL BX BX AL,[BX]		-TIME C	LOCK ;MOVE ;WRITE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU THE TENS OF MIN	RS URS UTES		•
WRII	MOV MOV OUT INC MOV OUT INC MOV OUT INC MOV MOV OUT INC INC	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX AL,[BX] DX,REG5 DX,AL BX AL,[BX] DX,REG4 DX,AL BX BX BX BX BX BX BX		-TIME C	LOCK ;MOVE ;WRITE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU THE TENS OF MIN	RS URS UTES		
WRII	MOV MOV MOV MOV MOV MOV MOV MOV MOV MOV	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX AL,[BX] DX,REG5 DX,AL BX AL,[BX] DX,REG4 DX,AL BX BX AL,[BX]		-TIME C	LOCK ;MOVE ;WRITE ;WRITE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU THE TENS OF MIN	RS URS UTES NUTES		· ·
WRII	MOV MOV OUT INC MOV OUT INC MOV OUT INC MOV MOV OUT INC MOV MOV	ME OF DAY INT BX,OFFSET E AL,[BX] DX,REG7 DX,AL BX AL,[BX] DX,REG6 DX,AL BX AL,[BX] DX,REG5 DX,AL BX AL,[BX] DX,REG4 DX,AL BX BX AL,[BX] DX,REG3		-TIME C	LOCK ;MOVE ;WRITE ;WRITE ;WRITE ;WRITE	TO STARTING ADDR THE TENS OF HOU THE UNITS OF HOU THE TENS OF MIN THE UNITS OF MIN	RS URS UTES NUTES		

• • • •

3

```
LISTING 1-RTCWR.ASM (Continued)
      MOV
          DX,REG2
      OUT
            DX.AL
                                 WRITE THE UNITS OF SECONDS
;
; START CLOCK ON KEY STRIKE
;
      MOV BX, OFFSET MSG7 ;LOAD STARTING ADDR. OF MSG7
      CALL DISPLAY
                                  DISPLAY MESSAGE
LP6:
      MOV AH,1
                                 :FUNCTION = INPUT FROM KEYBOARD
                        AH IS A FUNCTION PARAMETER IN BIOS ROUTINE
;
      MOV BH,O
      OR
           BH,BH
                                 ;SET ZF = 1
      INT
           16H
                                 ;INVOKE BIOS ROUTINE -
                                  RETURNS ZF = 0 IF KEY IS STRUCK
;
                                  OTHERWISE ZF = 1
;
      JZ
          LP6
                                 :LOOP BACK IF ON KEY IS STRUCK
      MOV AL,O
      MOV
          DX,REGO
      OUT
           DX,AL
                                 GIVE START COMMAND TO CLOCK
      RET
                                 RETURN TO DOS
                        ; "BUFFER" SUBROUTINE
                    -STORES THE DATE OR TIME OF DAY IN 8 BYTE
                     BUFFER. STARTING LOCATION OF BUFFER IS AT
:
                     LABEL BUFF1
;
     ENTRY: NONE
;
      OUTPUT: BUFFL ARRAY CONTAINS TIME OR DATE
;
            AX, BX, CX ALTERED
PUBLIC BUFFER
BUFFER PROC NEAR
INPUT: MOV CL,9
          BX, OFFSET BUFF1 ;MOVE TO STARTING ADDR. OF BUFFER
     MOV
INP: CALL INPCHAR
                                ;INPUT CHAR. FROM KEYBOARD
      CALL DISPCHAR
                                ;ECHO CHAR.
      MOV [BX].AL
      DEC CL
      INC BX
      CMP AL, ODH
                             ;IS CHAR. A CARRIAGE RETURN?
           CK
      JE
                                 ;YES, JUMP
      JMP INP
                                :NO, GO BACK AND INPUT ANOTHER CHAR.
CK:
      CMP CL,8
                                ;IS FIRST CHAR. A <CR>?
           EXITL
                                YES, DON'T CHANGE BUFFER . . . . EXIT
      JE
      CMP CL,O
                                ;IS LAST CHAR. A <CR>?
                                YES, BUFFER FULL. . . . EXIT
      JE
            EXIT1
      MOV BX.OFFSET MSG8
                                :LOAD STARTING ADDR. OF MSG8
      CALL DISPLAY
                                ;DISPLAY ERROR MESSAGE
      JMP INPUT
                                RELOAD BUFFER
EXIT1: RET
BUFFER ENDP
```

''AMP	ENTRY:	TO SET AM OR P	OR A 'P' FROM THE KEYBOARD VIA BIOS M TIME
	PUBLIC		
MPM P	ROC NEAR		
P4:		BX,OFFSET MSG3	LOAD STARTING ADDR. OF MSG3
	CALL	DISPLAY	DISPLAY MESSAGE
UP2:	CALL	INPCHAR	;INPUT CHAR. FROM KEYBOARD
	CALL	DISPCHAR	;ECHO CHAR.
	CMP	AL, 'A'	;IS CHAR. AN 'A'?
	JE	AM	YES, SET AM TIME
	CMP	AL, 'a'	;IS CHAR. AN 'a'
	JE	AM	;YES, SET AM TIME
	CMP	AL, 'p'	;IS CHAR. A 'p'
	JE	PM	;YES, SET PM TIME
	CMP	AL,'P'	;IS CHAR. A 'P'?
	JE	PM	;YES, SET PM TIME
	MON	BX,OFFSET MSG8	;LOAD STARTING ADDR. OF MSG8
	CALL	DISPLAY	;DISPLAY ERROR MESSAGE
	JMP	LUP2	;BAD ENTRY RENTER CHAR.
M:	MOV	AL,O	
	MOV	DX,REG15	
	OUT	DX,AL	;LOAD CODE FOR AM TIME
	JMP	EXI	
M :	MOV	AL,2	and the second
	MOV	DX,REG15	
	OUT	DX,AL	;LOAD CODE FOR PM TIME
XI:	RET		
MPM E	NDP	•	
	ENTRY :	NUMBER IS THE D NONE : AX,BX,CX ALTERED	R FROM O TO 3 FROM TO KEYBOARD. THIS NUMBER OF YEARS FROM LAST LEAP YEAR.
	PUBLIC ROC NEAR		
			:LOAD STARTING ADDR. OF MSG4
		DISPLAY	DISPLAY MESSAGE
	CALL		;INPUT CHAR. FROM KEYBOARD
25:	CALL	INPCHAR	
25: JP3:	CALL	INPCHAR DISPCHAR	
25: JP3:	CALL	DISPCHAR	;ECHO CHAR.
25: JP3:	CALL CALL CMP	DISPCHAR AL,'4'	
25: JP3:	CALL CALL CMP JAE	DISPCHAR AL,'4' ERR1	;ECHO CHAR. ;CHECK FOR INVALID ENTRY
25: JP3:	CALL CALL CMP JAE CMP	DISPCHAR AL,'4' ERR1 AL,'0'	;ECHO CHAR. ;CHECK FOR INVALID ENTRY ; " ; "
P5: JP3:	CALL CALL CMP JAE CMP	DISPCHAR AL,'4' ERR1	;ECHO CHAR. ;CHECK FOR INVALID ENTRY

3-73

3

LISTING	1—RTCW	R.ASM (Continu	ied)		
	ROL	AL,CL		;ROTATE LEFT TWO TIMES	
	MOV	BL,AL		;SAVE AL IN BL	
	MOV	DX,REG15			
		AL,DX		INPUT CLOCK SETTING REG	
		AL,03H		CLEAR DB3 TO DB2	
		AL,BL		WRITE TO ONLY DB3, DB2 OF CLK SET. REG	
		DX,AL			
		RTRN		·	
RR1:		BX.OFFSET N	1600	;LOAD STARTING ADDR. OF MSG8	
		DISPLAY	1200	DISPLAY ERROR MESSAGE	
		LUP3			
TRN:		LUF3		GO BACK AND TRY AGAIN	
EAP EN					
; ''INP' ; ;	ENTRY:		KEYBOARD	ROUTINE TO INPUT CHARACTER FROM	
;					
	PUBLIC	INPCHAR			
NPCHAR	PROC NE.	AR			
	MON	AH.O		:FUNCTION = INPUT CHAR. INTO AL	
:	MON	AH,O	AH IS A	;FUNCTION = INPUT CHAR. INTO AL FUNCTION PARAMETER FOR BIOS ROUTINE	
;			AH IS A	FUNCTION PARAMETER FOR BIOS ROUTINE	
;	INT	AH,0 16H	AH IS A		
	INT RET		AH IS A	FUNCTION PARAMETER FOR BIOS ROUTINE	
INPCHAR	INT RET ENDP		AH IS A	FUNCTION PARAMETER FOR BIOS ROUTINE	
NPCHAR	INT RET ENDP	16H		FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE	
NPCHAR	INT RET ENDP	16H	DISPLAYS MESS	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15.	
INPCHAR	INT RET ENDP PLAY'' SP	16H UBROUTINE -	DISPLAYS MESS USES DISPCHAN	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE	
INPCHAR	INT RET ENDP PLAY'' SU ENTRY:	16H UBROUTINE - BX=OFFSET	DISPLAYS MESS USES DISPCHAN OF MESSAGE	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15.	
NPCHAR	INT RET ENDP PLAY'' SI ENTRY: OUTPUT:	16H UBROUTINE -	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL	
NPCHAR	INT RET ENDP PLAY'' SI ENTRY: OUTPUT:	16H UBROUTINE - BX=OFFSET AX,CX ALTE	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15.	
NPCHAR	INT RET ENDP PLAY'' SI ENTRY: OUTPUT: PUBLIC I	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL	
NPCHAR	INT RET ENDP PLAY'' SI ENTRY: OUTPUT: PUBLIC I PROC NE	16H UBROUTINE – BX=OFFSET AX,CX ALTE DISPLAY AR	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL	
NPCHAR	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC D PROC NE. MOV	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER	
NPCHAR	INT RET ENDP PLAY'' SI ENTRY: OUTPUT: PUBLIC I PROC NE. MOV MOV	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX]	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE	
NPCHAR	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC D PROC NE. MOV MOV CALL	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER	
NPCHAR	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC D PROC NE. MOV MOV CALL INC	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR.	
INPCHAR  ''DIS 	INT RET ENDP PLAY'' SI ENTRY: OUTPUT: PUBLIC I PROC NE. MOV MOV CALL INC LOOP	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX DISP1	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR. ;LOOP BACK 40 TIMES	
INPCHAR  ''DIS 	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC P PROC NE MOV MOV CALL INC LOOP CALL	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR.	
INPCHAR ;; ; ''DIS; ; ; ; DISPLAY	INT RET ENDP PLAY'' SI ENTRY: OUTPUT: PUBLIC I PROC NE. MOV MOV CALL INC LOOP	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX DISP1	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR. ;LOOP BACK 40 TIMES	
NPCHAR  ''DIS S DISPLAY DISP1:	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC P PROC NE MOV MOV CALL INC LOOP CALL RET	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX DISP1	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR. ;LOOP BACK 40 TIMES	
INPCHAR ; ; ''DIS; ; ; DISPLAY DISPLAY ;	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC P PROC NE MOV MOV CALL INC LOOP CALL RET ENDP	16H UBROUTINE - BX = OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX DISP1 CR_LF	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR. ;LOOP BACK 40 TIMES ; <cr> AND <lf></lf></cr>	
NPCHAR 	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC P PROC NE MOV MOV CALL INC LOOP CALL RET ENDP	16H UBROUTINE - BX = OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX DISP1 CR_LF	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED INVOKES BIOS	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR. ;LOOP BACK 40 TIMES ; <cr> AND <lf> ROUTINE TO DISPLAY A CHARACTER</lf></cr>	
INPCHAR  : ''DIS : DISPLAY DISPLAY 	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC P PROC NE MOV MOV CALL INC LOOP CALL RET ENDP	16H UBROUTINE - BX = OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX DISP1 CR_LF	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR. ;LOOP BACK 40 TIMES ; <cr> AND <lf> ROUTINE TO DISPLAY A CHARACTER</lf></cr>	
; ; ; DISPLAY DISPLAY ;	INT RET ENDP PLAY'' SP ENTRY: OUTPUT: PUBLIC P PROC NE MOV MOV CALL INC LOOP CALL RET ENDP	16H UBROUTINE - BX=OFFSET AX,CX ALTE DISPLAY AR CX,40 AL,[BX] DISPCHAR BX DISP1 CR_LF UBROUTINE -	DISPLAYS MESS USES DISPCHAN OF MESSAGE ERED INVOKES BIOS	FUNCTION PARAMETER FOR BIOS ROUTINE ;INVOKE BIOS ROUTINE SAGES AT MEMORY LOCATIONS MSGO TO MSG15. R SUBROUTINE FOR BIOS CALL ;LOAD MESSAGE CHAR. COUNTER ;SINGLELY LOAD CHAR. OF MESSAGE ;DISPLAY THAT CHAR. ;LOOP BACK 40 TIMES ; <cr> AND <lf> ROUTINE TO DISPLAY A CHARACTER</lf></cr>	

AN-443

...

LISTING 1-R1	CWR.ASM (Continued)	
PUBI	JIC DISPCHAR	
DISPCHAR PRO	C NEAR	
PUSI	I BX	;SAVE REC. BX
MOV	BX,O	
MOV	AH,14	;FUNCTION = WRITE TO SCREEN
		;AH IS A FUNCTION PARAMETER FOR BIOS ROUTINE
INT	10H	;INVOKE BIOS ROUTINE
POP	BX	;RESTORE REG. BX
RET		
DISPCHAR ENI	)P	· · · · · · · · · · · · · · · · · · ·
:		
;''CR_LF'' \$	SUBROUTINE - PRODUC	CES A CARRIAGE RETURN AND LINE FEED ON THE
:	SCREEL	Ν.
: ENTI	RY: NONE	
•	PUT: ALL REGISTERS	PRESERVED
-		
PUBI	LIC CR_LF	
CR_LF PROC 1	IEAR	·
PUSH	I AX	SAVE AX
MOV	AL, ODH	
CALI	DISPCHAR	CARRIAGE RETURN
MOV	AL, OAH	· · · · · · · · · · · · · · · · · · ·
CALI	-	:LINE FEED
POP	AX	RESTORE AX
RET		•
CR_LF ENDP		
:		
:		
START ENDP		END OF MAIN PROGRAM
CODE ENDS		
END	START	
END	JIMII	

. -

3

,	THIS PF	OGRAM READS FRO	M THE REAL-	-TIME CLOCK (MM582774)	<ul> <li>Anglad</li> </ul>	
;	DATA IS	READ FROM THE	MM58274 ANI	CHECK WITH THE 'DATA		
:	CHANGEL	FLAG'. THE TIM	E AND DATE	IS DISPLAYED IN THE		
:				ALSO WRITES THE TIME		
:				CTIONS IN PC DOS.		
				Alah Mendalah Juli Par		
; TABLE	OF EQUA				÷ .	1.
;	-			en de la composition de la composition En la composition de l		
REGO	EQU	300H		CONTROL REG		
REG1	EQU	301H		TENTHS OF SEC		
REG2	•	302H		UNITS OF SEC	a a sur an	
	EQU	303H	·. : · ·	TENS OF SEC	eter a service a	a state a
REG4	EQU	304H		UNITS OF MINUTES	n an	
REG5	EQU	305H		TENS OF MINUTES		
REG6	EQU	306H		UNITS OF HOURS	· · · · · · · · · · · · · · · · · · ·	
REG7	•	307H		TENS OF HOURS	and the state of the	•
REG8	EQU	308H		UNITS OF DAYS		an a
REG9	EQU	309H		TENS OF DAYS	Array and A Array and Array and Ar	
REGIO	EQU	30AH		UNITS OF MONTHS	· · · · · · · · · · · · · · · · · · ·	
REG11	•	30BH		TENS OF MONTHS		an e
	EQU	30CH		UNITS OF YEARS	an a	
REG12	EQU	30DH		TENS OF YEARS		
REG13	•	30EH		DAY OF WEEK	1.487 	• • • • • • • • • • • • • • • • • • • •
REG15	EQU	30FH		CLOCK SETTING AND I	את הסווסה את	· .
;	240			, or our positing model		
	פת	ARA STACK 'STAC	// <b>/</b>			
STACK E	DB NDS	256 DUP(0)				
STACK E ;			<b>A</b>	Ne zer		
;	NDS			No. N. W		
; data se	NDS GMENT PA	256 DUP(0)		1999 - 1999 - 1999 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 - 1999 -		
; DATA SE MON_NO	NDS GMENT PA DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB',	' 'MAR', 'APP	R', 'MAY', 'JUN', 'JUL	', 'AUG', 'SEP'	
; DATA SE MON_NO MONTH	NDS GMENT PA DB DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV',	'MAR', 'APP 'DEC'			
; DATA SE MON_NO MONTH	NDS GMENT PA DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB',	'MAR', 'APP 'DEC'		', 'AUG', 'SEP' WEDNESDAY ',	
; DATA SE MON_NO MONTH	NDS GMENT PA DB DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','		
; data se mon_no month day	NDS GMENT PA DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','		
; data se mon_no month day date	NDS GMENT PA DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ',' ','SATURDAY '		
; DATA SE MON_NO MONTH DAY DATE TIME	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA FUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY ' 'THURSDAY ' 'MMM DD, 19YR'	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ',' ','SATURDAY ' ;***ARRAY FOR DATE	WEDNESDAY ',	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ',' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN D_OF_W	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN D_OF_W	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN D_OF_W DATA EN	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12	'MAR', 'APP 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN D_OF_W DATA EN ; ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN D_OF_W DATA EN ; ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 0	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN D_OF_W DATA EN ; ; CODE SE ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 0 RA PUBLIC 'CODE	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN D_OF_W DATA EN ; ; CODE SE ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 0 RA PUBLIC 'CODE	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A ;LOCATION TO SAVE TH	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN D_OF_W DATA EN ; CODE SE ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'HURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 O RA PUBLIC 'CODE G - RETURN TO 12	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A ;LOCATION TO SAVE TH	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN DATA EN ; ; CODE SE ; ; PROGR ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB DB DB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 O RA PUBLIC 'CODE G - RETURN TO 12	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A ;LOCATION TO SAVE TH	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN DAY_LEN DATA EN ; ; CODE SE ; ; PROGR ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB CB CB CB CB CB CB CB CB CB CB CB CDB CB CDB CB CDB CD	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'HURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 O RA PUBLIC 'CODE G - RETURN TO D START	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A ;LOCATION TO SAVE TH INATION OF PROGRAM	WEDNESDAY ', MONTH DAY	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN DATA EN ; ; CODE SE ; ; PROGR ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB DB CB CB CB CB CB CB CB CB CB CB CB CB CB	256 DUP(0) RA PUBLIC 'DATA O 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'HURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 O RA PUBLIC 'CODE G - RETURN TO D START	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A ;LOCATION TO SAVE TH INATION OF PROGRAM	WEDNESDAY ', MONTH DAY E 'DAY OF WEEK'	
; DATA SE MON_NO MONTH DAY DATE TIME MON_LEN DAY_LEN DAY_LEN DAY_LEN DATA EN ; ; CODE SE ; ; PROGR ;	NDS GMENT PA DB DB DB DB DB DB DB DB DB DB CB CB CB CB CB CB CB CB CB CB CB CB CB	256 DUP(0) RA FUBLIC 'DATA 0 'JAN', 'FEB', 'OCT', 'NOV', 'SUNDAY 'THURSDAY 'MMM DD, 19YR' 'HR:MM:SS 3 12 0 RA FUBLIC 'CODE G - RETURN TO D START CS: CODE	'MAR', 'APF 'DEC' ,'MONDAY ,'FRIDAY	','TUESDAY ','' ','SATURDAY ' ;***ARRAY FOR DATE ;***ARRAY FOR TIME ;NO. OF CHARS. IN A ;NO. OF CHARS. IN A ;LOCATION TO SAVE TH INATION OF PROGRAM ;BEGIN MAIN PROGRAM	WEDNESDAY ', MONTH DAY E 'DAY OF WEEK'	

----

AN-443

LISTING	2-RTCRE	D.ASM (Continued)	
	MON	AX,DATA	
	MOA	DS,AX	
	NOV	ES,AX	
	ASSUME	DS: DATA,ES:DATA	;DATA AND EXTRA SEGMENT ARE THE SAME
;			
; PERF	ORM DUMMY	READ OF CNTL REG TO SET I	OCF = 0
;			
READ:	MOV	DX,REGO	
	IN	AL,DX	
;			
•	DAY OF W	EEK	
;	MOV	DX,REG14	
	IN	AL,DX	:READ DAY - CODE IS 1-7 WHERE SUN. = 1
	MOV	D_OF_W,AL	SAVE DAY OF WEEK
;		200 Eu jui	
READ	DATE		
;			
	MOV	DX,REG11	
	IN	AL,DX	READ TENS OF MONTHS
	SUB	AL, 30H	CONVERT TO BCD
	CMP	AL,O	IS MONTHS=0
	JE	ADD1	YES, JUMP
	MOV	AL,10D	NO, SET MONTHS=10
ADD1:	MOV	BL,AL	SAVE AL IN BL
	MOV	DX,REG10	
	IN	AL, DX	READ UNITS OF MONTHS
	SUB	AL, 30H	CONVERT TO BCD
	ADD	AL,BL	(TENS OF MONTH) + (UNITS OF MONTHS)
	MOV	MON_NO,AL	;SAVE THE MONTH NUMBER
	SUB	AL,1	
	MUL	MON_LEN	;AX=AL*(NO. OF CHARS. IN A MONTH)
	MOV	SI, OFFSET MONTH	;SI=STARTING ADDR. OF ARRAY 'MONTH'
	ADD	SI,AX	;SI=OFFSET INTO ARRAY 'MONTH'
	MOV	DI,OFFSET DATE	;DI=STARTING ADDR. OF ARRAY 'DATE'
	CALL	MOV_STR	;MOVE MONTH INTO 'DATE' ARRAY
	INC	DI	
	MOV	DX, REG9	
	IN	AL,DX	;READ TENS OF DAYS
	CMP	AL,30H	;IS 'TENS OF DAYS' = 0
	JNE	TEN	;NO, JUMP
	MOV	AL,' '	;YES, MOVE IN A BLANK FOR TENS OF DAYS
TEN:	MOV	[DI],AL	;MOVE IT INTO 'DATE' ARRAY
	INC	DI	
	MOV	DX,REG8	
	IN	AL,DX	READ UNITS OF DAYS
	MOV	[DI],AL	;MOVE IT INTO 'DATE' ARRAY
	ADD	DI,5	
	MOV	DX,REG13	
	IN	AL,DX	READ TENS OF YEARS
	MOV	[DI],AL	;MOVE IT INTO 'DATE' ARRAY

-----

------

3

		D.ASM (Continued)				
	INC	DI				
	MON	DX,REG12				11.6
	IN	AL,DX		READ UNITS OF YEARS		
•	NON	[DI],AL		;MOVE IT INTO 'DATE' ARRAY	• • • •	• •
, ; READ	TIME OF	DAY AND MOVE IT INTO A	RRAY	'TIME'		
	MOV	BX, OFFSET TIME		;MOVE TO STARTING ADDR. OF A	ARRAY 'TIME'	
	MON	DX,REG7				
	IN	AL,DX		READS TENS OF HOURS		
	MOV	[BX],AL		;MOVE IT INTO 'TIME' ARRAY		
	INC	BX				1.1
	MOV	DX,REG6				
	IN	AL,DX		READ UNITS OF HOURS		
	MOV	[BX],AL		MOVE IT INTO 'TIME' ARRAY		
	ADD	BX.2				
	MOV	DX, REG5		-		
	IN	AL,DX		READ TENS OF MINUTES		
	MOV	[BX],AL		, TEAD IEND OF MERCIED		
	INC	BX BX				
	MOV	DX,REG4		DEAD UNITED OF MINUMED		
	IN	AL,DX		READ UNITS OF MINUTES		
	MOV	[BX],AL				
	ADD	BX,2				
	MON	DX,REG3				
	IN	AL,DX		READ TENS OF SECONDS		
	MON	[BX],AL				
	INC	BX		6. 1. 1.		
	MOV	DX,REG2	l.	:		
	IN	AL,DX		READ UNITS OF SECONDS		
	MON	[BX],AL				
; ; DATA	VALIDAT	ION CHECK				
;						
	MOV	DX,REGO				
	IN	AL,DX		;READ CNTL REG		
	TEST	AL,08H		;IS DCF=1?		
	JZ	DSPLY		NO. DISPLAY DATE AND TIME	·	
	JMP	READ		;YES, INVALID DATE	READ AGAIN	
•	-					1.7
DISPI	LAY DATE	AND TIME				
•						
, DSPLY	MOV	AL,D_OF_W		;AL = 'DAY OF WEEK'		
	SUB	AL, 31H	÷	CONVERT ASCII TO BCD		
	MUL	DAY_LEN		;AX=AL*(DAY_LEN) CALC	IIT.ATTNC OFFET	TNTO
	т	DAT_DBM			OLATING UPPSEI	
;		DV ADDOD DAY		ARRAY 'DAY'		
	MON	BX, OFFSET DAY		;MOVE TO STARTING ADDR OF A		124
		DTF 117				
	ADD	BX,AX		BX=STARTING ADDR OF DAY ST		
	ADD MOV	BX,AX DX,0040H	•	;BX= STARTING ADDR OF DAY SI ;DH AND DL PARAMETERS TO BE DH=ROW DL=COL		

.

AN-443

	D.ASM (Continued)	
CALL	SET_CURSOR	;MOVE CURSOR TO ROW 0, COL 48
CALL	DISPLAY	;DISPLAY THE DAY
MOV	BX, OFFSET DATE	;MOVE TO STARTING ADDR OF ARRAY 'DAY'
MON	DX,0140H	
CALL	SET_CURSOR	;SET CURSOR TO ROW 1, COL 48
CALL	DISPLAY	;DISPLAY THE DATE
MOM	BX,OFFSET TIME	;MOVE TO STARTING ADDR. OF ARRAY 'DATE'
MON	DX,0240H	
CALL	SET_CURSOR	;SET CURSOR TO ROW 2, COL 48
CALL	DISPLAY	;DISPLAY THE TIME
MOVE CURSOR	TO BOTTOM OF SCREEN	
MOV	DX,1700H	:ROW=24 COL.=0
MOV	AH,2	;FUNCTION=MOVE CURSOR
MOV	BX,0	,
INT	10H	;INVOKE BIOS ROUTINE
		$\mathbf{C}_{i}$ , and $\mathbf{C}_{i}$ , $\mathbf{C}_{i}$ , $\mathbf{C}_{i}$
WRITE DATE T	0 DOS	
MOV	AL, MON_NO	;MOVE IN MONTH NUMBER
MOV	DH,AL	;DH=MONTHS _ PARM FOR DOS ROUTINE
MOV	SI, OFFSET DATE	:MOVE IN STARTING ADDR. OF ARRAY 'DATE'
ADD	SI,4	MOVE TO DAYS INTO ARRAY 'DATE'
CALL	INP_BCD	INPUT DAYS OF MONTH
CALL	CONVERT	CONVERT BCD TO BINARY
MOV	DL,AL	DL=DAYS _ PARM. FOR DOS ROUTINE
ADD	SI,5	
CALL	INP_BCD	INPUT YEARS
CALL	CONVERT	
CBW		;MAKE AL INTO 16 BITS
MOV	CX,076CH	;MOVE IN 1900D
ADD	CX,AX	;CX = 1900 + (YEARS)
MOV	AH,02BH	;FUNCTION=SET DATE IN DOS
INT	21H	;INVOKE DOS ROUTINE
WRITE TIME T	D DOS	
	·	
MOV	SI, OFFSET TIME	;MOVE TO STARTING ADDR. OF ARRAY 'TIME'
CALL	INP_BCD	;INPUT HOURS
CALL	CONVERT	
MOV	CH, AL	;CH=HOURS _ PARM. FOR DOS
ADD	SI,2	
CALL	INP_BCD	;INPUT MINUTES
CALL	CONVERT	
MOV	CL,AL	;CL=MINUTES _ PARM. FOR DOS
ADD	SI,2	
	INP_BCD	INPUT SECONDS
CALL	INI_DOD	,11101 0200100

. س

3

LISTING 2-RTCRD.ASM (Continued) CALL CONVERT MOV DH.AL :DH = SECONDS - PARM. FOR DOS MOV DX,REG1 IN AL,DX ;INPUTS TENTHS OF SECONDS PUSH CX :SAVE CX MOV CL.4 SHL AL,CL SHIFT AL LEFT FOUR TIMES CALL CONVERT MOV DL,AL :DL=1/100 SECONDS POP CX :RESTORE CX AH,02DH ;FUNCTION = SET TIME IN DOS MOV INT 21H ;INVOKE DOS ROUTINE : END OF MAIN PROGRAM - RETURN TO DOS : RET ; ''INP\_BCD'' SUBROUTINE - INPUTS A 4-BIT BCD INTO AL, SHIFTS IT LEFT FOUR TIMES AND THEN ANOTHER 4-BIT BCD ; ; NUMBER IS INPUTTED. ENTRY: SI = OFFSET OF 'TIME' OR 'DATE' ARRAY ; OUTPUT: AL = CONTAINS TWO BCD NUMBERS : PUBLIC INP\_BCD INP\_BCD PROC NEAR PUSH BX SAVE BX PUSH CX SAVE CX MOV AL,[SI] ;ENTER BCD NUMBERS MOV CL,4 AL.CL SHIFT AL LEFT FOUR TIMES SHL INC SI MOV BL.[SI] :ENTER ANOTHER BCD AND BL.OFH ;CLEAR UPPER NIBBLE OF BL COMBINE BOTH BCD'S TOGETHER 0R AL,BL POP CX :RESTORE CX POP BX RESTORE BX RET INP\_BCD ENDP ; ''CONVERT'' SUBROUTINE - TWO PACKED BCD NUMBERS ARE CONVERTED TO THEIR BINARY EQUIVALENT ; ENTRY: AL = CONTAINS PACKED BCD NUMBERS ; OUTPUT: AL=BINARY CONVERSION : PUBLIC CONVERT CONVERT PROC NEAR PUSH AX ;SAVE AX PUSH CX ;SAVE CX MOV CL.4 AL,CL SHIFT AL RIGHT FOUR TIMES SHR POP CX :RESTORE CX POP ВХ ;RESTORE CONTENTS OF AX INTO BX MOV BH, OAH ;AX=BH\*(MOST SIG. BCD DIGIT) MUL BH

AN-443

	BL,OFH AL,BL	=BINARY EQUIV. OF MOST S			
DD ET		CLEAR OFF MOST SIG BCD DIG	IT IN BL		
ET	•	ADD BINARY EQUIV. OF BOTH I			
NDP		· · ·			
			1. C. A.		
RSOR		RSOR AT DESIRED POSITION. THE	i ' '		
		DL=COLUMN	÷		
NTRY:	DX	• .			
				•	
		FUNCTION-MOUT CURSOR			
			•		
	-	•			
		INVOKE BIOS ROOTINE			
	BROUTINE -	MOVES A STRING OF 3 CHARS. ]	FROM THE 'MONTH'		
	and the state of the	ARRAY INTO THE 'DATE' ARRAY. THESE 3 CHARS.			
		REPRESENT A MONTH eg. MAR=N	MARCH.		
NTRY :	DI=OFFSET OF DATE			4.11	
	SI=OFFSET OF MONTH				
UTPUT :		3	1 A. S. 1997		
			11 March 11		
UBLIC N	IOV_STR		17 - 17 T		
IOV_STR PROC NEAR		and the South			
ov	CX,3				
		;MOVE CHARS. OF 'MONTH' ARRA	AY INTO		
		; 'DATE' ARRAY			
		in a second second	the second second		
		<ul> <li>(c) (c) (c) (c) (c) (c) (c) (c) (c) (c)</li></ul>		(1, 1, 2)	
ET				2	
NDP					
	UBLIC S R PROC OV NT ET R ENDP TR'' SU UTPUT: UUTPUT: UUTPUT: UUBLIC M ROC NEA OV OV OV NC NC OOP ET NDP	<pre>i.e. DH=ROW NTRY: DX UBLIC SET_CURSOR R PROC NEAR OV AH,2 OV BH,0 NT 10H ET R ENDP TR'' SUBROUTINE - NTRY: DI=OFFSET OF DATE SI=OFFSET OF MONTH UTPUT: DI,SI, BOTH INCREMETED BY AX ALTERED UBLIC MOV_STR ROC NEAR OV CX,3 OV AL,[SI] OV [D],AL NC DI NC SI OOP LP1 ET NDP</pre>	UBLIC SET_CURSOR R FROC NEAR OV AH,2 ;FUNCTION=MOVE CURSOR OV BH,O ; " NT 10H ;INVOKE BIOS ROUTINE ET R ENDP TR'' SUBROUTINE - MOVES A STRING OF 3 CHARS. ARRAY INTO THE 'DATE' ARRAY REPRESENT A MONTH eg. MAR=) NTRY: DI=OFFSET OF DATE SI=OFFSET OF MONTH UTFUT: DI,SI, BOTH INCREMETED BY 3 AX ALTERED UBLIC MOV_STR ROC NEAR OV CX,3 OV AL,[SI] ;MOVE CHARS. OF 'MONTH' ARR OV [D],AL ; 'DATE' ARRAY NC DI NC SI OOP LP1 ET	<pre>1.e. DH=ROW DL=COLUMN NTRY: DX UBLIC SET_CURSOR R PROC NEAR OV AH,2 ;FUNCTION=MOVE CURSOR OV BH,0 ; " NT 10H ;INVOKE BIOS ROUTINE ET R ENDP TR'' SUBROUTINE - MOVES A STRING OF 3 CHARS. FROM THE 'MONTH' ARRAY INTO THE 'DATE' ARRAY. THESE 3 CHARS. REPRESENT A MONTH 'eg. MAR=MARCH. NTRY: DI=OFFSET OF DATE SI=OFFSET OF MONTH UTPUT: DI,SI, BOTH INCREMETED BY 3 AX ALTERED UBLIC MOV_STR ROC NEAR OV CX,3 OV AL,[SI] ;MOVE CHARS. OF 'MONTH' ARRAY INTO OV [D],AL ; 'DATE' ARRAY NC DI NC SI DOP LP1 ET NDP</pre>	

-----

- -

3-81

3

```
LISTING 2-RTCRD.ASM (Continued)
DISPLAY ENDP
"DISPCHAR" SUBROUTINE - INVOKES BIOS ROUTINE TO DISPLAY CHARACTER
                ON SCREEN
;
    ENTRY: NONE
:
    OUTPUT: AX ALTERED
PUBLIC DISPCHAR
DISPCHAR PROC NEAR
                        SAVE REG. BX
     PUSH BX
     MOV BX,O
     MOV AH,14
                           ;FUNCTION = WRITE TO SCREEN
         10H
                            INVOKE BIOS ROUTINE
     INT
     POP
         BX
                            ;RESTORE REG. BX
     RET
DISPCHAR ENDP
;"CF_LF" SUBROUTINE - PRODUCES A CARRIAGE RETURN AND LINE FEED ON THE
              SCREEN.
:
    ENTRY: NONE
:
    OUTPUT: ALL REG. PRESERVED
:
    ----
:-
     PUBLIC CR_LF
CR_LF PROC NEAR
     PUSH AX
                            :SAVE AX
     MOV AL, ODH
                            CARRIAGE RETURN
     CALL DISPCHAR
    MOV
         AL,OAH
                           LINE FEED
     CALL DISPCHAR
     POP
         AX
                            RESTORE AX
     RET
CR_LF ENDP
:
    _____
:-----
START ENDP
                            ;END MAIN PROGRAM
CODE ENDS
   END START
```

# Using External Oscillators for the DP857x Real Time Clocks with the Battery Backed Mode Selected

This application note describes how external oscillators may be used with the DP857x family of real time clocks, by using the "test mode" to configure the DP857x in the battery backed mode prior to starting the clock.

#### THE PROBLEM

In the battery backed mode, the external oscillator peak-topeak voltage must not exceed the voltage at the V<sub>BB</sub> pin. When the chip is first time powered up, it is in the single supply mode. The single supply mode references the oscillator inverter to V<sub>CC</sub>. This means that in normal operation the OSC in pin needs to swing positively to about 3.5V minimum. If an external oscillator is set to the V<sub>BB</sub> value, then its high going signal may not be high enough to trip the internal inverter. If the internal inverter doesn't pass the external signal, you cannot program the chip into the battery backed mode, because the internal OSC fail signal will always be set (catch-22).

# THE SOLUTION

# **General Description**

Select the test mode and disable the oscillator fail circuitry (refer to AN 589 in the Real Time Clock Handbook). Now, the battery backed mode may be selected independent of National Semiconductor Application Note 893 Milt Schwartz



N-893

any oscillator signal. This action references the internal inverter to VBB. As a result, the inverter will pass the external oscillator signal which is set to the battery voltage plus one diode drop. Once the chip is operating in the battery backed mode, clear the "test mode" register and leave the test mode. The circuits of Figures 1 and 2 were used to check out this solution. Both the LP2951 and LM611 are available as mini-dip packages. The LP2951 is more expensive, but is designed to do this type of application and is fully compensated for temperature and voltage changes. As shown, the circuits provide for battery backed operation of the external oscillator and DP857x. The disadvantage is extra current drain from the battery. The advantage is that the user has complete control over the oscillator design and can temperature compensate as well as tune the oscillator for maximum accuracy. The external oscillator was implemented using a 74HC04 (see Figures 3 and 4). The 74HC device was chosen because it is specified to operate down to 2.0V. A commercial oscillator could be used as long as it can operate at the V<sub>BB</sub> voltage chosen by the user. Figure 5 is a set of curves of COUT versus CIN for a 32.768 kHz Pierce parallel resonant oscillator. These curves are helpful for choosing starting values for the oscillator to ensure reliable start up and nominal operation.




FIGURE 1. Voltage Regulator as a V<sub>CC</sub> Supply for an External Oscillator




FIGURE 2. LM611 as a V<sub>CC</sub> Supply for an External Oscillator







FIGURE 3. 32.768 kHz Oscillator using 'HC Inverter



TL/F/11846-5

FIGURE 4. 4.9152 MHz Oscillator using 'HC Inverter

#### DETAILED DESCRIPTION

Initialization procedure for first time power on:

1. Adjust output of voltage regulator to be 0.25V higher than  $V_{BB}$ . This will make sure that D2 is reversed biased and the battery will not power the external oscillator when  $V_{CC}$  is powered. For this case D1 and D2 are the same diodes (1N914). An alternate method is to use a Schottky diode for D1 and a 1N914 for D2. Then adjust the output of the voltage regulator equal to the battery. D3 is a Schottky diode (1N6263) that ensures the high level output of the oscillator is slightly lower than  $V_{BB}$ .

TL/F/11846-2

- 2. Connect external oscillator to OSC IN pin, and leave OSC OUT unconnected.
- 3. Select the clock frequency by writing to bits D6,D7 of the Real Time Mode Register (RTMR).
- 4. Write a "1" to D7 of the Periodic Flag Register (PFR). This selects the test mode.
- Write a "1" to D7 of the RAM/Test Mode Register located at address 0x1F of page 0. Other bits = 0. The oscillator fail flag is now disabled.
- 6. Write "0" to D6 and "1" to D7 of the PFR. This action selects battery backed mode and test mode.
- Start the clock by writing "1" to D3 of the RTMR. To check that the clock is actually running, read D3 of the RTMR and test that it is a "1".
- 8. Clear the RAM/TEST Mode Register.
- 9. Write "0" to D7,D6 of the PFR. You have now left the test mode and are in battery backed mode.
- 10. Read D3 of the RTMR and test for a "1". This is a double check that the clock is running.
- 11. Continue your regular initialization of the chip.

The above concept could be applied to any chip that uses an oscillator and has separate  $V_{BB}/V_{CC}$  pins that require mode selection for battery/single supply operation.


## 32.768 kHz Oscillator Hints for a Pierce Parallel Resonant Circuit

J

The below curves are a plot of  $C_{OUT}$  versus  $C_{IN}$  for constant Load Capacitance ( $C_L$ ). The load capacitances selected show the typical range specified by various manufacturers.

AN-893

- 7



Refer to AN-588 for additional information.

**FIGURE 5** 

# DP8570A Experiments to Test the Low Battery Bit or Generate a Periodic Interrupt

National Semiconductor Application Note 894 Milt Schwartz



#### SUMMARY

This application note describes two experiments. One experiment allows the user to check that the low battery bit is working correctly. The other allows the user to generate a 10 ms periodic interrupt.

A program named RTC, written in Microsoft™ Quick C version 1, is used for both experiments. The code works with the circuit shown in *Figure 3*. This circuit is a general purpose interface for use with an IBM® PC-XT® or PC-AT® (or equivalent). Keyboard entries may be either upper or lower case, but the underscores must be included.

Type rtc to execute the program, then follow the instructions on the monitor.

#### LOW BATTERY BIT EXPERIMENT

Equipment: Variable lab supply or 20k pot, center tapped to the V<sub>BB</sub> pin.

An oscilloscope with 10 M $\Omega$ , 10 pF probe or higher impedance.

The initial screen output is shown in Message 1. Before selecting the LOW\_BATT\_BIT mode, set the voltage at the V<sub>BB</sub> pin to about 2.5V. If V<sub>BB</sub> is GND or too low a voltage, a message should appear (see Message 2). Once the LOW\_BATT\_BIT mode is running, you should see screen output (see Message 3). The status of the low battery bit is displayed in the lower left of the monitor. A value of 0 indicates V<sub>BB</sub> is higher than the internal threshold detector. A value of 40 indicates the low battery bit is set.

Monitor the waveform at the OSC OUT pin. Observing the peak-to-peak voltage of this waveform is the only way to know that the DP8570A is in the battery backed mode, unless the test mode is selected. The waveform is sinusoidal in form and swings within 0.6V of  $V_{BB}$  and ground. Refer to Figures 1a, 1b, 1c.

Vary the V<sub>BB</sub> voltage slowly as you approach 2.3V. If the V<sub>BB</sub> voltage gets too low (less than 1.8V) the oscillator may stop. During the low battery bit mode, if V<sub>BB</sub> is grounded or a too low a voltage, you will not get any indication on screen. If you hit the spacebar and re-enter the LOW\_BATT\_BIT mode, Message 1 warning will appear on the monitor.

#### 10 mS INTERRUPT EXPERIMENT

Equipment: An oscilloscope is needed to monitor the INTR pin.

Before starting this section of the program, connect  $V_{BB}$  to ground. The INTR\_10 ms code configures the DP8570A in the Single Supply mode. Message 4 is output to the monitor indicating you are in the 10 ms Interrupt mode. Figure 2a shows expected waveforms for a PC-XT (4.77 MHz); Figure 2b a 386/33 MHz AT.

Check that the Oscillator has started. If you don't get osc running in 5 seconds, the program will abort

The Oscillator is running. The Clock is started.

You may choose the 'Low Battery Bit' Test or 'the lOms Interrupt' Test or 'END to return to DOS'

Type in your choice in the following format, then hit ENTER:

Choices are: LOW\_BATT\_BIT or INTR\_10ms or

END to exit the Program

Enter your choice now:

Message 1: Initial Screen Display (Normal Operation)

Watch out! VBB is at Ground or some illegal value

VBB voltage should be between 2.2V and VCC - 0.4V

#### Message 2: V<sub>BB</sub> Warning

Battery backed mode selected.

Check waveform at osc out to see if referenced to the battery voltage Peak value should be less than the battery voltage


Adjust voltage on VBB pin while monitoring screen. The bottom left side of the screen will display zero if VBB > threshold (about 2.1 volts), or 40 if VBB < threshold. This test may be ended by hitting the space bar.

Message 3: Normal Message after Selecting LOW\_BATT\_BIT

3


AN-894






**C**....

 $\nabla$ 



3



3-90

đ

AN-894

**AN-894** /\*\*\*\*\*\*\*\*\*\*\*\*\* \* \* This program RTC.C is designed to work with the DP857x family of \* Real Time Clocks. It works with a demoboard interfaced to a PC/XT \* or PC/AT. This 'C' program is written in Microsoft C (version 6.0). \* This program has two parts: \* Part 1 allows testing the Low Battery Bit, in the Batt Back Mode. \* Part 2 initializes the 10 millisecond periodic interrupt. \* Also, it delays clearing the INT, after polling the int flag in \* the 'MSR' for the purpose of observing the output on an Oscilloscope. #include <stdio.h> #include <conio.h> #include <time.h> #include <graph.h> /\* main status register #define MSR 0x300 \*\*\*\*\*\* #define PFR 0x303 /\* periodic flag register
/\* real time mode register #define RTMR 0x301 #define IRR 0x304 /\* interrupt routing register 0x302 /\* output mode register 8 #define OMR /\* interrupt control register 0 #define ICR0 0x303 /\* interrupt control register 1 0x304 #define ICR1 \*'/ /\* timing control register 0 #define TCR0 0x301 #define TCR1 0x302 /\* timing control register 1 \*/ #define TESTR 0x31F /\* Test Mode register enum { LOW BATT BIT, INTR 10ms, END } mode; char buf[80]; char \*mode\_str[] = { "LOW\_BATT\_BIT", "INTR\_10ms", "END" }; main() char \*input; int i; /\* Initialize the RTC, select 32.768KHz. \*/ /\* The following while loop tries to start the clock \*/ \*/ /\* and tests the osc fail bit to see that the oscillato /\* is running. The oscillator must be running in order \*/ \*/ /\* to configure the DP857X for battery back mode clearscreen(\_GCLEARSCREEN); printf("\n\t Check that the Oscillator has started."); printf("\nIf you don't get osc running in 5 seconds, the program will abort\n") init(); 'Low Battry Bit' Test\tor"); printf("\n\nYou may choose the printf("\n 'the 10ms Interrupt' Test\tor"); 'END to return to DOS' "); printf("\n outp(MSR,0); mode = -1;do { while (mode != LOW BATT\_BIT && mode != INTR\_10ms && mode != END) printf("\n\nType in your choice in the following format, then hit ENTER:"); TL/F/11847-8

----

R

```
printf("\n\nChoices are:\tLOW_BATT_BIT or\
printf("\t\tEND to exit the Program\n");
                                                 or\n\t\tINTR 10ms or\n");
    printf("\nEnter your choice now: \n\n");
    input = gets(buf);
    for (1=0; 1<=3; 1++)
    if (!strcmpi(input, mode_str[i]))
    mode = i;
   }
  switch(mode)
ſ
case LOW BATT BIT:
init();
                                  /* Call 'init' function */
batbak();
                                  /* Call 'batbak' function */
mode = -1;
break;
case INTR 10ms:
init();
                                       /* Call init routine */
intr();
                                      /* Call intr Routine
                                                               */
mode = -1;
break;
case END:
printf("\n This is the END of the Program");
break;
3
} while (mode != END);
3
batbak()
/* This program configures the DP857X 32.768KHz oscillator
   Conditions: Vcc = 5V, VBB = 3.0V (adjustable),
   T = ambient temperature
                                                               */
{
   outp(MSR,0x40);
                          /* select bank 1
                                                               */
   outp(ICR1,0x80);
                          /* set PFAIL enable in ICR1
                                                               */
   outp(MSR,0);
   outp(PFR,0);
                          /* select battery backed mode
                                                               */
   if(inp(IRR) & Ox40)
    Ł
      _clearscreen(_GCLEARSCREEN);
_settextposition(11,15);
     printf("Watch out! VBB is at Ground or some illegal value");
      settextposition(13,15);
     printf("VBB voltage should be between 2.2V and VCC - 0.4V");
      settextposition(24,0);
     mode = -1;
     exit();
    }
    clearscreen(_GCLEARSCREEN);
   printf("\n\t Battery backed mode selected.");
   printf("\n\t Check waveform at osc out to see if referenced");
  printf("\n\t to the battery voltage.\n\t Peak value should be less");
printf(" than the battery voltage\n");
                                                                                       TL/F/11847-9
```

AN-894

----

```
printf("\n\n");
   printf("\n\t Adjust voltage on VBB pin while monitoring screen.");
  printf("\n\t The bottom left side of the screen will display zero");
printf("\n\t if VBB > threshold (about 2.lvolts),");
   printf("\n\t or 40 if VBB < threshold.");
   printf("\n\t This test may be ended by hitting the space bar.");
   printf("\n\n\n");
                                                                                */
                                                    /* select bank 0
   outp(MSR,0);
   while(!kbhit())
   Ł
    settextposition(24,0);
                                                  /* display low batt bit */
    printf("%x",inp(IRR) & 0x40);
   3
   getch();
}
   intr()
  {
        int i;
        i = 0;
                                                                                */
                                   /* clear all pending interrupts
   outp(MSR,0x3E);
   outp(PFR, 0x40);
   outp(TCR0,0);
   outp(TCR1,0);
                                                                                 */
                                   /* select per. intr to intr pin
   outp(IRR, 0x1D);
   outp(MSR, 0x40);
outp(OMR, 0x8);
                                   /* select register bank 1
                                    /* intr = push pull active lo
                                   /* select 10ms periodic intr
   outp(ICR0,0x10);
   outp(ICR1,0x80);
    printf("\n\Now you are in the 10ms_Interrupt mode");
printf("\nYou can use Oscilloscope to view the waveform");
    printf("\nHit spacebar to return to 'Selection Menu'");
   do {
    for (i=0; (i < 1300) \&\& ((inp(MSR) \& 0x05) != 5); i++)
     ;
      if (i == 1300)
     {
    printf("\nThere is something WRONG !!");
    printf("\n Please check the Voltage at the VBB pin");
     exit();
     3
 else
                                                                                 */
                                                /* this loop is for
  for(i=0; i < 300; i++)</pre>
                                                /* viewing the waveform
  /* The value in the 'FOR' loop is dependent on the speed of 
/* the Processor. The value '200' in this example is for
                                                                                 */
  /* the PC/XT running at 4.7 MHz.
                                                                                 */
                                                         /* clear per intr
                                                                                 */
   outp(MSR,0x3E);
  } while (!kbhit());
  getch();
 }
                                                                                             TI /F/11847-10
```

-3

3

**AN-894** 

```
init ()
                                                 /* function initialization */
/* This function selects 32 KHz Oscillator and attempts to start the *
 * clock. Check for 'OSC Running'. If not running, output message *
 * 'Harware Problem, not running'. Return to DOS. *

                                                                                   */
unsigned long int dt;
int pfr=0x40,rtmr=0, irr;
time_t t1, t2;
dt = 0;
                                     /* delta time. difference between
                                                                                   */
                                     /* the start & stop time.
                                                                                   *'/
                                     /* start time.
                                                                                   */
 outp(MSR,0);
                                     /* select page 0, register bank 0
                                                                                   */
 outp(PFR, 0xC0);
                                     /* select test mode
                                                                                   */
 outp(TESTR,0);
                                     /* clear test register
 outp(PFR, 0x40);
                                     /* deselect test mode
 outp(MSR,0x40);
 outp(ICR1,0x80);
 outp(RTMR,8);
                                     /* issue start clock command
                                                                                   */
 time(&t1);
while(((pfr == 0x40)||(rtmr == 0)) && dt <5 )
                                           /* if 1 stay in while loop
                                                                                   */
{
 outp(MSR, 0x40);
                                                   /* select bank 1
                                           /* select 32KHz,start clock
 outp(RTMR, 0x08);
                                          /* get start/stop bit
/* select bank 0
 rtmr = inp(RTMR) & 8;
 outp(MSR,0);
 pfr = (inp(PFR)&0x40);
irr = inp(IRR);
                                           /* get osc fail bit
 time(&t2);
 dt = t2 - t1;
}
 if (dt == 5)
 {
 printf("\nThere is something wrong with the Harware !");
 exit(0);
 3
else
printf("\n\t The Oscillator is running. The Clock is started.");
}
                                                                                             TL/F/11847-11
```

**AN-894** 

# Change the Battery on any DP857X Family Member Using Software without Losing Time

This application note describes a method for changing the battery on any of the DP857X family members while power is applied. The method involves use of the test mode. The clock remains running so that no time is lost.

#### THE PROBLEM

Your in the battery backed mode and the low battery bit has turned on (logic Hi). The battery needs to be changed but you don't want to lose time or have to re-initialize the clock.

#### THE SOLUTION

Assuming that the clock is still running (start/stop bit in the Real Time Mode Register = '1'), do the following sequence:

- 1. Write a '1' to bit D7 of the Periodic Flag Register (PFR). Now you are in the Test Mode.
- 2. Write '1' to bit D7 of the Test Register (address Hex 1F in page 0), all other bits are '0'. This action disables the OSC FAIL bit.
- 3. Write a '1' to bit D6 of the PFR. This action changes the RTC from battery backed mode to single supply mode.
- 4. Now the battery can be changed. If the change takes place within a half minute or so, the V<sub>BB</sub> pin can be left floating for that time. If the battery is soldered in such that many minutes will occur, then temporarily connect V<sub>BB</sub> to ground until the new battery is ready for installation.
- 5. After the battery is connected, to return to battery backed mode:

5.1 Write '0' to all bit positions of the Test Register (address Hex 1F in page 0). National Semiconductor Application Note 895 Milt Schwartz



5.2 Write '0' to bits D6 and D7 of the PFR. This write returns the chip to the battery backed mode.

# WHY CAN'T I SWITCH FROM BATTERY BACKED TO SINGLE SUPPLY UNDER NORMAL OPERATION?

Steps 1 thru 4 need to be done because a "glitch" can occur in the oscillator fail circuitry when switching from battery backed mode to single supply mode. This glitch can momentarily cause an OSC FAIL condition which stops the clock and sets the OSC FAIL bit (D6 in the PFR). The reason for entering the test mode is that this is the only way the OSC FAIL bit can be disabled.


#### HOW THE GLITCH OCCURS

In battery backed mode, the oscillator fail circuitry is powered by an internal voltage follower referenced to  $V_{BB}$ . When the single supply mode is selected, this voltage follower is disabled and the oscillator fail circuitry instantaneously sees the  $V_{CC}$  voltage. Bench tests indicate that the magnitude of the change is what causes the glitch, thus stopping the clock. If the difference between  $V_{BB}$  and  $V_{CC}$  is reduced, then the clock does not stop.

Example: If V<sub>BB</sub> is 2.5V and V<sub>CC</sub> is 5.0V then the clock continues running if you switch from battery backed mode to single supply mode. However, if V<sub>BB</sub> is 2V and V<sub>CC</sub> is 5V then the clock will stop when you switch from battery backed mode to single supply mode.

#### **TEST CONDITIONS**

Bench tests were made using a PC-AT® 386/33 MHz. The DP8570 was interfaced to the PC using the circuit shown in *Figure 1*.





# Section 4 Appendices/ Physical Dimensions




#### **Section 4 Contents**


Physical Dimensions	 	
Bookshelf		
Distributors		2



#### 24 Lead Ceramic Sidebrazed Dual-in-Line Package NS Package Number D24C




# 16 Lead Ceramic Dual-in-Line Package NS Package Number J16A



4




**Physical Dimensions** 




# Physical Dimensions


# 24 Lead (0.300" Wide) Molded Dual-in-Line Package NS Package Number N24C





4































#### **Bookshelf of Technical Support Information**

National Semiconductor Corporation recognizes the need to keep you informed about the availability of current technical literature.

This bookshelf is a compilation of books that are currently available. The listing that follows shows the publication year and section contents for each book.

For datasheets on new products and devices still in production but not found in a databook, please contact the National Semiconductor Customer Support Center at 1-800-272-9959.

We are interested in your comments on our technical literature and your suggestions for improvement.

Please send them to:

Technical Communications Dept. M/S 16-300 2900 Semiconductor Drive P.O. Box 58090 Santa Clara, CA 95052-8090

## ADVANCED BICMOS LOGIC (ABTC, IBF, BCT) DATABOOK-1993

ABTC/BCT Description and Family Characteristics • ABTC/BCT Ratings, Specifications and Waveforms ABTC Applications and Design Considerations • Quality and Reliability • Integrated Bus Function (IBF) Introduction 54/74ABT3283 Synchronous Datapath Multiplexer • 74FR900/25900 9-Bit 3-Port Latchable Datapath Multiplexer 54/74ACTQ3283 32-Bit Latchable Transceiver with Parity Generator/Checker and Byte Multiplexing 54/74ABTCXXX • 74BCTXXX

#### ALS/AS LOGIC DATABOOK—1990

Introduction to Advanced Bipolar Logic • Advanced Low Power Schottky • Advanced Schottky

#### ASIC DESIGN MANUAL/GATE ARRAYS & STANDARD CELLS-1987

SSI/MSI Functions • Peripheral Functions • LSI/VLSI Functions • Design Guidelines • Packaging

#### **CMOS LOGIC DATABOOK—1988**

CMOS AC Switching Test Circuits and Timing Waveforms • CMOS Application Notes • MM54HC/MM74HC MM54HCT/MM74HCT • CD4XXX • MM54CXXX/MM74CXXX • Surface Mount

## DATA ACQUISITION DATABOOK-1993

Data Acquisition Systems • Analog-to-Digital Converters • Digital-to-Analog Converters • Voltage References Temperature Sensors • Active Filters • Analog Switches/Multiplexers • Surface Mount

#### DATA ACQUISITION DATABOOK SUPPLEMENT-1992

New devices released since the printing of the 1989 Data Acquisition Linear Devices Databook.

#### DISCRETE SEMICONDUCTOR PRODUCTS DATABOOK-1989

Selection Guide and Cross Reference Guides • Diodes • Bipolar NPN Transistors Bipolar PNP Transistors • JFET Transistors • Surface Mount Products • Pro-Electron Series Consumer Series • Power Components • Transistor Datasheets • Process Characteristics

#### **DRAM MANAGEMENT HANDBOOK**—1993

Dynamic Memory Control • CPU Specific System Solutions • Error Detection and Correction Microprocessor Applications

#### **EMBEDDED CONTROLLERS DATABOOK—1992**

COP400 Family • COP800 Family • COPS Applications • HPC Family • HPC Applications MICROWIRE and MICROWIRE/PLUS Peripherals • Microcontroller Development Tools

#### FDDI DATABOOK—1991

FDDI Overview • DP83200 FDDI Chip Set • Development Support • Application Notes and System Briefs

#### F100K ECL LOGIC DATABOOK & DESIGN GUIDE-1992

Family Overview • 300 Series (Low-Power) Datasheets • 100 Series Datasheets • 11C Datasheets Design Guide • Circuit Basics • Logic Design • Transmission Line Concepts • System Considerations Power Distribution and Thermal Considerations • Testing Techniques • 300 Series Package Qualification Quality Assurance and Reliability • Application Notes

#### FACT™ ADVANCED CMOS LOGIC DATABOOK—1993

Description and Family Characteristics • Ratings, Specifications and Waveforms Design Considerations • 54AC/74ACXXX • 54ACT/74ACTXXX • Quiet Series: 54ACQ/74ACQXXX Quiet Series: 54ACTQ/74ACTQXXX • 54FCT/74FCTXXX • FCTA: 54FCTXXXA/74FCTXXXA/B

## FAST® ADVANCED SCHOTTKY TTL LOGIC DATABOOK—1990

Circuit Characteristics • Ratings, Specifications and Waveforms • Design Considerations • 54F/74FXXX

# FAST® APPLICATIONS HANDBOOK—1990

**Reprint of 1987 Fairchild FAST Applications Handbook** Contains application information on the FAST family: Introduction • Multiplexers • Decoders • Encoders Operators • FIFOs • Counters • TTL Small Scale Integration • Line Driving and System Design FAST Characteristics and Testing • Packaging Characteristics

#### HIGH-PERFORMANCE BUS INTERFACE DESIGNER'S GUIDE-1992

Futurebus + /BTL Devices • BTL Transceiver Application Notes • Futurebus + Application Notes High Performance TTL Bus Drivers • PI-Bus • Futurebus + /BTL Reference

#### **IBM DATA COMMUNICATIONS HANDBOOK—1992**

#### INTERFACE: LINE DRIVERS AND RECEIVERS DATABOOK-1992

EIA-232 • EIA-422/423 • EIA-485 • Line Drivers • Receivers • Repeaters • Transceivers • Application Notes

# LINEAR APPLICATIONS HANDBOOK—1991

The purpose of this handbook is to provide a fully indexed and cross-referenced collection of linear integrated circuit applications using both monolithic and hybrid circuits from National Semiconductor.

Individual application notes are normally written to explain the operation and use of one particular device or to detail various methods of accomplishing a given function. The organization of this handbook takes advantage of this innate coherence by keeping each application note intact, arranging them in numerical order, and providing a detailed Subject Index.

# LINEAR APPLICATION SPECIFIC IC's DATABOOK-1993

Audio Circuits • Radio Circuits • Video Circuits • Display Drivers • Clock Drivers • Frequency Synthesis Special Automotive • Special Functions • Surface Mount

# LOCAL AREA NETWORKS DATABOOK-1993

Integrated Ethernet Network Interface Controller Products • Ethernet Physical Layer Transceivers Ethernet Repeater Interface Controller Products • Token-Ring Interface Controller (TROPIC) Hardware and Software Support Products • FDDI Products • Glossary and Acronyms

## LOW VOLTAGE DATABOOK—1992

This databook contains information on National's expanding portfolio of Iow and extended voltage products. Product datasheets included for: Low Voltage Logic (LVQ), Linear, EPROM, EEPROM, SRAM, Interface, ASIC, Embedded Controllers, Real Time Clocks, and Clock Generation and Support (CGS).

#### MASS STORAGE HANDBOOK-1989

Rigid Disk Pulse Detectors • Rigid Disk Data Separators/Synchronizers and ENDECs Rigid Disk Data Controller • SCSI Bus Interface Circuits • Floppy Disk Controllers • Disk Drive Interface Circuits Rigid Disk Preamplifiers and Servo Control Circuits • Rigid Disk Microcontroller Circuits • Disk Interface Design Guide

#### **MEMORY DATABOOK—1992**

CMOS EPROMs • CMOS EEPROMs • PROMs • Application Notes

#### **MEMORY APPLICATION HANDBOOK—1993**

#### **OPERATIONAL AMPLIFIERS DATABOOK—1993**

Operational Amplifiers • Buffers • Voltage Comparators • Instrumentation Amplifiers • Surface Mount

#### PACKAGING DATABOOK—1993

Introduction to Packaging • Hermetic Packages • Plastic Packages • Advanced Packaging Technology Package Reliability Considerations • Packing Considerations • Surface Mount Considerations

#### POWER IC's DATABOOK—1993

Linear Voltage Regulators • Low Dropout Voltage Regulators • Switching Voltage Regulators • Motion Control Peripheral Drivers • High Current Switches • Surface Mount

# PROGRAMMABLE LOGIC DEVICE DATABOOK AND DESIGN GUIDE-1993

Product Line Overview • Datasheets • Design Guide: Designing with PLDs • PLD Design Methodology PLD Design Development Tools • Fabrication of Programmable Logic • Application Examples

## **REAL TIME CLOCK HANDBOOK—1993**

3-Volt Low Voltage Real Time Clocks • Real Time Clocks and Timer Clock Peripherals • Application Notes

#### **RELIABILITY HANDBOOK—1987**

Reliability and the Die • Internal Construction • Finished Package • MIL-STD-883 • MIL-M-38510 The Specification Development Process • Reliability and the Hybrid Device • VLSI/VHSIC Devices Radiation Environment • Electrostatic Discharge • Discrete Device • Standardization Quality Assurance and Reliability Engineering • Reliability and Documentation • Commercial Grade Device European Reliability Programs • Reliability and the Cost of Semiconductor Ownership Reliability Testing at National Semiconductor • The Total Military/Aerospace Standardization Program 883B/RETSTM Products • MILS/RETSTM Products • 883/RETSTM Hybrids • MIL-M-38510 Class B Products Radiation Hardened Technology • Wafer Fabrication • Semiconductor Assembly and Packaging Semiconductor Packages • Glossary of Terms • Key Government Agencies • AN/ Numbers and Acronyms Bibliography • MIL-M-38510 and DESC Drawing Cross Listing

#### SCAN<sup>™</sup> DATABOOK—1993

Evolution of IEEE 1149.1 Standard • SCAN Buffers • System Test Products • Other IEEE 1149.1 Devices

#### **TELECOMMUNICATIONS—1992**

COMBO and SLIC Devices • ISDN • Digital Loop Devices • Analog Telephone Components • Software Application Notes

and the Contract of the second sec

#### NATIONAL SEMICONDUCTOR CORPORATION DISTRIBUTORS

Sunnyvale

#### ALABAMA

Huntsville Hamilton/Avnet (205) 837-7210 Pioneer Technology (205) 837-9300

ARIZONA Chandler Hamilton/Avnet (602) 961-1211 Tempe Anthem Electronics (602) 966-6600 **Bell Industries** (602) 966-7800 Time Electronics (602) 967-2000 CALIFORNIA Agora Hills Bell Industries (818) 706-2608 Time Electronics (818) 707-2890 Zeus Components (818) 889-3838 Burbank Elmo Semiconductor (818) 768-7400 Calabasas F/X Electronics (818) 591-9220 Chatsworth Anthem Electronics (818) 775-1333 Time Electronics (818) 998-7200 Costa Mesa Hamilton Electro Sales (714) 641-4100 Cypress Bell Industries (714) 895-7801 Gardena Hamilton/Avnet (213) 516-8600 Irvine Anthem Electronics (714) 768-4444 Rocklin Anthem Electronics (916) 624-9744 Bell Industries (916) 652-0414 Roseville Hamilton/Avnet (916) 925-2216 San Diego Anthem Electronics (619) 453-9005 Hamilton/Avnet (619) 571-1900 Time Electronics (619) 586-0129 San Jose Anthem Electronics (408) 453-1200 Pioneer Technology (408) 954-9100 Zeus Components

(408) 629-4789

**Bell Industries** (408) 734-8570 Hamilton/Avnet (408) 743-3300 Time Electronics (408) 734-9888 Torrance Time Electronics (213) 320-0880 Tustin Time Electronics (714) 669-0100 Woodland Hills Hamilton/Avnet (818) 594-0404 Yorba Linda Zeus Components (714) 921-9000 COLORADO Denver **Bell Industries** (303) 691-9010 Englewood Anthem Electronics (303) 790-4500 Hamilton/Avnet (303) 799-7800 Time Electronics (303) 721-8882 CONNECTICUT Danbury Hamilton/Avnet (203) 743-6077 Shelton Pioneer Standard (203) 929-5600 Waterbury Anthem Electronics (203) 575-1575 FLORIDA Altamonte Springs Bell Industries (407) 339-0078 Pioneer Technology (407) 834-9090 Zeus Components (407) 788-9100 Deerfield Beach Pioneer Technology (305) 428-8877 Fort Lauderdale Hamilton/Avnet (305) 767-6377 Time Electronics (305) 484-1778 Orlando Chip Supply (407) 298-7100 Time Electronics (407) 841-6565 St. Petersburg Hamilton/Avnet (813) 572-4329 Winter Park Hamilton/Avnet (407) 657-3300 GEORGIA Duluth Hamilton/Avnet (404) 446-0611 Pioneer Technology

(404) 623-1003

Norcross **Bell Industries** (404) 662-0923 Time Electronics (404) 368-0969 ILLINOIS Addison **Pioneer Electronics** (708) 495-9680 Bensenville Hamilton/Avnet (708) 860-7700 Elk Grove Village Bell Industries (708) 640-1910 Schaumburg Anthem Electronics (708) 884-0200 Time Electronics (708) 303-3000 INDIANA Carmel Hamilton/Avnet (317) 844-9533 Fort Wayne **Bell Industries** (219) 423-3422 Indianapolis Advent Electronics Inc. (317) 872-4910 **Bell Industries** (317) 875-8200 Pioneer Standard (317) 573-0880 IOWA Cedar Rapids Advent Electronics (319) 363-0221 Hamilton/Avnet (319) 362-4757 KANSAS Lenexa Hamilton/Avnet (913) 888-8900 MARYLAND Columbia Anthem Electronics (410) 995-6840 Time Electronics (410) 964-3091 Zeus Components (410) 997-1118 Gaithersburg Pioneer Technology (301) 921-0660 MASSACHUSETTS Andover **Bell Industries** (508) 474-8880 Beverly Sertech Laboratories (508) 927-5820 Lexington Pioneer Standard (617) 861-9200 Norwood Gerber Electronics (617) 769-6000 Peabody Hamilton/Avnet (508) 531-7430 Time Electronics

(508) 532-9900

Tyngsboro Port Electronics (508) 649-4880 Wakefield Zeus Components (617) 246-8200 Wilmington Anthem Electronics (508) 657-5170 MICHIGAN Grand Rapids Pioneer Standard (616) 698-1800 Grandville Hamilton/Avnet (616) 243-8805 Livonia Pioneer Standard (313) 525-1800 Novi Hamilton/Avnet (313) 347-4720 Wyoming R. M. Electronics, Inc. (616) 531-9300 MINNESOTA Eden Prairie Anthem Electronics (612) 944-5454 Pioneer Standard (612) 944-3355 Edina Time Electronics (612) 943-2433 Minnetonka Hamilton/Avnet (612) 932-0600 MISSOURI Chesterfield Hamilton/Avnet (314) 537-1600 St. Louis Time Electronics (314) 391-6444 NEW JERSEY Cherry Hill Hamilton/Avnet (609) 424-0110 Fairfield Hamilton/Avnet (201) 575-3390 Pioneer Standard (201) 575-3510 Mariton Time Electronics (609) 596-6700 Mount Laurel Seymour Electronics (609) 235-7474 Pine Brook Anthem Electronics (201) 227-7960 Wayne Time Electronics (201) 785-8250 NEW MEXICO Albuquerque Alliance Electronics Inc. (505) 292-3360 **Bell Industries** (505) 292-2700 Hamilton/Avnet (505) 345-0001

#### NATIONAL SEMICONDUCTOR CORPORATION DISTRIBUTORS (Continued)

NEW YORK Binghamton Pioneer (607) 722-9300 Buffalo Summit Electronics (716) 887-2800 Commack Anthem Electronics (516) 864-6600 Fairport Pioneer Standard (716) 381-7070 Hauppauge Hamilton/Avnet (516) 231-9444 Time Electronics (516) 273-0100 North Syracuse Hamilton/Avnet (315) 437-2641 Port Chester **Zeus Components** (914) 937-7400 Rochester Hamilton/Avnet (716) 292-0730 Summit Electronics (716) 334-8110 Syracuse Time Electronics (315) 432-0355 Westbury Hamilton/Avnet Export Div. (516) 997-6868 Woodbury **Pioneer Electronics** (516) 921-8700 NORTH CAROLINA Charlotte Hamilton/Avnet (704) 527-2485 Pioneer Technology (704) 527-8188 Durham Pioneer Technology (919) 544-5400 Morrisville Pioneer Technology (919) 460-1530 Raleigh Hamilton/Avnet (919) 878-0810 OHIO Cleveland Pioneer (216) 587-3600 Columbus Time Electronics


(614) 794-3301

Dayton Bell Industries (513) 435-8660 Bell Industries-Military (513) 434-8231 Hamilton/Avnet (513) 439-6700 Pioneer Standard (513) 236-9900 Zeus Components (513) 293-6162 Independence Hamilton/Avnet (216) 349-5100 OKLAHOMA Tulsa Hamilton/Avnet (918) 664-0444 Pioneer Standard (918) 665-7840 Radio Inc. (918) 587-9123 OREGON Beaverton Anthem Electronics (503) 643-1114 Bell Industries (503) 644-3444 Hamilton/Avnet (800) 332-8638 Portland Time Electronics (503) 684-3780 PENNSYLVANIA Horsham Anthem Electronics (215) 443-5150 Pioneer Technology (215) 674-4000 Mars Hamilton/Avnet (412) 281-4150 Pittsburgh Pioneer (412) 782-2300 TEXAS Austin Hamilton/Avnet (512) 837-8911 Minco Technology Labs (512) 834-2022 Pioneer Standard (512) 835-4000 Time Electronics (512) 346-7346 Dallas Hamilton/Avnet (214) 308-8111 Pioneer Standard

(214) 386-7300

Houston Hamilton/Avnet (713) 240-7733 Pioneer Standard (713) 495-4700 Richardson Anthem Electronics (214) 238-7100 Time Electronics (214) 644-4644 Zeus Components (214) 783-7010 UTAH Midvale **Bell Industries** (801) 255-9611 Salt Lake City Anthem Electronics (801) 973-8555 Hamilton/Avnet (801) 972-2800 West Valley Time Electronics (801) 973-8494 WASHINGTON Bothell Anthem Electronics (206) 483-1700 Kirkland Time Electronics (206) 820-1525 Redmond **Bell Industries** (206) 867-5410 Hamilton/Avnet (206) 881-6697 WISCONSIN Brookfield **Pioneer Electronics** (414) 784-3480 Mequon Taylor Electric (414) 241-4321 Waukesha **Bell Industries** (414) 547-8879 Hamilton/Avnet (414) 784-8205 CANADA WESTERN PROVINCES Burnaby Hamilton/Avnet (604) 420-4101 Semad Electronics (604) 420-9889

Calgary Electro Sonic Inc. (403) 255-9550 Semad Electronics (403) 252-5664 Zentronics (403) 295-8838 Edmonton Zentronics (403) 482-3038 Markham Semad Electronics 1 td (416) 475-3922 Richmond Electro Sonic Inc. (604) 273-2911 Zentronics (604) 273-5575 Winnipeg Zentronics (204) 694-1957 EASTERN PROVINCES Mississauga Hamilton/Avnet (416) 795-3825 Time Electronics (416) 672-5300 Zentronics (416) 507-2600 Nepean Hamilton/Avnet (613) 226-1700 Zentronics (613) 226-8840 Ottawa Electro Sonic Inc. (613) 728-8333 Semad Electronics (613) 727-8325 Pointe Claire Semad Electronics (514) 694-0860 St. Laurent Hamilton/Avnet (514) 335-1000 Zentronics (514) 737-9700 Willowdale ElectroSonic Inc. (416) 494-1666 Winnipeg Electro Sonic Inc. (204) 783-3105





National Semiconductor Corporation

2900 Semiconductor Drive P.O. Box 58090 Santa Clara, CA 95052-8090

For sales, literature and technical support for North America, please contact the National Semiconductor Customer Support Center at 1-800-272-9959.

# SALES OFFICES

#### CANADA

National Semiconductor 5925 Airport Rd. Suite 615 Mississauga, Ontario L4V 1W1 Tel: (416) 678-2920 Fax: (416) 678-2535

#### PUERTO RICO

National Semiconductor La Electronica Bldg. Suite 312, R.D. # 1 KM 14.5 Rio Piedias, Puerto Rico 00927 Tel: (809) 758-9211 Fax: (809) 763-6959

#### INTERNATIONAL» OFFICES

National Semiconductor (Australia) Pty, Ltd. 16 Business Park Dr. Notting Hill, VIC 3168 Australia Tel: (3) 558-9999 Fax: (3) 558-9998 National Semiconductores

Do Brazil Ltda. Av. Brig. Faria Lima, 1409 6 Andar Cep-01451, Paulistano, Sao Paulo, SP Brazil Tel: (55-11) 212-5066 Telex: 391-1131931 NSBR BR Fax: (55-11) 212-1181

National Semiconductor Bulgaria P.C.1.S.A. Dondukov Bld. 25/3 Sofia 1000 Bulgaria

Tel: (02) 88 01 16 Fax: (02) 80 36 18 National Semiconductor

(UK) Ltd. Valdemarsgade 21 DK-4100 Ringsted Denmark Tel: (57) 67 20 80 Fax: (57) 67 20 82

National Semiconductor (UK) Ltd. Mekaanikonkatu 13 SF-00810 Helsinki Finland Tel: 358-0-759-1855 Telex: 126116 Fax: 358-0-759-1393 National Semiconductor France Centre d'Affaires "La Boursidière" Bătiment Champagne BP 90 Route Nationale 186 F-92357 Le Piessis Robinson Paris, France Tel: (01) 40-94-88-88 Telex: 631065 Fax: (01) 40-94-88-11

National Semiconductor S.A. Bâtiment ZETA-Z.A. COURTABOEUF 3, Avenue du Canada F-91966 LES ULIS Cedex 16 Tel: (1) 69 18 37 00 Fax: (1) 69 18 37 69

National Semiconductor GmbH Dieselstrasse 23 D-3004 Isernhagen 2 Germany Tel: (05-11) 72 34 49 Fax: (05-11) 77 88 72

National Semiconductor GmbH Eschborner Landstrasse 130-132 D-6000 Frankfurt 90 Germany Tel: (D-69) 78 91 09 0 Fax: (D-69) 78-94-38-3

National Semiconductor GmbH Industriestrasse 10 D-8080 Fürstenfeldbruck Germany Tel: (0-81-41) 103-0 Telex: 527649

Fax: (0-81-41) 10-35-06 National Semiconductor GmbH Untere Waldplätze 37 D-7000 Stuttgart 80

Germany Tel: (07-11) 68-65-11 Telex: 7255993 Fax: (07-11) 68-65-260

National Semiconductor Hong Kong Ltd. 13th Floor, Straight Block Ocean Centre 5 Canton Rd. Tsimshatsui, Kowloon Hong Kong Tel: (852) 737-1600 Telex: 51292 NSHKL Felex: 51292 NSHKL Fax: (852) 736-9960 National Semiconductor (UK) Ltd. Unit 2A

Cionskeagh Square Cionskeagh Road Dublin 14 Ireland Tel: (01) 269-5344 Fax: (01) 283-0650

National Semiconductor SpA Strada 7, Pallazo R/3 I-20089 Rozzano-Milanofiori Italy Tel: (02) 57500300 Telex: 352647 Fax: (02) 57500400

National Semiconductor Japan Ltd. Sanseido Bldg. 5F 4-15-3, Nishi-shinjuku, Shinjuku-ku Tokyo Japan 160 Tel: (03) 3299-7001

Fax: (03) 3299-7000 National Semiconductor (Far East) Ltd. Korea Branch 13th Floor, Dai Han Life Insurance 63 Building 60, Yoido-dong, Youngdeungpo-ku Seoul Korea 150-763 Tel: (02) 784-8051 Telex: 24942 NSRKLO

Fax: (02) 784-8054 Electronica NSC de Mexico SA Juventino Rosas No. 118-2 Col Guadalupe Inn Mexico, 01020 D.F. Mexico Tel: (525) 524-9402 Fax: (525) 524-9342

National Semiconductor Benelux B.V. Flevolaan 4 Postbus 90 1380 AB Weesp The Netherlands Tel: (02) 94 03 04 48 Fax: (02) 94 03 04 30

National Semiconductor (UK) Ltd. Isveien 45 N-1390 Vollen Norway

Norway Tel: (2) 79-6500 Fax: (2) 79-6040

#### National Semiconductor Asia Pacific Pte. Ltd. 200 Cantonment Road # 13-01 Soutppoint Singapore 0208 Singapore Tel: (65) 225-2226 Telex: NATSEMI RS 33877

Fax: (65) 225-7080 National Semiconductor Calle Agustin de Foxa, 27 (9°D) E-28036 Madrid Spain Tel: (01) 7-33-29-58 Telex: 46133 Fax: (01) 7-33-80-18

National Semiconductor AB P.O. Box 1009 Grosshandlarvagen 7 S-12123 Johanneshov Sweden Tel: (08) 7228050 Fax: (08) 7229095

National Semiconductor Alte Winterthurerstrasse 53 CH-8304 Wallisellen-Zürich Switzerland Tel: (01) 8-30-27-27 Fax: (01) 8-30-19-00

National Semiconductor (Far East) Ltd. Taiwan Branch 9th Fioor, No. 18 Sec. 1, Chang An East Road Taipei, Taiwan, R.O.C. Tel: (02) 521-3288 Fax: (02) 561-3054

National Semiconductor (UK) Ltd. The Maples, Kembrey Park Swindon, Wiltshire SN2 6UT United Kingdom Tel: (07-93) 61 41 41 Telex: 444674 Fax: (07-93) 52 21 80